

APPENDIX B
APPLICABILITY OF NUREG-0933 ISSUES TO OPERATING AND FUTURE REACTOR PLANTS

This appendix contains a listing of those residual GSIs that are applicable to operating and future reactor plants and includes: issues that have been resolved with requirements [I, NOTE 3(a)]; USI, HIGH- and MEDIUM-priority issues scheduled for resolution; nearly-resolved issues scheduled for resolution (NOTES 1 and 2); and issues that are scheduled for prioritization (NOTE 4). The priority designations for all issues are consistent with those listed in Table II of the Introduction. In accordance with 10 CFR 52.47(a)(1)(iv), any future application for design certification must contain proposed technical resolutions for the issues in this listing that are designated USI, HIGH, MEDIUM, NOTE 1, and NOTE 2. (In July 1998, the priority categories NOTES 1 and 2 were eliminated and all GSIs in these categories were given a HIGH priority ranking.¹⁷¹⁸) Also included in this listing are those GSIs that were either prioritized or resolved with no impact on operating reactor plants but contain recommendations for future reactor plants (NOTE 6).

Legend

NOTES: 1	- Possible Resolution Identified for Evaluation (Discontinued 07-06-98)
2	- Resolution Available [Documented in NUREG, NRC Memorandum, SER or equivalent] (Discontinued 07-06-98)
3(a)	- Resolution Resulted in the Establishment of New Regulatory Requirements [Rule, Regulatory Guide, SRP Change, or equivalent]
4	- Issue to be Prioritized in the Future
6	- New Requirements for Future Plants Recommended
B&W	- Babcock & Wilcox Company
CE	- Combustion Engineering Company
GE	- General Electric Company
CONTINUE	- Work on the issue continues in accordance NRC Management Directive 6.4 ¹⁸⁵⁸
HIGH	- High Safety Priority
I	- Resolved TMI Action Plan Item with Implementation of Resolution Mandated by NUREG-0737
MEDIUM	- Medium Safety Priority
MPA	- Multiplant Action
NA	- Not Applicable
TBD	- To Be Determined
USI	- Unresolved Safety Issue
<u>W</u>	- Westinghouse Electric Corporation

Appendix B (Continued)

Action Plan Item/Issue No.	Title	Safety Priority/Status	Affected NSSS Vendor		Operating Plants- MPA No	Operating Plants - Effective Date	Future Plants- Effective Date
			BWR	PWR			

TMI ACTION PLAN ITEMSI.A OPERATING PERSONNELI.A.1 Operating Personnel and Staffing

I.A.1.1	Shift Technical Advisor	I	All	All	F-01	09/13/79	09/27/79
I.A.1.2	Shift Supervisor Administrative Duties	I	All	All		09/13/79	09/27/79
I.A.1.3	Shift Manning	I	All	All	F-02	07/31/80	06/26/80
I.A.1.4	Long-Term Upgrading	NOTE 3(a)	All	All		04/28/83	04/28/83

I.A.2 Training and Qualifications of Operating Personnel

I.A.2.1	Immediate Upgrading of Operator and Senior Operator Training and Qualifications	-	-	-	-	-	-
I.A.2.1(1)	Qualifications – Experience	I	All	All	F-03	03/28/80	03/28/80
I.A.2.1(2)	Training	I	All	All	F-03	03/28/80	03/28/80
I.A.2.1(3)	Facility Certification of Competence and Fitness of Applicants for Operator and Senior Operator Licenses	I	All	All	F-03	03/28/80	03/28/80
I.A.2.3	Administration of Training Programs	I	All	All		03/28/80	03/28/80
I.A.2.6	Long-Term Upgrading of Training and Qualifications	-	-	-	-	-	-
I.A.2.6(1)	Revise Regulatory Guide 1.8	NOTE 3(a)	All	All		TBD	05/--/87

I.A.3 Licensing and Requalification of Operating Personnel

I.A.3.1	Revise Scope of Criteria for Licensing Examinations	I	All	All		03/28/80	03/28/80
---------	---	---	-----	-----	--	----------	----------

I.A.4 Simulator Use and Development

I.A.4.1	Initial Simulator Improvement	-	-	-	-	-	-
I.A.4.1(2)	Interim Changes in Training Simulators	NOTE 3(a)	All	All		04/--/81	03/28/81
I.A.4.2	Long-Term Training Simulator Upgrade	-	-	-	-	-	-
I.A.4.2(1)	Research on Training Simulators	NOTE 3(a)	All	All		04/--/87	04/--/87
I.A.4.2(2)	Upgrade Training Simulator Standards	NOTE 3(a)	All	All		04/--/81	04/--/81
I.A.4.2(3)	Regulatory Guide on Training Simulators	NOTE 3(a)	All	All		04/--/81	04/--/81
I.A.4.2(4)	Review Simulators for Conformance to Criteria	NOTE 3(a)	All	All		03/25/87	03/25/87

Appendix B (Continued)

Action Plan Item/Issue No.	Title	Safety Priority/Status	Affected NSSS Vendor		Operating Plants- MPA No	Operating Plants - Effective Date	Future Plants- Effective Date
			BWR	PWR			
<u>I.C</u>	<u>OPERATING PROCEDURES</u>						
I.C.1	Short-Term Accident Analysis and Procedures Revision	-	-	-	-	-	-
I.C.1(1)	Small Break LOCAs	I	All	All		09/13/79	09/13/79
I.C.1(2)	Inadequate Core Cooling	I	All	All	F-04	09/13/79	09/13/79
I.C.1(3)	Transients and Accidents	I	All	All	F-05	09/13/79	09/27/79
I.C.2	Shift and Relief Turnover Procedures	I	All	All		09/13/79	09/27/79
I.C.3	Shift Supervisor Responsibilities	I	All	All		09/13/79	09/27/79
I.C.4	Control Room Access	I	All	All		09/13/79	09/27/79
I.C.5	Procedures for Feedback of Operating Experience to Plant Staff	I	All	All	F-06	05/07/80	06/26/80
I.C.6	Procedures for Verification of Correct Performance of Operating Activities	I	All	All	F-07	10/31/80	10/31/80
I.C.7	NSSS Vendor Review of Procedures	I	All	All		NA	06/26/80
I.C.8	Pilot Monitoring of Selected Emergency Procedures for Near-Term Operating License Applicants	I	All	All		NA	06/26/80
I.C.9	Long-Term Program Plan for Upgrading of Procedures	NOTE 3(a)	All	All		09/13/79	06/--/85
<u>I.D</u>	<u>CONTROL ROOM DESIGN</u>						
I.D.1	Control Room Design Reviews	I	All	All	F-08	06/26/80	06/26/80
I.D.2	Plant Safety Parameter Display Console	I	All	All	F-09	06/26/80	06/26/80
I.D.5	Improved Control Room Instrumentation Research	-	-	-	-	-	-
I.D.5(2)	Plant Status and Post-Accident Monitoring	NOTE 3(a)	All	All		NA	12/--/80
<u>I.F</u>	<u>QUALITY ASSURANCE</u>						
I.F.2	Develop More Detailed QA Criteria	-	-	-	-	-	-
I.F.2(2)	Include QA Personnel in Review and Approval of Plant Procedures	NOTE 3(a)	All	All		NA	07/--/81
I.F.2(3)	Include QA Personnel in All Design, Construction, Installation, Testing, and Operation Activities	NOTE 3(a)	All	All		NA	07/--/81
I.F.2(6)	Increase the Size of Licensees' QA Staff	NOTE 3(a)	All	All		NA	07/--/81
I.F.2(9)	Clarify Organizational Reporting Levels for the QA Organization	NOTE 3(a)	All	All		NA	07/--/81
<u>I.G</u>	<u>PREOPERATIONAL AND LOW-POWER TESTING</u>						
I.G.1	Training Requirements	I	All	All		NA	06/26/80
I.G.2	Scope of Test Program	NOTE 3(a)	All	All		NA	07/--/81

Appendix B (Continued)

Action Plan Item/Issue No.	Title	Safety Priority/Status	Affected NSSS Vendor		Operating Plants- MPA No	Operating Plants - Effective Date	Future Plants- Effective Date
			BWR	PWR			
<u>II.B</u>	<u>CONSIDERATION OF DEGRADED OR MELTED CORES IN SAFETY REVIEW</u>						
II.B.1	Reactor Coolant System Vents	I	All	All	F-10	09/13/79	09/27/79
II.B.2	Plant Shielding to Provide Access to Vital Areas and Protect Safety Equipment for Post-Accident Operation	I	All	All	F-11	09/13/79	09/27/79
II.B.3	Post-Accident Sampling	I	All	All	F-12	09/13/79	09/27/79
II.B.4	Training for Mitigating Core Damage	I	All	All	F-13	03/28/80	03/28/80
II.B.6	Risk Reduction for Operating Reactors at Sites with High Population Densities	NOTE 3(a)	All	All		TBD	NA
II.B.8	Rulemaking Proceeding on Degraded Core Accidents	NOTE 3(a)	All	All		TBD	01/25/85
<u>II.D</u>	<u>REACTOR COOLANT SYSTEM RELIEF AND SAFETY VALVES</u>						
II.D.1	Testing Requirements	I	All	All	F-14	09/13/79	09/27/79
II.D.3	Relief and Safety Valve Position Indication	I	All	All		07/21/79	09/27/79
<u>II.E</u>	<u>SYSTEM DESIGN</u>						
<u>II.E.1</u>	<u>Auxiliary Feedwater System</u>						
II.E.1.1	Auxiliary Feedwater System Evaluation	I	NA	All	F15	03/10/80	03/10/80
II.E.1.2	Auxiliary Feedwater System Automatic Initiation and Flow Indication	I	NA	All	F-16, F-17	09/13/79	09/27/79
II.E.1.3	Update Standard Review Plan and Develop Regulatory Guide	NOTE 3(a)	All	All		NA	07/--/81
<u>II.E.3</u>	<u>Decay Heat Removal</u>						
II.E.3.1	Reliability of Power Supplies for Natural Circulation	I	NA	All		09/13/79	09/27/79
<u>II.E.4</u>	<u>Containment Design</u>						
II.E.4.1	Dedicated Penetrations	I	All	All	F-18	09/13/79	09/27/79
II.E.4.2	Isolation Dependability	I	All	All	F-19	09/13/79	09/27/79
II.E.4.4	Purging	-	-	-	-	-	-
II.E.4.4(1)	Issue Letter to Licensees Requesting Limited Purging	NOTE 3(a)	All	All		11/28/78	NA
II.E.4.4(2)	Issue Letter to Licensees Requesting Information on Isolation Letter	NOTE 3(a)	All	All		10/22/79	NA
II.E.4.4(3)	Issue Letter to Licensees on Valve Operability	NOTE 3(a)	All	All		09/27/79	NA

Appendix B (Continued)

Action Plan Item/Issue No.	Title	Safety Priority/Status	Affected NSSS Vendor		Operating Plants-MPA No	Operating Plants - Effective Date	Future Plants-Effective Date
			BWR	PWR			
<u>II.E.5</u>	<u>Design Sensitivity of B&W Reactors</u>						
II.E.5.1	Design Evaluation	NOTE 3(a)	NA	B&W			
II.E.5.2	B&W Reactor Transient Response Task Force	NOTE 3(a)	NA	B&W			
<u>II.E.6</u>	<u>In Situ Testing of Valves</u>						
II.E.6.1	Test Adequacy Study	NOTE 3(a)	All	All		06/--/89	06/--/89
<u>II.F</u>	<u>INSTRUMENTATION AND CONTROLS</u>						
II.F.1	Additional Accident Monitoring Instrumentation	I	All	All	F-20, F-21 F-22, F-23 F-24, F-25 F-26	09/13/79	09/27/79
II.F.2	Identification of and Recovery from Conditions Leading to Inadequate Core Cooling	I	All	All		07/02/79	09/27/79
II.F.3	Instruments for Monitoring Accident Conditions	NOTE 3(a)	All	All		NA	12/--/80
<u>II.G</u>	<u>ELECTRICAL POWER</u>						
II.G.1	Power Supplies for Pressurizer Relief Valves, Block Valves, and Level Indicators	I	NA	All		09/13/79	09/27/79
<u>II.J</u>	<u>GENERAL IMPLICATIONS OF TMI FOR DESIGN AND CONSTRUCTION ACTIVITIES</u>						
<u>II.J.4</u>	<u>Revise Deficiency Reporting Requirements</u>						
II.J.4.1	Revise Deficiency Reporting Requirements	NOTE 3(a)	All	All		07/31/91	07/31/91
<u>II.K</u>	<u>MEASURES TO MITIGATE SMALL-BREAK LOSS-OF-COOLANT ACCIDENTS AND LOSS-OF-FEEDWATER ACCIDENTS</u>						
II.K.1	IE Bulletins	-	-	-	-	-	-
II.K.1(1)	Review TMI-2 PN's and Detailed Chronology of the TMI-2 Accident	NOTE 3(a)	All	All		03/31/80	NA
II.K.1(2)	Review Transients Similar to TMI-2 That Have Occurred at Other Facilities and NRC Evaluation of Davis-Besse Event	NOTE 3(a)	NA	B&W		03/31/80	NA
II.K.1(3)	Review Operating Procedures for Recognizing, Preventing, and Mitigating Void Formation in Transients and Accidents	NOTE 3(a)	NA	All		03/31/80	NA

Appendix B (Continued)

Action Plan Item/Issue No.	Title	Safety Priority/Status	Affected NSSS Vendor		Operating Plants-MPA No	Operating Plants - Effective Date	Future Plants-Effective Date
			BWR	PWR			
II.K.1(4)	Review Operating Procedures and Training Instructions	NOTE 3(a)	All	All		03/31/80	NA
II.K.1(5)	Safety-Related Valve Position Description	NOTE 3(a)	All	All		03/31/80	03/31/80
II.K.1(6)	Review Containment Isolation Initiation Design and Procedures	NOTE 3(a)	All	All		03/31/80	NA
II.K.1(7)	Implement Positive Position Controls on Valves That Could Compromise or Defeat AFW Flow	NOTE 3(a)	NA	B&W		03/31/80	NA
II.K.1(8)	Implement Procedures That Assure Two Independent 100% AFW Flow Paths	NOTE 3(a)	NA	B&W		03/31/80	NA
II.K.1(9)	Review Procedures to Assure That Radioactive Liquids and Gases Are Not Transferred out of Containment Inadvertently	NOTE 3(a)	All	All		03/31/80	NA
II.K.1(10)	Review and Modify Procedures for Removing Safety-Related Systems from Service	NOTE 3(a)	All	All		03/31/80	03/31/80
II.K.1(11)	Make All Operating and Maintenance Personnel Aware of the Seriousness and Consequences of the Erroneous Actions Leading up to, and in Early Phases of, the TMI-2 Accident	NOTE 3(a)	All	All		03/31/80	NA
II.K.1(12)	One Hour Notification Requirement and Continuous Communications Channels	NOTE 3(a)	All	All			NA
II.K.1(13)	Propose Technical Specification Changes Reflecting Implementation of All Bulletin Items	NOTE 3(a)	All	All		01/01/81	01/01/81
II.K.1(14)	Review Operating Modes and Procedures to Deal with Significant Amounts of Hydrogen	NOTE 3(a)	GE	CE, <u>W</u>		03/31/80	NA
II.K.1(15)	For Facilities with Non-Automatic AFW Initiation, Provide Dedicated Operator in Continuous Communication with CR to Operate AFW	NOTE 3(a)	NA	CE, <u>W</u>		NA	
II.K.1(16)	Implement Procedures That Identify PRZ PORV "Open" Indications and That Direct Operator to Close Manually at "Reset" Setpoint	NOTE 3(a)	NA	CE, <u>W</u>		NA	
II.K.1(17)	Trip PZR Level Bistable so That PZR Low Pressure Will Initiate Safety Injection	NOTE 3(a)	NA	<u>W</u>			
II.K.1(18)	Develop Procedures and Train Operators on Methods of Establishing and Maintaining Natural Circulation	NOTE 3(a)	NA	B&W		NA	
II.K.1(19)	Describe Design and Procedure Modifications to Reduce Likelihood of Automatic PZR PORV Actuation in Transients	NOTE 3(a)	NA	B&W		03/31/80	NA
II.K.1(20)	Provide Procedures and Training to Operators for Prompt Manual Reactor Trip for LOFW, TT, MSIV Closure, LOOP, LOSG Level, and LO PZR Level	NOTE 3(a)	NA	B&W		03/31/80	03/31/80

Appendix B (Continued)

Action Plan Item/Issue No.	Title	Safety Priority/Status	Affected NSSS Vendor		Operating Plants- MPA No	Operating Plants - Effective Date	Future Plants- Effective Date
			BWR	PWR			
II.K.1(21)	Provide Automatic Safety-Grade Anticipatory Reactor Trip for LOFW, TT, or Significant Decrease in SG Level	NOTE 3(a)	NA	B&W		03/31/80	03/31/80
II.K.1(22)	Describe Automatic and Manual Actions for Proper Functioning of Auxiliary Heat Removal Systems When FW System Not Operable	NOTE 3(a)	All	NA		03/31/80	03/31/80
II.K.1(23)	Describe Uses and Types of RV Level Indication for Automatic and Manual Initiation Safety Systems	NOTE 3(a)	All	NA		03/31/80	03/31/80
II.K.1(24)	Perform LOCA Analyses for a Range of Small-Break Sizes and a Range of Time Lapses Between Reactor Trip and RCP Trip	NOTE 3(a)	NA	All		NA	
II.K.1(25)	Develop Operator Action Guidelines	NOTE 3(a)	NA	All		NA	
II.K.1(26)	Revise Emergency Procedures and Train ROs and SROs	NOTE 3(a)	NA	All		NA	
II.K.1(27)	Provide Analyses and Develop Guidelines and Procedures for Inadequate Core Cooling Conditions	NOTE 3(a)	NA	All		NA	
II.K.1(28)	Provide Design That Will Assure Automatic RCP Trip for All Circumstances Where Required	NOTE 3(a)	NA	All		01/01/81	01/01/82
II.K.2	Commission Orders on B&W Plants	-	-	-	-	-	-
II.K.2(1)	Upgrade Timeliness and Reliability of AFW System	NOTE 3(a)	NA	B&W		NA	
II.K.2(2)	Procedures and Training to Initiate and Control AFW Independent of Integrated Control System	NOTE 3(a)	NA	B&W		NA	
II.K.2(3)	Hard-Wired Control-Grade Anticipatory Reactor Trips	NOTE 3(a)	NA	B&W		NA	
II.K.2(4)	Small-Break LOCA Analysis, Procedures and Operator Training	NOTE 3(a)	NA	B&W		NA	
II.K.2(5)	Complete TMI-2 Simulator Training for All Operators	NOTE 3(a)	NA	B&W		NA	
II.K.2(6)	Reevaluate Analysis for Dual-Level Setpoint Control	NOTE 3(a)	NA	B&W		NA	
II.K.2(7)	Reevaluate Transient of September 24, 1977	NOTE 3(a)	NA	B&W		NA	
II.K.2(9)	Analysis and Upgrading of Integrated Control System	I	NA	B&W	F-27	01/01/81	01/01/81
II.K.2(10)	Hard-Wired Safety-Grade Anticipatory Reactor Trips	I	NA	B&W	F-28	01/01/81	01/01/81
II.K.2(11)	Operator Training and Drilling	I	NA	B&W	F-29	01/01/81	01/01/81
II.K.2(13)	Thermal-Mechanical Report on Effect of HPI on Vessel Integrity for Small-Break LOCA With No AFW	I	NA	B&W	F-30	01/01/81	01/01/81
II.K.2(14)	Demonstrate That Predicted Lift Frequency of PORVs and SVs Is Acceptable	I	NA	B&W	F-31	01/01/81	01/01/81
II.K.2(15)	Analysis of Effects of Slug Flow on Once-Through Steam Generator Tubes After Primary System Voiding	I	NA	B&W		06/01/80	06/01/80
II.K.2(16)	Impact of RCP Seal Damage Following Small-Break LOCA With Loss of Offsite Power	I	NA	B&W	F-32	06/01/80	06/01/80

Appendix B (Continued)

Action Plan Item/Issue No.	Title	Safety Priority/Status	Affected NSSS Vendor		Operating Plants-MPA No	Operating Plants - Effective Date	Future Plants-Effective Date
			BWR	PWR			
II.K.2(17)	Analysis of Potential Voiding in RCS During Anticipated Transients	I	NA	B&W	F-33	NA	
II.K.2(19)	Benchmark Analysis of Sequential AFW Flow to Once-Through Steam Generator	I	NA	B&W	F-34	01/01/81	NA
II.K.2(20)	Analysis of Steam Response to Small-Break LOCA That Causes System Pressure to Exceed PORV Setpoint	I	NA	B&W	F-35	01/01/81	NA
II.K.2(21)	LOFT L3-1 Predictions	NOTE 3(a)	NA	B&W		NA	
II.K.3	Final Recommendations of Bulletins and Orders Task Force	-	-	-	-	-	-
II.K.3(1)	Install Automatic PORV Isolation System and Perform Operational Test	I	NA	All	F-36	07/01/81	07/01/81
II.K.3(2)	Report on Overall Safety Effect of PORV Isolation System	I	NA	All	F-37	01/01/81	01/01/81
II.K.3(3)	Report Safety and Relief Valve Failures Promptly and Challenges Annually	I	All	All	F-38	04/01/80	04/01/80
II.K.3(5)	Automatic Trip of Reactor Coolant Pumps	I	NA	All	F-39, G-01	01/01/81	01/01/81
II.K.3(7)	Evaluation of PORV Opening Probability During Overpressure Transient	I	NA	B&W		01/01/81	01/01/81
II.K.3(9)	Proportional Integral Derivative Controller Modification	I	NA	<u>W</u>	F-40	07/01/80	07/01/80
II.K.3(10)	Anticipatory Trip Modification Proposed by Some Licensees to Confine Range of Use to High Power Levels	I	NA	<u>W</u>	F-41		
II.K.3(11)	Control Use of PORV Supplied by Control Components, Inc. Until Further Review Complete	I	All	All			
II.K.3(12)	Confirm Existence of Anticipatory Trip Upon Turbine Trip	I	NA	<u>W</u>	F-42	07/01/80	07/01/80
II.K.3(13)	Separation of HPCI and RCIC System Initiation Levels	I	GE	NA	F-43	10/01/80	10/01/80
II.K.3(14)	Isolation of Isolation Condensers on High Radiation	I	GE	NA	F-44	01/01/81	NA
II.K.3(15)	Modify Break Detection Logic to Prevent Spurious Isolation of HPCI and RCIC Systems	I	GE	NA	F-45	01/01/81	01/01/81
II.K.3(16)	Reduction of Challenges and Failures of Relief Valves - Feasibility Study and System Modification	I	GE	NA	F-46	01/01/81	01/01/81
II.K.3(17)	Report on Outage of ECC Systems - Licensee Report and Technical Specification Changes	I	GE	NA	F-47	01/01/81	01/01/81
II.K.3(18)	Modification of ADS Logic - Feasibility Study and Modification for Increased Diversity for Some Event Sequences	I	GE	NA	F-48	01/01/81	01/01/81
II.K.3(19)	Interlock on Recirculation Pump Loops	I	GE	NA	F-49	01/01/81	NA
II.K.3(20)	Loss of Service Water for Big Rock Point	I	GE	NA		01/01/81	NA

Appendix B (Continued)

Action Plan Item/Issue No.	Title	Safety Priority/Status	Affected NSSS Vendor		Operating Plants- MPA No	Operating Plants - Effective Date	Future Plants- Effective Date
			BWR	PWR			
II.K.3(21)	Restart of Core Spray and LPCI Systems on Low Level - Design and Modification	I	GE	NA	F-50	01/01/81	01/01/81
II.K.3(22)	Automatic Switchover of RCIC System Suction - Verify Procedures and Modify Design	I	GE	NA	F-51	01/01/81	01/01/81
II.K.3(24)	Confirm Adequacy of Space Cooling for HPCI and RCIC Systems	I	GE	NA	F-52	01/01/82	01/01/82
II.K.3(25)	Effect of Loss of AC Power on Pump Seals	I	GE	NA	F-53	01/01/82	01/01/82
II.K.3(27)	Provide Common Reference Level for Vessel Level Instrumentation	I	GE	NA	F-54	10/01/80	10/01/80
II.K.3(28)	Study and Verify Qualification of Accumulators on ADS Valves	I	GE	NA	F-55	01/01/82	01/01/82
II.K.3(29)	Study to Demonstrate Performance of Isolation Condensers with Non-Condensibles	I	GE	NA	F-56	04/01/81	NA
II.K.3(30)	Revised Small-Break LOCA Methods to Show Compliance with 10 CFR 50, Appendix K	I	All	All	F-57	01/01/83	01/01/83
II.K.3(31)	Plant-Specific Calculations to Show Compliance with 10 CFR 50.46	I	All	All	F-58	01/01/83	01/01/83
II.K.3(44)	Evaluation of Anticipated Transients with Single Failure to Verify No Significant Fuel Failure	I	GE	NA	F-59	01/01/81	01/01/81
II.K.3(45)	Evaluate Depressurization with Other Than Full ADS	I	GE	NA	F-60	01/01/81	01/01/81
II.K.3(46)	Response to List of Concerns from ACRS Consultant	I	GE	NA	F-61	07/01/80	07/01/80
II.K.3(57)	Identify Water Sources Prior to Manual Activation of ADS	I	GE	NA	F-62	10/01/80	NA
<u>III.A</u>	<u>EMERGENCY PREPAREDNESS AND RADIATION EFFECTS</u>						
<u>III.A.1</u>	<u>Improve Licensee Emergency Preparedness - Short Term</u>						
III.A.1.1	Upgrade Emergency Preparedness	-	-	-	-	-	-
III.A.1.1(1)	Implement Action Plan Requirements for Promptly Improving Licensee Emergency Preparedness	I	All	All		10/10/79	08/19/80
III.A.1.2	Upgrade Licensee Emergency Support Facilities	-	-	-	-	-	-
III.A.1.2(1)	Technical Support Center	I	All	All	F-63	09/13/79	09/27/79
III.A.1.2(2)	On-Site Operational Support Center	I	All	All	F-64	09/13/79	09/27/79
III.A.1.2(3)	Near-Site Emergency Operations Facility	I	All	All	F-65	09/13/79	09/27/79
<u>III.A.2</u>	<u>Improving Licensee Emergency Preparedness-Long Term</u>						
III.A.2.1	Amend 10 CFR 50 and 10 CFR 50, Appendix E	-	-	-	-	-	-
III.A.2.1(1)	Publish Proposed Amendments to the Rules	NOTE 3(a)	All	All			
III.A.2.1(4)	Revise Inspection Program to Cover Upgraded Requirements	I	All	All	F-67		

Appendix B (Continued)

Action Plan Item/Issue No.	Title	Safety Priority/Status	Affected NSSS Vendor		Operating Plants- MPA No	Operating Plants - Effective Date	Future Plants- Effective Date
			BWR	PWR			
III.A.2.2	Development of Guidance and Criteria	I	All	All	F-68		
<u>III.A.3</u>	<u>Improving NRC Emergency Preparedness</u>						
III.A.3.3	Communications	-	-	-	-	-	-
III.A.3.3(1)	Install Direct Dedicated Telephone Lines	NOTE 3(a)	All	All			
III.A.3.3(2)	Obtain Dedicated, Short-Range Radio Communication Systems	NOTE 3(a)	All	All			
<u>III.D</u>	<u>RADIATION PROTECTION</u>						
<u>III.D.1</u>	<u>Radiation Source Control</u>						
III.D.1.1	Primary Coolant Sources Outside the Containment Structure	-	-	-	-	-	-
III.D.1.1(1)	Review Information Submitted by Licensees Pertaining to Reducing Leakage from Operating Systems	I	All	All		07/02/79	09/27/79
<u>III.D.3</u>	<u>Worker Radiation Protection Improvement</u>						
III.D.3.3	Implant Radiation Monitoring	-	-	-	-	-	-
III.D.3.3(1)	Issue Letter Requiring Improved Radiation Sampling Instrumentation	I	All	All	F-69	09/13/79	09/27/79
III.D.3.3(2)	Set Criteria Requiring Licensees to Evaluate Need for Additional Survey Equipment	NOTE 3(a)	All	All		09/13/79	09/27/79
III.D.3.3(3)	Issue a Rule Change Providing Acceptable Methods for Calibration of Radiation-Monitoring Instruments	NOTE 3(a)	All	All		09/13/79	09/27/79
III.D.3.3(4)	Issue a Regulatory Guide	NOTE 3(a)	All	All		09/13/79	09/27/79
III.D.3.4	Control Room Habitability	I	All	All	F-70	05/07/80	06/26/80
<u>TASK ACTION PLAN ITEMS</u>							
A-1	Water Hammer (former USI)	NOTE 3(a)	All	All		NA	03/15/84
A-2	Asymmetric Blowdown Loads on Reactor Primary Coolant Systems (former USI)	NOTE 3(a)	NA	All	D-10	01/--/81	01/--/81
A-3	Westinghouse Steam Generator Tube Integrity (former USI)	NOTE 3(a)	NA	<u>W</u>		04/17/85	04/17/85
A-4	CE Steam Generator Tube Integrity (former USI)	NOTE 3(a)	NA	CE		04/17/85	04/17/85
A-5	B&W Steam Generator Tube Integrity (former USI)	NOTE 3(a)	NA	B&W		04/17/85	4/17/85
A-6	Mark I Short-Term Program (former USI)	NOTE 3(a)	GE	NA		12/--/77	NA
A-7	Mark I Long-Term Program (former USI)	NOTE 3(a)	GE	NA	D-01	08/--/82	08/--/82
A-8	Mark II Containment Pool Dynamic Loads - Long Term Program (former USI)	NOTE 3(a)	GE	NA		08/--/81	08/--/81
A-9	ATWS (former USI)	NOTE 3(a)	All	All		06/26/84	06/26/84

Appendix B (Continued)

Action Plan Item/Issue No.	Title	Safety Priority/Status	Affected NSSS Vendor		Operating Plants- MPA No	Operating Plants - Effective Date	Future Plants- Effective Date
			BWR	PWR			
A-10	BWR Feedwater Nozzle Cracking (former USI)	NOTE 3(a)	All	NA	B-25	11/--/80	11/--/80
A-11	Reactor Vessel Materials Toughness (former USI)	NOTE 3(a)	All	All		10/--/82	NA
A-12	Fracture Toughness of Steam Generator and Reactor Coolant Pump Supports (former USI)	NOTE 3(a)	NA	All		NA	TBD
A-13	Snubber Operability Assurance	NOTE 3(a)	All	All	B-17, B-22	1980	1980
A-16	Steam Effects on BWR Core Spray Distribution	NOTE 3(a)	GE	NA	D-12	NA	
A-24	Qualification of Class 1E Safety Related Equipment (former USI)	NOTE 3(a)	All	All	B-60	08/--/81	08/--/81
A-25	Non-Safety Loads on Class 1E Power Sources	NOTE 3(a)	All	All		09/--/78	
A-26	Reactor Vessel Pressure Transient Protection (former USI)	NOTE 3(a)	NA	All	B-04	09/--/78	09/--/78
A-28	Increase in Spent Fuel Pool Storage Capacity	NOTE 3(a)	All	All		04/17/78	NA
A-31	RHR Shutdown Requirements (former USI)	NOTE 3(a)	All	All		05/--/78	10/01/78
A-35	Adequacy of Offsite Power Systems	NOTE 3(a)	All	All	B-23	06/02/77 1980	
A-36	Control of Heavy Loads Near Spent Fuel (former USI)	NOTE 3(a)	All	All	C-10, C-15	07/--/80	07/--/80
A-39	Determination of Safety Relief Valve Pool Dynamic Loads and Temperature Limits (former USI)	NOTE 3(a)	GE	NA		02/29/80	09/30/80
A-40	Seismic Design Criteria (former USI)	NOTE 3(a)	All	All		TBD	09/--/89
A-42	Pipe Cracks in Boiling Water Reactors (former USI)	NOTE 3(a)	All	NA	B-05	02/--/81	02/--/81
A-43	Containment Emergency Sump Performance (former USI)	NOTE 3(a)	NA	All		NA	11/--/85
A-44	Station Blackout (former USI)	NOTE 3(a)	All	All		TBD	06/--/88
A-46	Seismic Qualification of Equipment in Operating Plants (former USI)	NOTE 3(a)	All	All		02/--/87	NA
A-47	Safety Implications of Control Systems (former USI)	NOTE 3(a)	All	All		09/20/89	09/20/89
A-48	Hydrogen Control Measures and Effects of Hydrogen Burns on Safety Equipment	NOTE 3(a)	All	<u>W</u>		12/--/81	12/--/81
A-49	Pressurized Thermal Shock (former USI)	NOTE 3(a)	NA	All	A-21	TBD	07/--/85
B-10	Behavior of BWR Mark III Containments	NOTE 3(a)	GE	NA		NA	09/--/84
B-36	Develop Design, Testing, and Maintenance Criteria for Atmosphere Cleanup System Air Filtration and Adsorption Units for Engineered Safety Feature Systems and for Normal Ventilation Systems	NOTE 3(a)	All	All		03/--/78	
B-56	Diesel Reliability	NOTE 3(a)	All	All	D-19	06/--/93	06/--/93
B-63	Isolation of Low Pressure Systems Connected to the Reactor Coolant Pressure Boundary	NOTE 3(a)	All	All	B-45	04/20/81	
B-64	Decommissioning of Reactors	NOTE 3(a)	All	All		06/27/88	NA
B-66	Control Room Infiltration Measurements	NOTE 3(a)	All	All		NA	07/--/81
C-1	Assurance of Continuous Long Term Capability of Hermetic Seals on Instrumentation and Electrical Equipment	NOTE 3(a)	All	All		05/27/80	05/27/80

Appendix B (Continued)

Action Plan Item/Issue No.	Title	Safety Priority/Status	Affected NSSS Vendor		Operating Plants- MPA No	Operating Plants - Effective Date	Future Plants- Effective Date
			BWR	PWR			
C-10	Effective Operation of Containment Sprays in a LOCA	NOTE 3(a)	All	All		NA	
C-17	Interim Acceptance Criteria for Solidification Agents for Radioactive Solid Wastes	NOTE 3(a)	All	All		12/27/82	12/27/82
<u>NEW GENERIC ISSUES</u>							
25.	Automatic Air Header Dump on BWR Scram System	NOTE 3(a)	All	NA		01/09/81	01/09/81
40.	Safety Concerns Associated with Pipe Breaks in the BWR Scram System	NOTE 3(a)	All	NA	B-65	08/31/81	08/31/81
41.	BWR Scram Discharge Volume Systems	NOTE 3(a)	All	NA	B-58	12/09/80	NA
43.	Reliability of Air Systems	NOTE 3(a)	All	All	B-107	08/08/88	08/08/88
45	Inoperability of Instrumentation Due to Extreme Cold Weather	NOTE 3(a)	All	All		NA	09/01/83
51.	Proposed Requirements for Improving the Reliability of Open Cycle Service Water Systems	NOTE 3(a)	All	All	L-913	07/18/89	07/18/89
67.	<u>Steam Generator Staff Actions</u>	-	-	-	-	-	-
67.3.3	Improved Accident Monitoring	NOTE 3(a)	All	All	A-17	12/17/82	12/17/82
70.	PORV and Block Valve Reliability	NOTE 3(a)	NA	All		06/25/90	06/25/90
73.	Detached Thermal Sleeves	NOTE 3(a)	NA	<u>W</u>		NA	
75.	Generic Implications of ATWS Events at the Salem Nuclear Plant	NOTE 3(a)	All	All	B-76, B-77, B-78, B-79, B-80, B-81, B-82, B-85, B-86, B-87, B-88, B-89, B-90, B-91, B-92, B-93	07/08/83	TBD
86.	Long Range Plan for Dealing with Stress Corrosion Cracking in BWR Piping	NOTE 3(a)	All	NA	B-84	TBD	TBD
87.	Failure of HPCI Steam Line Without Isolation	NOTE 3(a)	All	All		06/28/89	06/28/89
89.	Stiff Pipe Clamps	NOTE 6	All	All	NA	NA	TBD
93.	Steam Binding of Auxiliary Feedwater Pumps	NOTE 3(a)	NA	All	B-98	10/--/85	10/--/85
94.	Additional Low Temperature Overpressure Protection for Light Water Reactors	NOTE 3(a)	NA	CE, <u>W</u>		06/25/90	06/25/90
99.	RCS/RHR Suction Line Valve Interlock on PWRs	NOTE 3(a)	NA	All	L-817	10/17/88	10/17/88
103.	Design for Probable Maximum Precipitation	NOTE 3(a)	All	All		10/19/89	10/19/89
118.	Tendon Anchorage Failure	NOTE 3(a)	All	All	NA	NA	07/--/90
124.	Auxiliary Feedwater System Reliability	NOTE 3(a)	All	All		TBD	TBD
128.	Electrical Power Reliability	NOTE 3(a)	All	All		04/29/91	04/29/91
130.	Essential Service Water Pump Failures at Multiplant	NOTE 3(a)	NA	All		09/19/91	09/19/91

Appendix B (Continued)

Action Plan Item/Issue No.	Title	Safety Priority/Status	Affected NSSS Vendor		Operating Plants- MPA No	Operating Plants - Effective Date	Future Plants- Effective Date
			BWR	PWR			
	Sites						
155	<u>Generic Concerns Arising from TMI-2 Cleanup</u>	-	-	-	-	-	-
155.1	More Realistic Source Term Assumptions	NOTE 3(a)	All	All	NA	NA	02/--/95
163.	Multiple Steam Generator Tube Leakage	HIGH	NA	All		TBD	TBD
177.	Vehicle Intrusion at TMI	NOTE 3(a)	All	All		08/01/94	08/01/94
186.	Potential Risk and Consequences of Heavy Load Drops in Nuclear Power Plants	CONTINUE	All	All		TBD	TBD
189.	Susceptibility of Ice Condenser Containments to Early Failure from Hydrogen Combustion During A Severe Accident	CONTINUE	All	All		TBD	TBD
191.	Assessment of Debris Accumulation on PWR Sump Performance	HIGH	NA	All		TBD	TBD
193.	BWR ECCS Suction Concerns	CONTINUE	All	NA		TBD	TBD
199.	Implications of Updated Probabilistic Seismic Hazard Estimates in Central and Eastern United States	CONTINUE	All	All		TBD	TBD
<u>HUMAN FACTORS ISSUES</u>							
<u>HF1</u>	<u>STAFFING AND QUALIFICATIONS</u>						
HF.1.1	Shift Staffing	NOTE 3(a)	All	All		01/--/84	01/--/84