

8

7

6

5

4

3

2

1

F

E

D

C

B


A

KEY NOTES:

1	DRINKING FOUNTAIN- ELKAY MODEL EMABFTL8WSLK
2	REFRIGERATOR
3	CONFERENCE TABLE (144" X 48")
4	BREAK ROOM TABLE (72" X 30")
5	TABLE (42" X 18")
6	TABLE (72" X 30")
7	4x8' WORK COUNTER W/OPEN SHELVING
8	BOOKCASE (60"L X 16"D X 78"H)
9	BOOKCASE (72"L X 16"D X 78"H)
10	BOOKCASE (24"L X 16"D X 78"H)
11	FRISK
12	MOBILE DRAWING HANGING RACK (43" X 27")
13	DESK (60" X 29 1/2")
14	NOT USED
15	NOT USED
16	WORKBENCH (144" X 24" X 6")
17	SMALL TOOL PEGBOARD
18	NOT USED
19	STORAGE SHELVES (60"W X 24"D X 72"H)
20	FIRE-RATED CABINET (23.25"W X 18"D X 64"H)
21	STORAGE CABINET (36" X 16")
22	VERTICAL FILE CABINET (18"W X 22"D X 52"H)
23	COMPUTER STATION (60" X 29 1/2")
24	WHITEBOARD (72"L X 48"H)
25	BULLETIN BOARD (96"L X 48" H)
26	ROLLER WINDOW SHADE-INTERIOR OF JAMBS
27	WHITEBOARD (96"L X 48"H)
28	BOOKCASE (36"W X 16"D X 78"H)
29	COPIER/PRINTER
30	LAVATORY- KOHLER K-2084-N-0 WITH AMERICAN STANDARD MODEL 6053.204.002 FAUCET
31	ADA WATER CLOSET- AMERICAN STANDARD MODEL 3043.528.020
32	STAINLESS STEEL DOUBLE BOWL KITCHEN SINK- AMERICAN STANDARD MODEL 22DB.6332283C.075
33	MOP SINK- MUSTEE MODEL 63M WITH CHICAGO FAUCETS 897-RCF FAUCET

NOTES

- SEE VFS-EMP-000-DWG-A-010 SHEET 1 FOR GENERAL NOTES, LEGEND AND ABBREVIATIONS.
- REFER TO ELECTRICAL DRAWINGS FOR EQUIPMENT IN ELECTRICAL ROOM 101
- DOORS, WALLS, AND WINDOWS BETWEEN PROCESS AND NON PROCESS ARE FIRE SEPARATION RATED
- FURNISHINGS ARE FOR ILLUSTRATION PURPOSES ONLY AND WILL VARY BASED ON OCCUPANT NEEDS.



WATF FURNISHINGS LAYOUT
SCALE: 1/4" = 1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST							

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY
S. MOORE	REVISED	VEOLIA
J. PIERCE	REVISED	VEOLIA
M. CORBIN	REVISED	VEOLIA
J. WILLIAMS	REVISED	VEOLIA
E. FLOYD	REVISED	VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
FURNISHINGS LAYOUT

VFS-EMP-000-DWG-A-100

SCALE: 1/4" = 1'-0" SHEET 6 OF 6

DWG NO VFS-EMP-000-DWG-A-100 SH 6 OF 6 REV E

LEGEND

- ROOM NUMBER
- DOOR NUMBER
- WALL TYPE
- WINDOW / OPENING NUMBER
- NEW WALL
- 1-HR RATED WALL
- LIGHTING FIXTURE, LED
- EXIT LIGHT
- LIGHTING FIXTURE, WALL MOUNT
- 2A-10B-C RATED FIRE EXTINGUISHER MOUNTED NO HIGHER THAN 40" A.F.F.
- TEMPERED GLASS
- NUMBER (DETAIL REFERENCE)
- SHEET NUMBER REFERENCE
- NUMBER (DETAIL REFERENCE) REFERENCE ON SAME SHEET AS DETAIL CALLOUT
- NUMBER (DETAIL REFERENCE) DRAWING NUMBER REFERENCE
- LETTER (SECTION/ELEVATION REFERENCE)
- DRAWING OR SHEET NUMBER REFERENCE
- METAL WALL PANEL
- COMBINATION EMERGENCY LIGHTING AND EXIT SIGN PER I.B.C./NFPA/IFC. (BATTERY BACK UP)
- EXTERIOR SIGNAGE LIGHTING
- EXTERIOR SECURITY LIGHT FIXTURE
- INDICATES ROOF DRAIN AND OVERFLOW
- INDICATES SLOPE
- 2 PORT CAT6 ETHERNET WALL PORT
- 2 PORT CAT6 ETHERNET FLOOR PORT
- 2'x4' ACOUSTICAL CEILING TILE
- INDICATES ROOF ELEVATION CHANGE
- METAL ROOF PANEL

ABBREVIATIONS

- | | | | |
|-------|-----------------------------------|-------|---------------------------------------|
| ACT | ACOUSTICAL CEILING TILE | MISC | MISCELLANEOUS |
| ADA | AMERICANS WITH DISABILITIES ACT | MTL | METAL |
| AFF | ABOVE FINISHED FLOOR | NIC | NOT IN CONTRACT |
| ALUM | ALUMINUM | NTS | NOT TO SCALE |
| ANDZ | ANODIZED | OF | OVERFLOW DRAIN |
| BOB | BOTTOM OF BEAM | OF | OWNER FURNISHED, CONTRACTOR INSTALLED |
| C/C | CENTER TO CENTER | OFCI | OWNER FURNISHED, OWNER INSTALLED |
| CFMS | COLD FORMED METAL STUD | OSB | ORIENTED STRAND BOARD |
| CJ | CONTROL JOINT | P-# | PAINT TYPE NUMBER |
| C.I. | CONTINUOUS INSULATIONS | PLM | PLASTIC LAMINATE |
| CLG | CEILING | PLN | PLAN |
| C-BRD | CEMENT BOARD | PLWD | PLYWOOD |
| CG | CORNER GUARD | PRE | PRE FINISHED |
| CLR | CLEAR | PT | PRESSURE TREATED |
| CMU | CONCRETE MASONRY UNIT | RBR | RUBBER |
| CONC | CONCRETE | RD | ROOF DRAIN |
| CONST | CONSTRUCTION | REFR | REFRIGERATOR |
| CONT | CONTINUOUS | RM | ROOM |
| CPT | CARPET | RO | ROUGH OPENING |
| CT | CERAMIC TILE | RWL | RAIN WATER LEADER |
| DS | DOWN SPOUT | S-TRD | STAIR TREAD |
| EIFS | EXTERIOR INSULATION FINISH SYSTEM | SAI | SOUND ATTENUATION INSULATION |
| ELEV | ELEVATION | SATC | SUSPENDED ACOUSTICAL TILE CEILING |
| ENAM | ENAMEL | SC | SOLID CORE |
| EQP | EQUIPMENT | SD | SOAP DISPENSER |
| EWC | ELECTRIC WATER COOLER | SF | SQUARE FEET |
| EXPD | EXPOSED | SHT | SHEET |
| FD | FLOOR DRAIN | SHT-V | SHEET VINYL |
| FE | FIRE EXTINGUISHER | SIM | SIMILAR |
| FEC | FIRE EXTINGUISHER CABINET | SLR | SEALER |
| FF | FINISHED FLOOR | SPEC | SPECIFICATION |
| FFIN | FACTORY FINISH | STL | STEEL |
| FS | FINISHED SURFACE | TBD | TO BE DETERMINED |
| GA | GAUGE | THK | THICKNESS |
| GALV | GALVANIZED | TPD | TOILET PAPER DISPENSER |
| GB | GRAB BAR | TOC | TOP OF CONCRETE |
| GWB | GYPNUM WALL BOARD | TYP | TYPICAL |
| HB | HOSE BIB | UNO | UNLESS NOTED OTHERWISE |
| HM | HOLLOW METAL | UR | URINAL |
| HORIZ | HORIZONTAL | UR | URINAL |
| HR | HOUR | VERT | VERTICAL |
| INSPN | INSPECTION | VCT | VINYL COMPOSITION TILE |
| LAV | LAVATORY | VGB | VERTICAL GRAB BAR |
| LS | LANDSCAPING | VIN | VINYL |
| MATL | MATERIAL | WC | WATER CLOSET |
| MAX | MAXIMUM | WD | WOOD |
| MCJ | MASONRY CONTROL JOINT | WH | WATER HEATER |
| MFRS | MANUFACTURERS | "X" | FIRE RESISTANT LABELED |
| MIN | MINIMUM | GWB | GWB |

BUILDING ENVELOPE NOTES

CLIMATE ZONE 5B

INSULATION VALUES:
 ROOF: R-25+ R-11 LINER SYSTEM WITH SPACER BLOCKS
 WALLS: R-19 CONTINUOUS INSULATION
 SLAB: R-10, 24 INCH MIN FROM TOP OF SLAB

OPENINGS:
 OPAQUE DOORS: U 0.37
 NON-SWING DOORS: R-4.75

VAPOR RETARDER: PROVIDE ON WARM SIDE OF THE WALLS, SEAL SEAMS.

AIR BARRIER: PROVIDE AIR BARRIER AT BUILDING ENVELOPE ON ALL WALLS, ROOFS, AND FLOORS.

BUILDING ENVELOPE: SEAL, CAULK GASKET AND/OR WEATHER SEAL ALL EXTERIOR PENETRATIONS.

BUILDING AIR INFILTRATION REQUIREMENT - PER WA 51-11C-40609 AIR INFILTRATION SHALL BE VERIFIED BY WHOLE BUILDING PRESSURIZATION TESTING CONDUCTED IN ACCORDANCE WITH ASTM E779 OR ASTM E1827 BY AN INDEPENDENT THIRD PARTY ENGAGED BY THE GENERAL CONTRACTOR. THE MEASURED AIR LEAKAGE RATE OF THE BUILDING ENVELOPE SHALL NOT EXCEED 0.40 CFM/FT² (2.0 L/S-M²) UNDER A PRESSURE DIFFERENTIAL OF 0.3 IN. WATER (75 PA), WITH THE CALCULATED SURFACE AREA BEING THE SUM OF THE ABOVE AND BELOW GRADE BUILDING ENVELOPE. A REPORT THAT INCLUDES THE TESTED SURFACE AREA, FLOOR AREA, AIR BY VOLUME, STORIES ABOVE GRADE, AND LEAKAGE RATES SHALL BE SUBMITTED TO THE CODE OFFICIAL AND THE BUILDING OWNER.

GENERAL NOTES (UNLESS OTHERWISE SPECIFIED)

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE 2015 INTERNATIONAL BUILDING CODE (IBC), NFPA 101, 2017 NATIONAL ELECTRIC CODE, UNIFORM PLUMBING CODE, AND LOCAL JURISDICTION REQUIREMENTS.
2. CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF SITE CONDITIONS, INSTALLATION STANDARDS, AND CONSTRUCTION CONDITIONS. FIELD VERIFY ALL NECESSARY DIMENSIONS. DISCREPANCIES BETWEEN SITE CONDITIONS AND THE CONSTRUCTION DRAWINGS SHALL BE CALLED TO THE ATTENTION OF THE OWNER'S REPRESENTATIVE. WORK DONE WITHOUT THE OWNER REPRESENTATIVE'S APPROVAL IS THE RESPONSIBILITY OF THE CONTRACTOR.
3. DRAWINGS MAY BE REDUCED, VERIFY SCALE.
4. THE CONTRACTOR ALONE SHALL BE RESPONSIBLE FOR SAFETY. THE CONTRACTOR SHALL PROVIDE ADEQUATE SAFEGUARDS, SAFETY DEVICES, AND PROTECTIVE EQUIPMENT, AND TAKE ANY OTHER NEEDED ACTIONS NECESSARY TO PROTECT THE LIFE, HEALTH AND SAFETY OF THE PUBLIC AND TO PROTECT PROPERTY IN CONNECTION WITH THE WORK COVERED BY THE CONTRACT.
5. REFER TO ELECTRICAL AND MECHANICAL DRAWINGS FOR ADDITIONAL INFORMATION PERTAINING TO EACH DISCIPLINE.
6. REFER TO PROJECT CONSTRUCTION SPECIFICATIONS FOR ADDITIONAL INFORMATION.
7. ALL METAL BUILDING DETAILS AND CALLOUTS ARE FOR REFERENCE ONLY. METAL BUILDING MANUFACTURER DETAILS SHALL SUPERCEDE DETAILS IN THIS SET.

CONCEPTUAL DESIGN



NAME	DATE	COMPANY
CL GREEN	10/2021	VEOLIA
M CORBIN		VEOLIA
S MOORE		VEOLIA
J WILSON		VEOLIA
F FLOYD		VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT FACILITY
NOTES AND LEGEND

FILE: VFS-EPM-000-DWG-A-010

SCALE: NONE SET SHEET 1 OF 2

DWG NO	TITLE	REF NUMBER	TITLE	REF	REV	DESCRIPTION	REV	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST	NEXT USED ON	REFERENCES							

VFS-EPM-000-DWG-A-010 SH 1 OF 2

CODE ANALYSIS:

GENERAL INFORMATION

AUTHORITY HAVING JURISDICTION: CITY OF CIMARRON
 CODE: IBC
 PROJECT ADDRESS: N/A
 ZONING:
 PROJECT DESCRIPTION:

PARKING REQUIRED:
 EV PARKING INFRASTRUCTURE: NO

CHAPTER 3
 OCCUPANCY CLASSIFICATION: F-2 (LOW HAZARD FACTORY)

CHAPTER 5
 ALLOWABLE HEIGHT (FT.), TABLE 504.3: 55 FT. (NON-SPRINKLERED)
 ALLOWABLE STORIES ABOVE GRADE, TABLE 504.4: F-2: 3 STORIES (NON-SPRINKLERED)

ALLOWABLE AREA (SQ. FT.), TABLE 506.2: F-2: 23,000 SQ. FT. (NON-SPRINKLERED)
 PER SECTION 507.3 BUILDING IS ALLOWED TO BE UNLIMITED AREA

ALLOWABLE AREA INCREASE, SECTION 506:
 $<A = (A + (NS \times I))>$
 $<W = (L1 \times w1 + L2 \times w2...)/ F>$
 $<I = (F/P - 0.25) W / 30>$

PROPOSED HEIGHT (FT.): 25'-8"
 PROPOSED STORIES ABOVE GRADE: 1 STORY
 PROPOSED AREA, PER FLOOR: 16,100
 PROPOSED TOTAL BUILDING AREA: 16,100
 REQUIRED OCCUPANCY SEPARATION, TABLE 508.4: PRE ENGINEERED MTL. BLDG.

CHAPTER 6
 CONSTRUCTION TYPE, TABLE 601: TYPE II-B CMU W/INTERIOR METAL STUDS WALLS
 EXTERIOR WALL FIRE RATING REQUIREMENT, TABLE 602: N/A, NOT REQUIRED


CHAPTER 7
 ALLOWED EXTERIOR WALL OPENINGS, TABLE 705.8: NO LIMIT
 PARAPET EXCEPTION, SECTION 705.11: NOT REQ'D, EXCEPTION 1

CHAPTER 9
 FIRE SPRINKLER SYSTEM REQUIRED, IBC SECTION 903/IEBC SECTION 904.2.2: NO
 FIRE SPRINKLER SYSTEM INSTALLED: N/A
 FIRE EXTINGUISHERS REQUIRED, SECTION 906: YES SEE EXIT PLAN
 FIRE ALARM SYSTEM, SECTION 907: YES
 IF REQUIRED, SYSTEM SHALL MEET NFPA 72 REQUIREMENTS

CHAPTER 10
 OCCUPANT LOAD, TABLE 1004.1.2:
 NON PROCESS OCCUPANCY: 41 OCCUPANTS
 F-2 PROCESS OCCUPANCY: 78 OCCUPANTS
 TOTAL BUILDING OCCUPANCY: 119 OCCUPANTS
 MEANS OF EGRESS CAPACITY, SECTION 1005:
 MEANS OF EGRESS COMPONENTS: B/M: 119 OCCUPANTS X 0.2" = 23.8" REQ'D WIDTH
 MEANS OF EGRESS, STAIRWAYS: N/A
 NUMBER OF EXITS, SECTION 1006:
 NON-PROCESS 41-49 = 1 EXIT REQ'D, 2 PROVIDED
 F-2 (PROCESS) 78-49 = 2 EXITS REQ'D, 7 PROVIDED
 (TOTAL OF 9 EXITS PROVIDED)

PANIC HARDWARE REQUIRED, SECTION 1010.1.10: NO
 EXIT SIGNS SHOWN ON PLANS, SECTION 1013: VFS-EMP-000-DWG-E-120 SHEET 1&2 (REFLECTED CEILING & LIGHTING PLAN)
 HANDRAIL TYPE, SECTION 1014.3:
 MAXIMUM EXIT TRAVEL DISTANCE, TABLE 1017.2: F-2: 300'-0" TRAVEL DISTANCE

CHAPTER 29
 MINIMUM NUMBER OF PLUMBING FIXTURES, TABLE 2902.1:
 OCCUPANCY CLASSIFICATION: F-2 (*USING REQUIREMENTS OF M OCCUPANCY) TOTAL
 OCCUPANTS (PER GENDER): OCCUPANTS: 119 / 2 = 60
 WATER CLOSETS:
 FEMALE: (1:100) = 1 REQ'D, 1 PROVIDED
 MALE: (1:100) = 1 REQ'D, 1 PROVIDED
 LAVATORIES:
 FEMALE: (1:100) = 1 REQ'D, 1 PROVIDED
 MALE: (1:100) = 1 REQ'D, 1 PROVIDED



LEGEND

1-HR FIRE RATED CORRIDOR WALLS

FIRE AND LIFE SAFETY PLAN
 SCALE: 3/32"=1'-0"

CONCEPTUAL DESIGN



NAME	DATE	COMMENTS
G GREEN	10/17/21	ISS
M CORBIN	10/25/21	ISS
S MOORE	11/15/21	ISS
J WILSON	11/15/21	ISS
E LLOYD	11/15/21	ISS


CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
 WESTERN AREA
 TREATMENT FACILITY
 CODE INFORMATION
 VFS-EPM-000-DWG-A-010

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		NEXT USED ON					
			REFERENCES					
				REVISIONS				

VFS-EPM-000-DWG-A-010 SH 2 OF 2 REV E

NOTE

- SEE VFS-EMP-000-DWG-A-010 SHEET 1 FOR GENERAL NOTES, LEGEND AND ABBREVIATIONS.
- SEE VFS-EMP-000-DWG-A-130 SHEET 1 FOR ASSEMBLY TYPES.



1 ENLARGED NON PROCESS AREA PLAN
 SH 1 SCALE: 1/4"=1'-0"



VEOLIA
 VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

NAME	DATE	COMPL.
V. DAVISON	10/20/12	DESIGN
J. PIERCE		USERS
M. CORBIN		DES
J. WILSON		USERS
E. LLOYD		USERS

CONCEPTUAL DESIGN
 CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
 WESTERN AREA
 TREATMENT FACILITY
 ARCHITECTURAL PLAN
 VFS-EMP-000-DWG-A-100
 SCALE AS SHOWN
 SHEET 2 OF 6

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		NEXT USED ON					

VFS-EMP-000-DWG-A-100 SH 2 OF 6 REV D

8

7

6

5

4

3


2

1




NOTE

- 1. SEE VFS-EMP-000-DWG-A-010 SHEET 1 FOR GENERAL NOTES, LEGEND AND ABBREVIATIONS.
- 2. CEILING IN PROCESS AREA IS 5/8" DENSGLOSS SHEATHING ON RESILIENT CHANNELS ATTACHED TO ROOF PURLINS AT 18" OC.
- 3. REFER TO ELECTRICAL DRAWINGS FOR LIGHT FIXTURE LAYOUT.



REFLECTED CEILING PLAN

SCALE: 1/8" = 1'-0"



CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
REFLECTED CEILING PLAN

VFS-EPM-000-DWG-A-100

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		NEXT USED ON					
			REFERENCES					
				REVISIONS				

NAME	DATE	DESCRIPTION
S. MOORE	10/20/23	ISSUED
L. PIERCE		ISSUED
M. CORBIN		ISSUED
L. WILSON		ISSUED
E. LLOYD		ISSUED


SCALE AS SHOWN	EST	SHEET 3	OF 6
----------------	-----	---------	------

VFS-EPM-000-DWG-A-100 SH. 3 OF 6 REV. E

8 7 6 5 4 3 2 1

NOTE

1. SEE VFS-EMP-000-DWG-A-010 SHEET 1 FOR GENERAL NOTES, LEGEND AND ABBREVIATIONS.
2. SEE ELECTRICAL DRAWINGS FOR LIGHT FIXTURE LAYOUT.
3. 9'-0" ACT CEILING IN CORRIDORS. BOTTOM OF JOISTS ABOVE (2'-0" ABOVE ACT CEILING) WILL HAVE 2 LAYERS 5/8" TYPE 'X' GWB APPLIED ABOVE CORRIDOR ONLY.



1 ENLARGED REFLECTED CEILING PLAN
SHEET 1 SCALE: 1/4"=1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV	DESCRIPTION	REV DATE	ENGR
	DRAWING TRACEABILITY LIST		REFERENCES				
					REVISIONS		

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY
V DAVISON	REVISED	VEOLIA
J PIERCE	ISSUED	VEOLIA
M CORBIN	ISSUED	VEOLIA
J WILLSON	ISSUED	VEOLIA
E LLOYD	ISSUED	VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
ENLARGED CEILING PLAN

VFS-EMP-000-DWG-A-100

SCALE AS SHOWN SHEET 4 OF 6

DWG NO VFS-EMP-000-DWG-A-100 SH 4 OF 6 (REV. D)

8

7

6

5

4

3

2


1




ROOF CALLOUTS:	
①	PRE-FINISHED METAL ROOF PANELS
②	GUTTER
③	WALL OUTLINE BELOW
④	SNOW / ICE RETENTION BAR TO BE INSTALLED ABOVE ALL SWINGING DOORS ALONG GRIDLINES 1 & 6
⑤	PREFINISHED METAL ROOF PANELS, TYP

NOTE

- SEE VFS-EIP-000-DWG-A-010 SHEET 1 FOR GENERAL NOTES, LEGEND AND ABBREVIATIONS.



ROOF PLAN
SCALE: 1/8" = 1'-0"



CONCEPTUAL DESIGN

VEOLIA
VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY
S. MOORE	10/10/15	VEOLIA
J. PIERCE		VEOLIA
M. CORBIN		VEOLIA
E. WELSON		VEOLIA
E. LLOYD		VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA
TREATMENT FACILITY
ROOF PLAN

VFS-EPM-000-DWG-A-100
SCALE AS SHOWN
SHEET 5 OF 6


DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							

DWG NO VFS-EPM-000-DWG-A-100 SHEET 5 OF 6 REV E

KEY NOTES:

1	DRINKING FOUNTAIN- ELKAY MODEL EMABFTL8WSLK
2	REFRIGERATOR
3	CONFERENCE TABLE (144" X 48")
4	BREAK ROOM TABLE (72" X 30")
5	TABLE (42" X 18")
6	TABLE (72" X 30")
7	4x8' WORK COUNTER W/OPEN SHELVING
8	BOOKCASE (60"L X 16"D X 78"H)
9	BOOKCASE (72"L X 16"D X 78"H)
10	BOOKCASE (24"L X 16"D X 78"H)
11	FRISK
12	MOBILE DRAWING HANGING RACK (43" X 27")
13	DESK (60" X 29 1/2")
14	NOT USED
15	NOT USED
16	WORKBENCH (144" X 24" X 6")
17	SMALL TOOL PEGBOARD
18	NOT USED
19	STORAGE SHELVES (60"W X 24"D X 72"H)
20	FIRE-RATED CABINET (23.25"W X 18"D X 64"H)
21	STORAGE CABINET (36" X 16")
22	VERTICAL FILE CABINET (18"W X 22"D X 52"H)
23	COMPUTER STATION (60" X 29 1/2")
24	WHITEBOARD (72"L X 48"H)
25	BULLETIN BOARD (96"L X 48" H)
26	ROLLER WINDOW SHADE-INTERIOR OF JAMBS
27	WHITEBOARD (96"L X 48"H)
28	BOOKCASE (36"W X 16"D X 78"H)
29	COPIER/PRINTER
30	LAVATORY- KOHLER K-2084-N-0 WITH AMERICAN STANDARD MODEL 6053.204.002 FAUCET
31	ADA WATER CLOSET- AMERICAN STANDARD MODEL 3043.528.020
32	STAINLESS STEEL DOUBLE BOWL KITCHEN SINK- AMERICAN STANDARD MODEL 22DB.6332283C.075
33	MOP SINK- MUSTEE MODEL 63M WITH CHICAGO FAUCETS 897-RCF FAUCET

- NOTES
- SEE VFS-EMP-000-DWG-A-010 SHEET 1 FOR GENERAL NOTES, LEGEND AND ABBREVIATIONS.
 - REFER TO ELECTRICAL DRAWINGS FOR EQUIPMENT IN ELECTRICAL ROOM 101
 - DOORS, WALLS, AND WINDOWS BETWEEN PROCESS AND NON PROCESS ARE FIRE SEPARATING RATED
 - FURNISHINGS ARE FOR ILLUSTRATION PURPOSES ONLY AND WILL VARY BASED ON OCCUPANT NEEDS.



WATF FURNISHINGS LAYOUT
SCALE: 1/4" = 1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES				

CONCEPTUAL DESIGN

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
FURNISHINGS LAYOUT

VFS-EMP-000-DWG-A-100

SCALE 1/4"=1'-0" EST SHEET 6 OF 6

VFS-EMP-000-DWG-A-100 SH. 6 OF 6 REV E

8

7

6

5

4


3

2


1

ELEVATION KEY NOTES:

1	PRE-FINISHED METAL WALL PANEL, TYP.
2	SECURITY LIGHTING OVER DOOR (PROVIDE EMERGENCY BACKUP POWER), TYP.
3	EXTERIOR LIGHT FIXTURE, TYP.
4	KNOX BOX
5	HOLLOW METAL DOOR, TYP.
6	24"x24" OPENING FOR FAN, REFER TO MECHANICAL
7	OVERHEAD DOOR
8	DOWNSPOUT
9	44"x26" DUCT PENETRATION
10	22"x26" COMPRESSOR DUCT PENETRATION (REFER TO MECHANICAL)
11	32"x20" COMPRESSOR DUCT PENETRATION (REFER TO MECHANICAL)
12	32"x18" DUCT PENETRATION
13	18"x26" DUCT PENETRATION
14	SNOW GUARD



A NORTH ELEVATION
A-100-1 SCALE: 1/8"=1'-0"



B WEST ELEVATION
A-100-1 SCALE: 1/8"=1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
BUILDING ELEVATIONS

VFS-EPM-000-DWG-A-110


SCALE AS SHOWN SHEET 1 OF 3

VFS-EPM-000-DWG-A-110 BH 1 OF 3 REV E


8 7 6 5 4 3 2 1

ELEVATION KEY NOTES:


1	PRE-FINISHED METAL WALL PANEL, TYP.
2	SECURITY LIGHTING OVER DOOR (PROVIDE EMERGENCY BACKUP POWER), TYP.
3	EXTERIOR LIGHT FIXTURE, TYP.
4	KNOX BOX
5	HOLLOW METAL DOOR, TYP.
6	24"x24" OPENING FOR FAN, REFER TO MECHANICAL
7	OVERHEAD DOOR
8	DOWNSPOUT
9	44"x26" DUCT PENETRATION
10	NOT USED
11	NOT USED
12	32"x18" DUCT PENETRATION
13	NOT USED
14	SNOW GUARD



C SOUTH ELEVATION
A-100-1 SCALE: 1/8"=1'-0"



D EAST ELEVATION
A-100-1 SCALE: 1/8"=1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	DESCRIPTION
	DRAWING TRACEABILITY LIST		REFERENCES						

CONCEPTUAL DESIGN

VEOLIA VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMMENTS
V. DAVISON	10/15/21	ISSUED
J. PIERCE		
M. CORBIN		
J. WILSON		
E. LLOYD		

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
BUILDING ELEVATIONS


DWG NO: VFS-EPM-000-DWG-A-110
SCALE: AS SHOWN
SHEET 2 OF 3

DWG NO: VFS-EPM-000-DWG-A-110 SH: 2 OF 3 REV: D


8 7 6 5 4 3 2 1

ELEVATION KEY NOTES:


①	PRE-ENGINEERED BUILDING FRAME, TYP.
②	BATT INSULATION, TYP.
③	8" WALL GIRT, TYP.
④	DENSGLOSS WALL SHEATHING, TYP.
⑤	HOLLOW METAL DOOR, TYP.
⑥	8" ROOF PURLIN, TYP.
⑦	ENDWALL BUILDING COLUMNS, TYP.



E SECTION
A-100-2 SCALE: 1/8"=1'-0"



F SECTION
A-100-2 SCALE: 1/8"=1'-0"



ENLARGED SECTION
A-110-3 SCALE: 1/2"=1'-0"

CONCEPTUAL DESIGN



NAME	DATE	COMPANY
V. DAVISON	10/1/13	VEOLIA
J. PIERCE		VEOLIA
M. CORBIN		VEOLIA
J. WILSON		VEOLIA
E. LLOYD		VEOLIA


CIMARRON
PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA
TREATMENT FACILITY
BUILDING SECTIONS

SCALE AS SHOWN
VFS-EPM-000-DWG-A-110
REV D


DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV BY DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST							
NEXT USED ON		REFERENCES		REVISIONS			

DWG NO VFS-EPM-000-DWG-A-110 SHEET 3 OF 3 REV D


8 7 6 5 4 3 2 1




ENLARGED RESTROOM PLAN
SCALE: 1/2" = 1'-0"




ELEVATION A



ELEVATION B




ELEVATION C



ELEVATION D

RESTROOM ELEVATION A
SCALE: 1/4" = 1'-0"




TYPICAL ADA RESTROOM PLAN
SCALE: 1/2" = 1'-0"

RESTROOM KEY NOTES:	
1	FIBER REINFORCED PLASTIC PANEL, SEE INTERIOR FINISH SCHEDULE SHEET VFS-EPM-100-DWG-A-130
2	FAUCET-AMERICAN STANDARD MODEL 6053-204-002
3	MIRROR
4	LAVATORY-KOHLER K-2084-N-D
5	TOILET SEAT COVER DISPENSER
6	S.S. GRAB BAR
7	ADA WATER CLOSET-AMERICAN STANDARD MODEL 3043.528.020
8	TOILET PAPER DISPENSER
9	DOOR
10	6" RESILIENT WALLBASE


NOTES:	
1	ALL FIXTURES TO MEET ADA REQUIREMENTS
2	CONTRACTOR TO SUBMIT ALL ADA CASEWORK AND HARDWARE FOR REVIEW PRIOR TO ORDERING.

KEYED NOTES:	
1	A.D.A. S.S. VERTICAL GRAB BAR
2	S.S. GRAB BAR, MOUNT W/ CENTERLINE AT 36" A.F.F.
3	FRP TO 5'-0" A.F.F. (VERIFY)
4	A.D.A. APPROVED TOILET (PROVIDE SUBMITTAL)
5	RECESSED TOILET TISSUE DISPENSER
6	A.D.A. PAPER DISPENSER
7	A.D.A. APPROVED MIRROR
8	A.D.A. APPROVED SINK


NOTE: CONTRACTOR TO PROVIDE SHOP DRAWINGS AND HARDWARE SUBMITTALS FOR REVIEW PRIOR TO ORDERING.




TYPICAL ADA RESTROOM SECTION
SCALE: 1/2" = 1'-0"




ELEVATION A



ELEVATION B



ELEVATION C



ELEVATION D

RESTROOM ELEVATION B
SCALE: 1/4" = 1'-0"

CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
265 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMMENTS
G GREEN	10/1/21	ISS
J PIERCE		VMPS
M CORBIN		VMPS
J WILSON		VMPS
ELLOYD		VMPS

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA
TREATMENT FACILITY
RESTROOM PLAN

VFS-EPM-000-DWG-A-120

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REVISIONS
	DRAWING TRACEABILITY LIST		NEXT USED ON		

VFS-EPM-000-DWG-A-120 SH 1 OF 2 REV D

DWG NO

SHEET

REV

DATE

BY

APP

8

7

6

5

4

3

2

1

GENERAL NOTES:

- CONTRACTOR SHALL HAVE A FULL SET OF THE CURRENT APPROVED CONSTRUCTION DOCUMENTS INCLUDING ANY APPROVED CHANGE DOCUMENTATION ON THE PROJECT AT ALL TIMES.
- CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OR PROPER RESETTING OF ALL EXISTING STRUCTURES, MONUMENTS AND FACILITIES UNLESS OTHERWISE NOTED ON THE PLANS. ANY EXISTING STRUCTURES, MONUMENTS, OR FACILITIES THAT ARE DAMAGED DURING CONSTRUCTION ACTIVITIES SHALL BE RESTORED TO A CONDITION EQUAL TO OR BETTER THAN ORIGINAL AT CONTRACTOR'S EXPENSE.
- ANY DEVIATION FROM THESE PLANS WITHOUT PRIOR APPROVAL FROM THE ENGINEER AND OWNER SHALL BE AT THE CONTRACTOR'S OWN RISK AND EXPENSE.
- SITE CONDITIONS SHALL BE CONFIRMED BY CONTRACTOR PRIOR TO STARTING WORK.
- IT IS CONTRACTOR'S RESPONSIBILITY TO CONTACT UTILITIES TO IDENTIFY UNDERGROUND UTILITIES PRIOR TO COMMENCING CONSTRUCTION ACTIVITIES.
- EROSION AND SEDIMENT CONTROL BMP'S INSTALLATION AND MAINTENANCE IS THE RESPONSIBILITY OF CONTRACTOR THROUGHOUT THE DURATION OF THE CONSTRUCTION ACTIVITIES.
- CONTRACTOR SHALL MAINTAIN CONSTRUCTION REDLINES TO DOCUMENT AS-BUILT CONDITION. REDLINES WILL BE AVAILABLE FOR ENGINEERING REVIEW AT ALL TIMES. AT THE COMPLETION OF CONSTRUCTION ACTIVITIES REDLINES SHALL BE DELIVERED TO ENGINEER.

ABBREVIATIONS:

- BMP BEST MANAGEMENT PRACTICES
- EL ELEVATION
- EP EDGE OF PAVEMENT
- FG FINISHED GRADE
- FF FINISHED FLOOR
- GB GRADE BREAK
- LF LINEAR FEET
- R RADIUS
- RG ROUGH GRADE
- TOE TOE OF SLOPE
- TOF TOP OF FOUNDATION
- TOP TOP OF SLOPE

LEGEND:

- E ELECTRICAL CONDUIT/CABLE
- I COMMUNICATION CONDUIT/CABLE
- FO FIBER OPTIC CABLE
- IS INJECTION SKID
- W DOMESTIC WATER LINE
- SAN SANITARY SEWER LINE
- X FENCE LINE
- GRADE BREAK
- ANGULAR STONE
- CONCRETE
- TRUEGRID PERMABLE PAVERS
- GRAVEL
- COMPACTED SOIL OR STRUCTURAL FILL
- O ELECTRICAL POLE
- DOMESTIC WATER VALVE
- BACK FLOW PREVENTER
- FIRE HYDRANT
- 7 SITE ELECTRICAL NOTES
- COMMUNICATION NOTES
- SANITARY SEWER NOTES
- △ DOMESTIC WATER NOTES

D

C

B

A

F

E

D

C

A

CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, VA 99352

NAME	DATE	COMPANY
S. MOORE	12/15/20	VEOLIA
J. PIERCE	12/15/20	VEOLIA
D. NELSON	12/15/20	VEOLIA
J. WILSON	12/15/20	VEOLIA
E. LLOYD	12/15/20	VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
CIVIL SYMBOLS, NOTES
AND ABBREVIATIONS

VFS-EPM-000-DWG-C-101

DWG NO	TITLE	REF NUMBER	TITLE	WHO	REV NO	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REV REL		REVISIONS				

VFS-EPM-000-DWG-C-101 SH 1 OF 1 REV C

8

7

6

5

4

3

2

1

SCALE NONE EST SHEET 1 OF 1

8

7

6

5

4

3

2

1

F

E

D

C

B

A

F

E

D


C

B

A

GENERAL NOTES:

- 1. SEE BMCD-GWREMCD-C006 FOR WATF GRADING PLAN AND LAYOUT.
- 2. SEE VFS-EPM-000-DWG-C-113 FOR SITE UTILITY PLAN.
- 3. SEE VFS-EPM-000-DWG-S-101 FOR STRUCTURAL NOTES.





TRUEGRID PRO NOTES:

- 1. FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF TRUEGRID PRODUCT
- 2. USE 5/8" TO 3/4" AGGREGATE FOR GRAVEL FILL-IN OF GRID.

TRUEGRID PRO PAVING SECTION A

SCALE: NONE



SITE PLAN
SCALE: 1" = 20'-0"

CONCEPTUAL DESIGN



NAME	DATE	COMPANY
S. MOORE	11/15/18	VEOLIA
J. PIERCE	11/15/18	VEOLIA
D. NELSON	11/15/18	VEOLIA
J. WILSON	11/15/18	VEOLIA
F. LLOYD	11/15/18	VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA
TREATMENT FACILITY
SITE PLAN

VFS-EPM-000-DWG-C-110

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							

VFS-EPM-000-DWG-C-110 SH 1 OF 1 REV J

8

7

6


5

4

3

2

1



- GENERAL NOTES:**
- CONSTRUCTION OF ALL SITE UTILITIES SHALL CONFORM TO LOCAL JURISDICTION REQUIREMENTS AND APPROVED CONSTRUCTION SPECIFICATIONS.
 - SEE VFS-EPM-000-DWG-C-101 FOR GENERAL NOTES, LEGEND, AND ABBREVIATIONS.

- SITE ELECTRICAL/COMMS/SECURITY NOTES:**
- SEE VFS-EPM-000-DWG-E-112 FOR ELECTRICAL SITE PLAN.
 - SEE VFS-EPM-000-DWG-J-111 FOR SECURITY SITE PLAN.

- SANITARY SEWER NOTES:**
- CONNECT TO INTERIOR PLUMBING LINE. INSTALL CLEANOUT. SEE VFS-EPM-000-DWG-P-100 FOR FURTHER DETAILS.
 - INSTALL 3" SANITARY SEWER AT A MINIMUM SLOPE OF 2%.
 - INSTALL SANITARY SEWER LINE FOR CONTINUATION TO SEPTIC SYSTEM. CLEANOUT AND LOCATION OF SEPTIC SYSTEM BY OTHERS.

- DOMESTIC WATER NOTES:**
- 1 DOMESTIC WATER FROM WATER METER TO VALVE BY OTHERS. POINT OF CONNECTION AT VALVE FLANGE.
 - 2 NOT USED.
 - 3 INSTALL 160 LF OF 3" DOMESTIC WATER SERVICE. ALL JOINTS TO BE FULLY RESTRAINED.
 - 4 STUB DOMESTIC WATER AT BUILDING. SEE VFS-EPM-000-DWG-P-100 FOR FURTHER DETAILS.

0 20 40 Feet
SITE PLAN
 SCALE: 1" = 20'-0"

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

NAME	DATE	COMPANY
S. MOORE	REVISION	VNSFS
J. PIERCE	REVISION	VNSFS
D. NELSON	REVISION	VNSFS
B. ROBERTSON	REVISION	VNSFS
J. WILSON	REVISION	VNSFS
E. LLOYD	REVISION	VNSFS

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
 TREATMENT FACILITY
 SITE UTILITY PLAN

DWG NO	TITLE	REF NUMBER	TITLE	REF NUMBER	TITLE	REF NUMBER	TITLE	REF NUMBER	TITLE	REF NUMBER	TITLE
DRAWING TRACEABILITY LIST											
NEXT USED ON											
REVISIONS											
SCALE AS SHOWN											
SHEET 1 OF 1											



DWG NO	TITLE	REF NUMBER	TITLE	REF NUMBER	TITLE	REF NUMBER	TITLE	REF NUMBER	TITLE	REF NUMBER	TITLE
DRAWING TRACEABILITY LIST											
NEXT USED ON											
REVISIONS											
SCALE AS SHOWN											
SHEET 1 OF 1											

VFS-EPM-000-DWG-C-113 SH 1 OF 1 REV H

8 7 6 5 4 3 2 1

F
E
D
C
B
A

F
E
D
C
B
A



CONCEPTUAL DESIGN

VEOLIA
 VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

NAME	DATE	COMPANY	REV
S. MOORE	11/15/18	VEOLIA	1
D. NELSON	11/15/18	VEOLIA	2
J. PIERCE	11/15/18	VEOLIA	3
J. WILSON	11/15/18	VEOLIA	4
E. ELLOYD	11/15/18	VEOLIA	5

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA
 TREATMENT FACILITY
 ELEVATIONS

SCALE AS SHOWN



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	BY	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							

VFS-EPM-000-DWG-C-130 SHEET 1 OF 2 REV D

8 7 6 5 4 3 2 1

8

7

6

5

4

3

2

1

F

E

D

C

B

A

F

E

D

C


REV D

SH


2 OF 2

A


DWG NO
VFS-EPM-100-DWG-C-130



C NORTH ELEVATION
SCALE: 1/8"=1'-0"



D SOUTH ELEVATION
SCALE: 1/8"=1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	BY	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

DESIGNED BY	S. MOORE	DATE	01/13/2016
DRAWN BY	D. NELSON	DATE	01/13/2016
CHECKED BY	J. PIERCE	DATE	01/13/2016
APPROVED BY	J. WILSON	DATE	01/13/2016
PROJECT MANAGER	E. LLOYD	DATE	01/13/2016

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
ELEVATIONS

DWG NO: VFS-EPM-000-DWG-C-130


SCALE AS SHOWN

SHEET 2 OF 2


8 7 6 5 4 3 2 1

GENERAL NOTES:


- SEE VFS-EPM-000-DWG-C-101 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.




1 CHAIN-LINK FENCE WITH GATE DETAIL
C-110 SCALE: NONE



2 CHAIN-LINK FENCE WITH PERSONNEL GATE DETAIL
C-110 SCALE: NONE





BOLLARD DETAIL



REMOVABLE BOLLARD DETAIL

3 BOLLARD DETAILS
C-110 SCALE: NONE



A SECTION
SCALE: NONE

(CURB ONLY REQUIRED IN LOCATIONS INDICATED ON CIVIL LAYOUTS)

4 MISCELLANEOUS EQUIPMENT PAD
C-110 SCALE: NONE

CONCEPTUAL DESIGN

VEOLIA
VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME		DATE	STATUS
S. MOORE	DESIGNED	10/1/20	VMG
V. DAVISON	DRAWN		VMG
D. NELSON	CHECKED		VMG
J. WILSON	APPROVED		VMG
M. MOORE			VMG
E. LLOYD			VMG

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

CIVIL DETAILS

DWG NO	TITLE	REF NUMBER	TITLE	INFO	REV	DATE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES								




SCALE: NONE SHEET 1 OF 2

8 7 6 5 4 3 2 1

8 7 6 5 4 3 2 1

GENERAL NOTES:

- SEE VFS-EPM-000-DWG-C-101 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.



5 TRASH ENCLOSURE DETAIL
SCALE: NONE

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMMENTS
S. MOORE	1/21/2015	ISSUE 1
V. DAVISON		ISSUE 2
D. NELSON		ISSUE 3
J. WILSON		ISSUE 4
E. ELLOYD		ISSUE 5

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

CIVIL DETAILS

DWG NO: VFS-EPM-000-DWG-C-150

SCALE: NONE


SHEET 2 OF 2

DWG NO	TITLE	REF NUMBER	TITLE	WFO	REV NO	DESCRIPTION	REV BY	DATE	EXOR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							


VFS-EPM-000-DWG-C-150 SH 2 OF 2 REV. C

8 7 6 5 4 3 2 1

LINES:




SYMBOLS: (CONTINUED)



ABBREVIATIONS:

- A AMPERES
- BA1 BURIAL AREA 1
- CBL CABLE
- CKT CIRCUIT
- CTRL CONTROL
- DP DISTRIBUTION PANEL
- DS DISCONNECT SWITCH
- EGC EQUIPMENT GROUNDING CONDUCTOR
- FACP FIRE ALARM CONTROL PANEL
- F.O. FIBER OPTIC
- G GROUND
- GEC GROUNDING ELECTRODE CONDUCTOR
- GES GROUNDING ELECTRODE SYSTEM
- GFCI GROUND FAULT CIRCUIT INTERRUPTER
- GFEP GROUND FAULT EQUIPMENT PROTECTOR
- GND GROUNDING CONDUCTOR
- HMI HUMAN MACHINE INTERFACE
- HP HORSE POWER
- HVAC HEATING, VENTILATION & AIR CONDITIONING
- HZ HERTZ
- I/O INPUT/OUTPUT
- IX ION EXCHANGE
- KV KILO-VOLT
- KVA KILO-VOLT AMPERES
- KW KILO-WATT
- KWH KILO-WATT HOUR
- LED LIGHT EMITTING DIODE
- LP LIGHTING PANEL
- LSI LONG SHORT INSTANTANEOUS
- LSIG LONG SHORT INSTANTANEOUS GROUND FAULT
- MCC MOTOR CONTROL CENTER
- MLO MAIN LUGS ONLY
- N NEUTRAL
- NEC NATIONAL ELECTRICAL CODE
- P PUMP/POLE BREAKER
- PH PHASE
- PLC PROGRAMMABLE LOGIC CONTROLLER
- PLG PLUG
- PP POWER PANEL
- PWR POWER
- RCPT RECEPTACLE
- SKD SKID
- SPD SURGE PROTECTIVE DEVICE
- SWBD SWITCHBOARD
- V VOLTS
- VA VOLT AMPERES
- VFD VARIABLE FREQUENCY DRIVE
- W WATT/WIRE
- WATF WESTERN AREA TREATMENT FACILITY
- WP WEATHERPROOF
- XFMR TRANSFORMER
- XO TRANSFORMER SECONDARY NEUTRAL


INSTRUMENT/FUNCTION SYMBOLS:



GENERAL NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE, 2017 EDITION.

SYMBOLS:



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISONS						

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY
S. MOORE	11/15/23	VEOLIA
D. KING	11/15/23	VEOLIA
J. PIERCE	11/15/23	VEOLIA
R. JENSEN	11/15/23	VEOLIA
E. ELLOYD	11/15/23	VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WATF ELECTRICAL
SYMBOLS, NOTES, AND
ABBREVIATIONS

SCALE	NONE	EST	SHEET	1	OF	1
-------	------	-----	-------	---	----	---

VFS-EPM-000-DWG-E-101 SH 1 OF 1 REV C

8 7 6 5 4 3 2 1


ELECTRICAL LOAD SUMMARY:

	CONNECTED LOAD	LOAD FACTOR	DESIGN LOAD
LARGEST KVA MOTOR	43.2 KVA	X 1.25	= 54 KVA
REMAINING MOTORS	259.8 KVA	(NEC 430.24)	= 259.8 KVA
GENERAL LOADS	78.7 KVA	(NEC 215.2)	= 78.7 KVA
RECEPTACLES	14.2 KVA	(NEC 220.44)	= 12.1 KVA
HVAC & HEATING	248.6 KVA	(NEC 220.60)	= 185.9 KVA
LIGHTS	8.6 KVA	X 1.25	= 10.8 KVA
TOTAL DESIGN LOAD			= 601.3 KVA, 723.3 AMPS

GENERAL NOTES:

- SEE VFS-EPM-000-DWG-E-101 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.
- SEE DRAWING BMCD-GWREMED-E101 FOR MCC-1 SINGLE LINE DIAGRAM.
- SEE DRAWING VFS-EPM-000-DWG-E-140 FOR PANEL SCHEDULE CIRCUIT ASSIGNMENTS.
- CURRENT TRANSFORMER METERING CABINET SHALL MEET OG&E UNDERGROUND STANDARD U765.

F
E
D
C
B
A



WESTERN AREA TREATMENT FACILITY SINGLE LINE DIAGRAM
SCALE: NOT TO SCALE

CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY
D. KING	11/11/10	VEOLIA
D. KING		VEOLIA
S. MOORE		VEOLIA
R. JENSEN		VEOLIA
M. ELLOYD		VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA TREATMENT FACILITY SINGLE LINE DIAGRAM

SCALE: NONE
SHEET 1 OF 1

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	DESCRIPTION
	DRAWING TRACEABILITY LIST		REFERENCES						

8 7 6 5 4 3 2 1

8

7

6

5

4

3

2

1

GENERAL NOTES:

1. GROUNDING SHALL BE IN ACCORDANCE WITH THE 2017 NATIONAL ELECTRICAL CODE.
2. SEE SINGLE LINE DIAGRAM DRAWINGS FOR SIZES OF NEUTRAL CONDUCTORS AND EQUIPMENT GROUNDING CONDUCTORS (EGC).
3. INSTALL GROUNDING ELECTRODE CONDUCTORS, SIZED BASED ON NEC TABLE 250.66 USING THE SERVICE PHASE CONDUCTOR EQUIVALENT SIZE, BUT NOT SMALLER THAN #4 AWG.
4. INSTALL BONDING JUMBER THAT IS SIZED BASED ON NEC TABLE 250.66 USING THE LARGEST SERVICE OR SEPARATELY DERIVED SYSTEM PHASE CONDUCTOR.
5. INSTALL GROUNDING ELECTRODE CONDUCTOR (GEC) THAT IS SIZED BASED ON NEC TABLE 250.66 USING THE SEPARATELY DERIVED SYSTEM PHASE CONDUCTOR SIZE.
6. INSTALL BONDING CONDUCTOR THAT IS SIZED BASED ON NEC TABLE 250.66 USING THE SERVICE PHASE CONDUCTOR SIZE.
7. IRREVERSIBLE COMPRESSION CONNECTOR OR EXOTHERMIC WELD.
8. INSTALL MAIN GROUND ELECTRODE GROUND BAR FOR SINGLE POINT GROUNDING. LOCATE AT AN ACCESSIBLE AND VISIBLE POINT NEAR THE SERVICE ENTRANCE EQUIPMENT. MAKE CONNECTIONS TO THE GROUND BAR USING TWO-HOLE COMPRESSION SPADE LUGS THAT MEET IEEE 837 REQUIREMENTS.
9. LOW VOLTAGE GROUNDING AT PAD-MOUNTED UTILITY TRANSFORMER.
10. CONNECTION OF GROUNDING ELECTRODE SYSTEM TO MAIN GROUNDING ELECTRODE GROUND BAR.
11. GROUNDING CONNECTION TO EXTERIOR PAD-MOUNTED ELECTRICAL EQUIPMENT. SEE GROUNDING PLAN FOR LOCATIONS.

F

F

E

E

D

D

C


C

B

B

A

A



WATF GROUNDING DIAGRAM

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richard, IA 59352

NAME	DATE	COMPANY	CIMARRON PUMP AND TREAT SYSTEM PROJECT WESTERN AREA TREATMENT FACILITY GROUNDING DIAGRAM
DESIGNED BY	18-03-11	VEOLIA	
CHECKED BY		VEOLIA	
PROJECT MANAGER		VEOLIA	
REVISIONS		VEOLIA	

DWG NO	TITLE	REF NUMBER	TITLE	MFR	REV	DATE	DESCRIPTION	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES				REVISIONS		

SCALE: NONE EST SHEET 1 OF 1

VFS-EPM-000-DWG-E-111 SH 1 OF 1 REV B

8

7

6


5


4


3

2

1



- GENERAL NOTES:**
- SEE VFS-EPM-000-DWG-E-101 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.
 - SEE DRAWING VFS-EPM-000-DWG-E-113 FOR UNDERGROUND CONDUIT PLAN.
 - CURRENT TRANSFORMER (CT) METERING CABINET SHALL MEET OG&E UNDERGROUND STANDARD U765. CT CABINET WIRING SHALL BE IN ACCORDANCE WITH DIAGRAM U765.1.
 -  PULL BOX FOR WELL FIELD INSTRUMENTATION THAT CONNECTS TO INJECTION SKID.



ELECTRICAL SITE PLAN
SCALE: 1"=10'-0"

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	BY	DATE	DESCRIPTION
DRAWING TRACEABILITY LIST		REFERENCES		REV		REVISIONS			

CONCEPTUAL DESIGN

VEOLIA


VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, VA 99352

<table border="1"> <thead> <tr> <th>NAME</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr><td>S. MOORE</td><td>08/02/23</td><td>ISSUED</td></tr> <tr><td>J. PIERCE</td><td>08/02/23</td><td>ISSUED</td></tr> <tr><td>D. KING</td><td>08/02/23</td><td>ISSUED</td></tr> <tr><td>J. WILSON</td><td>08/02/23</td><td>ISSUED</td></tr> <tr><td>E. ELLOYD</td><td>08/02/23</td><td>ISSUED</td></tr> </tbody> </table>	NAME	DATE	DESCRIPTION	S. MOORE	08/02/23	ISSUED	J. PIERCE	08/02/23	ISSUED	D. KING	08/02/23	ISSUED	J. WILSON	08/02/23	ISSUED	E. ELLOYD	08/02/23	ISSUED	<p>CIMARRON PUMP AND TREAT SYSTEM PROJECT</p> <p>WESTERN AREA TREATMENT FACILITY</p> <p>ELECTRICAL SITE PLAN</p>
NAME	DATE	DESCRIPTION																	
S. MOORE	08/02/23	ISSUED																	
J. PIERCE	08/02/23	ISSUED																	
D. KING	08/02/23	ISSUED																	
J. WILSON	08/02/23	ISSUED																	
E. ELLOYD	08/02/23	ISSUED																	
<table border="1"> <thead> <tr> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td>F</td> <td>08/02/23</td> <td>ISSUED</td> </tr> </tbody> </table>	REV	DATE	DESCRIPTION	F	08/02/23	ISSUED	<table border="1"> <tr> <td>DWG NO</td> <td>VFS-EPM-000-DWG-E-112</td> <td>REV</td> <td>E</td> </tr> <tr> <td>SCALE</td> <td>AS SHOWN</td> <td>SHEET</td> <td>1 OF 1</td> </tr> </table>	DWG NO	VFS-EPM-000-DWG-E-112	REV	E	SCALE	AS SHOWN	SHEET	1 OF 1				
REV	DATE	DESCRIPTION																	
F	08/02/23	ISSUED																	
DWG NO	VFS-EPM-000-DWG-E-112	REV	E																
SCALE	AS SHOWN	SHEET	1 OF 1																


VFS-EPM-000-DWG-E-112 SH 1 OF 1 REV E

GENERAL NOTES:

1. SEE VFS-EPM-000-DWG-E-141 FOR CONDUIT SCHEDULE.
2. SEE DRAWING BMCD-GWREMEDIATION-E101 FOR MCC-1 SINGLE LINE DIAGRAM.
3. SEE DRAWING VFS-EPM-000-DWG-E-115 FOR CIRCUIT ASSIGNMENTS.
4. CONDUIT ROUTING IS SHOWN DIAGRAMMATICALLY. FIELD ROUTE AS REQUIRED TO AVOID INTERFERENCES WITH STRUCTURAL FOUNDATIONS. INSTALL CONDUIT SHOWN PRIOR TO POURING CONCRETE.
5. MINIMUM CONDUIT DEPTH SHALL BE PER NEC REQUIREMENTS. COORDINATE UNDERGROUND CONDUIT INSTALLATION DEPTHS TO AVOID INTERFERENCES AT INTERSECTIONS SHOWN.
6. TRANSITION PVC CONDUIT BELOW GRADE TO RMC ABOVE GRADE USING 90 DEGREE RMC SWEEPS.



ELECTRICAL UNDERGROUND CONDUIT PLAN
SCALE: 1" = 10'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST										
NEXT USED ON										
REVISIONS										

CONCEPTUAL DESIGN

VEOLIA
VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT FACILITY UNDERGROUND CONDUIT PLAN

NAME	DATE	COMPANY
S. MOORE	8/20/13	VEOLIA
J. PIERCE	8/20/13	VEOLIA
D. KING	8/20/13	VEOLIA
J. WILSON	8/20/13	VEOLIA
E. ELLOYD	8/20/13	VEOLIA

REV	DATE	DESCRIPTION
F	8/20/13	VFS-EPM-000-DWG-E-113

SCALE AS SHOWN | SHEET 1 OF 1

VFS-EPM-000-DWG-E-113 SH 1 OF 1 REV E

8

7

6

5

4


3

2

1

GENERAL NOTES:

- SEE VFS-EPM-000-DWG-E-101 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.
- BUILDING GROUNDING ELECTRODE SYSTEM IS COMPRISED OF CONCRETE-EMBEDDED REBAR BONDED TOGETHER.
- ALL GROUNDING SYSTEM CONDUCTORS ARE #4/0 AWG COPPER UNLESS OTHERWISE SPECIFIED.
- BOND ALL METAL WATER PIPES WITHIN 5 FEET OF SERVICE ENTRANCE TO GROUNDING ELECTRODE SYSTEM.
- TIE 1/2 INCH MINIMUM DIAMETER EMBEDDED REBAR SECTIONS TOGETHER USING STEEL WIRE TIES OR WELDING TO FORM A CONTINUOUS GROUNDING ELECTRODE.
- BOND EVERY OTHER STEEL COLUMN TO GROUNDING ELECTRODE SYSTEM.
- INSTALL MAIN GROUNDING ELECTRODE GROUND BAR IN APPROXIMATE LOCATION SHOWN. CONNECT TO GROUNDING ELECTRODE SYSTEM.
- PROVIDE 5 FEET OF GROUNDING ELECTRODE CONDUCTOR ABOVE FINISHED FLOOR FOR BONDING TO MAIN GROUNDING ELECTRODE GROUND BAR AND MINI POWER CENTERS.
- REBAR BONDED TOGETHER IN CONCRETE SLAB.
- INSTALL GROUNDING PLATES IN APPROXIMATE LOCATION SHOWN AND BOND TO GROUNDING ELECTRODE SYSTEM.
- ALL LIGHTNING PROTECTION SYSTEM COUNTERPOISE CONDUCTORS ARE #2 AWG UNLESS OTHERWISE SPECIFIED.
- BOND LIGHTNING PROTECTION SYSTEM COUNTERPOISE TO GROUNDING ELECTRODE SYSTEM.
- CONNECT LIGHTNING PROTECTION SYSTEM DOWN CONDUCTORS TO COUNTERPOISE. SEE SHEET E-118 FOR LIGHTNING PROTECTION SYSTEM AIR TERMINAL LAYOUT.
- INSTALL LIGHTNING PROTECTION SYSTEM GROUND RING (COUNTERPOISE) AROUND THE PERIMETER OF THE BUILDING FOUNDATION. COUNTERPOISE SHALL BE INSTALLED A MINIMUM OF 3'-0" BELOW GRADE, A MINIMUM OF 5'-0" FROM THE FOUNDATION FOOTING AND A MINIMUM OF 6'-0" FROM ANY ELECTRICAL SYSTEM OR COMMUNICATION SYSTEM GROUND ELECTRODE.



GROUNDING PLAN
SCALE: 1/8" = 1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	BY	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS						

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, VA 99352

NAME	DATE	COMPANY
S. MOORE	03/10/2011	VEOLIA
J. PIERCE		VEOLIA
D. KING		VEOLIA
L. WILSON		VEOLIA
E. LLOYD		VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
GROUNDING PLAN

VFS-EPM-000-DWG-E-114


SCALE: SHOWN
SHEET 1 OF 3

VFS-EPM-000-DWG-E-114 SH 1 OF 3 REV E

8 7 6 5 4 3 2 1

F
E
D
C
B
A

- NOTES**
1. GROUNDING SHALL BE IN ACCORDANCE WITH THE 2017 NATIONAL ELECTRICAL CODE.
 2. INSTALL #4/0 AWG BARE STRANDED COPPER A MINIMUM OF 30" UNDERGROUND FOR HIGH VOLTAGE GROUND RING, AT LEAST 36" FROM EDGE OF TRANSFORMER.
 3. INSTALL 8' LONG UL LISTED GROUND RODS IN LOCATIONS SHOWN. CONNECT GROUND RING TO GROUND ROD USING UL LISTED CLAMP SUITABLE FOR DIRECT BURIAL OR EXOTHERMAL WELD.
 4. PROVIDE A MINIMUM SEPARATION OF 20' FROM SECONDARY GROUNDING ELECTRODE TO HIGH VOLTAGE GROUND RING.



1 ENLARGED GROUNDING PLAN
1 SCALE: 3/4" = 1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES					
				REVISIONS				

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY
D KING	11/15/23	VEOLIA
D KING		VEOLIA
S MIDORE		VEOLIA
R JEFFERSON		VEOLIA
E LLOYD		VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
ENLARGED GROUNDING PLAN

VFS-EPM-000-DWG-E-114

SCALE SHOWN: 1/8" = 1'-0" SHEET 2 OF 3

VFS-EPM-000-DWG-E-114 SH 2 OF 3 REV. C

8

7

6

5

4




3

2

1

NOTES:

- 1. SEE SHEET 1 FOR GENERAL NOTES.



CONCEPTUAL DESIGN

VEOLIA VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY
D KING	10/1/14	VEOLIA
D KING	10/1/14	VEOLIA
S MOORE	10/1/14	VEOLIA
R JENSON	10/1/14	VEOLIA
E LLOYD	10/1/14	VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
GROUNDING DETAILS

VEOLIA PROJECT NUMBER: VFS-EPM-000-DWG-E-114

SCALE: AS SHOWN


SHEET 3 OF 3

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	ENR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS			


DWG NO VFS-EPM-000-DWG-E-114 ISH 3 OF 3 REV C

GENERAL NOTES:

1. SEE VFS-EPM-000-DWG-E-101 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.
2. REFER TO SINGLE LINE DIAGRAM VFS-EPM-000-DWG-E-110 FOR CONNECTION DETAILS.
3. HEAT TRACE CIRCUIT.
4. POWER FOR PUMP ENCLOSURE FREEZE PROTECTION HEATER.



POWER PLAN
SCALE: 1/8" = 1'-0"



CONCEPTUAL DESIGN

VEOLIA


VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>NAME</th> <th>DATE</th> <th>COMPANY</th> </tr> </thead> <tbody> <tr> <td>S. MOORE</td> <td>04/20/13</td> <td>VEOLIA</td> </tr> <tr> <td>J. PIERCE</td> <td></td> <td>VEOLIA</td> </tr> <tr> <td>D. KING</td> <td></td> <td>VEOLIA</td> </tr> <tr> <td>J. WILSON</td> <td></td> <td>VEOLIA</td> </tr> <tr> <td>E. LLOYD</td> <td></td> <td>VEOLIA</td> </tr> </tbody> </table>	NAME	DATE	COMPANY	S. MOORE	04/20/13	VEOLIA	J. PIERCE		VEOLIA	D. KING		VEOLIA	J. WILSON		VEOLIA	E. LLOYD		VEOLIA	<p>CIMARRON PUMP AND TREAT SYSTEM PROJECT</p> <p>WESTERN AREA TREATMENT FACILITY BUILDING POWER PLAN</p> <p>VFS-EPM-000-DWG-E-115</p>																					
NAME	DATE	COMPANY																																						
S. MOORE	04/20/13	VEOLIA																																						
J. PIERCE		VEOLIA																																						
D. KING		VEOLIA																																						
J. WILSON		VEOLIA																																						
E. LLOYD		VEOLIA																																						
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>DWG NO</th> <th>TITLE</th> <th>REF NUMBER</th> <th>TITLE</th> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td></td> <td>DRAWING TRACEABILITY LIST</td> <td></td> <td>REFERENCES</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>	DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	DESCRIPTION		DRAWING TRACEABILITY LIST		REFERENCES																	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> </tr> </tbody> </table>	REV	DATE	DESCRIPTION						
DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	DESCRIPTION																															
	DRAWING TRACEABILITY LIST		REFERENCES																																					
REV	DATE	DESCRIPTION																																						
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>SCALE</th> <th>SHOWN</th> <th>EXT</th> <th>SHEET</th> <th>OF</th> <th>3</th> </tr> </thead> <tbody> <tr> <td>F</td> <td></td> <td></td> <td>1</td> <td></td> <td>3</td> </tr> </tbody> </table>	SCALE	SHOWN	EXT	SHEET	OF	3	F			1		3	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> <td></td> </tr> </tbody> </table>	REV	DATE	DESCRIPTION																								
SCALE	SHOWN	EXT	SHEET	OF	3																																			
F			1		3																																			
REV	DATE	DESCRIPTION																																						

VFS-EPM-000-DWG-E-115 SH 1 OF 3 REV E

NOTES:

1. SEE SHEET 1 FOR GENERAL NOTES.



1 ENLARGED POWER PLAN
SHEET-1 SCALE: 3/16"=1'-0"



CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY	SCALE	DWG NO	REV	BY	CHKD	COMPANY
S. MOORE	11/15/18	VEOLIA	3/16"=1'-0"	F	1			
J. PIERCE								
D. KING								
J. W. SON								
E. FLOYD								

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
BUILDING POWER PLAN

VFS-EPM-000-DWG-E-115

SCALE SHOWN: 3/16"=1'-0" SHEET 2 OF 3

REF NUMBER	TITLE	REV	DATE	BY	CHKD	COMPANY


DWG NO	TITLE	REV	DATE	BY	CHKD	COMPANY

VFS-EPM-000-DWG-E-115 SH. 2 OF 3 REV. E

8 7 6 5 4 3 2 1

NOTES:

- SEE SHEET 1 FOR GENERAL NOTES.



2 ENLARGED POWER PLAN
SHEET-1 SCALE: 3/16"=1'-0"



CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY							
DESIGNED BY S. MOORE	10/13/11	VEOLIA							
CHECKED BY J. PIERCE		VEOLIA							
DESIGNED BY D. KING		VEOLIA							
DESIGNED BY J. WILSON		VEOLIA							
DESIGNED BY E. LLOYD		VEOLIA							

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
BUILDING POWER PLAN

DWG NO: VFS-EPM-000-DWG-E-115 REV: D

DWG NO	TITLE	REF NUMBER	TITLE	REV	REV DATE	DESCRIPTION	ENG	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES					
						REVISIONS		

VFS-EPM-000-DWG-E-115 SH 3 OF 3 REV D

8 7 6 5 4 3 2 1

8

7

6

5

4

3

2

1



F

E

D

C

B

A

F


E

D

C

B

A



GENERAL NOTES:

1. SEE VFS-EPM-000-DWG-E-101 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.
2. INSTALL RECEPTACLES IN APPROXIMATE LOCATIONS SHOWN.
3. MOUNT RECEPTACLES AT 16" AFF TO BOTTOM OF RECEPTACLE UNLESS OTHERWISE NOTED.
4. INSTALL RECEPTACLE ON TOP OF MEZZANINE.
5. INSTALL 5' LONG MULTI-OUTLET ASSEMBLY AT 48" AFF FOR WORKBENCH, 2 PLACES.
6. INSTALL RECEPTACLE IN FLOOR WITH SINGLE GANG FLOOR KIT.
7. INSTALL GFCI RECEPTACLES ABOVE COUNTERTOP.

RECEPTACLE PLAN
SCALE: 1/8" = 1'-0"



CONCEPTUAL DESIGN

VEOLIA VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY							
S. MOORE	10/13/13	VNS/F							
J. PIERCE		VNS/F							
D. KING		VNS/F							
J. WILSON		VNS/F							
E. LLOYD		VNS/F							

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT
FACILITY RECEPTACLE
PLAN

REV	DATE	BY	CHKD	COMPANY	DESCRIPTION	REV NO	REV REL	REV	DATE	BY	CHKD	COMPANY	DESCRIPTION
F													


DWG NO: VFS-EPM-000-DWG-E-117
SCALE: SHOWN
SHEET 1 OF 1

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	CHKD	COMPANY
DRAWING TRACEABILITY LIST		NEXT USED ON		REVISONS				

VFS-EPM-000-DWG-E-117 SH 1 OF 1 REV C

GENERAL NOTES:

1. INSTALLATION SHALL COMPLY IN ALL RESPECTS TO LIGHTNING PROTECTION INSTITUTE CODE 175, INSTALLATION SHALL BE MADE UNDER THE SUPERVISION OF A LIGHTNING PROTECTION INSTITUTE CERTIFIED MASTER INSTALLER.
2. ALL LIGHTNING PROTECTION CONDUCTORS SHALL BE COPPER.
3. INSTALL #2 AWG COPPER DOWN CONDUCTOR AND BOND TO COUNTERPOISE. ALL TELECOMMUNICATION CONDUIT/WIRE SHALL MAINTAIN 6'-0" MINIMUM CLEARANCE FROM LIGHTNING PROTECTION DOWN CONDUCTORS.
4. MAIN CONDUCTOR SHALL BE #2 AWG COPPER MINIMUM.
5. INSTALL AIR TERMINALS IN LOCATION SHOWN. AIR TERMINALS SHALL BE NOT LESS THAN 10" IN LENGTH.
6. EDGE AIR TERMINALS SHALL BE LOCATED WITHIN 2'-0" OF ENDS OF EDGES.



LIGHTNING PROTECTION PLAN
SCALE: 1/8" = 1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	BY	COMPANY
DRAWING TRACEABILITY LIST		NEXT USED ON		REFERENCES		REVISIONS				

CONCEPTUAL DESIGN

VEOLIA VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 309
Richland, WA 99352

NAME	DATE	COMPANY
DESIGNED BY S. MOORE	10/13/23	VEOLIA
DRAWN BY J. PIERCE	10/13/23	VEOLIA
CHECKED BY D. KING	10/13/23	VEOLIA
ENGINEER/RESPONSIBLE J. WILSON	10/13/23	VEOLIA
PROJECT MANAGER E. FLOYD	10/13/23	VEOLIA


CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
LIGHTNING PROTECTION PLAN

REV	DWG NO	REV	DATE	BY	COMPANY
F	VFS-EPM-000-DWG-E-118	B			

SCALE: SHOWN EDT SHEET 1 OF 1

VFS-EPM-000-DWG-E-118 SH 1 OF 1 REV B



- GENERAL NOTES:**
- SEE VFS-EPM-000-DWG-E-101 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.
 - INSTALL EXTERIOR LIGHTS IN LOCATIONS SHOWN AT 8' ABOVE FINISHED GRADE UNLESS OTHERWISE NOTED.
 - PROVIDE UNSWITCHED POWER TO EMERGENCY LIGHT FIXTURE BALLASTS.
 - MOUNT LIGHTS IN ELECTRICAL ROOM AT 14' AFF.
 - MOUNT LIGHTS IN LOW BAY AT 19' AFF UNLESS OTHERWISE NOTED.
 - MOUNT LIGHTS IN HIGH BAY AT 39' AFF UNLESS OTHERWISE NOTED.
 - MOUNT EXIT SIGNS DIRECTLY ABOVE DOOR FRAMES IN LOCATIONS SHOWN. SIGNS MUST BE VIEWABLE AND CLEAR OF OBSTRUCTIONS.
- INSTALL EXTERIOR LIGHT IN LOCATION SHOWN AT 12' ABOVE FINISHED GRADE.

LUMINAIRE SCHEDULE				
TYPE	DESCRIPTION	INPUT VOLTAGE	INPUT WATTS	MANUFACTURER/MODEL NO.
A	LED LOW BAY SUSPENDED LUMINAIRE, 4000 NOMINAL LUMENS, 4000K COLOR	UNIVERSAL 120-277 VAC	29.8W	LITHONIA LIGHTING MSL4000LM SBL MVOLT GZ10 40K 80CRI WH
A-E	LED LOW BAY SUSPENDED LUMINAIRE, 4000 NOMINAL LUMENS, 4000K COLOR, 10 WATT CONSTANT BATTERY PACK	UNIVERSAL 120-277 VAC	29.8W	LITHONIA LIGHTING MSL4000LM SBL MVOLT GZ10 40K 80CRI WH E10WLCB
B	2' X 4' LED RECESSED TROFFER, 3000 NOMINAL LUMENS, #19 PATTERN ACRYLIC LENS, 4000K COLOR	UNIVERSAL 120-277 VAC	23.3W	LITHONIA LIGHTING G2TL430L A19 EZ1 LP840
B-E	2' X 4' LED RECESSED TROFFER, 3000 NOMINAL LUMENS, #19 PATTERN ACRYLIC LENS, 4000K COLOR, 10 WATT CONSTANT BATTERY PACK	UNIVERSAL 120-277 VAC	23.3W	LITHONIA LIGHTING G2TL430L A19 EZ1 LP840 E10WLCB
C	HIGH BAY, LED, 18000 NOMINAL LUMENS, CLEAR ACRYLIC, WIDE DISTRIBUTION, 4000K COLOR TEMPERATURE, 90 CRI COLOR RENDERING INDEX	120 VAC	131W	LITHONIA LIGHTING JHBL 18000LM ACL WD 120 GZ10 40K 90CRI
C-E	HIGH BAY, LED, 18000 NOMINAL LUMENS, CLEAR ACRYLIC, WIDE DISTRIBUTION, 4000K COLOR TEMPERATURE, 90 CRI COLOR RENDERING INDEX, 15 W CONSTANT BATTERY PACK	120 VAC	131W	LITHONIA LIGHTING JHBL 18000LM ACL WD 120 GZ10 40K 90CRI E15WCPFC
D	HIGH BAY, LED, 12000 NOMINAL LUMENS, CLEAR ACRYLIC, WIDE DISTRIBUTION, 4000K COLOR TEMPERATURE, 90 CRI COLOR RENDERING INDEX	120 VAC	83W	LITHONIA LIGHTING JHBL 12000LM ACL WD 120 GZ10 40K 90CRI
E	HIGH BAY, LED, 24000 NOMINAL LUMENS, CLEAR ACRYLIC, NARROW DISTRIBUTION, 4000K COLOR TEMPERATURE, 90 CRI COLOR RENDERING INDEX	120 VAC	185W	LITHONIA LIGHTING JHBL 24000LM ACL ND 120 GZ10 40K 90CRI
E-E	HIGH BAY, LED, 24000 NOMINAL LUMENS, CLEAR ACRYLIC, WIDE DISTRIBUTION, 4000K COLOR TEMPERATURE, 90 CRI COLOR RENDERING INDEX, 15 W CONSTANT BATTERY PACK	120 VAC	185W	LITHONIA LIGHTING JHBL 24000LM ACL ND 120 GZ10 40K 90CRI E15WCPFC
F	WALL MOUNT, LED, 4000K COLOR TEMPERATURE, BUTTON PHOTOCELL	UNIVERSAL 120-277 VAC	8.4W	LITHONIA LIGHTING LIL LED 40K MVOLT PE DDBTXD
G	WALL MOUNTED EXIT SIGN, WITH BATTERY BACKUP	UNIVERSAL 120-277 VAC	41W	LITHONIA LBL4 40L EZ1 LP840
H	CEILING MOUNTED EXIT SIGN, WITH BATTERY BACKUP	UNIVERSAL 120-277 VAC	41W	LITHONIA LBL4 40L EZ1 LP840

LIGHTING PLAN
SCALE: 1/8" = 1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS						
NEXT USED ON										

CONCEPTUAL DESIGN

VEOLIA
VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY
S. MOORE	10/20/20	VEOLIA
D. KING	10/20/20	VEOLIA
J. PIERCE	10/20/20	VEOLIA
R. JENSEN	10/20/20	VEOLIA
E. LLOYD	10/20/20	VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT
FACILITY
LIGHTING PLAN

VFS-EPM-000-DWG-E-120

REV D


VFS-EPM-000-DWG-E-120 SH 1 OF 2 REV D

8 7 6 5 4 3 2 1



NOTES:

- 1. SEE VFS-EPM-000-DWG-E-101 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.
- 2. FOR GENERAL NOTES AND LUMINAIRE TYPES, SEE SHEET 1.



1 ENLARGED LIGHTING PLAN
 SCALE: 1/4" = 1'-0"



CONCEPTUAL DESIGN

VEOLIA VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPL.
S. MOORE	11/15/12	YNSP#
D. KING		YNSP#
S. WILSON		YNSP#
J. PIERCE		YNSP#
R. JENSEN		YNSP#
E. FLOYD		YNSP#

**CIMARRON
PUMP AND TREAT SYSTEM PROJECT**

**WESTERN AREA TREATMENT
FACILITY
LIGHTING PLAN**

DWG NO	TITLE	REF NUMBER	TITLE	REF	REV	DATE	DESCRIPTION	ENG	COMP
DRAWING TRACEABILITY LIST		NEXT USED ON		REFERENCES		REVISIONS			


SCALE: SHOWN EST SHEET 2 OF 2

VFS-EPM-000-DWG-E-120 SH 2 OF 2 REV D


8 7 6 5 4 3 2 1

GENERAL NOTES:


- FOR LEGEND, NOTES AND ABBREVIATIONS SEE VFS-EPM-000-DWG-E-101.
- EQUIPMENT SHALL BE INSTALLED PER MANUFACTURER'S INSTRUCTIONS USING THE APPROPRIATE HARDWARE.



A SWITCHBOARD FLOOR MOUNTING SECTION
E-115-2 SCALE: NONE



B MCC FLOOR MOUNTING SECTION
E-115-2 SCALE: NONE



C TRANSFORMER MOUNTING
E-115-2 SCALE: NONE

CONCEPTUAL DESIGN

VEOLIA VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, VA 99352

NAME	DATE	COMPANY
S. MOORE	08/15/20	VEOLIA
D. KING	08/15/20	VEOLIA
J. PIERCE	08/15/20	VEOLIA
R. JENKINSON	08/15/20	VEOLIA
E. LLOYD	08/15/20	VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREAT TREATMENT
FACILITY ELECTRICAL
DETAILS AND SECTIONS


DWG NO	TITLE	REF NUMBER	TITLE	REV	DESCRIPTION	REV	DATE	BY	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS					
NEXT USED ON									

SCALE: NONE SHEET 1 OF 4


DWG NO	TITLE	REF NUMBER	TITLE	REV	DESCRIPTION	REV	DATE	BY	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS					
NEXT USED ON									

8 7 6 5 4 3 2 1


- NOTES:**
- SEE DRAWING VFS-EPM-000-DWG-E-114 SHEET 2 FOR TRANSFORMER GROUNDING DETAILS.
 - SEE SINGLE LINE DIAGRAM FOR CONDUCTOR SIZES.
 - UTILITY CONNECTIONS PROVIDED BY OTHERS.
 - SECURE UNISTRUT RACK TO CONCRETE FOUNDATION OR PAD.



D SECTION
E-112-1 SCALE: 1" = 1'-0"




FRONT VIEW



SIDE VIEW

F ELEVATION
E-112-1 SCALE: 1 1/2" = 1'-0"



E SECTION
E-112-1 SCALE: 1" = 1'-0"

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	BY	CHK	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY
S. MOORE	05/18/2017	VEOLIA
D. KING		VEOLIA
J. PIERCE		VEOLIA
R. JENSEN		VEOLIA
E. LLOYD		VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREAT TREATMENT
FACILITY ELECTRICAL
DETAILS AND SECTIONS

VFS-EPM-000-DWG-E-130

SCALE: NONE
SHEET 2 OF 4

8 7 6 5 4 3 2 1

8

7

6

5

4

3


2

1


NOTES:

- 1. SEE SHEET 1 FOR GENERAL NOTES.

SECTION 1 SECTION 2 SECTION 3 SECTION 4 SECTION 5




G MCC-1 ELEVATION
E-115-1 SCALE: NONE



PLAN VIEW FOLD OUT

1 ELECTRICAL VAULT E-1 DETAIL
E-113-1 SCALE: 3/4" = 1'-0"



PLAN VIEW FOLD OUT

2 TRANSFORMER VAULT DETAIL
E-113-1 SCALE: 1/2" = 1'-0"

CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY
S. MOORE	11/12/20	VNSP
D. KING		VNSP
J. PIERCE		VNSP
R. JENSEN		VNSP
E. LLOYD		VNSP

CIMARRON PUMP AND TREAT SYSTEM PROJECT	
WESTERN AREAT TREATMENT FACILITY ELECTRICAL DETAILS AND SECTIONS	
SEE SHEET NO.	F
SCALE	NONE
EST	
SHEET	3 OF 4

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		NEXT USED ON							
			REFERENCES							

DWG NO VFS-EPM-000-DWG-E-130 SH 3 OF 4 REV B

8

7

6

5


4

3


2

1


NOTES:
 1. SEE SHEET 1 FOR GENERAL NOTES.



3 HOUSEKEEPING PAD DETAIL
 E-113-1 SCALE: 1" = 1'-0"



H HOUSEKEEPING PAD DETAIL
 SCALE: 1" = 1'-0"



J SWBD-A ELEVATION
 E-115-2 SCALE: NONE

VEOLIA
 VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
WESTERN AREAT TREATMENT
FACILITY ELECTRICAL
DETAILS AND SECTIONS

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	ENG	COMP
DRAWING TRACEABILITY LIST		NEXT USED ON		REFERENCES		REVISIONS		

NAME	DATE	COMP
S. MOORE	8/13/2014	VEOLIA
D. KING		VEOLIA
J. PIERCE		VEOLIA
R. JENSEN		VEOLIA
E. LLOYD		VEOLIA

SCALE: SHOWN
 SHEET 4 OF 4

VFS-EPM-000-DWG-E-130 SH 4 OF 4 REV B

8

7

6

5

4


3

2


1

GENERAL NOTES:

- 1 PLASTIC JERSEY BARRIER, 6 FT, TYP.
- 2 PLASTIC JERSEY BARRIER, 8 FT, TYP.
- 3 THE LOCATION OF THE BACKWASH WATER TANK IS TBD. THE FINAL LOCATION WILL BE DETERMINED DURING FINAL DESIGN.



GENERAL ARRANGEMENT
SCALE: 1/8" = 1'-0"



CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY	REV	DESCRIPTION	SCALE	SHOWN	EPT	SHEET	OF	1
S. MOORE		VEOLIA								
J. WILSON		VEOLIA								
J. PIERCE		VEOLIA								
J. WILSON		VEOLIA								
E. ELLOYD		VEOLIA								

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
GENERAL ARRANGEMENT

DWG NO: VFS-EPM-000-DWG-G-100

SHEET 1 OF 1

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		NEXT USED ON		REFERENCES		REVISIONS				

VFS-EPM-000-DWG-G-100 SH 1 OF 1 REV F




GENERAL NOTES:

- NOZZLE LOCATIONS SHOWN ON TANK TK-101 ARE FOR INFORMATION ONLY, ACTUAL NOZZLE LOCATIONS TO BE DETERMINED BY VENDOR'S FINAL SUBMITTAL.
- FOR PIPE SUPPORT DETAILS SEE DRAWING VFS-EPM-000-DWG-S-115. INSTALL PER SPECIFICATION SECTION 22 05 29 - HANGERS AND SUPPORTS FOR PIPING AND EQUIPMENT.

NOZZLE SCHEDULE FOR TANK TK-101				
MARK	QTY	RATING	SIZE	LOCATION
N1 - FILL	1	150#	4"	ROOF (NOTE A)
N2 - DISCHARGE	1	150#	4"	8" ABOVE TOC
N3 - HIGH LEVEL SWITCH	1	150#	(NOTE 1)	ROOF
N4 - VENT	1	150#	(NOTE 1)	ROOF
N5 - LEVEL DETECTION	1	150#	(NOTE 1)	ROOF
N6 - LEAK DETECTION	1	N/A	(NOTE 1)	BETWEEN SHELLS
MANWAY	1	(NOTE 1)	24"	20" TO 60" ABOVE TOC
MANWAY	1	(NOTE 1)	24"	ROOF

SCHEDULE NOTES:
A. INFLUENT PIPE RUN IS TO BE SUPPORTED DOWN THE SIDE OF THE TANK.



INFLUENT HANDLING PLAN
SCALE: 1/2" = 1'-0"
(INSULATION AND HEAT TRACE NOT SHOWN FOR CLARITY)



CONCEPTUAL DESIGN

VEOLIA VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, VA 99352

NAME	DATE	COMPLD
S. MOORE	REVISED	UNCLD
E. LLOYD	UNCLD	UNCLD
J. PIERCE	UNCLD	UNCLD
M. WILSON	UNCLD	UNCLD
E. LLOYD	UNCLD	UNCLD

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
INFLUENT HANDLING PLAN

VFS-EPM-000-DWG-G-105

DWG NO	TITLE	REF NUMBER	TITLE	REV	REV BY	DESCRIPTION	DATE	SCALE	DWG NO	TITLE
	DRAWING TRACEABILITY LIST		REFERENCES							

REVISIONS

SCALE SHOWN: 1/2" = 1'-0" SHEET 1 OF 1

VFS-EPM-000-DWG-G-105 SH 1 OF 1 REV C

8

7

6

5

4


3

2

1


GENERAL NOTES:

- 1. NOZZLE LOCATIONS SHOWN ON TANK TK-101 ARE FOR INFORMATION ONLY. ACTUAL NOZZLE LOCATIONS TO BE DETERMINED BY VENDOR'S FINAL SUBMITTAL.
- 2. INTERFACE FLANGE TO BE 12" ABOVE GRADE, CENTER CONNECTION POINT PIPE IN 18" SONNET TUBE X 30" DEEP. FILL SONNET TUBE WITH SAND OR CRUSHED ROCK AFTER HEAT TRACE HAS BEEN INSTALLED.
- 3. FOR PIPE SUPPORT DETAILS SEE DRAWING VFS-EPM-000-DWG-S-115. INSTALL PER SPECIFICATION SECTION 22 05 29 - HANGERS AND SUPPORTS FOR PIPING AND EQUIPMENT.



TK-101
INFLUENT TANK
12000 GALLONS

CONNECTION POINT
TO WA EXTRACTION
LINE (BY BMCD)




4"-GW-11502-AS01-HT&I

Level 2
20'-0"

Level 1
0'-0"

A INFLUENT HANDLING ELEVATION
G-105-1 SCALE: 1/2" = 1'-0"
(INSULATION AND HEAT TRACE NOT SHOWN FOR CLARITY)



CONCEPTUAL DESIGN

VEOLIA VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY
S. MOORE	12/1/15	VEOLIA
E. ELLOYD	1/28/16	VEOLIA
J. PIERCE	1/28/16	VEOLIA
L. WILSON	1/28/16	VEOLIA
E. ELLOYD	1/28/16	VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
INFLUENT HANDLING

DWG NO	TITLE	REF NUMBER	TITLE	REF	REV	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES					

SCALE SHOWN: 1/2" = 1'-0"

SHEET 1 OF 2

VFS-EPM-000-DWG-G-106 SH 1 OF 2 REV C

8

7

6

5

4


3

2

1

NOTES:

1. SEE SHEET 1 FOR GENERAL NOTES.



B INFLUENT HANDLING ELEVATION
 Q-105-1 SCALE: 1/2" = 1'-0"
 (INSULATION AND HEAT TRACE NOT SHOWN FOR CLARITY)



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV BY	DATE	CHKD	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							
						REVISIONS				



CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

<table border="1"> <thead> <tr> <th>NAME</th> <th>DATE</th> <th>COMPANY</th> </tr> </thead> <tbody> <tr> <td>S. MOORE</td> <td>11/13/13</td> <td>VEOLIA</td> </tr> <tr> <td>E. ELLOYD</td> <td>11/13/13</td> <td>VEOLIA</td> </tr> <tr> <td>J. PIERCE</td> <td>11/13/13</td> <td>VEOLIA</td> </tr> <tr> <td>J. VILSON</td> <td>11/13/13</td> <td>VEOLIA</td> </tr> <tr> <td>E. ELLOYD</td> <td>11/13/13</td> <td>VEOLIA</td> </tr> </tbody> </table>	NAME	DATE	COMPANY	S. MOORE	11/13/13	VEOLIA	E. ELLOYD	11/13/13	VEOLIA	J. PIERCE	11/13/13	VEOLIA	J. VILSON	11/13/13	VEOLIA	E. ELLOYD	11/13/13	VEOLIA	<p>CIMARRON PUMP AND TREAT SYSTEM PROJECT</p> <p>WESTERN AREA TREATMENT FACILITY INFLUENT HANDLING</p>
NAME	DATE	COMPANY																	
S. MOORE	11/13/13	VEOLIA																	
E. ELLOYD	11/13/13	VEOLIA																	
J. PIERCE	11/13/13	VEOLIA																	
J. VILSON	11/13/13	VEOLIA																	
E. ELLOYD	11/13/13	VEOLIA																	
<table border="1"> <thead> <tr> <th>SCALE</th> <th>DWG NO</th> <th>SCALE SHOWN</th> <th>REV</th> </tr> </thead> <tbody> <tr> <td>F</td> <td>VFS-EPM-000-DWG-G-106</td> <td></td> <td>C</td> </tr> </tbody> </table>	SCALE	DWG NO	SCALE SHOWN	REV	F	VFS-EPM-000-DWG-G-106		C	<table border="1"> <thead> <tr> <th>SCALE</th> <th>SHOWN</th> <th>REV</th> <th>SHEET</th> <th>OF</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> <td></td> <td>2</td> <td>2</td> </tr> </tbody> </table>	SCALE	SHOWN	REV	SHEET	OF				2	2
SCALE	DWG NO	SCALE SHOWN	REV																
F	VFS-EPM-000-DWG-G-106		C																
SCALE	SHOWN	REV	SHEET	OF															
			2	2															

DWG NO VFS-EPM-000-DWG-G-106 SH 2 OF 2 REV C



EFFLUENT HANDLING PLAN
 SCALE: 1/2" = 1'-0"
 (INSULATION AND HEAT TRACE NOT SHOWN FOR CLARITY)

- GENERAL NOTES:**
1. PUMP ENCLOSURE SHALL BE HUBBELL HOT BOX MODEL NUMBER DF4FEH, PART NUMBER HD041041045 WITH 1000W HEATER AND VENTILATION FAN. CENTER ENCLOSURE OVER CENTER OF PUMP AND ATTACH TO CONCRETE PAD USING SUPPLIED HARDWARE. ENSURE THAT THERE IS 12" OF CLEARANCE FROM INSIDE DIMENSIONS OF ENCLOSURE TO EDGE OF CONCRETE FOR ENCLOSURE MOUNTING. CONTRACTOR TO CUT HOLES IN SIDES OF ENCLOSURE FOR PIPE, HOLES SHALL BE 1/2" LARGER THAN PIPE SIZE. AFTER INSTALLATION APPLY EXPANDING FOAM AROUND THE PERIMETER OF THE PENETRATIONS.
 2. NOZZLE LOCATIONS SHOWN ON TANK TK-102 ARE FOR INFORMATION ONLY. ACTUAL NOZZLE LOCATIONS TO BE DETERMINED BY VENDOR'S FINAL SUBMITTAL.
 3. FOR PIPE SUPPORT DETAILS SEE DRAWING VFS-EPM-000-DWG-S-115. INSTALL PER SPECIFICATION SECTION 22 05 29 - HANGERS AND SUPPORTS FOR PIPING AND EQUIPMENT.

NOZZLE SCHEDULE FOR TANK TK-102				
MARK	QTY	RATING	SIZE	LOCATION
N1 - FILL	1	150#	4"	ROOF (NOTE A)
N2 - DISCHARGE	1	150#	4"	BOTTOM, 8" ABOVE TOC
N3 - DETECTION	1	150#	(NOTE 2)	ROOF
N4 - VENT	1	150#	(NOTE 2)	ROOF
N5 - SPARE	1	150#	(NOTE 2)	ROOF
N6 - SPARE	1	150#	(NOTE 2)	ROOF
MANWAY	1	(NOTE 1)	24"	20" TO 60" ABOVE TOC
MANWAY	1	(NOTE 1)	24"	ROOF

SCHEDULE NOTES:

A. EFFLUENT PIPE RUNS TO BE SUPPORTED DOWN THE SIDE OF THE TANK.

B. NOZZLE ADDED FOR FUTURE SYSTEM BYPASS ONCE MCL IS ACHIEVED FOR URANIUM AND NITRATE.

CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

NAME	DATE	COMPANY
S. MOORE	8/11/20	VNSFS
E. LLOYD		VNSFS
J. PIERCE		VNSFS
J. WILSON		VNSFS
E. LLOYD		VNSFS

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA
 TREATMENT FACILITY
 EFFLUENT HANDLING PLAN

VFS-EPM-000-DWG-G-130

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES					
					REVISIONS			

VFS-EPM-000-DWG-G-130 SH 1 OF 1 REV C

A

C

8

7

6

5

4

3

2

1

F

E

D

C

B

A

F

E

D


C

B

A

GENERAL NOTES:

- 1. NOZZLE LOCATIONS SHOWN ON TANK TK-102 ARE FOR INFORMATION ONLY. ACTUAL NOZZLE LOCATIONS TO BE DETERMINED BY VENDOR'S FINAL SUBMITTAL.
- 2. FOR PIPE SUPPORT DETAILS SEE DRAWING VFS-EPM-000-DWG-S-115. INSTALL PER SPECIFICATION SECTION 22 05 29 - HANGERS AND SUPPORTS FOR PIPING AND EQUIPMENT.



A EFFLUENT HANDLING ELEVATION
 Q-130 SCALE: 1/2" = 1'-0"
 (INSULATION AND HEAT TRACE NOT SHOWN FOR CLARITY)

1/2" = 1'-0"
 SCALE FEET

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	BY	CHKD
	DRAWING TRACEABILITY LIST		REFERENCES							

CONCEPTUAL DESIGN

VEOLIA VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

NAME	DATE	COMPANY
BM EKAR		VEOLIA
E LLOYD		VEOLIA
J PIERCE		VEOLIA
J WILSON		VEOLIA
E LLOYD		VEOLIA

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
 TREATMENT FACILITY
 EFFLUENT HANDLING

VEOLIA PROJECT NO: VFS-EPM-000-DWG-G-131

SCALE	SHOWN	EST	SHEET 1	OF 2
-------	-------	-----	---------	------

VFS-EPM-000-DWG-G-131 SHEET 1 OF 2 REV C

8

7

6

5

4


3

2


1

NOTES:

- 1. SEE SHEET 1 FOR GENERAL NOTES.
- 2. INTERFACE FLANGE TO BE 12" ABOVE GRADE, CENTER CONNECTION POINT PIPE IN 18" SONNET TUBE X 30" DEEP. FILL SONNET TUBE WITH SAND OR CRUSHED ROCK AFTER HEAT TRACE HAS BEEN INSTALLED.



B EFFLUENT HANDLING ELEVATION
 Q-130 SCALE: 1/2" = 1'-0"
 (INSULATION AND HEAT TRACE NOT SHOWN FOR CLARITY)



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	BY	CHKD
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS						

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352


<table border="1"> <thead> <tr> <th>NAME</th> <th>DATE</th> <th>COMPANY</th> </tr> </thead> <tbody> <tr><td>S. MOORE</td><td></td><td>VEOLIA</td></tr> <tr><td>E. LLOYD</td><td></td><td>VEOLIA</td></tr> <tr><td>J. PIERCE</td><td></td><td>VEOLIA</td></tr> <tr><td>J. WILSON</td><td></td><td>VEOLIA</td></tr> <tr><td>E. LLOYD</td><td></td><td>VEOLIA</td></tr> </tbody> </table>	NAME	DATE	COMPANY	S. MOORE		VEOLIA	E. LLOYD		VEOLIA	J. PIERCE		VEOLIA	J. WILSON		VEOLIA	E. LLOYD		VEOLIA	<p style="text-align: center;">CIMARRON PUMP AND TREAT SYSTEM PROJECT</p> <p style="text-align: center;">WESTERN AREA TREATMENT FACILITY EFFLUENT HANDLING</p>
NAME	DATE	COMPANY																	
S. MOORE		VEOLIA																	
E. LLOYD		VEOLIA																	
J. PIERCE		VEOLIA																	
J. WILSON		VEOLIA																	
E. LLOYD		VEOLIA																	
<table border="1"> <thead> <tr> <th>REV</th> <th>DWG NO</th> <th>SCALE</th> <th>SHOWN</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>F</td> <td>VFS-EPM-000-DWG-G-131</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>	REV	DWG NO	SCALE	SHOWN	DATE	F	VFS-EPM-000-DWG-G-131				<p style="text-align: center;">VFS-EPM-000-DWG-G-131</p> <p style="text-align: right;">SHEET 2 OF 2</p>								
REV	DWG NO	SCALE	SHOWN	DATE															
F	VFS-EPM-000-DWG-G-131																		

VFS-EPM-000-DWG-G-131 SH 2 OF 2 REV C



GENERAL NOTES:

1. SEE VFS-EPM-000-DWG-E-101 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.
2. SEE VFS-EPM-000-DWG-J-115 FOR REQUIRED CONTROL SYSTEM INTERCONNECTIONS.
3. FIELD ROUTE CAT-6 ETHERNET CABLE FROM CONTROL PANELS TO DATA ROOM SCADA RACK AND FROM SCADA RACK TO CONTROL SYSTEM WORKSTATION COMPUTERS.
4. EQUIPMENT RACK CONTAINING CONTROL SYSTEM PLC'S, ETHERNET SWITCHES, MEDIA CONVERTERS, PATCH PANELS, AND UPS.
5. CABINET FOR LOCAL AREA NETWORK SERVER, ROUTERS, AND UPS.
6. LOCATION FOR COMPUTER WORKSTATIONS FED BY DESKTOP UPS UNITS.



INSTRUMENTATION AND CONTROL PLAN
 SCALE: 1/8" = 1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	BY	CHKD	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES			REVISIONS			

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

NAME	DATE	COMPANY
S. MOORE	01/11/18	VEOLIA
J. PIERCE		VEOLIA
D. KING		VEOLIA
J. WILSON		VEOLIA
E. LLOYD		VEOLIA

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT FACILITY INSTRUMENTATION AND CONTROL PLAN

REV	DATE	DESCRIPTION
F		VFS-EPM-000-DWG-J-110

SCALE: AS SHOWN SHEET 1 OF 1

VFS-EPM-000-DWG-J-110 | SHEET 1 OF 1 | REV E

8 7 6 5 4 3 2 1



- SYMBOLS LEGEND:**
- DOOR POSITION SWITCH
 - ELECTRIFIED LOCK, DOOR POSITION SWITCH, REX
 - CARD READER - PEDESTAL MOUNTED
 - FIXED DOME CAMERA - POLE MOUNTED
 - C-XX CAMERA NUMBER/TYPE (DEFINED IN SPECIFICATION SECTION 282000)
 - 01
 - AFG ABOVE FINISHED GRADE



SECURITY GATE WITH PADLOCK, KEY TO BE LOCATED IN KEY CABINET IN CONTROL ROOM.

SECURE ALL ACCESS DOORS WITH PADLOCK, KEY TO BE LOCATED IN KEY CABINET IN CONTROL ROOM. PROVIDE DOOR POSITION SWITCHES AT ALL INJECTION SKID DOORS (QUANTITY AND LOCATION TO BE DETERMINED).

SECURITY GATE WITH PADLOCK, KEY TO BE LOCATED IN KEY CABINET IN CONTROL ROOM.



SECURITY SITE PLAN
SCALE: 1" = 20'-0"

CONCEPTUAL DESIGN



NAME	DATE	COMPANY
S. MOORE	11/12/10	VEOLIA
J. PIERCE		VEOLIA
D. KING		VEOLIA
J. WILSON		VEOLIA
E. LLOYD		VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA
TREATMENT FACILITY
SITE SECURITY PLAN

VFS-EPM-000-DWG-J-111

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							

VFS-EPM-000-DWG-J-111 SH 1 OF 1 REV D


8 7 6 5 4 3 2 1

8 7 6 5 4 3 2 1

GENERAL NOTES:
 1. ACCESS CONTROL SYSTEM SERVER TO BE INSTALLED IN DATA ROOM, SECURITY SYSTEM, CCTV CONTROLLER, AND MONITORS TO BE INSTALLED IN THE CONTROL ROOM.

SYMBOLS LEGEND:

- DM DOOR POSITION SWITCH
- EL ELECTRIFIED LOCK, DOOR POSITION SWITCH, REX
- CR CARD READER - WALL MOUNTED
- FC FIXED DOME CAMERA - CEILING MOUNTED
- FW FIXED DOME CAMERA - WALL MOUNTED
- C-XX CAMERA NUMBER/TYP (DEFINED IN SPECIFICATION SECTION 282000)
- AFG ABOVE FINISHED GRADE
- AFF ABOVE FINISHED FLOOR



BUILDING SECURITY PLAN
 SCALE: 1/8" = 1'-0"



CONCEPTUAL DESIGN

VEOLIA
 VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

NAME	DATE	COMPANY							
REVIEWED	10/1/21	VEOLIA							
DESIGNED									
CHECKED									
APPROVED									
PROJECT MANAGER									
CLIENT									
DATE									
SCALE	SHOWN	EDT							

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA
 TREATMENT FACILITY
BUILDING SECURITY PLAN

VFS-EPM-000-DWG-J-112


SHEET 1 OF 1

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		NEXT USED ON		REVISIONS				

VFS-EPM-000-DWG-J-112 SH 1 OF 1 REC

GENERAL NOTES:

- 1. SEE VFS-EPM-000-DWG-E-101 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.
- 2. ETHERNET CABLE RUNS LENGTHS SHALL NOT EXCEED 328 FEET. FOR LONGER RUNS, UTILIZE FIBER OPTIC CABLE WITH MEDIA CONVERTERS.
- 3. SEE BMCD-GWREMED-E109 AND BMCD-GWREMED-E110 FOR WELL FIELD AND INJECTION SYSTEMS COMMUNICATION SYSTEM ARCHITECTURE.



CONTROL SYSTEM NETWORK INTERCONNECTION DIAGRAM

LEGEND

- ANALOG
- - - ETHERNET
- FIBER

CONCEPTUAL DESIGN



NAME	DATE	COMPANY
D. KING	10/2013	VEOLIA
D. KING	10/2013	VEOLIA
J. PIERCE	10/2013	VEOLIA
R. JENSEN	10/2013	VEOLIA
E. LLOYD	10/2013	VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
INSTRUMENTATION AND
CONTROL SYSTEM NETWORK
INTERCONNECTION DIAGRAM



VEOLIA
VFS-EPM-000-DWG-J-115
SCALE: NONE
SHEET 1 OF 1

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		NEXT USED ON		REVISIONS				

VFS-EPM-000-DWG-J-115 SH 1 OF 1 REV H

GENERAL NOTES:

1. FOR DOMESTIC WATER PLUMBING SEE DRAWING VFS-EPM-000-DWG-P-100 AND VFS-EPM-000-DWG-P-500.
2. HEAT PUMP, CARRIER SERIES 50TCQ-17-24-03PD, 20 TON UNIT.
3. FAN, 12" AXIAL DIRECT DRIVE, DAYTON MODEL DR12HFA.
4. FAN, 24" TPI MODEL CE 24-DS.
5. EYEWASH, PEDESTAL MOUNT, BRADLEY SERIES S19214.
6. FAN, 24 FT, BIG ASS FAN BASIC MODEL 6.
7. FAN, 14 FT, BIG ASS FAN BASIC MODEL 6.
8. NOT USED.
9. LOUVER, 36" x 36", GRAINGER MODEL 3HHN9.
10. HEAT PUMP, CARRIER 50TC SERIES, 5 TON UNIT.
11. TANKLESS WATER HEATER, BRADLEY CLE SERIES.



MECHANICAL PLAN
SCALE: 1/8" = 1'-0"

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY
J. PIERCE	11/13/23	VEOLIA
N. HERTELUNDY	11/13/23	VEOLIA
S. MOORE	11/13/23	VEOLIA
J. WILSON	11/13/23	VEOLIA
E. FLOYD	11/13/23	VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
MECHANICAL PLAN

DRAWING NO: **VFS-EPM-000-DWG-M-100**


DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		NEXT USED ON		REVISIONS				

VFS-EPM-000-DWG-M-100 SH 1 OF 1 REV E

GENERAL NOTES

- 1 INITIAL SETTING 80 PSIG, DETERMINE SETTING DURING STARTUP TESTING.
- 2 INITIAL SETTING 35% OPEN, DETERMINE SETTING TO MAINTAIN A PUMP RUNNING DURING STARTUP TESTING.
- 3 INITIAL SETTING 45 PSIG, DETERMINE SETTING DURING STARTUP TESTING.
- 4 WOODFORD FREEZELESS UNDERCOVER WALL HYDRANT MODEL 68.
- 5 SMITH-COOPER INTERNATIONAL BRASS NO-KINK HOSE BIBB, MODEL 01901681L (3/4" FIP), OR MODEL 01901691L (3/4" MIP) OR EQUIVALENT LEAD FREE NSF 61. INSTALL LEAD FREE HOSE END VACUUM BREAKER (SMITH-COOPER INTERNATIONAL MODEL 01901671IL OR EQUIVALENT).
- 6 WATTS 909AGF AIR GAP DISCHARGE OUTSIDE.
- 7 INITIAL SETTING 70 PSIG.

F
E
D
C
B
A



CONCEPTUAL DESIGN



NAME	DATE	COMPANY
V. DAVISON	10/20/21	VEOLIA
S. MOORE		VEOLIA
J. WILSON		VEOLIA
D. SMITH		VEOLIA
E. LLOYD		VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA TREATMENT FACILITY P&ID DOMESTIC WATER

REF: DWG NO: VFS-EPM-000-DWG-P-500
SCALE: NONE
SHEET 1 OF 1

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		NEXT USED ON		REVISIONS				

VFS-EPM-000-DWG-P-500 BH 1 OF 1 REV E

GENERAL NOTES:

- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE 2015 EDITION OF THE INTERNATIONAL BUILDING CODE (IBC), LOCAL RULES AND STANDARDS OF GOVERNING AGENCIES HAVING JURISDICTION.
- CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF SITE CONDITIONS, INSTALLATION STANDARDS AND CONSTRUCTION CONDITIONS. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS PRIOR TO SHOP FABRICATION AND/OR FIELD ERECTION. DISCREPANCIES BETWEEN SITE CONDITIONS AND THE CONSTRUCTION DRAWINGS SHALL BE CALLED TO THE ATTENTION OF THE ENGINEER. WORK DONE WITHOUT THE ENGINEER'S APPROVAL IS THE RESPONSIBILITY OF THE CONTRACTOR.
- ALL SPECIAL INSPECTION AND TESTING SHALL BE PERFORMED BY AN INDEPENDENT INSPECTION AND TESTING AGENCY HIRED BY THE OWNER. CONTRACTOR TO COORDINATE WITH INSPECTION AND TESTING AGENCY FOR REQUIRED CONSTRUCTION INSPECTIONS AND MATERIAL TESTING.
- ELEVATIONS ON THE STRUCTURAL DRAWINGS REFERENCE THE FINISHED FLOOR ELEVATION, ASSIGNED THE DATUM 0'-0".
- THE DIMENSIONS, LOCATIONS, AND ELEVATIONS OF ANY EXISTING STRUCTURES WHICH RELATE TO OR INFLUENCE NEW CONSTRUCTION SHALL BE VERIFIED BY FIELD MEASUREMENT BY THE CONTRACTOR PRIOR TO PREPARATION AND SUBMISSION OF CHECKED SHOP DRAWINGS TO THE ENGINEER OF RECORD FOR REVIEW.
- PROTECTION OF EXISTING STRUCTURES DURING THE COURSE OF THE CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
- THIS BUILDING SHALL BE CONSTRUCTED USING THE STANDARD DETAILS CONTAINED WITHIN THIS DRAWING SET UNLESS NOTED OTHERWISE. WHERE NO DETAIL IS NOTED IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO CHOOSE THE APPROPRIATE STANDARD DETAIL FROM THOSE PROVIDED.
- PRIOR TO DIGGING VERIFY LOCATION AND DEPTH OF UTILITIES AND OTHER UNDERGROUND INTERFERENCES. CALL TWO BUSINESS DAYS BEFORE YOU DIG AT 811.
- FOUNDATION DESIGN REACTIONS AND FINAL COLUMN LOCATIONS ARE BASED UPON PRE-ENGINEERED METAL BUILDING CALCULATIONS. ALL BUILDING MODIFICATIONS PRIOR TO CONSTRUCTION MUST BE REVIEWED BY MANUFACTURER AND ENGINEER OF RECORD.
- CONTRACTOR SHALL PROVIDE "UFER" GROUND CONNECTIONS TO BUILDING STEEL, EQUIPMENT, AND MAIN GROUNDING ELECTRODE GROUND BAR, REFER TO ELECTRICAL DRAWINGS FOR DETAILS. ELECTRICAL CONTRACTOR SHALL COORDINATE INSTALLATION WITH BUILDING FOUNDATION CONTRACTOR.
- DESIGN CRITERIA (PER 2018 IBC AND ASCE 7-16)
 - VERTICAL LOADS:
SEE LOADING PLAN SHEETS FOR UNIFORM DEAD LOADS, UNIFORM LIVE LOADS, UNIFORM SNOW LOADS, DRIFT SNOW LOADS, AND COMPONENT WIND UPLIFT LOADS.
 - A. DEAD LOADS:
ROOF (FLAT) 10 PSF + FRAMING WEIGHT
COLLATERAL 10 PSF
 - B. LIVE LOADS (IBC 1607):
ROOF LIVE LOAD 20 PSF
MEZZANINE 60 PSF
 - C. SNOW LOADS (IBC 1608):
GROUND SNOW LOAD Pg=15 PSF
UNIFORM ROOF SNOW LOAD Pm=20 PSF
 - D. SNOW EXPOSURE FACTOR: Ce=1.0
SNOW LOAD IMPORTANCE FACTOR: Is=1.0
THERMAL FACTOR: Ct=1.0
 - LATERAL LOADS:
A. WIND DESIGN LOAD DATA: (PER ASCE 7-16 AND IBC 2018)
VELOCITY (3-SEC.-GUST) V = 110 MPH
EXPOSURE C
RISK CATEGORY II
INTERNAL PRESSURE COEFFICIENT ±0.18
 - B. SEISMIC DESIGN LOAD DATA: (PER ASCE 7-16 AND IBC 2018)
RISK CATEGORY II
IMPORTANCE FACTOR I
RHO (N-S) 1.0
RHO (E-W) 1.0
 - MAPPED SPECTRAL RESPONSE ACCELERATIONS:
Sg = 0.245
S1 = 0.070
 - SEISMIC SITE CLASS D
 - DESIGN SPECTRAL RESPONSE COEFFICIENTS:
Sds = 0.262
Sd1 = 0.118
 - SEISMIC DESIGN CATEGORY B
 - SEISMIC FORCE RESISTING SYSTEM AND RESPONSE MODIFICATION FACTOR:
SPECIAL STEEL MOMENT FRAME R= 8.0
SPECIAL STEEL CONCENTRICALLY BRACED FRAMES R= 6.0
 - SEISMIC RESPONSE COEFFICIENT Cs = 0.139
DESIGN BASED SHEAR 0.139W
 - ANALYSIS PROCEDURE:
EQUIVALENT LATERAL FORCE PER ASCE 7-16, 12.8

FOUNDATION NOTES:

- FOR SLAB ON GRADE AND FOUNDATION SUBGRADE PREPARATION THE CONTRACTOR SHALL REFERENCE RECOMMENDATIONS OF THE GEOTECHNICAL ENGINEERING REPORT.
- FOUNDATION DESIGN BASED ON AN ALLOWABLE SOIL BEARING OF 2,000 PSF.
- EXCAVATE FOOTING TRENCHES AND AREA BELOW SLABS TWO FEET WIDER THAN FOOTING WIDTH AND ONE FOOT DEEPER THAN DESIGN FOOTING GRADE. PROOF ROLL THE EXPOSED TRENCH BOTTOM TO 95% OF MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D-1557. PLACE MIRAFI 500X ON COMPACTED NATIVE SOIL. PLACE A 12" THICK LAYER OF 3/4" MINUS CRUSHED ROCK OVER FABRIC.

CONCRETE NOTES:

- CONCRETE SLABS SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI AT 28 DAYS WITH A WATER TO CEMENT RATIO OF 0.45. ALL OTHER CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI AT 28 DAYS WITH A WATER TO CEMENT RATIO OF 0.5. CONCRETE DESIGN IS BASED UPON ACI 318-14 COMPRESSIVE STRENGTH OF 2500 PSI WITH NO SPECIAL INSPECTION REQUIRED PER IBC 1705.3 REQUIRED.
- CAST IN PLACE CONCRETE SHALL MEET THE FOLLOWING REQUIREMENTS:
ACI 117 - STANDARD SPECIFICATIONS FOR TOLERANCES FOR CONCRETE CONSTRUCTION AND MATERIALS.
ACI 301 - SPECIFICATIONS FOR STRUCTURAL CONCRETE.
ACI 302 - GUIDE FOR CONCRETE FLOOR AND SLAB CONSTRUCTION.
ACI 305 - HOT WEATHER CONCRETING.
ACI 306 - COLD WEATHER CONCRETING.
- UNLESS NOTED OTHERWISE, ALL CONCRETE FLAT WORK SHALL CONFORM TO THE FOLLOWING FINISHING TOLERANCES 1/8" GAP UNDER A 10'-0" STRAIGHT EDGE MEASURED AS PER ASTM E1155:
OVERALL FLATNESS NUMBER, Ff=20
MINIMUM LOCAL FLATNESS NUMBER, Ff=15
OVERALL LEVELNESS NUMBER, Fl=15
MINIMUM LOCAL LEVELNESS NUMBER, Fl=10
- ALL SAWN CONTROL JOINTS ARE TO BE CUT WITHIN 12 HOURS AFTER THE FLOOR SLAB IS POURED, SUCH THAT NO SURFACE DEFECTS ARE MADE FROM FLOOR TRAFFIC AS PER ACI 302.
- ALL CONCRETE FLOORS ARE TO BE WET CURED FOR 7 DAYS IMMEDIATELY AFTER PLACEMENT, AS PER THE RECOMMENDATIONS OF ACI 302, UNLESS NOTED OTHERWISE.
- ALL REINFORCING STEEL SHALL BE GRADE 60 DEFORMED BARS COMPLYING WITH ASTM SECTION A615. REINFORCING STEEL WHICH IS INDICATED ON THE PLANS AS BEING WELDED SHALL COMPLY WITH ASTM A706, AND SHALL ALSO BE DEFORMED. WELDING OF REINFORCING BARS SHALL BE PER AWS D1.4. SPECIAL INSPECTION SHALL BE PREPARED PER AWS D1.1 AND IBC 1705.2.2.1
- ANCHOR RODS SHALL CONFORM TO ASTM F1554 Fy=36 KSI WITH HEAVY HEX HEADED END OR THREADED WITH NUT UNLESS NOTED OTHERWISE ON PLANS. TACK WELD NUT TO ANCHOR ROD.
- REINFORCEMENT LAP HOOKS, ETC.; SHALL BE PER THE REINFORCEMENT TABLE ON VFS-EPM-000-DWG-S-101-2 UNLESS NOTED OTHERWISE.
- THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCEMENT: (MIN. COVER LISTED)
(A) CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH: 3"
(B) CONCRETE EXPOSED TO EARTH OR WEATHER:
#6 THROUGH #18 BARS: 2"
#5 BAR, W31 OR D31 WIRE AND SMALLER: 1 1/2"
(C) CONCRETE NOT EXPOSED TO WEATHER OR IN CONTACT WITH GROUND:
SLABS, WALLS, JOISTS
#14 AND 18 BARS: 1 1/2"
#11 BAR AND SMALLER: 3/4"
BEAMS, COLUMNS
PRIMARY REINFORCEMENT, TIES, STIRRUPS, SPIRALS: 1 1/2"
SHELLS, FOLDED PLATE MEMBERS
#6 BAR AND LARGER: 3/4"
#5 BAR, W31 OR D31 WIRE, AND SMALLER: 1/2"
- CONCRETE ADHESIVE ANCHORS SHALL USE A36 ALL-THREAD ROD WITH HILTI HIT HY 200 ADHESIVE OR SIMPSON SET ADHESIVE, OR ENGINEER APPROVED EQUAL. SPECIAL INSPECTION OF ADHESIVE ANCHORS IS REQUIRED.
- CONCRETE EXPANSION ANCHORS SHALL BE HILTI KWIK BOLT TZ OR SIMPSON STRONG BOLT OR ENGINEER APPROVED EQUAL. STAINLESS STEEL ANCHORS SHALL BE USED AT ALL EXTERIOR APPLICATIONS. SPECIAL INSPECTION OF EXPANSION ANCHORS REQUIRED.
- REINFORCING DOWEL ADHESIVE SHALL BE HILTI HIT HY 200 ADHESIVE, OR SIMPSON SET-XP ADHESIVE. SPECIAL INSPECTION OF ADHESIVE DOWELS IS REQUIRED.
- ALL EXPOSED CORNERS OF CONCRETE SHALL BE FORMED INTO A 3/4" x 45 DEGREE CHAMFER, OR SCRIBED WITH A CONCAVE TOOLING DEVICE UNLESS NOTED OTHERWISE PER ACI 318.
- THOROUGHLY CLEAN FORMS AND ADJACENT SURFACES TO RECEIVE CONCRETE. REMOVE CHIPS, WOOD, SAWDUST, DIRT, OR ANY OTHER DEBRIS PRIOR TO CONCRETE PLACEMENT.
- CLEAN REINFORCING OF LOOSE RUST, MILL SCALE, DIRT, OR ANY OTHER FOREIGN MATERIAL. ACCURATELY POSITION, SUPPORT AND SECURE REINFORCEMENT PER ACI 302.
- PROPORTION AND DESIGN MIXES TO RESULT IN CONCRETE SLUMP AT POINT OF PLACEMENT NOT LESS THAN 3" AND NOT MORE THAN 5" PRIOR TO SUPERPLASTICIZER. ADDITION OF WATER TO READY-MIX CONCRETE IN THE FIELD SHALL BE ALLOWED IF ON TRIP TICKET BEFORE DISCHARGE AND TESTING.
- DEPOSIT CONCRETE IN A CONTINUOUS OPERATION UNTIL THE PLACING OF CONCRETE IS COMPLETE. IF THE POUR IS TO BE DISCONTINUOUS, CONTRACTOR SHALL USE CONSTRUCTION JOINTS, AS DETAILED ON THE DRAWINGS OR APPROVED BY THE ENGINEER.
- UNLESS NOTED OTHERWISE, REINFORCING IS NOT TO EXTEND THROUGH CONSTRUCTION JOINTS OF FLOOR SLABS-ON-GRADE.
- REPAIR ALL SURFACE DEFECTS INCLUDING TIE HOLES, MINOR HONEYCOMBING AND OTHER VISUAL IRREGULARITIES WITH CEMENT MORTAR. MORTAR FOR PATCHING SHALL BE THE SAME COMPOSITION AS THAT USED IN THE CONCRETE. PATCHING SHALL BE DONE AS SOON AS THE FORMS ARE REMOVED.
- PROVIDE (1) 2'-0" LONG #4 REBAR AT ALL RE-ENTRANT CORNERS FOR SLABS, PITS, RECESSES, OR SLAB THICKNESS CHANGES IN THE TOP 1/3 OF THE SLAB-ON-GRADE.
- GROUT MATERIAL FOR BASE PLATES, SLEEVES, AND EMBEDDED STEEL SHALL BE NONMETALLIC, NON-SHRINK, PREPACKAGED GROUT CONFORMING TO ASTM C 1107.
- REINFORCEMENT SHALL BE CONTINUOUS BENT AROUND CORNERS, OR CORNER BARS OF THE SAME SIZE MAY BE INSTALLED WITH MINIMUM LEG LENGTH THAT CONFORMS TO ACI 318-11, CLASS "B" SPLICES.
- EMBEDDED ANGLES CONFORM TO ASTM A36 OR EQUAL.
- AVOID HOT AND WINDY CONDITIONS FOR CURING SLABS. SLABS MUST BE SEALED WITH CURING COMPOUND OR "WATER CURED".

CONCRETE - ADHESIVE ANCHORED REINFORCEMENT AND THREADED RODS NOTES:

- SPECIAL INSPECTION IS REQUIRED AND SHALL BE PER IBC APPROVED ESR REPORT.
- MATERIALS:
ADHESIVE: HILTI-HIT-HY-200
- INSTALLATION:
A. INSTALL PER ESR REPORT IN CLEAN HOLES.
- DO NOT INSTALL REINFORCEMENT OR ANCHORS IN CONCRETE THAT IS LESS THAN 7 DAYS OLD.

CONCRETE - EXPANSION ANCHORS NOTES:

- SPECIAL INSPECTION IS REQUIRED AND SHALL BE PER ICC ESR 1917.
- MATERIALS:
HILTI ANCHORS: KWIK-BOLT TZ
- INSTALLATION:
A. USE CARBIDE-TIPPED DRILL BITS CONFORMING TO ANSI B212.15-1994. DRILL BIT SIZE IS EQUAL TO ANCHOR DIAMETER.
B. CLEAN HOLES OF DUST AND DEBRIS USING OIL-FREE COMPRESSED AIR AND A NYLON BRUSH. HOLE DEPTH TO EXCEED EMBEDMENT DEPTH BY TWO ANCHOR DIAMETERS.
- DO NOT INSTALL ANCHORS IN CONCRETE THAT IS LESS THAN 7 DAYS OLD.
- PROVIDE STAINLESS STEEL ANCHORS OR MECHANICALLY GALVANIZED ANCHORS (PER ASTM B-695) WHERE ANCHORS ARE USED IN EXTERIOR CONDITIONS.

STEEL NOTES:

- STRUCTURAL STEEL MATERIALS SHALL CONFORM TO THE FOLLOWING ASTM SPECIFICATIONS:
A. ALL W & WT SHAPES SHALL CONFORM TO A992 (50 KSI)
B. ALL PLATES, CHANNELS, ANGLES, BARS AND FLATS SHALL CONFORM TO A36 (36 KSI)
C. ALL HOLLOW STRUCTURAL SECTIONS (HSS) SHALL CONFORM TO A500, GRADE B (46 KSI) (46 KSI FOR SHAPED & 42 KSI FOR ROUND)
D. ALL STEEL PIPE SHALL CONFORM TO A53, GRADE B (35 KSI)
- ALL DETAILING, FABRICATION, AND ERECTION OF STRUCTURAL STEEL SHALL COMPLY WITH THE REQUIREMENTS OF THE AISC LOAD AND RESISTANCE FACTOR DESIGN SPECIFICATION FOR STRUCTURAL STEEL BUILDINGS, AND THE AISC REPORT NO. 13.
- ALL FIELD CONNECTIONS SHALL BE MADE WITH 3/4" DIAMETER HIGH STRENGTH BOLTS (A325) UNLESS OTHERWISE NOTED ON THE DRAWING. THE MINIMUM NUMBER OF BOLTS PER CONNECTION SHALL BE TWO (2). BOLTED CONNECTIONS SHALL BE "SNUG TIGHT" WITH SPECIAL INSPECTION PERIODIC MONITORING PER IBC 1705.2. CONNECTIONS SHALL BE DESIGNED AS BEARING TYPE WITH THREADS IN SHEAR PLANE, UNLESS NOTED OTHERWISE. ALL CONNECTIONS ARE TO BE STANDARD, SIMPLE SHEAR FRAMED CONNECTIONS WITH A SHEAR CAPACITY OF AT LEAST 50% OF THE TOTAL CAPACITY OF THE MEMBER. IF MEMBER FRAMING CONNECTIONS ARE NOT SPECIFICALLY DESIGNED AND DETAILED ON THE CONTRACT DRAWINGS BY THE ENGINEER OF RECORD, THE FABRICATOR IS ALLOWED TO SELECT CONNECTION TYPES WHEN PREPARING SHOP DRAWINGS. THE FABRICATOR'S DETAILERS AND CHECKERS MAY DETERMINE THE APPROPRIATE CONNECTION EITHER BY SIMPLE CALCULATION OR BY SELECTION FROM TABLES SHOWN IN A.I.S.C. PUBLICATIONS. THESE CONNECTIONS SHALL BE INDICATED AS FABRICATOR SELECTED ON THE SHOP DRAWINGS AND APPROVED BY ENGINEER OF RECORD PRIOR TO FABRICATION.
- ERECTION AND FABRICATION SHOP DRAWINGS FOR STRUCTURAL STEEL WILL BE REVIEWED BY THE ENGINEER OF RECORD PRIOR TO COMMENCING FABRICATION. ALL DRAWINGS ARE TO BE CHECKED BY THE CONTRACTOR PRIOR TO BEING SUBMITTED FOR THE ENGINEER OF RECORD'S REVIEW.
- BOLT HOLES SHALL BE BOLT DIAMETER + 1/16". BOLT END AND EDGE DISTANCES AND BOLT LENGTHS SHALL BE PER AISC SPECIFICATION 360, SECTION J3.3 AND J3.4, UNLESS NOTED OTHERWISE. BASE PLATE BOLT HOLES MAY BE OVERSIZED BY 1/8".
- ALL WELDING SHALL BE PERFORMED IN ACCORDANCE WITH THE SPECIFICATIONS AND PROCEDURES OF THE AMERICAN WELDING SOCIETY BY AWS CERTIFIED WELDERS AND SHALL CONFORM TO AWS D1.1:2010. WELDERS PERFORMING THE WORK SHALL HAVE BEEN RE-TESTED WITHIN 6 MONTHS PRIOR TO THE START OF STEEL FABRICATION. WELDING FOR STRUCTURAL STEEL SHALL BE MADE WITH E70XX LOW HYDROGEN ELECTRODES. WELDING FOR ATTACHING STEEL DECKING MAY BE MADE WITH E60 ELECTRODES. ALL WELDS SHALL BE SPECIAL INSPECTED PER IBC 1705.2 AND AWS 101.1.
- FIELD WELDING SYMBOLS HAVE NOT NECESSARILY BEEN INDICATED ON THE DRAWINGS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE THE USE OF SHOP AND FIELD WELDING.
- ENDS OF HOLLOW STRUCTURAL SECTION COLUMNS AND EXPOSED MEMBERS SHALL HAVE 3/16" CAP PLATES AND SEAL WELDS ALL ROUND.
- WELDED STEEL GRATING SHALL HAVE 1 1/4" x 3/16" BEARING BARS AT 1 3/16" C/C WITH CROSS BARS AT 4" C/C. BEARING BARS SHALL CONFORM TO ASTM A-589. GRATING LIMITS ARE TO BE THE CENTER LINE OF WIDE FLANGE MEMBERS, OR EDGE OF CHANNEL MEMBERS UNLESS NOTED OTHERWISE. WELD GRATING TO SUPPORTING MEMBERS EVERY 6TH BAR WITH 3/16" x 2" LONG FILET WELDS, 4 WELDS PER PANEL MINIMUM.
- HOLES SHALL NOT BE CUT THROUGH BEAMS UNLESS INDICATED OR PRE-APPROVED BY THE ENGINEER OF RECORD.
- THE MINIMUM THICKNESS OF ANY GUSSET PLATE IS TO BE 3/8 INCH.

- IN ADDITION TO THE STANDARDS OUTLINED IN THE MANUAL FOR STEEL CONSTRUCTION, THE FOLLOWING TOLERANCES MUST ALSO BE FOLLOWED, AS OUTLINED IN AISC TECHNICAL REPORT NO. 13; SWEEP IS NOT TO EXCEED 1/4" IN A 50 FOOT BEAM LENGTH. CAMBER IS NOT TO VARY FROM THE CAMBER GIVEN ON THE DRAWING BY MORE THAN 1/4" IN A 50 FOOT BEAM. SQUARENESS IS TO BE WITHIN 18 INCHES OF EACH GIRDER END, THE FLANGE SHALL BE FREE OF CURVATURE AND NORMAL TO THE GIRDER WEB.
- COLUMN BASE PLATES SHALL BE WITHIN 1/16 IN OF THEORETICAL ELEVATION AND BE LEVEL WITHIN 0.01 INCHES ACROSS THE PLATE LENGTH OR WIDTH.
- PAINT ALL FERROUS METALS FOR EXTERIOR EXPOSURE OR PER PLANT STANDARDS.

STAINLESS STEEL NOTES:

- STAINLESS STEEL TUBES (HSS) SHALL BE TYPE 304 STAINLESS STEEL. STAINLESS STEEL PLATE SHALL BE TYPE 304/304L CONFORMING TO ASTM A240 OR EQUAL.
- ALL WELDING OF STAINLESS STEEL SHALL BE DONE BY AWS CERTIFIED WELDERS AND SHALL CONFORM TO AWS D1.6:2007, WITH APPROPRIATE STAINLESS STEEL ELECTRODES.

ANCHOR RODS NOTES:

- ANCHOR RODS SHALL BE ASTM F1554 GRADE 36 WITH CLASS 1A THREADS, UNLESS NOTED OTHERWISE.
- FURNISH ANCHOR RODS PREFABRICATED WITH MATCHING DOUBLE HEAVY HEX NUTS JAMMED AT THE END EMBEDDED IN CONCRETE.
- FURNISH HARDENED PLATE WASHERS AND MATCHING HEAVY HEX NUTS FOR SECURING THE BASE PLATE TO THE ANCHOR RODS.
- A RIGID TEMPLATE SHALL BE USED TO LOCATE ANCHOR RODS WHILE PLACING CONCRETE.
- NO HEATING OR BENDING OF THE ANCHOR RODS IS PERMITTED.
- HOLES IN THE BASE MATERIAL SHALL NOT BE ENLARGED BY BURNING.

COLD-FORMED STEEL NOTES:

- ALL COLD FORMED STEEL MEMBERS SHALL HAVE A MINIMUM YIELD STRESS OF 33 KSI.
- METAL STUDS SHALL BE ATTACHED TO TOP AND BOTTOM TRACKS WITH (2) #10 SCREWS. METAL STUD MEMBERS IN CONTINUOUS CONTACT SHALL BE CONNECTED WITH #10 SCREWS AT 12" C/C MINIMUM, FY = 33 KSI.
- CONTRACTOR SHALL SUBMIT A SET OF MANUFACTURER'S RECOMMENDED INSTALLATION PROCEDURES FOR METAL STUD FRAMING FOR APPROVAL. DESIGN DOCUMENTS ALONG WITH THE APPROVED INSTALLATION PROCEDURES SHALL BE THE BASIS FOR ACCEPTANCE OF METAL STUD FRAMING.
- BOTTOM TRACK AT NON-SHEARWALLS SHALL BE CONNECTED TO CONCRETE FOUNDATION OR FLOORS WITH POWER ACTUATED FASTENERS AT 12" C/C. POWER ACTUATED FASTENERS SHALL BE HILTI X-U WITH 1" EMBEDMENT OR SIMPSON PDPH WITH 1" EMBEDMENT. ALL WELDS SHALL BE TOUCHED UP WITH ZINC-RICH PAINT. METAL STUDS AND TOP AND BOTTOM TRACK OF FASTENERS AT SHEAR WALLS SHALL BE PER PROVIDED SHEAR WALL SCHEDULE. ATTACHMENT OF STUDS OR TRACK TO ADJACENT STRUCTURE SHALL BE PER PROVIDED DETAILS.
- UNLESS NOTED OTHERWISE, ALL HEADERS FOR OPENINGS UP TO 4'-0" WIDE SHALL BE HDR1 PER THE PROVIDED SCHEDULE. ALL OTHER COLD FORMED STEEL HEADERS SHALL BE PER THE PROVIDED SCHEDULE AS NOTED ON THE DESIGN DRAWINGS.
- SPlice ALL TOP LIGHT GAUGE TRACKS PER TYPICAL STEEL TRACK SPLICE DETAIL. SPLICES IN FRAMING COMPONENTS, OTHER THAN TOP TRACKS, SHALL NOT BE PERMITTED.
- ALL STEEL WALL STUDS SHALL BE 600S162-33 OR 600S162-43, UNLESS NOTED OTHERWISE.
- ALL STUDS AND ACCESSORIES SHALL BE MADE OF THE TYPE, SIZE, GAUGE AND SPACING SHOWN ON THE DRAWINGS WITH 1 5/8" FLANGES, UNLESS NOTED OTHERWISE.
- STEEL STUD DESIGNATIONS BASED ON STEEL STUD MANUFACTURERS ASSOCIATION (SSMA) DESIGNATIONS FROM ICC ESR-3064P.
- ALL METAL STUD FRAMING MEMBERS SHALL BE ZINC COATED AND BEAR PROPER IDENTIFICATION MARKINGS IN ACCORDANCE WITH SSMA STANDARDS.

CONCEPTUAL DESIGN

VEOLIA
NUCLEAR SOLUTIONS - FEDERAL SERVICES
295 Bradley Blvd, Suite 300
Richland, WA 99352
www.nuclearsolutions.veolia.com

NAME	DATE	COMPANY
J. KIENHOLZ		VEOLIA
D. NELSON		VEOLIA
S. MOORE		VEOLIA
J. WILSON		VEOLIA
F. ELLOYD		VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT FACILITY STRUCTURAL NOTES AND ABBREVIATIONS

VFS-EPM-000-DWGS-101

REV	DATE	DESCRIPTION

SCALE: NONE SHEET 1 OF 2

DWG NO	TITLE	REF NUMBER	TITLE

COLD-FORMED STEEL NOTES: (CONTINUED)

- 11. LENGTH OF UNTHREADED "DRILLING" PORTION OF SELF-DRILLING SCREWS USED WITH METAL STUD FRAMING SHALL BE GREATER THAN THE COMBINED THICKNESS OF CONNECTED MATERIALS. IN ADDITION, A MINIMUM OF THREE FULL SCREW THREADS SHALL BE EXPOSED ON SCREWS INSTALLED IN METAL STUD FRAMING MEMBERS.
- 12. ALL STRUCTURAL MEMBERS SHALL BE INSTALLED IN ACCORDANCE WITH AMERICAN IRON AND STEEL INSTITUTE (AISI) "SPECIFICATION FOR THE DESIGN OF COLD-FORMED STEEL STRUCTURAL MEMBERS", LATEST EDITION.
- 13. ALL METAL STUDS SHALL BE FORMED FROM CORROSION-RESISTANT STEEL, CORRESPONDING TO THE REQUIREMENTS OF ASTM C955, WITH A MINIMUM YIELD STRENGTH OF 33 KSI FOR STUDS AND TRACKS, UNLESS OTHERWISE NOTED.
- 14. ALL METAL STUDS AND TRACKS SHALL BE ZINC COATED MEETING ASTM A653, G-60, OR EQUIVALENT.
- 15. PREFABRICATED PANELS SHALL BE SQUARE, WITH COMPONENTS ATTACHED IN A MANNER TO PREVENT RACKING AND TO MINIMIZE DISTORTION WHILE LIFTING AND TRANSPORTING.
- 16. ALL FRAMING COMPONENTS SHALL BE CUT SQUARE FOR ATTACHMENT TO PERPENDICULAR MEMBERS OR, AS REQUIRED, FOR AN ANGULAR FIT AGAINST ABUTTING MEMBERS.
- 17. ALL FRAMING COMPONENTS SHALL BE PLUMBED, ALIGNED AND LEVELED.
- 18. TEMPORARY BRACING, WHERE REQUIRED, SHALL BE PROVIDED UNTIL ERECTION IS COMPLETE.
- 19. COMPLETE, UNIFORM AND LEVEL BEARING SUPPORT SHALL BE PROVIDED FOR THE BOTTOM RUNNER.
- 20. WHERE SUB-FLOORS OR DECKING DO NOT PROVIDE LATERAL SUPPORT, FLOOR JOISTS MUST BE BRACED AT ALL BEARING POINTS AND AT INTERVALS WITHIN SPANS. FOR JOISTS IN CONTINUOUS SPAN CONDITIONS, PORTIONS OF THE BOTTOM FLANGES ARE IN COMPRESSION AND MUST BE LATERALLY BRACED, BASED ON DESIGN REQUIREMENTS, BETWEEN SOLID BLOCKING.
- 21. METAL STUD SHEAR WALLS SHALL BE CONSTRUCTED WITH 1/2" APA STRUCTURAL 1 RATED PLYWOOD PLACED WITH THE LONG DIMENSION PERPENDICULAR TO STUDS. FASTEN SHEATHING WITH NO.8 SELF-DRILLING FLAT OR WAFER HEAD SCREWS AT 6" C/C AT ALL PANEL EDGES AND BLOCKING LINES AND 12" C/C AT STUDS IN PANEL FIELD. PANEL EDGES MAY BE BLOCKED WITH 1 1/2" X 33 MIL CONTINUOUS STRAP WITH (1) NO. 8 AT EACH STUD.
- 22. LENGTH UNTHREADED "DRILLING" PORTION OF SELF-DRILLING SCREWS USED WITH METAL STUD FRAMING SHALL BE GREATER THAN THE COMBINED THICKNESS OF CONNECTED MATERIALS. IN ADDITION, A MINIMUM OF THREE FULL SCREW THREADS SHALL BE EXPOSED ON SCREWS INSTALLED IN METAL STUD FRAMING MEMBERS.

STATEMENT OF SPECIAL INSPECTION NOTES:

- 1. IN ACCORDANCE WITH THE 2015 INTERNATIONAL BUILDING CODE SECTION 1704, THE OWNER SHALL EMPLOY ONE OR MORE APPROVED AGENCIES TO PERFORM INSPECTIONS DURING CONSTRUCTION ON THE TYPES OF WORK AND AS SPECIFIED BELOW. CONTRACTOR SHALL COORDINATE WITH INSPECTION AND TESTING AGENCY(S) FOR REQUIRED CONSTRUCTION INSPECTIONS AND MATERIAL TESTING. SPECIAL INSPECTION REPORTS SHALL BE SUBMITTED TO THE ARCHITECT/ENGINEER AND THE AUTHORITY HAVING JURISDICTION WEEKLY FOR REVIEW.
- 2. WELDING OF CONSTRUCTION OTHER THAN STRUCTURAL STEEL: SPECIAL INSPECTION PER TABLE 1705.2.2 OF THE IBC.
- 3. STEEL: SPECIAL INSPECTION SHALL BE PER SECTION 1705.2 OF THE IBC AND AISC 360 AND AISC 341.
- 4. CONCRETE CONSTRUCTION: SPECIAL INSPECTION PER SECTION 1705.3 AND TABLE 1705.3 OF THE IBC. EXCEPTIONS: NO SPECIAL INSPECTION IS REQUIRED FOR THE FOUNDATIONS IF THE DESIGN STRENGTH OF THE FOUNDATIONS IS BASED ON A COMPRESSIVE STRENGTH OF 2500 PSI.
- 5. SEISMIC RESISTANCE: SPECIAL INSPECTION FOR SEISMIC RESISTANCE SHALL BE PER SECTION 1705.11 OF THE IBC AND AISC 341.
- 6. POST INSTALLED ANCHORS: SPECIAL INSPECTION SHALL BE PER THE ANCHORS ASSOCIATED ICC-ES ESR.


METAL BUILDING NOTES:

- 1. INSTALL PRE-ENGINEERED METAL BUILDING PER MANUFACTURER.

ABBREVIATIONS:

AB	ANCHOR BOLT	KSI	KIPS PER SQUARE INCH
ACI	AMERICAN CONCRETE INSTITUTE	L	ANGLE
AFF	ABOVE FINISH FLOOR	LB	POUND; POUNDS
AISC	AMERICAN INSTITUTE OF STEEL	LF	LINEAR FOOT
	CONSTRUCTION	LL	DOUBLE ANGLE
ALT	ALTERNATE	LLH	LONG LEG HORIZONTAL
AR	ANCHOR ROD	LLV	LONG LEG VERTICAL
ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIALS	MAX	MAXIMUM
		MFR	MANUFACTURER
AWS	AMERICAN WELDING SOCIETY	MIN	MINIMUM
BM	BEAM	MISC	MISCELLANEOUS
BOB	BOTTOM OF BEAM	N	NORTH
BOBP	BOTTOM OF BASE PLATE	N-S	NORTH-SOUTH
BOD	BOTTOM OF DECK	NS	NEAR SIDE
BOF	BOTTOM OF FOOTING	NTS	NOT TO SCALE
BP#	BASE PLATE NUMBER	OPP	OPPOSITE HAND
C/C	CENTER TO CENTER	OVS	OVERSIZE
C/P	CAST-IN-PLACE	OWJ	OPEN WEB JOIST
CJ	CONSTRUCTION JOINT	P	PRESSURE
CL	CLEARANCE	PAF	POWER ACTUATED FASTENER
CLR	CLEAR	PCF	PER CUBIC FOOT
COC	CENTER LINE OF COLUMN	PEMB	PRE-ENGINEERED METAL BUILDING
COL	COLUMN	PERP	PERPENDICULAR
CONC	CONCRETE	PL	PLATE
CONN	CONNECTION	PLF	PER LINEAR FOOT
CONT	CONTINUOUS	PP	PANEL POINT
COTF	CLEAN OUT TO FLOOR	PREFAB	PREFABRICATED
CTR	CENTER	PSF	POUNDS PER SQUARE FOOT
CP	CONTROL POINT	PSI	POUNDS PER SQUARE INCH
DB	DOUBLE	PT	POINT
DET	DETAIL	R	RADIUS
DIA	DIAMETER	REF	REFERENCE
DIAG	DIAGONAL	REINF	REINFORCEMENT; REINFORCING
DICA	DRILLED IN CONCRETE ANCHOR	REQD	REQUIRED
DIM	DIMENSION	SC	SCALE
DJ	DUMMY JOINT	SCJ	SAWN CONTROL JOINT
DL	DEAD LOAD	SECT	SECTION
DN	DOWN	SIM	SIMILAR
DSL	DRIFT SNOW LOAD	SJ	STEEL JOIST
DWL	DOWEL	SL	SNOW LOAD
(E)	EXISTING	SOG	SLAB ON GRADE
EA	EACH	STD	STANDARD
EF	EACH FACE	SPEC	SPECIFICATION
EJ	EXPANSION JOINT	SQ	SQUARE
EL OR ELEV	ELEVATION	SSL	STAINLESS STEEL
EMBED	EMBEDMENT	STIFF	STIFFENER
EQ SP	EQUALLY SPACED	STL	STEEL
EW	EACH WAY	STRUC	STRUCTURAL
FD	FLOOR DRAIN	T&B	TOP AND BOTTOM
FDN	FOUNDATION	TEMP	TEMPORARY
FF	FINISH FLOOR	TOC	TOP OF CONCRETE
FIN	FINISHED	TOD	TOP OF DECK
FL	FLOOR	TOF	TOP OF FOOTING
FOS	FACE OF STUD	TOS	TOP OF STEEL
FOW	FACE OF WALL	TOSW	TOP OF STEM WALL
FS	FLOOR SINK	TOT	TOP OF TRACK
FT	FOOT; FEET	TYP	TYPICAL
FT#	FOOT TYPE - NUMBER	UNO	UNLESS NOTED OTHERWISE
FTG	FOOTING	VERT	VERTICAL
GB	GYPSON BOARD	W	WIDE; WIDTH
H	HIGH	W	WITH
HP	HIGH POINT	WO	WITHOUT
HSS	HOLLOW STRUCTURAL SECTION	WF	WIDE FLANGE
ICBO	INTERNATIONAL COUNCIL OF BUILDING OFFICIALS	WP	WORK POINT
		WUL	WIND UPLIFT LOAD
IN	INCH; INCHES		
INT	INTERIOR		
JB	JOIST BEARING		
JST	JOIST		
JT	JOINT		
K	KIP; KIPS		

SYMBOLS:



EXPANSION ANCHOR SCHEDULE

ANCHOR DIAMETER	HILTI KWIK BOLT TZ			SIMPSON STRONG BOLT		
	SHALLOW	STANDARD	DEEP	SHALLOW	STANDARD	DEEP
1/2"	2"	3 1/4"	-	2 3/4"	3 7/8"	5"
5/8"	3 1/8"	4"	-	3 3/8"	5 1/8"	6 1/8"
3/4"	3 3/4"	5"	-	4 1/8"	5 3/4"	7 1/2"
1"	-	-	-	-	5 1/4"	9 3/4"

F

F

E

E

D

D

C

C

B

B

A

A

CONCEPTUAL DESIGN

VEOLIA NUCLEAR SOLUTIONS - FEDERAL SERVICES
 295 Bradley Blvd, Suite 300
 Richland, WA 99352
 www.nuclearsolutions.veolia.com

NAME	DATE	COMPANY
J KIENHOLZ	10/11/11	VEOLIA
D NELSON		VEOLIA
S MOORE		VEOLIA
J WILLSON		VEOLIA
E LLOYD		VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT


WESTERN AREA TREATMENT FACILITY STRUCTURAL NOTES AND ABBREVIATIONS

DESIGN AUTHORITY: **F** DWG NO: **VFS-EPM-000-DWG-S-101** REV: **B**

SCALE: NONE EST SHEET 2 OF 2

DWG NO	TITLE	REF NUMBER	TITLE	WFS	REV NO	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							

VFS-EPM-000-DWG-S-101 REV B




- NOTES:**
- SEE VFS-EPM-000-DWG-S-101 FOR NOTES, ABBREVIATIONS AND SCHEDULE.
 - FIELD LOCATE HOUSEKEEPING PADS. SEE SECTION G ON VFS-EPM-000-DWG-S-115 SHEET 3 FOR REINFORCEMENT.
 - SEE BURNS & McDONALD CIVIL DRAWINGS FOR FINISH FLOOR ELEVATION.
 - SEE VFS-EPM-000-DWG-S-120 FOR STEEL FRAMING FOR MEZZANINE.
 - LOCATE PIPE SUPPORTS PER GENERAL ARRANGEMENT DRAWING. SEE VFS-EPM-000-DWG-S-115 SHEET 4 FOR PIPE SUPPORT.
 - SEE SHEET 2 FOR TRENCH AND SUMP LOCATIONS, AND SLOPE OF SLAB.


FOOTING SCHEDULE

KEY: FOOTING TYPE DIMENSION WIDTH FTX-XX DIMENSION LENGTH

FOOTING	DIMENSIONS			REINFORCEMENT EQ SP EW	PEDESTAL				REMARKS/DETAILS
	L	W	T		A	B	C	D	
FT1-55	5'-0"	5'-0"	2'-0"	(6) #5, TOP & BOTTOM	0'-9"	1'-0"	1'-3"	-	DETAIL 3/S-115 SHEET 1 (END COLUMNS)
FT2-55	5'-0"	5'-0"	2'-0"	(6) #5, TOP & BOTTOM	1'-0"	1'-0"	1'-0"	1'-0"	DETAIL 2/S-115 SHEET 1 (CORNER COLUMNS)
FT1-66	6'-6"	6'-6"	2'-0"	(7) #5, TOP & BOTTOM	0'-9"	1'-0"	1'-3"	-	DETAIL 3/S-115 SHEET 1 (END COLUMNS)
FT2-66	6'-0"	6'-0"	2'-0"	(7) #5, TOP & BOTTOM	1'-0"	1'-0"	1'-0"	1'-0"	DETAIL 2/S-115 SHEET 1 (CORNER COLUMNS)
FT1-1010	10'-0"	10'-0"	2'-0"	(11) #5, TOP & BOTTOM	0'-9"	1'-0"	1'-3"	-	DETAIL 1/S-115 SHEET 1



BOLT DIA	A	B
1/2"	6"	2"
5/8"	8"	2"
3/4"	10"	2"
7/8"	12"	2"
1"	14"	3"
1 1/8"	16"	3"
1 1/4"	18"	3"
1 1/2"	20"	3"



WATF FOUNDATION - PLAN

SCALE: 1/8" = 1'-0"
1/8" = 1'-0"
SCALE

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REVISIONS

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352


CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT FACILITY STRUCTURAL FOUNDATION PLAN

VFS-EPM-000-DWG-S-110

SCALE SHOWN 1 OF 2

VFS-EPM-000-DWG-S-110 SH 1 OF 1 REV C



- NOTES:
- SEE VFS-EPM-000-DWG-S-101 FOR NOTES, ABBREVIATIONS AND SCHEDULE.
 - FIELD LOCATE HOUSEKEEPING PADS. SEE SECTION G ON VFS-EPM-000-DWG-S-115 SHEET 3 FOR REINFORCEMENT.
 - SEE BURNS & McDONALD CIVIL DRAWINGS FOR FINISH FLOOR ELEVATION.
 - SEE VFS-EPM-000-DWG-S-120 FOR STEEL FRAMING FOR MEZZANINE.

TRENCH AND SUMP PLAN
 SCALE: 1/8" = 1'-0"
 1/8" = 1'-0" SCALE FEET

VEOLIA
 VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

CONCEPTUAL DESIGN

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT FACILITY STRUCTURAL FOUNDATION PLAN

VFS-EPM-000-DWG-S-110

DATE: 10/13/21
 DESIGNED BY: J. KIENHOLZ
 CHECKED BY: D. NELSON
 DRAWN BY: S. MOORE
 REVISIONS BY: J. WILSON, M. BLOOMER, E. ELLOYD

SCALE: SHOWN EST SHEET 2 OF 2

DWG NO	TITLE	REF NUMBER	TITLE	WFO	REV	DESCRIPTION	REV	DATE	ENGR	COMPL
DRAWING TRACEABILITY LIST		REFERENCES		WFO	REV	DESCRIPTION	REV	DATE	ENGR	COMPL
NEXT USED ON		REVISED								

VFS-EPM-000-DWG-S-110 SH 1 OF 1 REV C

8

7

6

5

4


3

2


1

NOTES:

- 1. SEE VFS-EPM-000-DWG-S-101 FOR NOTES, ABBREVIATIONS AND SCHEDULE.
- 2. SEE CIVIL FOR PLAN LOCATIONS, VFS-EPM-000-DWG-C-110.



1 12K TANK FOUNDATIONS
 C-110 SCALE: 3/4" = 1'-0"



A SECTION
 SCALE: 1 1/2" = 1'-0"

CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT
 FACILITY TANK FOUNDATION
 PLAN VIEW /DETAIL

VFS-EPM-000-DWG-S-114

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST									
NEXT USED ON									
REVISIONS									

NAME	DATE	CONTR
IS MOORE	10/25/14	VEOLIA
CHRISTOPHER	10/25/14	VEOLIA
J PIERCE	10/25/14	VEOLIA
D NELSON	10/25/14	VEOLIA
J WILSON	10/25/14	VEOLIA
ELLOYD	10/25/14	VEOLIA

SCALE	SHOWN	REV	SHEET	OF
F			1	1

VFS-EPM-000-DWG-S-114 SH. 1 OF 1 (REV)

8

7

6

5

4


3

2

1


8 7 6 5 4 3 2 1

- NOTES:**
- SEE VFS-EPM-000-DWG-S-101 FOR NOTES, ABBREVIATIONS AND SCHEDULE.
 - UNO, USE MINIMUM CONCRETE EMBEDMENT, SPLICES, REBAR, ETC. PER ACI 318.




1 DETAIL
S-110-1 SCALE: 3/4"=1'-0"

NOTE:
1. SEE FOOTING SCHEDULE TABLE ON DRAWING VFS-EPM-000-DWG-S-110 FOR DETAIL CALLOUT.




2 DETAIL
S-110-1 SCALE: 3/4"=1'-0"

NOTE:
1. SEE FOOTING SCHEDULE TABLE ON DRAWING VFS-EPM-000-DWG-S-110 FOR DETAIL CALLOUT.



3 DETAIL
S-110-1 SCALE: 3/4"=1'-0"

NOTE:
1. SEE FOOTING SCHEDULE TABLE ON DRAWING VFS-EPM-000-DWG-S-110 FOR DETAIL CALLOUT.



4 DETAIL
S-110-1 SCALE: 3/4"=1'-0"

NOTE:
1. SEE FOOTING SCHEDULE TABLE ON DRAWING VFS-EPM-000-DWG-S-110 FOR DETAIL CALLOUT.

CONCEPTUAL DESIGN

VEOLIA NUCLEAR SOLUTIONS - FEDERAL SERVICES
295 Bradley Blvd, Suite 300
Richland, WA 99352
www.nuclearsolutions.veolia.com

NAME	DATE	COMMENTS
J. KRIENHOLZ	10/1/11	ISS
D. NELSON		ISS
S. MOORE		ISS
J. WILSON		ISS
E. LLOYD		ISS

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA
TREATMENT FACILITY
STRUCTURAL DETAILS

VFS-EPM-000-DWG-S-115

DWG NO	TITLE	REF NUMBER	TITLE	REF	REV	NO	DESCRIPTION	REV	DATE	BY	CHKD	APPV
DRAWING TRACEABILITY LIST				REFERENCES				REVISIONS				
		NEXT USED ON										


VFS-EPM-000-DWG-S-115 SH. 1 OF 2 REV C

8 7 6 5 4 3 2 1

8 7 6 5 4 3 2 1

NOTES:

1. SEE VFS-EPM-000-DWG-S-101 FOR NOTES, ABBREVIATIONS AND SCHEDULE.
2. UNO, USE MINIMUM CONCRETE EMBEDMENT, SPLICES, REBAR, ETC. PER ACI 318.



- NOTE:**
1. USE ZURN Z882 WITH DUCTILE IRON SLOTTED GRATE - CLASS E.
 2. DIMENSION "A" IS MINIMUM 6.25"
DIMENSION "B" IS MAXIMUM 11.25"

17 **DETAIL**
S-110-3 SCALE: 1"=1'-0"

CONCEPTUAL DESIGN

VEOLIA NUCLEAR SOLUTIONS - FEDERAL SERVICES
 295 Bradley Blvd, Suite 300
 Richland, WA 99352
 www.nuclearsolutions.veolia.com

NAME	DATE	COMPANY
J. KRENHOLZ	10/13/21	VEOLIA
D. NELSON		VEOLIA
S. MOORE		VEOLIA
J. WILSON		VEOLIA
E. LLOYD		VEOLIA

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA
 STRUCTURAL DETAILS

VFS-EPM-000-DWG-S-115


DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	DESCRIPTION
DRAWING TRACEABILITY LIST		REFERENCES		REV		REV		REV	
NEXT USED ON		REFERENCES		REV		REV		REV	

SCALE	SHOWN	EDT	SHEET	OF	REV
F			2	5	C


8 7 6 5 4 3 2 1

VFS-EPM-000-DWG-S-115 | BH | 1 OF 2 | REV C


- NOTES:**
- SEE VFS-EPM-000-DWG-S-101 FOR NOTES, ABBREVIATIONS AND SCHEDULE.
 - SEE VFS-EPM-000-DWG-S-110 SHEET 1 FOR FOUNDATION PLAN.
 - UNO, USE MINIMUM CONCRETE EMBEDMENT, SPLICES, REBAR, ETC. PER ACI 318.




A SECTION
S-115-1 SCALE: 3/4" = 1'-0"




B SECTION
S-115-1 SCALE: 3/4" = 1'-0"




C SECTION
S-110-1 SCALE: 3/4" = 1'-0"




D SECTION
S-110-1 SCALE: 3/4" = 1'-0"
NOTE:
1. TYPICAL AT DOORS.




E SECTION
S-110-1 SCALE: 3/4" = 1'-0"




F SECTION
S-115-1 SCALE: NONE



G SECTION
S-110-1, -2 SCALE: 3/4" = 1'-0"



H SECTION
S-110-1 SCALE: 3/4" = 1'-0"
NOTE:
1. ALL JOINTS BELOW GRADE SHALL HAVE BENTONITE WATERSTOP.



J SECTION
S-110-3 SCALE: 3/4" = 1'-0"
NOTE:
1. ALL JOINTS BELOW GRADE SHALL HAVE BENTONITE WATERSTOP.

CONCEPTUAL DESIGN

VEOLIA
NUCLEAR SOLUTIONS - FEDERAL SERVICES
295 Bradley Blvd, Suite 300
Richland, WA 99352
www.nuclearsolutions.veolia.com

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
STRUCTURAL DETAILS

VFS-EPM-000-DWG-S-115

NO.	DATE	BY	CHKD.	DESCRIPTION
1	10/12/11	J. KRIEGER	D. NELSON	ISSUE FOR PERMIT
2		S. MOORE	J. WILSON	REVISED FOR COMMENTS
3		J. WILSON	E. LLOYD	REVISED FOR COMMENTS


DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV	DATE	BY	CHKD.

VFS-EPM-000-DWG-S-115 SH. 2 OF 2 (REV. B)


8 7 6 5 4 3 2 1

NOTES:


1. SEE VFS-EPM-000-DWG-S-101 FOR NOTES, ABBREVIATIONS AND SCHEDULE.
2. SEE VFS-EPM-000-DWG-S-110 SHEET 1 FOR FOUNDATION PLAN.
3. UNO, USE MINIMUM CONCRETE EMBEDMENT, SPLICES, REBAR, ETC. PER ACT 318.




12 DETAIL - WALL PIPE SUPPORTS
SCALE: 1" = 1'-0"




13 DETAIL - FLOOR PIPE SUPPORTS
SCALE: 1" = 1'-0"





14 DETAIL - ROOF PIPE SUPPORTS
SCALE: 1" = 1'-0"



15 DETAIL-PIPE SUPPORT EXTERIOR
SCALE: 1 1/2" = 1'-0"



16 DETAIL - PIPE SUPPORTS - EXTERIOR
SCALE: 1" = 1'-0"



17 DETAIL - FLOOR PIPE SUPPORTS - INTERIOR
SCALE: 1" = 1'-0"

CONCEPTUAL DESIGN

VEOLIA
NUCLEAR SOLUTIONS - FEDERAL SERVICES
295 Bradley Blvd, Suite 300
Richland, WA 99352
www.nuclearsolutions.veolia.com

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
STRUCTURAL DETAILS

VFS-EPM-000-DWG-S-115


NO.	DATE	BY	CHKD	APP'D	DESCRIPTION
1	10/13/21	J. RIENHOLZ			ISSUED FOR PERMIT
2		D. NELSON			REVISED
3		S. MOORE			REVISED
4		B. MOORE			REVISED
5		J. WILSON			REVISED
6		M. ELLOYD			REVISED

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	ENGR	COMPANY

SCALE: SHOWN 1:1 SHEET 4 OF 5

VFS-EPM-000-DWG-S-115 SH 2 OF 2 REV B

8 7 6 5 4 3 2 1




RECOMMENDED END HOOKS, ALL GRADES OF STEEL

BAR SIZE	D	180° HOOKS		90° HOOKS	
		A OR G	J	A OR G	
#3	2 1/4"	5"	3"	6"	
#4	3"	6"	4"	8"	
#5	3 3/4"	7"	5"	10"	
#6	4 1/2"	8"	6"	1'-0"	
#7	5 1/4"	10"	7"	1'-2"	
#8	6"	11"	8"	1'-4"	
#9	9 1/2"	1'-3"	11 3/4"	1'-7"	
#10	10 3/4"	1'-5"	1'-1 1/4"	1'-10"	
#11	12"	1'-7"	1'-2 3/4"	2'-0"	
#14	18 1/4"	2'-3"	1'-9 3/4"	2'-7"	
#18	24"	3'-0"	2'-4 1/2"	3'-5"	

- ALL GRADES OF STEEL:
- D = FINISHED INSIDE BEND DIAMETER.
 - d_b = NOMINAL BAR DIAMETER.
 - MIN. D = 6 d_b FOR #3 THROUGH #8.
 - MIN. D = 8 d_b FOR #9, 10 AND #11.
 - MIN. D = 10 d_b FOR #14 AND #18.


1 STANDARD BAR BENDS
SCALE: 3/4" = 1'-0"



BAR SIZE	D	90° HOOKS		135° HOOKS	
		A OR G	A OR G	H	
#3	1 1/2"	4"	4"	2 1/2"	
#4	2"	4 1/2"	4 1/2"	3"	
#5	2 1/2"	6"	5 1/2"	3 3/4"	
#6	4 1/2"	1'-0"	8"	4 1/2"	
#7	5 1/4"	1'-2"	9"	5 1/4"	
#8	6"	1'-4"	10 1/2"	6"	

* - H DIMENSION IS APPROXIMATE

2 STANDARD BAR BENDS
SCALE: 3/4" = 1'-0"



4 REINF CORNER WALL LAP SPLICE
SCALE: 3/4" = 1'-0"

f _c = 2500 psi				f _c = 3000 psi			
BAR SIZE	LAP CLASS	LENGTH (INCHES)		BAR SIZE	LAP CLASS	LENGTH (INCHES)	
		TOP BARS	OTHER BARS			TOP BARS	OTHER BARS
#3	A	24	18	#3	A	22	17
	B	31	24		B	28	22
#4	A	32	24	#4	A	29	22
	B	41	32		B	38	29
#5	A	39	30	#5	A	36	28
	B	51	39		B	47	36
#6	A	47	36	#6	A	43	33
	B	61	47		B	56	43
#7	A	55	42	#7	A	50	39
	B	71	55		B	65	50
#8	A	63	48	#8	A	57	44
	B	82	63		B	75	57
#9	A	71	54	#9	A	65	50
	B	92	71		B	84	65
#10	A	78	60	#10	A	72	55
	B	102	78		B	93	72
#11	A	86	66	#11	A	79	61
	B	112	86		B	102	79

- NOTES
- TABULATED VALUES ARE BASED ON GRADE 60 REINFORCING BARS AND NORMAL WEIGHT CONCRETE.
 - TENSION DEVELOPMENT LENGTHS AND TENSION LAP SPLICE LENGTHS ARE CALCULATED PER ACI 318-14, SECTIONS 25.4.2 AND 25.5.2, RESPECTIVELY. TABULATED VALUES FOR BEAMS OR COLUMNS ARE BASED ON TRANSVERSE REINFORCEMENT AND CONCRETE COVER MEETING MINIMUM CODE REQUIREMENTS. LENGTHS ARE IN INCHES.
 - CASE 1 COVER AT LEAST 1.0 d_b AND C.-C. SPACING AT LEAST 2.0 d_b.
 - CASE 2 COVER LESS THAN 1.0 d_b OR C.-C. SPACING LESS THAN 2.0 d_b.
 - ALL OTHERS:
 - CASE 1 COVER AT LEAST 1.0 d_b AND C.-C. SPACING AT LEAST 3.0 d_b.
 - CASE 2 COVER LESS THAN 1.0 d_b OR C.-C. SPACING LESS THAN 3.0 d_b.
 - LAP SPLICE LENGTHS ARE MULTIPLES OF TENSION DEVELOPMENT LENGTHS; CLASS A = 1.0 l_d AND CLASS B = 1.3 l_d (ACI 318-14, SECTION 20.5.2).
 - ACI 318-14 DOES NOT ALLOW LAP SPLICES OF #14 OR #18 BARS AND ARE NOT SHOWN FOR CLARITY.
 - TOP BARS ARE HORIZONTAL BARS WITH MORE THAN 12 INCHES OF CONCRETE CAST BELOW THE BARS.
 - FOR LIGHTWEIGHT AGGREGATE CONCRETE, MULTIPLY THE TABULATED VALUES BY 1.3.
 - FOR EPOXY-COATED BARS, MULTIPLY THE TABULATED VALUES BY ONE OF THE FOLLOWING FACTORS

CONCRETE COVER AND SPACING	TOP BARS	OTHER BARS
COVER < 3.0 d _b OR C.-C. SPACING < 7.0 d _b	1.7/1.3 = 1.31	1.50
COVER ≥ 3.0 d _b OR C.-C. SPACING ≥ 7.0 d _b	1.20	1.20
 - ALL CALCULATIONS SHOWN ABOVE ARE ASSUMED TO BE CASE 2.

3 LAP SPLICE AND DEVELOPMENT LENGTH
SCALE: NOT TO SCALE

CONCEPTUAL DESIGN

VEOLIA NUCLEAR SOLUTIONS - FEDERAL SERVICES
295 Bradley Blvd, Suite 300
Richland, WA 99352
www.nuclearsolutions.veolia.com

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA
TREATMENT FACILITY
STRUCTURAL DETAILS

VFS-EPM-000-DWG-S-115

NAME	DATE	COMPANY
J. KIENHOLZ	10/13/21	VEOLIA
D. NELSON		VEOLIA
S. MOORE		VEOLIA
J. WILSON		VEOLIA
E. LLOYD		VEOLIA

DWG NO	TITLE	REF NUMBER	TITLE	REF NUMBER	TITLE	REF NUMBER	TITLE

REV	DATE	DESCRIPTION	BY	CHKD


SCALE: SHOWN

SHEET 5 OF 5

VFS-EPM-000-DWG-S-115 5H 3 OF 5 REV B

NOTES & SPECIFICATIONS:

- DIMENSIONS AND TOLERANCES PER ASME Y14.5M-94. DIMENSIONS ARE IN INCHES. TOLERANCES: X ± .1, XX ± .03, XXX ± .005. FRACTIONAL: ± 1/8. ANGULAR: ± 2'
- INTERIOR PROCESS AREA SURFACES SHALL BE NON-POROUS. AVOID USE OF ZINC ON INTERIOR SURFACES IN THE PROCESS AREA.
- FOR PENETRATIONS AND MOUNTING OF PANELS SEE ELECTRICAL INSTALLATION DRAWINGS.
- BREAK SHARP EDGES, REMOVE BURRS.
- WELDING PER AWS D1.6. PROCEDURE AND WELDER QUALIFICATIONS PER ASME SECTION IX ARE ACCEPTABLE.
- FABRICATION DETAILS AND STANDARDS PER NORMAL AND CUSTOMARY FOR INTERMODAL CONSTRUCTION.
- PIPE AND COMPONENTS TO BE WELDED OR FLANGE CONNECTIONS USING FLEXITALLIC CGI-150
- APPROXIMATE DRY WEIGHT 14,303 LBS



1 WESTERN AREA TREATMENT FACILITY URANIUM TRAIN SKID
SCALE: NOT TO SCALE

PARTS/MATERIAL LIST

ITEM NO.	QTY.	PART NUMBER	TITLE	DESCRIPTION	MATERIAL/REFERENCE
1	-		WESTERN AREA TREATMENT FACILITY URANIUM TRAIN SKID	N/A	N/A
2	1	VFV-EPM-000-DWG-M-110	SKID FRAME	WESTERN AREA TREATMENT FACILITY SKID FRAME	N/A
3	AR	20893104	FLEXIBLE HOSE	2", CORRUGATED EPDM	CONTINENTAL
4	6	1700DL SERIES	COUPLER	2" DRY DISCONNECT	KAMVALOK
5	6	1600AN SERIES	ADAPTER	2" ADAPTER FOR DRY DISCONNECT	KAMVALOK
6	3		PROCESS VESSEL	48" DIA.	TBD
7	2	EJA-530E	PRESSURE TRANSDUCER	WITH VALVE	YOKOGAWA
8	1	A242408LP	PLC ENCLOSURE	24x24x8	HOFFMAN
9	1	FLT93B-AB00	LEAK DETECTOR	FLT93B FLEXSWITCH	FCI
10	1	52005381	PH ELEMENT	NPT THREADED INPRO4260I	METTLER TOLEDO
11	1	52402401	PH HOUSING	INTRAC 787 INPRO	METTLER TOLEDO
12	1		I&C RACK	HSS2X2X.25	OTS STAINLESS STEEL
13	4	EJA110E-JHS5G-912DJFF1/D1/N4	DIFFERENTIAL PRESSURE TRANSMITTER	WITH VALVE BLOCK	YOKOGAWA
14	1	MH4BF07-60-2SH	MOTOR OPERATED VALVE	3" FLANGED VALVE	INDELAC
15	1	DS3-3	INLINE STATIC MIXER	3IN X 19IN LG	JDMIX
16	2	3" DL2R-36-36-5-36	CHECK VALVE	3IN FLANGED SWING TYPE	KECKLEY
17	12	ANH-K5L-G-03	BALL VALVE	3IN FLANGE WITH POSITION SWITCH	PMB
18	1	AFX	FLOW METER	MAGNETIC	YOKAGAWA
19	1	32RFS-36062P34-BK	SIMPLEX BASKET STRAINER	3IN RF FLANGE	KECKLEY
20	1	58-031-404	UNICOND CONDUCTIVITY SENSOR	2-ELECTRODE	METTLER TOLEDO
21	1	LPG4MA-KTC1-SKO	ACID DOSING SKID	41 GPD @ 250 PSI 115 VAC	NOVATECH
22	8			1/2" DIA HILTI KWIK BOLT TZ WITH 3 5/8" EMBED	
23	4	ANH-K5L-G	BALL VALVE	3IN FLANGE	PMB
24	1		SAMPLE BOX ASSEMBLY		
25	1	ANH-C5P-G	BALL VALVE	1/2" FULL-PORT, FNPT, SS	PMB

CONCEPTUAL DESIGN

VEOLIA NUCLEAR SOLUTIONS - FEDERAL SERVICES
295 Bradley Blvd, Suite 300
Richland, VA 99352
www.nuclearsolutions.veolia.com

NAME	DATE	COMPANY	SCALE
J. PIERCE		VEOLIA	
E. LLOYD		VEOLIA	
S. MOORE		VEOLIA	
J. WILSON		VEOLIA	
E. LLOYD		VEOLIA	

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

MECHANICAL
WESTERN AREA TREATMENT FACILITY
URANIUM TRAIN SKID ARRANGEMENT


F VFS-EPM-000-DWG-M-110 **D**
SCALE SHOWN SHEET 1 OF 6

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV DATE	BY	CHK	APP
	DRAWING TRACEABILITY LIST		REFERENCES					


DWG NO VFS-EPM-000-DWG-M-110 ST 1 OF 6

8 7 6 5 4 3 2 1


F
E
D
C
B
A




PLAN VIEW
SCALE 1:16
ITEMS NOT SHOWN FOR CLARITY



B SECTION
SCALE 1:16



A SECTION
SCALE 1:16



RIGHT SIDE
SCALE 1:16
ITEMS NOT SHOWN FOR CLARITY

F
E
D
C
B
A
REV D
SHEET 2 OF 6

CONCEPTUAL DESIGN

VEOLIA NUCLEAR SOLUTIONS - FEDERAL SERVICES
295 Bradley Blvd, Suite 300
Richland, WA 99352
www.nuclearsolutions.veolia.com

NAME	DATE	COMPANY
J. PIERCE	11/27/14	VEOLIA
F. FLOYD		VEOLIA
S. MOORE		VEOLIA
T. WILSON		VEOLIA
F. FLOYD		VEOLIA

CIMARRON	
PUMP AND TREAT SYSTEM PROJECT	
MECHANICAL	
WESTERN AREA TREATMENT FACILITY	
URANIUM TRAIN SKID ARRANGEMENT	
REV	DESCRIPTION
F	SCALE SHOWN

DWG NO	TITLE	REF NUMBER	TITLE	REF	REV	DESCRIPTION	REV	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							

8 7 6 5 4 3 2 1

8

7

6

5

4

3

2

1

F

F

E

E

D

D

C


C

B

B

A

A



ISO
SCALE: NOT TO SCALE

CONCEPTUAL DESIGN


VEOLIA NUCLEAR SOLUTIONS - FEDERAL SERVICES
 295 Bradley Blvd, Suite 300
 Richland, WA 99352
 www.nuclearsolutions.veolia.com

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
 MECHANICAL
 WESTERN AREA TREATMENT FACILITY
 URANIUM TRAIN SKID ARRANGEMENT

SCALE SHOWN: **F**
 SHEET 3 OF 6

DWG NO	TITLE	REF NUMBER	TITLE	REF NO	REV NO	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS						

DWG NO VFS-EPM-000-DWG-M-110 3 of 6 REV'D



FRONT
SCALE 1:12
ITEMS NOT SHOWN
FOR CLARITY

CONCEPTUAL DESIGN

VEOLIA NUCLEAR SOLUTIONS - FEDERAL SERVICES
295 Bradley Blvd, Suite 300
Richland, WA 99352
www.nuclearsolutions.veolia.com

NAME	DATE	COMMENTS
LI PIERCE	11/27/14	UNFRD
FLOYD		UNFRD
S MOORE		UNFRD
T WILSON		UNFRD
FLOYD		UNFRD

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

MECHANICAL
WESTERN AREA TREATMENT FACILITY
URANIUM TRAIN SKID ARRANGEMENT

REF: ENGINEERING
F VFS-EPM-000-DWG-M-110 **D**
SCALE SHOWN SHEET 4 OF 6

DWG NO	TITLE	REF NUMBER	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV	BY	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		NEXT USED ON		REFERENCES						

VFS-EPM-000-DWG-M-110 4 of 6

8

7

6

5

4

3

2

1

F

F

E

E

D

D

C


C

B


B

A

A



PLAN VIEW
SCALE 1:12
ITEMS NOT SHOWN FOR CLARITY



SECTION
SCALE 1:12

CONCEPTUAL DESIGN

VEOLIA NUCLEAR SOLUTIONS - FEDERAL SERVICES
295 Bradley Blvd, Suite 300
Richland, WA 99352
www.nuclearsolutions.veolia.com

NAME	DATE	COMPANY	
APPROVED L PIERCE		VEOLIA	
DESIGNED E TLOYD		VEOLIA	
CHECKED S MOORE		VEOLIA	
PROJECT MANAGER T WILSON		VEOLIA	
PROJECT ENGINEER E TLOYD		VEOLIA	

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

MECHANICAL
WESTERN AREA TREATMENT FACILITY
URANIUM TRAIN SKID ARRANGEMENT

SCALE SHOWN: **F** SHEET 5 OF 6

DWG NO	TITLE	REF NUMBER	TITLE	REV	KEY NO	DESCRIPTION	REV DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST									
NEXT USED ON		REFERENCES							
REVISIONS									

DWG NO VFS-EPM-000-DWG-M-110 5 OF 6

8

7

6

5

4

3

2

1

F

F

E

E

D

D

C


C

B

B

A

A



RIGHT SIDE
 SCALE: 1:3
 ITEMS NOT SHOWN FOR CLARITY

CONCEPTUAL DESIGN

VEOLIA NUCLEAR SOLUTIONS - FEDERAL SERVICES
 295 Bradley Blvd, Suite 300
 Richland, WA 99352
 www.nuclearsolutions.veolia.com

NAME	DATE	COMMENTS
J. PIERCE	11/27/13	ISSUED
F. LLOYD	11/27/13	ISSUED
S. MOORE	11/27/13	ISSUED
J. W. SON	11/27/13	ISSUED
F. LLOYD	11/27/13	ISSUED

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT

MECHANICAL
 WESTERN AREA TREATMENT FACILITY
 URANIUM TRAIN SKID ARRANGEMENT

SCALE SHOWN: **F** SHEET 6 OF 6

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS					
		NEXT USED ON							

8

7

6

5

4

3


2

1

DWG NO: VFS-EPM-000-DWG-M-110 6 of 6

NOTES & SPECIFICATIONS:

1. DIMENSIONS AND TOLERANCES PER ASME Y14.5M-94. DIMENSIONS ARE IN INCHES.
TOLERANCES: .X ± .1, .XX ± .03, .XXX ± .005
FRACTIONAL: ± 1/8
ANGULAR: ± 2'
2. MAINTAIN STANDARD SHIPPING CONTAINER LOWER CORNERS FOR TRANSPORTATION ANCHOR POINT
3. REINFORCE FLOOR PAN FOR PUMP MOUNTING. REINFORCEMENT METHOD SHALL PRECLUDE BREACH OF FLOOR CONTAINMENT.
4. DIMENSIONS FOR PIPE CONNECTIONS ARE BASED ON PIPING LAYOUT. CONFIRM PRIOR TO FABRICATION.
5. EXTERIOR COATING SHALL BE BS12944 - C3 MARINE OR APPROVED EQUAL.
6. INTERIOR PROCESS AREA SURFACES SHALL BE NON-POROUS. AVOID USE OF ZINC ON INTERIOR SURFACES IN THE PROCESS AREA.
▽ RECESSED BOXES TO BE SUPPORTED BY FABRICATOR IN FIELD
8. FLOORS IN THE PROCESS AREA SHALL DRAIN INTO THE CONTAINMENT TRAY AND BE INTEGRATED TO FRAME FOR CONTINUOUS LIQUID CONTAINMENT WITHIN THE MODULE. A METHOD MUST BE PROVIDED TO AVOID WATER PATHWAY OUTSIDE THE CONTAINMENT. ALL CONTACT AREAS SHALL BE STAINLESS STEEL.
9. FOR PENETRATIONS AND MOUNTING SEE ELECTRICAL INSTALLATION DRAWINGS.
10. TESTING WILL BE REQUIRED FOR SECONDARY CONTAINMENT
11. BREAK SHARP EDGES, REMOVE BURRS.
12. WELD AND INSPECT CARBON STEEL STRUCTURAL WELDS TO AWS D1.1-2015, WELD AND INSPECT STAINLESS STEEL STRUCTURAL WELD TO D1.6-2017. PROCEDURE AND WELDER QUALIFICATIONS PER ASME SECTION IX ARE ACCEPTABLE.
13. FABRICATION DETAILS AND STANDARDS PER NORMAL AND CUSTOMARY FOR INTERMODAL CONSTRUCTION.
14. DESIGN TO BE CERTIFIED FOR DOT HIGHWAY TRAVEL.



1 SKID FRAME
SCALE: NOT TO SCALE

CONCEPTUAL DESIGN

VEOLIA NUCLEAR SOLUTIONS - FEDERAL SERVICES
295 Bradley Blvd, Suite 300
Richland, WA 99352
www.nuclearsolutions.veolia.com

NAME	DATE	COMMENTS
DESIGNED: J. PERCE	11/22/2019	UNDR
DRAWN: F. FLOYD		UNDR
CHECKED: S. MOORE		UNDR
APPROVED: J. WILSON		UNDR
DATE: 11/22/2019		UNDR
BY: F. FLOYD		UNDR

CIMARRON
PUMP AND TREAT SYSTEM PROJECT





MECHANICAL
WESTERN AREA TREATMENT FACILITY
SKID FRAME

SCALE: NONE

DWG NO	TITLE	REF NUMBER	TITLE	REF NO	REV DATE	DESCRIPTION	REV BY	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS					
		NEXT USED ON							

DWG NO: VFS-EPM-000-DWG-M-111 Rev 1 of 4

SHEET 1 OF 4



CONCEPTUAL DESIGN

VEOLIA NUCLEAR SOLUTIONS - FEDERAL SERVICES
285 Bradley Blvd, Suite 300
Richland, WA 99352
www.nuclearsolutions.veolia.com

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

MECHANICAL
WESTERN AREA TREATMENT FACILITY
SKID FRAME

NAME	DATE	COMMENTS
LI PIERCE	11/22/2011	UNSP
F FLOYD		UNSP
S MOORE		UNSP
J WILSON		UNSP
F FLOYD		UNSP


DWG NO	TITLE	REF NUMBER	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							
			NEXT USED ON							
						REVISIONS				

SCALE NONE


F **A**

SHEET 2 OF 4

DWG NO: VFS-EPM-000-DWG-M-111 1/2 of 4



CONCEPTUAL DESIGN


 NUCLEAR SOLUTIONS - FEDERAL SERVICES
 295 Bradley Blvd, Suite 300
 Richland, WA 99352
 www.nuclearsolutions.veolia.com


CIMARRON	
PUMP AND TREAT SYSTEM PROJECT	
MECHANICAL	
WESTERN AREA TREATMENT FACILITY	
SKID FRAME	
REV	DATE
F	02/28/2010
SCALE NONE	
DWG NO	REV
VFS-EPM-000-DWG-M-111	A
SHEET 3 OF 4	

DWG NO	TITLE	REF NUMBER	TITLE	REF NO	REV NO	DESCRIPTION	REV DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST									
DRAWING TRACEABILITY LIST				NEXT USED ON		REVISED			


DWG NO VFS-EPM-000-DWG-M-111 Rev 3 of 4 Rev A

8 7 6 5 4 3 2 1



F
E
D
C
B
A





C SECTION
SHEET 3 SCALE: 1:16



D SECTION
SHEET 3 SCALE: 1:16



B SECTION
SHEET 2 SCALE: 1:16



CONCEPTUAL DESIGN

VEOLIA NUCLEAR SOLUTIONS - FEDERAL SERVICES
295 Bradley Blvd, Suite 300
Richland, WA 99352
www.nuclearsolutions.veolia.com

NAME	DATE	COMPANY	REV	DESCRIPTION
PIERCE	10/22/19	VEOLIA	1	ISSUED FOR PERMIT
FLOYD				
S. MOORE				
T. WILSON				
FLOYD				

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
MECHANICAL
WESTERN AREA TREATMENT FACILITY
SKID FRAME

SCALE NONE SHEET 4 OF 4

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES				
		NEXT USED ON					


DWG NO VFS-EPM-000-DWG-M-111 BY 4 OF 4

8 7 6 5 4 3 2 1


LINES:

- PRIMARY PIPING
- INSTRUMENTATION OR OTHER PIPING
- TANKS/PITS/BUILDINGS
- ELECTRICAL POWER OR SIGNAL
- SKID BOUNDARY
- DATA LINK
- FLEX HOSE
- PROCESS BOUNDARY
- OPERATIONAL FLOW

INSTRUMENT SYMBOLS:



DRAWING CONTINUATION ARROW:



ABBREVIATIONS:

- B POSITIVE DISPLACEMENT BLOWER
- BA BURIAL AREA
- BMCD BURNS & MCDONNELL
- BS BASKET STRAINER
- C CENTRIFUGE
- CMPR COMPRESSOR
- CS CARBON STEEL
- CV CHECK VALVE
- DV DISCONNECT VALVE
- DOE DEPARTMENT OF ENERGY
- FL FAIL LOCKED
- FC FAIL CLOSE
- FDR SOLIDS FEEDER
- FH FLEX HOSE
- FLT FILTER
- FO FAIL OPEN
- GV GAUGE VALVE
- GPD GALLONS PER DAY
- H INTERCONNECTING HOSE
- HPR HOPPER
- IX ION EXCHANGE
- LC LOCKED CLOSED
- LO LOCKED OPEN
- MCL MAXIMUM CONTAMINANT LEVEL
- MOV MOTOR OPERATED VALVE
- MVD MANUAL VALVE DOUBLE
- MPa MEGA-PASCALS
- NC NORMALLY CLOSED
- NO NORMALLY OPENED
- P PUMP
- P&ID PIPING AND INSTRUMENTATION DIAGRAM
- PRV PRESSURE RELIEF VALVE
- PSE PRESSURE SAFETY ELEMENT
- PVC POLYVINYL CHLORIDE
- RB RIBBON BLENDER
- S SAMPLE PORT
- T/TK TANK
- V VALVE
- VFD VARIABLE FREQUENCY DRIVE
- VNSFS VEOLIA NUCLEAR SOLUTIONS FEDERAL SERVICES
- VSL VESSEL ION EXCHANGE VESSEL
- WA WESTERN AREA
- WAA WESTERN ALLUVIAL AREA
- WATF WESTERN AREA TREATMENT FACILITY
- YS WYE STRAINER


PIPING/EQUIPMENT:

- BALL VALVE
- V-PORT BALL VALVE
- GATE VALVE
- PINCH VALVE
- BUTTERFLY VALVE
- CHECK VALVE
- SLIDE VALVE
- MAGNETIC FLOW METER
- FILTER
- VARIABLE FREQUENCY DRIVE
- GRAB SAMPLE
- SAMPLE PORT
- MOTOR
- PRESSURE OR VACUUM RELIEF
- QUICK CONNECT
- HOSE CONNECTION
- PIPE CAP
- PIPE FLANGE
- PIPE REDUCER
- DRY DISCONNECT WITH SHUTOFF
- FULL PORT DRY DISCONNECT
- ROTARY VALVE
- EDUCTOR
- BASKET STRAINER
- WYE STRAINER
- IN-LINE SILENCER
- IN-LINE MIXER
- MECHANICAL VIBRATOR
- NEEDLE VALVE
- GAUGE VALVE
- MOTOR OPERATED VALVE
- PRESSURE CONTROL VALVE
- BACK-PRESSURE VALVE
- FLOW CONTROL VALVE
- ROTAMETER

- AIR GAP
- PRESSURE RELIEF VALVE
- UNION
- COMBINATION VACUUM AND PRESSURE RELIEF VALVE
- TANK VENT
- TANK VENT WITH BIRD / INSECT SCREEN
- CENTRIFUGAL PUMP
- PERISTALTIC PUMP
- DIAPHRAGM PUMP
- METERING PUMP
- POSITIVE DISPLACEMENT BLOWER
- SPARGE VESSEL
- TANK
- HOPPER
- RIBBON BLENDER
- SACK UNLOADER
- SCROLLING CENTRIFUGE
- SOLIDS DRUM
- AIR COMPRESSOR
- SAFETY SHOWER
- EYE / FACE WASH
- PULSATION DAMPENERS
- INSULATION WITH HEAT TRACE
- HOSE BIB

- VACUUM RELIEF VALVE
- STREAM NUMBER
- SCREW CONVEYOR
- AUTOMATIC DRAIN VALVE
- REFRIGERATED AIR DRYER
- HOPPER
- OIL / WATER SEPARATOR
- WET / DRY AIR RECEIVER

LINE NUMBERING:



LINE SERVICE CODES:

- CA COMPRESSED AIR
- DR DRAIN
- FW FILTERED WATER
- GW GROUNDWATER
- HCL HYDROCHLORIC ACID (37%)
- IA INSTRUMENT AIR
- POTW POTABLE WATER
- RV RELIEF VENT
- SWW SERVICE WATER
- VAP VAPOR
- WW WASTE WATER
- WWO WASH/WASTE OIL

PIPING CLASS CODES:

- 1ST CHARACTER - NOMINAL PRESSURE RATING
 - A - CLASS 150
 - B - CLASS 300
 - C - CLASS 600
 - D - CLASS 900
 - E - CLASS 1500
 - F - CLASS 125
- 2ND CHARACTER - GENERAL MATERIAL TYPE
 - A - PVC
 - B - CPVC
 - D - ALLOY 20
 - E - HASTELLOY
 - F - FRP
 - G - GALVANIZED STEEL
 - H - HDPE
 - J - POLYPROPYLENE
 - K - PVDF (KYNAR)
 - L - LINED CARBON STEEL
 - M - MONEL
 - N - DOUBLE CONTAINED (PTFE/CPVC)
 - P - PVC OR CPVC
 - R - ABS
 - S - STAINLESS STEEL
 - T - ALUMINUM
- 3RD AND 4TH CHARACTERS - SEQUENTIAL NUMBERING
 - ## - SEQUENTIAL TWO DIGIT NUMBER DISTINCT FOR AN INDIVIDUAL PIPE MATERIAL CLASS
- 5TH CHARACTER - MODIFIER
 - x - DESIGNATOR INDICATING MODIFICATION

NOTE: NOT NORMALLY USED IN THE PIPE MATERIAL CLASS NAME. USED ONLY WHEN A PARTICULAR PIPE MATERIAL CLASS REQUIRES MODIFICATION TO SATISFY PROJECT SPECIFIC REQUIREMENTS, EITHER DOE TO CLIENT SPECIFICATIONS AND / OR SPECIAL PROJECT REQUIREMENTS. IN THIS INSTANCE THE PIPE MATERIAL CLASSIFICATION SHALL BE MARKED WITH THE PROJECT OR TENDER NUMBER AND USED ONLY FOR THE APPLICABLE PROJECT OF TENDER.

EXAMPLE: 150# CLASS, CARBON STEEL, 2ND CARBON STEEL PIPE MATERIAL CLASS WITH 150# CLASS AC02-DESIGNATION

INSTRUMENT IDENTIFICATION (ISA 5.1 R2009)				
FIRST-LETTER	MEASURED OR INITIATING VARIABLE	MODIFIER	SUCCEEDING-LETTERS	
			READOUT OR PASSIVE FUNCTION	OUTPUT FUNCTION
A	ANALYSIS		ALARM	
B	BURNER, COMBUSTION		USER'S CHOICE	USER'S CHOICE
C	CONDUCTIVITY			CONTROL
D	USER'S CHOICE	DIFFERENTIAL	DETECTOR	DEVIATION
E	VOLTAGE		SENSOR (PRIMARY ELEMENT)	
F	FLOW, FLOW RATE	RATIO (FRACTION)		
G	USER'S CHOICE		GLASS, VIEWING DEVICE	
H	HAND			HIGH
I	CURRENT (ELECTRICAL)		INDICATE	
J	POWER		SCAN	
K	TIME, TIME SCHEDULE	TIME RATE OF CHANGE		CONTROL STATION
L	LEVEL		LIGHT	LOW
M	USER'S CHOICE			MIDDLE, INTERMEDIATE
N	USER'S CHOICE		USER'S CHOICE	USER'S CHOICE
O	USER'S CHOICE		ORIFICE, RESTRICTION	OPEN
P	PRESSURE, VACUUM		POINT (TEST CONNECTION)	
Q	QUANTITY	INTEGRATE, TOTALIZE	INTEGRATE, TOTALIZE	
R	RADIATION		RECORD	RUN
S	SPEED, FREQUENCY	SAFETY		SWITCH
T	TEMPERATURE			TRANSMIT
U	MULTIVARIABLE		MULTIFUNCTION	MULTIFUNCTION
V	VIBRATION, MECHANICAL ANALYSIS			VALVE, DAMPER, LOUVER
W	WEIGHT, FORCE		WELL, PROBE	
X	UNCLASSIFIED	X AXIS	TROUBLE	UNCLASSIFIED
Y	EVENT, STATE OR PRESENCE	Y AXIS		RELAY, COMPUTE, CONVERT
Z	POSITION, DIMENSION	Z AXIS		DRIVER, ACTUATOR, UNCLASSIFIED

NOTES:

- 1. LD IS USED TO DESIGNATE LEAK DETECTION INSTRUMENT.

CONCEPTUAL DESIGN



NAME		DATE	COMMENTS
MOORE		10/20/21	INITIAL
DAVISON			
WILSON			
SMITH			
WILSON			
SMITH			
WILSON			
E LLOYD			

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
PROCESS
SYMBOLS, NOTES, AND
ABBREVIATIONS

VFS-EPM-000-DWG-P-001

DWG NO	TITLE	REF NUMBER	TITLE	REF NO	DESCRIPTION	REV	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES						

8

7

6

5

4


3

2

1

GENERAL NOTES:

- 1 URANIUM TRAIN BYPASS IS BUILT INTO SKIDS IN CASE OPERATIONS ARE REQUIRED AFTER INFLUENT < MCL.
- 2 DOUBLE-WALLED INFLUENT TANK.



CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
 WESTERN AREA TREATMENT
 FACILITY OVERALL
 PROCESS FLOW DIAGRAM

NAME	DATE	COMPANY
S. MOORE	11/20/10	VEOLIA
J. PIERCE	11/20/10	VEOLIA
J. WILSON	11/20/10	VEOLIA
R. GARRETT	11/20/10	VEOLIA
E. LLOYD	11/20/10	VEOLIA

SCALE: NONE
 EST: 11/20/10
 SHEET 1 OF 2

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	DESCRIPTION
DRAWING TRACEABILITY LIST									
NEXT USED ON									
REVISIONS									

DWG NO VFS-EPM-000-DWG-P-110
 SHEET 1 OF 2
 REV'D

Stream #		1	2	3	4	5	6	7	8	12A	12B	13A	13B	14	15
Description		WA IX Feed	BA1 IX Feed	WA Uranium Treatment Effluent to TK-102	WA Uranium Treatment Effluent to Injection Skid	BA1 Uranium Treatment Effluent to TK-102	BA1 Uranium Treatment Effluent to Injection Skid	Combined Outfall from TK-102	Uranium Treatment Hydrochloric Acid (36%)	WA Refilled Vessels	BA1 Refilled Vessels	WA Spent Uranium Treatment Vessels	BA1 Spent Uranium Treatment Vessels	Effluent for Backwashing	Filter Backflush
Parameter	Units														
Liquid Streams															
Flow	gpm	107	100	99	8	82	18	181	-	-	-	-	-	195.0	3.4 - 17.7
	gpd	-	-	-	-	-	-	-	35.3	-	-	-	-	-	-
Liquid Concentrations															
Uranium (total)	ppb	159	1215	0	0	0	0	0	-	-	-	-	-	0	-
Suspended Solids	ppm (dry)	5	5	0	0	0	0	5.7	-	-	-	-	-	0	306
Solid Streams															
Flow															
Unused IX Resin	cu ft/yr	-	-	-	-	-	-	-	-	117	331	-	-	-	-
Exhausted IX Resin	cu ft/yr	-	-	-	-	-	-	-	-	-	-	161	455	-	-

Stream table based on design conditions; actual conditions will vary over the course of remediation. Design conditions result in a higher usage than actually anticipated.

CONCEPTUAL DESIGN




CIMARRON
PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA TREATMENT
FACILITY OVERALL
PROCESS FLOW DIAGRAM

NAME	DATE	REVISION
S. MOORE	11/15/23	1
J. PIERCE	11/15/23	2
J. WILSON	11/15/23	3
B. GARRETT	11/15/23	4
E. LLOYD	11/15/23	5

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							

SCALE: NONE
SHEET 2 OF 2

DWG NO VFS-EPM-000-DWG-P-110 SH 2 OF 2



- GENERAL NOTES:**
- 1 ADDED FOR FUTURE SYSTEM BYPASS ONCE MCL IS ACHIEVED FOR URANIUM AND NITRATE.
 - 2 HIGH ALARM SIGNAL SENT TO WELL FIELD HMI.
 - 3 DETECTED LEAK (LDA-101) SHUT DOWN SIGNAL SENT TO WELL FIELD HMI.
 - 4 STOP WELL-FIELD PUMPS.
 - 5 TRUCK TO BE UNLOADED WITH 15 TO 20 PSIG PRESSURE (VIA AIR).
 - 6 PORTABLE SAFETY EYEWASH REQUIRED DURING FILL.
 - 7 pH PROBE CONNECTION VIA HOT TAP WITH ISOLATION VALVE.
 - 8 CONCRETE BERM WITH EPOXY COAT.
 - 9 CLEAR TUBING FOR OBSERVATION OF FILTER DRAINING.
 - 10 PIPING RUN 6"-VAP-11500-AR01-N NOT IN VENDOR SCOPE.

- INTERLOCK LIST:**
- 11 LDA-100 : FCV-100 CLOSE, P-121 AND P-104 STOP
 - 12 LDA-150 : FCV-150 CLOSE, P-130 AND P-154 STOP
 - 13 LD-132 : P-130 STOP
 - 14 LDA-122 : P-121 STOP
 - 15 LDA-101 OR LSH-101 : MOV-101 CLOSE
 - 16 LDA-103 OR LSH-103 : MOV-103 CLOSE

CONCEPTUAL DESIGN
REVIEW AID

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

CIMARRON
PUMP AND TREAT SYSTEM PROJECT


WESTERN AREA
P&ID
URANIUM IX TREATMENT

VFS-EPM-000-DWG-P-115


REV	DATE	DESCRIPTION	BY	CHK	APP
1	12/07/15	ISSUED FOR REVIEW	V. DAVISON	S. WOODRUFF	
2	01/08/16	REVISED PER COMMENTS	J. WILSON	D. SMITH	
3	01/20/16	REVISED PER COMMENTS	D. SMITH	E. FLOYD	

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV	DATE	BY	CHK	APP
DRAWING TRACEABILITY LIST									
NEXT USED ON									
REVISIONS									


DWG NO VFS-EPM-000-DWG-P-115 SH 1 OF 5 REV F




*** VALVE POSITION DETAIL**



**** SAMPLE DETAIL**



***** SAMPLE DETAIL**



GENERAL NOTES:

- 1 VSL-101, VSL-102, AND VSL-103 DESIGNATE THE PHYSICAL POSITION NOT THE SPECIFIC VESSEL. RESIN SWELLS DURING OPERATION. NORMAL VALVE ALIGNMENT CAN VARY BASED ON LEAD VESSEL. VALVE ALIGNMENT SHOWN IS FOR VSL-101 AS LEAD.
- 2 FLUSH WATER PORT. SEE DRAWING VFS-EPM-000-DWG-P-500.
- 3 NOT USED.
- 4 AE-101 TO BE LOCATED 2 TO 4 PIPE DIAMETERS DOWNSTREAM OF MX-101.
- 5 pH CONTROL IS FEED FORWARD WITH FEEDBACK TRIM, pH SETPOINT TO BE ADJUSTED BASED ON ACHIEVING A LCI = 0.
- 6 VENT, SLUICE, SPARGER, AND SAMPLE NOZZLES NOT SHOWN FOR CLARITY.
- 7 pH PROBE CONNECTION VIA HOT TAP WITH ISOLATION VALVE.
- 8 FILTER NOT PROVIDED TO ALLOW FOR TSS ANALYSIS.
- 9. SEE SHEET 1 FOR INTERLOCK LIST.

**URANIUM IX WA TRAIN
ION EXCHANGE SKID**

CONCEPTUAL DESIGN
REVIEW AID




NAME	DATE	COMPAN
V. DAVISON	10/20/23	VEOLIA
S. MOORE	10/20/23	VEOLIA
J. WILSON	10/20/23	VEOLIA
D. SMITH	10/20/23	VEOLIA
E. LLOYD	10/20/23	VEOLIA

CIMARRON PUMP AND TREAT SYSTEM PROJECT	
WESTERN AREA P&ID URANIUM IX TREATMENT	
DWG NO	VFS-EPM-000-DWG-P-115
SCALE	NONE
SHEET	2 OF 5

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	ENDOR	COMPANY
DRAWING TRACEABILITY LIST										
NEXT USED ON										
REVISIONS										

VFS-EPM-000-DWG-P-115 SH. 2 OF 5 (REV. E)

TK-105 INFLUENT TANK 12,000 GAL
 TK-106 BACKWASH TANK 9,000 GAL
 P-140 PUMP
 P-130 PUMP
 FLT-131 FILTER NO 1
 FLT-132 FILTER NO 2
 FLT-133 FILTER NO 3



- GENERAL NOTES:**
- 1 ADDED FOR FUTURE SYSTEM BYPASS ONCE MCL IS ACHIEVED FOR URANIUM.
 - 2 HIGH ALARM SIGNAL SENT TO WELL FIELD HMI.
 - 3 DETECTED LEAK (LDA-201) SHUT DOWN SIGNAL SENT TO WELL FIELD HMI.
 - 4 STOP WELL FIELD PUMPS.
 - 5. SEE DRAWING P-115 SHEET 1 FOR INTERLOCK LIST.

CONCEPTUAL DESIGN
REVIEW AID

VEOLIA
 VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT


WATF
 BURIAL AREA #1
 PROCESS P&ID

VFS-EPM-000-DWG-P-115

REV 3 OF 5

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		NEXT USED ON		REVISIONS				

VFS-EPM-000-DWG-P-115 REV 3 OF 5



**URANIUM IX BA1 TRAIN
ION EXCHANGE SKID**

- GENERAL NOTES:**
- 1 VSL-151, VSL-152, AND VSL-153 DESIGNATE THE PHYSICAL POSITION NOT THE SPECIFIC VESSEL. RESIN SWELLS UPON LOADING WITH URANIUM. NORMAL VALVE ALIGNMENT CAN VARY BASED ON LEAD VESSEL. VALVE ALIGNMENT SHOWN IS FOR VSL-151 AS LEAD.
 - 2 FLUSH WATER PORT. SEE DRAWING VFS-EPM-000-DWG-P-500.
 - 3 NOT USED.
 - 4 AE-151 TO BE LOCATED 2 TO 4 PIPE DIAMETERS DOWNSTREAM OF MX-151.
 - 5 pH CONTROL IS FEED FORWARD WITH FEEDBACK TRIM, pH SETPOINT TO BE ADJUSTED BASED ON ACHIEVING AN LCI = 0.
 - 6 VENT, SLUICE, SPARGER, AND SAMPLE NOZZLES NOT SHOWN FOR CLARITY.
 - 7 NOT USED.
 - 8 FILTER NOT PROVIDED TO ALLOW FOR TSS ANALYSIS.
 - 9. SEE SHEET 1 FOR INTERLOCK LIST.

CONCEPTUAL DESIGN
REVIEW AID



NAME	DATE	REVISION
S. MOORE	11/20/20	1
J. PIERCE	11/20/20	2
J. WILSON	11/20/20	3
B. CARRETT	11/20/20	4
E. ELLOYD	11/20/20	5

**CIMARRON
PUMP AND TREAT SYSTEM PROJECT**

**WATF
BURIAL AREA #1 P&ID
URANIUM IX TRAIN**


DWG NO: VFS-EPM-000-DWG-P-115

SCALE: NONE

SHEET 4 OF 5

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	BY	CHKD
DRAWING TRACEABILITY LIST										
NEXT USED ON										
REFERENCES										
REVISIONS										

VFS-EPM-000-DWG-P-115 SH. 4 OF 5 REV. C




GENERAL NOTES:

- 1. SEE FLAG NOTE 1 ON SHEET 1.
- 2. SEE SHEET 2 FOR *** SAMPLE DETAIL.
- 3. FLOW METER SIGNAL FROM BMCD INJECTION SKID SENT FOR IX HMI TO CONTROL FCV-104.
- 4. SEE SHEET 1 FOR INTERLOCK LIST.

**CONCEPTUAL DESIGN
REVIEW AID**


VEOLIA		VEOLIA NUCLEAR SOLUTIONS FEDERAL SERVICES, LLC 295 Bradley, Suite 300 Richland, WA 99352																											
CIMARRON PUMP AND TREAT SYSTEM PROJECT		WESTERN AREA P&ID URANIUM IX TREATMENT																											
VFS-EPM-000-DWG-P-115		SHEET 5 OF 5																											
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>DATE</th> <th>BY</th> <th>CHKD</th> <th>APP'D</th> </tr> </thead> <tbody> <tr> <td>11/20/2018</td> <td>S. MOORE</td> <td>J. PIERCE</td> <td></td> </tr> <tr> <td></td> <td>J. WILSON</td> <td>R. GARRETT</td> <td></td> </tr> <tr> <td></td> <td>R. GARRETT</td> <td>E. LLOYD</td> <td></td> </tr> </tbody> </table>	DATE	BY	CHKD	APP'D	11/20/2018	S. MOORE	J. PIERCE			J. WILSON	R. GARRETT			R. GARRETT	E. LLOYD		<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	REV	DATE	DESCRIPTION									
DATE	BY	CHKD	APP'D																										
11/20/2018	S. MOORE	J. PIERCE																											
	J. WILSON	R. GARRETT																											
	R. GARRETT	E. LLOYD																											
REV	DATE	DESCRIPTION																											
DWG NO: VFS-EPM-000-DWG-P-115 TITLE: WESTERN AREA P&ID URANIUM IX TREATMENT REFERENCE:		SCALE: NONE SHEET 5 OF 5																											

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		NEXT USED ON		REVISIONS				



- GENERAL NOTES:**
- 1 ACCESS FOR CLEAN BULK MATERIAL DELIVERIES.
 - 2 ACCESS FOR SPENT RESIN.
 - 3. FOR PIPE SUPPORT DETAILS SEE DRAWING VFS-EPM-000-DWG-S-115. INSTALL PER SPECIFICATION SECTION 22 05 29 - HANGERS AND SUPPORTS FOR PIPING AND EQUIPMENT.
 - 4 SEE BOLLARD DETAIL 3, ON SHEET 1, DRAWING VFS-EPM-000-DWG-C-150.

SPENT RESIN HANDLING - PLAN
SCALE: 1/4" = 1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	BY	CHKD

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	SCALE	REV
S. MOORE			
E. LLOYD			
J. PIERCE			
J. WILSON			
E. LLOYD			

CIMARRON
PUMP AND TREAT SYSTEM PROJECT


WESTERN AREA TREATMENT FACILITY GEN. ARRANGEMENT SPENT RESIN HANDLING



DWG NO: VFS-EPM-000-DWG-G-120

SCALE: SHOWN 1 OF 1

DWG NO: VFS-EPM-000-DWG-G-120 1 OF 1 REV C

8 | 7 | 6 | 5 | 4 | 3 | 2 | 1

- GENERAL NOTES:**
- FOR PIPE SUPPORT DETAILS SEE DRAWING VFS-EPM-000-DWG-S-115. INSTALL PER SPECIFICATION SECTION 22 05 29 - HANGERS AND SUPPORTS FOR PIPING AND EQUIPMENT.
-  DRUM LIFT NOT SHOWN.



DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	ENGR	COMPANY

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

DESIGNED BY	S. MOORE	DATE	10/13/11
CHECKED BY	E. FLOYD	DATE	10/13/11
APPROVED BY	J. PIERCE	DATE	10/13/11
DESIGNED BY	J. WILSON	DATE	10/13/11
CHECKED BY	E. FLOYD	DATE	10/13/11

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT FACILITY SPENT RESIN HANDLING SECTIONS

SCALE: AS SHOWN


SHEET 1 OF 3

VFS-EPM-000-DWG-G-121

8 | 7 | 6 | 5 | 4 | 3 | 2 | 1


8 7 6 5 4 3 2 1

NOTES:
1. SEE DRAWING SHEET 1 FOR GENERAL NOTES.



MEZZANINE RAILS NOT SHOWN FOR CLARITY

C SECTION
G-120-1 SCALE: 1/2"=1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	BY	CHKD

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

DESIGNED BY S. MOORE	DATE 10/12/11	COMPANY VEOLIA
DRAWN BY E. FLOYD	DATE 11/13/11	
CHECKED BY J. PIERCE	DATE 11/13/11	
PROJECT MANAGER J. WILSON	DATE 11/13/11	
PROJECT PROPOSER E. FLOYD	DATE 11/13/11	

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT FACILITY SPENT RESIN HANDLING SECTIONS

DWG NO: **VFS-EPM-000-DWG-G-121**

SCALE: AS SHOWN


SHEET 2 OF 3

DWG NO: VFS-EPM-000-DWG-G-121

8 7 6 5 4 3 2 1


8 7 6 5 4 3 2 1

NOTES:
 1. SEE DRAWING SHEET 1 FOR GENERAL NOTES.



MEZZANINE RAILS, DRUM LIFT, AND FORKLIFT NOT SHOWN FOR CLARITY

D SECTION
 G-120-1 SCALE: 1/2"=1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	BY	CHK	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES						
						REVISIONS			

CONCEPTUAL DESIGN

VEOLIA
 VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT
 FACILITY SPENT RESIN
 HANDLING SECTIONS

SCALE AS SHOWN


SHEET 3 OF 3

8 7 6 5 4 3 2 1


LINES:

- PRIMARY PIPING
- INSTRUMENTATION OR OTHER PIPING
- TANKS/PITS/BUILDINGS
- - - ELECTRICAL POWER OR SIGNAL
- - - SKID BOUNDARY
- - - DATA LINK
- ~ FLEX HOSE
- - - PROCESS BOUNDARY
- - - OPERATIONAL FLOW

INSTRUMENT SYMBOLS:



DRAWING CONTINUATION ARROW:



ABBREVIATIONS:

- B POSITIVE DISPLACEMENT BLOWER
- BA BURIAL AREA
- BMCD BURNS & MCDONNELL
- BS BASKET STRAINER
- C CENTRIFUGE
- CMPR COMPRESSOR
- CS CARBON STEEL
- CV CHECK VALVE
- DV DISCONNECT VALVE
- DOE DEPARTMENT OF ENERGY
- FL FAIL LOCKED
- FC FAIL CLOSE
- FDR SOLIDS FEEDER
- FH FLEX HOSE
- FLT FILTER
- FO FAIL OPEN
- GV GAUGE VALVE
- GPD GALLONS PER DAY
- H INTERCONNECTING HOSE
- HPR HOPPER
- IX ION EXCHANGE
- LC LOCKED CLOSED
- LO LOCKED OPEN
- MCL MAXIMUM CONTAMINANT LEVEL
- MOV MOTOR OPERATED VALVE
- MVD MANUAL VALVE DOUBLE
- MPa MEGA-PASCALS
- NC NORMALLY CLOSED
- NO NORMALLY OPENED
- P PUMP
- P&ID PIPING AND INSTRUMENTATION DIAGRAM
- PRV PRESSURE RELIEF VALVE
- PSE PRESSURE SAFETY ELEMENT
- PVC POLYVINYL CHLORIDE
- RB RIBBON BLENDER
- S SAMPLE PORT
- T/TK TANK
- V VALVE
- VFD VARIABLE FREQUENCY DRIVE
- VNSFS VEOLIA NUCLEAR SOLUTIONS FEDERAL SERVICES
- VSL VESSEL/ION EXCHANGE VESSEL
- WA WESTERN AREA
- W/AA WESTERN ALLUVIAL AREA
- WATF WESTERN AREA TREATMENT FACILITY
- YS WYE STRAINER


PIPING/EQUIPMENT:

- ⊘ BALL VALVE
- ⊘ BALL VALVE
- ⊘ V-PORT BALL VALVE
- ⊘ GATE VALVE
- ⊘ PINCH VALVE
- ⊘ BUTTERFLY VALVE
- ⊘ CHECK VALVE
- ⊘ SLIDE VALVE
- M MAGNETIC FLOW METER
- FLT FILTER
- VFD VARIABLE FREQUENCY DRIVE
- S GRAB SAMPLE
- ⊘ SAMPLE PORT
- M MOTOR
- ⊘ PRESSURE OR VACUUM RELIEF
- ⊘ QUICK CONNECT
- ⊘ HOSE CONNECTION
- ⊘ PIPE CAP
- ⊘ PIPE FLANGE
- ⊘ PIPE REDUCER
- ⊘ DRY DISCONNECT WITH SHUTOFF
- ⊘ FULL PORT DRY DISCONNECT
- M ⊘ ROTARY VALVE
- ⊘ EDUCTOR
- ⊘ BASKET STRAINER
- ⊘ WYE STRAINER
- S ⊘ IN-LINE SILENCER
- ⊘ IN-LINE MIXER
- ⊘ MECHANICAL VIBRATOR
- ⊘ NEEDLE VALVE
- ⊘ GAUGE VALVE
- M ⊘ MOTOR OPERATED VALVE
- ⊘ PRESSURE CONTROL VALVE
- ⊘ BACK-PRESSURE VALVE
- ⊘ FLOW CONTROL VALVE
- ⊘ ROTAMETER

- ∇ AIR GAP
- ∇ PRESSURE RELIEF VALVE
- || UNION
- ⊘ COMBINATION VACUUM AND PRESSURE RELIEF VALVE
- ∩ TANK VENT
- ∩ TANK VENT WITH BIRD / INSECT SCREEN
- ⊘ CENTRIFUGAL PUMP
- ⊘ PERISTALTIC PUMP
- ⊘ DIAPHRAGM PUMP
- ⊘ METERING PUMP
- ⊘ POSITIVE DISPLACEMENT BLOWER
- ⊘ SPARGE VESSEL
- ⊘ TANK
- ⊘ HOPPER
- ⊘ RIBBON BLENDER
- ⊘ SACK UNLOADER
- ⊘ SCROLLING CENTRIFUGE
- ⊘ SOLIDS DRUM
- ⊘ AIR COMPRESSOR
- ⊘ SAFETY SHOWER
- ⊘ EYE / FACE WASH
- ⊘ PULSATION DAMPENERS
- ⊘ INSULATION WITH HEAT TRACE
- ⊘ HOSE BIB

- ∇ VACUUM RELIEF VALVE
- X STREAM NUMBER
- ⊘ SCREW CONVEYOR
- ⊘ AUTOMATIC DRAIN VALVE
- ⊘ REFRIGERATED AIR DRYER
- ⊘ HOPPER
- ⊘ OIL / WATER SEPARATOR
- ⊘ WET / DRY AIR RECEIVER

LINE NUMBERING:



LINE SERVICE CODES:

- CA COMPRESSED AIR
- DR DRAIN
- FW FILTERED WATER
- GW GROUNDWATER
- HCL HYDROCHLORIC ACID (37%)
- IA INSTRUMENT AIR
- POTW POTABLE WATER
- RV RELIEF VENT
- SVW SERVICE WATER
- VAP VAPOR
- WW WASTE WATER
- WWO WASH/WASTE OIL

PIPING CLASS CODES:

- 1ST CHARACTER - NOMINAL PRESSURE RATING
- A - CLASS 150
- B - CLASS 300
- C - CLASS 600
- D - CLASS 900
- E - CLASS 1500
- F - CLASS 125

2ND CHARACTER - GENERAL MATERIAL TYPE

- A - PVC
- B - CPVC
- D - ALLOY 20
- E - HASTELLOY
- F - FRP
- G - GALVANIZED STEEL
- H - HDPE
- J - POLYPROPYLENE
- K - PVDF (KYNAR)
- L - LINED CARBON STEEL
- M - MONEL
- N - DOUBLE CONTAINED (PTFE/CPVC)
- P - PVC OR CPVC
- R - ABS
- S - STAINLESS STEEL
- T - ALUMINUM

3RD AND 4TH CHARACTERS - SEQUENTIAL NUMBERING

- SEQUENTIAL TWO DIGIT NUMBER DISTINCT FOR AN INDIVIDUAL PIPE MATERIAL CLASS

5TH CHARACTER - MODIFIER

x - DESIGNATOR INDICATING MODIFICATION

NOTE: NOT NORMALLY USED IN THE PIPE MATERIAL CLASS NAME. USED ONLY WHEN A PARTICULAR PIPE MATERIAL CLASS REQUIRES MODIFICATION TO SATISFY PROJECT SPECIFIC REQUIREMENTS, EITHER DOE TO CLIENT SPECIFICATIONS AND / OR SPECIAL PROJECT REQUIREMENTS. IN THIS INSTANCE THE PIPE MATERIAL CLASSIFICATION SHALL BE MARKED WITH THE PROJECT OR TENDER NUMBER AND USED ONLY FOR THE APPLICABLE PROJECT OF TENDER.

EXAMPLE: 150# CLASS, CARBON STEEL, 2ND CARBON STEEL PIPE MATERIAL CLASS WITH 150# CLASS AC02-DESIGNATION

INSTRUMENT IDENTIFICATION (ISA 5.1 R2009)				
FIRST-LETTER		SUCCEEDING-LETTERS		
MEASURED OR INITIATING VARIABLE	MODIFIER	READOUT OR PASSIVE FUNCTION	OUTPUT FUNCTION	MODIFIER
A ANALYSIS		ALARM		
B BURNER, COMBUSTION		USER'S CHOICE	USER'S CHOICE	USER'S CHOICE
C CONDUCTIVITY			CONTROL	CLOSE
D USER'S CHOICE	DIFFERENTIAL	DETECTOR		DEVIATION
E VOLTAGE		SENSOR (PRIMARY ELEMENT)		
F FLOW, FLOW RATE	RATIO (FRACTION)			
G USER'S CHOICE		GLASS, VIEWING DEVICE		
H HAND				HIGH
I CURRENT (ELECTRICAL)		INDICATE		
J POWER		SCAN		
K TIME, TIME SCHEDULE	TIME RATE OF CHANGE		CONTROL STATION	
L LEVEL		LIGHT		LOW
M USER'S CHOICE				MIDDLE, INTERMEDIATE
N USER'S CHOICE		USER'S CHOICE	USER'S CHOICE	USER'S CHOICE
O USER'S CHOICE		ORIFICE, RESTRICTION		OPEN
P PRESSURE, VACUUM		POINT (TEST CONNECTION)		
Q QUANTITY	INTEGRATE, TOTALIZE	INTEGRATE, TOTALIZE		
R RADIATION		RECORD		RUN
S SPEED, FREQUENCY	SAFETY		SWITCH	STOP
T TEMPERATURE			TRANSMIT	
U MULTIVARIABLE		MULTIFUNCTION	MULTIFUNCTION	
V VIBRATION, MECHANICAL ANALYSIS			VALVE, DAMPER, LOUVER	
W WEIGHT, FORCE		WELL, PROBE		
X UNCLASSIFIED	X AXIS	TROUBLE	UNCLASSIFIED	UNCLASSIFIED
Y EVENT, STATE OR PRESENCE	Y AXIS		RELAY, COMPUTE, CONVERT	
Z POSITION, DIMENSION	Z AXIS		DRIVER, ACTUATOR, UNCLASSIFIED	

NOTES:

- 1. LD IS USED TO DESIGNATE LEAK DETECTION INSTRUMENT.

CONCEPTUAL DESIGN

VEOLIA VEOLIA NUCLEAR SOLUTIONS FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352


CIMARRON
PUMP AND TREAT SYSTEM PROJECT

PROCESS
SYMBOLS, NOTES, AND ABBREVIATIONS

NAME	DATE	COMPANY
S. MOORE	10/20/11	AMER
V. DAVISON	11/20/11	AMER
J. WILSON	11/20/11	AMER
D. SMITH	11/20/11	AMER
E. LLOYD	11/20/11	AMER

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	BY	CHK	COMPANY

SCALE: NONE



GENERAL NOTES:

- 1 SPARE, FILLED VESSELS WILL BE AVAILABLE AND CHANGED OUT SO PROCESS CAN CONTINUE TO OPERATE QUICKLY.
- 2 VESSEL HUB ASSEMBLY AND RETENTION SCREENS.

SLUICE AND REFILL HOSE CONFIGURATION:

- A SLUICE NOZZLE INLET:
HOSE "A" CONNECTED FOR SLUICING AND FOR RESIN REFILL.
- B SLUICE NOZZLE OUTLET:
HOSE "B" CONNECTED FOR SLUICING.
- C WATER OUTLET:
HOSE "C" CONNECTED FOR WATER REMOVAL.

CONCEPTUAL DESIGN

VEOLIA VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT FACILITY RESIN HANDLING PROCESS FLOW DIAGRAM

NAME	DATE	COMPANY
V. DAVISON	10/20/22	VEOLIA
S. MOORE	11/21/22	VEOLIA
D. SMITH	11/21/22	VEOLIA
J. WILSON	11/21/22	VEOLIA
E. LLOYD	11/21/22	VEOLIA

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	ENGR	COMPANY

DWG NO: VFS-EPM-000-DWG-P-111 SHEET 1 OF 2 REV D

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	ENGR	COMPANY

DRAWING TRACEABILITY LIST

A

A

F

F

E

E

D

D

C

C

B

B

A

A

8

7

6

5

4

3

2

1

8

7

6

5

4

3

2

1

8

7

6

5

4

3

2

1

F

F

E

E

D

D

C

C

B

B

A


A

		Stream #	30	31	32
		Description	Fresh Resin (Unused)	Inert	Packaged Resin
Parameter	Units				
Solid Streams					
Flow					
Unused IX Resin	cu ft/yr		449	-	-
Exhausted IX Resin	cu ft/yr		-	-	-
Inert	cu ft/yr		-	44.9	-
Packaged Exhaust IX Resin	cu ft/yr		-	-	617

Stream table based on design conditions; actual conditions will vary over the course of remediation. Design conditions result in a higher usage than actually anticipated.

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	ENGR	COMPANY

CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME		DATE	REVISION
DESIGNED BY V. DAVISON		08/11/2015	1
CHECKED BY S. MOORE		08/11/2015	2
DRAWN BY J. WILSON		08/11/2015	3
PROJECT ENGINEER B. GARRETT		08/11/2015	4
PROJECT MANAGER E. LLOYD		08/11/2015	5

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT FACILITY RESIN HANDLING PROCESS FLOW DIAGRAM

SCALE	NONE	DATE	08/11/2015	SHEET	2	OF	2
-------	------	------	------------	-------	---	----	---

DWG NO VFS-EPM-000-DWG-P-111

8

7

6



5

4

3

2

1



- GENERAL NOTES:**
- 1 HIGH ALARM PUMP OUT TK-303 (OPERATOR ACTION).
 - 2 OPERATIONS IN THE RESIN PROCESS AREA ARE CONTROLLED LOCALLY.
 - 3 LONG RADIUS FITTINGS TO BE USED FOR LINES CARRYING RESIN.
 - 4 PORT FOR MANUAL ADDITION OF SAMPLE PURGE WATER.
 - 5 ADD CLEAR SECTION TO PIPE WORK FOR OBSERVATION OF SLUICING PROCESS.
 - 6 REFER TO DIAPHRAGM PUMP DETAIL FOR INSTRUMENT AIR SUPPLY TO P-302 AND P-305.

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	DRAWN	REVISED	BY
S. MOORE	11/13/13	ASST		
V. DAVISON	11/13/13	ASST		
J. WILSON	11/13/13	ASST		
D. SMITH	11/13/13	ASST		
E. LLOYD	11/13/13	ASST		

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT FACILITY P&ID
SPENT RESIN HANDLING

REV	DATE	DESCRIPTION	ENGR	COMPANY
F		VFS-EPM-000-DWG-P-125		

SCALE: NONE SHEET 1 OF 1


DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST								
		NEXT USED ON	REFERENCES					
REVISIONS								

DWG NO VFS-EPM-000-DWG-P-125 SHEET 1 OF 1 REV. D

8 7 6 5 4 3 2 1



- NOTES:**
- SEE VFS-EPM-000-DWG-S-101 FOR NOTES, ABBREVIATIONS AND SCHEDULE.
 - REMOVABLE RAILING SECTION FOR DRUM DUMPER OPERATION.
 - REMOVABLE RAILING FOR FORK LIFT/PALLET PLACEMENT.



MEZZANINE - PLAN
 SCALE: 1/4" = 1'-0"
 0' 2' 4' 8' 12'
 1/4" = 1'-0" SCALE FEET

CONCEPTUAL DESIGN



NAME	DATE	COMMENTS
S. MOORE	10/1/18	REVISED
J. PIERCE	10/1/18	REVISED
D. NELSON	10/1/18	REVISED
J. WILSON	10/1/18	REVISED
E. LLOYD	10/1/18	REVISED

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT

WESTERN AREA TREATMENT FACILITY SPENT RESIN HANDLING MEZZANINE - PLAN

SCALE: 1/4" = 1'-0"

DWG NO: VFS-EPM-000-DWG-S-120

REV: B


SHEET 1 OF 5

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES					
					REVISIONS			

8 7 6 5 4 3 2 1

VFS-EPM-000-DWG-S-120 SH 1 OF 5 REV. B

A



- NOTES:
1. SEE VFS-EPM-000-DWG-S-101 FOR NOTES, ABBREVIATIONS AND SCHEDULE.
 2. SEE VFS-EPM-000-DWG-S-110-1 FOR BASE PLATE LOCATIONS.
 3. ALL BRACES ARE L3x3x1/4. SEE DETAILS ON SH 5 FOR ANGLE.
 4. SEE SHEET 5 FOR ALL CONNECTION DETAILS.
 5. SEE SHEET 1 FOR REMOVABLE GUARDRAILS.

1 MEZZANINE FRAMING DETAIL (TOS +10'-6")
 S-120-1 SCALE: 1"=1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES					
					REVISIONS			

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

NAME	DATE	COMPANY
S. MOORE	11/15/17	VFS
J. PIERCE	11/15/17	VFS
D. NELSON	11/15/17	VFS
J. WILSON	11/15/17	VFS
E. LLOYD	11/15/17	VFS

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT

**WESTERN AREA TREATMENT
 FAC. SPENT RESIN HANDLING
 MEZZANINE - FRAMING**


SIZE	GRID NO	REV
F	VFS-EPM-000-DWG-S-120	B

SHEET 2 OF 5


VFS-EPM-000-DWG-S-120 SH 2 OF 5 REV. B

8 7 6 5 4 3 2 1

NOTES:
 1. SEE VFS-EPM-000-DWG-S-101 FOR NOTES, ABBREVIATIONS AND SCHEDULE.



2 STAIR DETAIL
 S-120-1 SCALE: 3/4" = 1'-0"



RISE AND RUN DETAIL
 SCALE: 3/4" = 1'-0"

CONCEPTUAL DESIGN

VEOLIA
 VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

NAME	DATE	COMPL.
S. MOORE	11/17/13	11/17/13
J. PIERCE	11/17/13	11/17/13
D. NELSON	11/17/13	11/17/13
J. WILSON	11/17/13	11/17/13
E. LLOYD	11/17/13	11/17/13

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
**WESTERN AREA TREATMENT
 FAC. SPENT RESIN HANDLING
 MEZZANINE - STAIR DETAILS**
 VFS-EPM-000-DWG-S-120
 SHEET 3 OF 5


DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS			

VFS-EPM-000-DWG-S-120 3 OF 5 REV B


8 7 6 5 4 3 2 1

NOTES:


- SEE VFS-EPM-000-DWG-S-101 FOR NOTES, ABBREVIATIONS AND SCHEDULE.



A SECTION
S-120-3 SCALE: NTS




B SECTION
S-120-3 SCALE: 1"=1'-0"




C SECTION
S-120-3 SCALE: 1"=1'-0"


- NOTE:
1. METAL TREAD STAIR (AT FINISHED FLOOR).



D SECTION
S-120-2, 3 SCALE: 1"=1'-0"



E SECTION
S-120-3 SCALE: 1"=1'-0"



F SECTION
S-120-3 SCALE: 1"=1'-0"

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352


CIMARRON PUMP AND TREAT SYSTEM PROJECT	WESTERN AREA TREATMENT FAC. SPENT RESIN HANDLING MEZZANINE - STAIR DETAILS
VFS-EPM-000-DWG-S-120	
F	B
SCALE: SHOWN	SHEET 4 OF 5

NO.	DATE	BY	CHKD.	DESCRIPTION
1	11/21/13	S. MOORE	J. PIERCE	ISSUED FOR PERMIT
2	11/21/13	J. PIERCE	D. NELSON	REVISED
3	11/21/13	D. NELSON	J. WILSON	REVISED
4	11/21/13	J. WILSON	E. FLOYD	REVISED

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	BY	CHKD.
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS				


VFS-EPM-000-DWG-S-120 4 OF 5 REV B

NOTES:
1. SEE VFS-EPM-000-DWG-S-101 FOR NOTES, ABBREVIATIONS AND SCHEDULE.




SUPPORTED BEAM SIZE	NUMBER OF 3/4" DIA BOLTS
W8	2
W10	2
W12	3
W14	3
W16	4
W18	5
W21	6
W24	7
W36	10

BEAM CONNECTION, TYP
SCALE: 1" = 1'-0"




BEAM TO COLUMN CONNECTION, TYP
SCALE: 1" = 1'-0"




BRACE TO BASE PLATE CONNECTION
SCALE: 1" = 1'-0"

DEG θ	a	b	NOTES
3.4-36	7 1/2"	15 1/2"	
21-22	8"	20"	HORIZONTAL LEG BOTTOM
15-16	8"	31"	
29,33,35.5	9"	16"	



BP1 - BASE PLATE DETAIL
SCALE: 3/4" = 1'-0"

- NOTE:
1. BASE PLATE DIMENSION SHALL ACCOMMODATE BRACE CONNECTOR PLATE LENGTH.
2. SEE VFS-EPM-000-DWG-S-110-01 FOR BP1 LOCATIONS.



BRACE TO BEAM/COLUMN CONNECTION - TYP
SCALE: 1" = 1'-0"

BEAM	DEG θ	a	b	c	d	e	f	NOTES
W10	21.6	21.5	6.5	1.5	0.75	7 1/2"	7 1/2"	
W10	29	13.25	7.0	1.5	1.0	8"	8"	
W10	33	11.25	8.0	1.5	1.5	8"	8"	
W10	35	11.5	9.5	1.5	2.25	9"	9"	
W12	15.5	32.75	6.5	2.75	0.75	9"	9"	
W12	34-35	12.5	11.0	1.5	3.0	9"	9"	
W12	36	11.25	11.0	1.5	3.0	9"	9"	

- NOTES:
1. THE PURPOSE OF THE WHITMORE STRESS BLOCK IS TO ENSURE A PLASTIC HINGE WILL FORM IN THE BRACE CONNECTION GUSSET PLATE DURING AN EXTREME SEISMIC EVENT. IN ORDER TO ACHIEVE THIS, NO ELEMENTS MAY BE ATTACHED TO THE GUSSET PLATE WITH IN THE WHITMORE STRESS BLOCK.
2. THE WORK POINT TO WORK POINT DISTANCE FOR SPECIAL CONCENTRIC BRACED FRAME CONNECTIONS SHALL BE ESTABLISHED BY ENSURING THAT THE VERTEXES OF THE TRIANGLES SHOWN ON THE DETAIL ARE COINCIDENT WITH ADJACENT MEMBERS.
3. IF THE VERTEX OF A STRESS BLOCK DOES NOT COINCIDE WITH A COLUMN, A STIFFENER PLATE SHALL BE PROVIDED THAT EXTENDS FROM THE VERTEX OF THE WHITMORE STRESS BLOCK TO THE ADJACENT COLUMN WEB AND FLANGES.
4. UNO, USE AWS D1.1 FOR MINIMUM WELD REQUIREMENTS.
5. UNO, USE AISC 14TH EDITION FOR MINIMUM EDGE MARGINS.

CONCEPTUAL DESIGN

VEOLIA VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPANY
S. MOORE	11/15/11	UNEP
J. PIERCE	11/15/11	UNEP
D. NELSON	11/15/11	UNEP
J. WILSON	11/15/11	UNEP
E. LLOYD	11/15/11	UNEP

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
WESTERN AREA TREATMENT FAC. SPENT RESIN HANDLING MEZZANINE - FRAME DETAILS

SCALE: SHOWN
SHEET 5 OF 5

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS				

VFS-EPM-000-DWG-S-120 SH 5 OF 5 REV B

8

7

6

5

4

3

2

1

GENERAL NOTES:

1. CONTRACTOR SHALL HAVE A FULL SET OF THE CURRENT APPROVED CONSTRUCTION DOCUMENTS INCLUDING ANY APPROVED CHANGE DOCUMENTATION ON THE PROJECT AT ALL TIMES.
2. CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OR PROPER RESETTING OF ALL EXISTING STRUCTURES, MONUMENTS AND FACILITIES UNLESS OTHERWISE NOTED ON THE PLANS. ANY EXISTING STRUCTURES, MONUMENTS, OR FACILITIES THAT ARE DAMAGED DURING CONSTRUCTION ACTIVITIES SHALL BE RESTORED TO A CONDITION EQUAL TO OR BETTER THAN ORIGINAL AT CONTRACTOR'S EXPENSE.
3. ANY DEVIATION FROM THESE PLANS WITHOUT PRIOR APPROVAL FROM THE ENGINEER AND OWNER SHALL BE AT THE CONTRACTOR'S OWN RISK AND EXPENSE.
4. SITE CONDITIONS SHALL BE CONFIRMED BY CONTRACTOR PRIOR TO STARTING WORK.
5. IT IS CONTRACTOR'S RESPONSIBILITY TO CONTACT UTILITIES LOCATE PROVIDER TO IDENTIFY UNDERGROUND UTILITIES PRIOR TO COMMENCING CONSTRUCTION ACTIVITIES.
6. EROSION AND SEDIMENT CONTROL BMP'S INSTALLATION AND MAINTENANCE IS THE RESPONSIBILITY OF CONTRACTOR THROUGHOUT THE DURATION OF THE CONSTRUCTION ACTIVITIES.
7. CONTRACTOR SHALL MAINTAIN CONSTRUCTION REDLINES TO DOCUMENT AS-BUILT CONDITION. REDLINES WILL BE AVAILABLE FOR ENGINEERING REVIEW AT ALL TIMES. AT THE COMPLETION OF CONSTRUCTION ACTIVITIES REDLINES SHALL BE DELIVERED TO ENGINEER.

ABBREVIATIONS:

- BMP BEST MANAGEMENT PRACTICES
- EL ELEVATION
- EP EDGE OF PAVEMENT
- FG FINISHED GRADE
- FF FINISHED FLOOR
- GB GRADE BREAK
- LF LINEAR FEET
- R RADIUS
- RG ROUGH GRADE
- TOE TOE OF SLOPE
- TOF TOP OF FOUNDATION
- TOP TOP OF SLOPE

LEGEND:

- E ELECTRICAL CONDUIT/CABLE
- I COMMUNICATION CONDUIT/CABLE
- FO FIBER OPTIC CABLE
- W DOMESTIC WATER LINE
- SAN SANITARY SEWER LINE
- X FENCE LINE
- GRADE BREAK
- ANGULAR STONE
- CONCRETE
- TRUEGRID PERMABLE PAVERS
- GRAVEL
- COMPACTED SOIL OR STRUCTURAL FILL
- O ELECTRICAL POLE
- DOMESTIC WATER VALVE
- BACK FLOW PREVENTER
- FIRE HYDRANT
- SITE ELECTRICAL NOTES
- COMMUNICATION NOTES
- SANITARY SEWER NOTES
- DOMESTIC WATER NOTES

D

C

B

A

F

E

D

C

A

CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

NAME	DATE	COMPANY
S. MOORE	10/1/2018	VEOLIA
D. NELSON		VEOLIA
J. PIERCE		VEOLIA
J. WILSON		VEOLIA
E. LLOYD		VEOLIA

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
 CIVIL SYMBOLS, NOTES
 AND ABBREVIATIONS

VEOLIA
 F

DWG NO	TITLE	REF NUMBER	TITLE	REV	REV DATE	DESCRIPTION	REV	REV DATE	BY	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							

DWG NO VFS-EPM-000-DWG-C-201 SH 1 OF 1 REV B

8

7

6

5

4

3



2

1



GENERAL NOTES:


1. SEE VFS-EPM-000-DWG-C-201 FOR CIVIL NOTES.
2. SEE VFS-EPM-000-DWG-G-200 FOR GENERAL EQUIPMENT ARRANGEMENT AND PIPING.
3. SEE VFS-EPM-000-DWG-C-220 FOR SITE UTILITY PLAN, SEE BMCD-GWREMED-C006 AND BMCD-GWREMED-C008.
4. SEE VFS-EPM-000-DWG-S-201 FOR STRUCTURAL NOTES.
5. ROAD FINISH IS TO MATCH NEW SURFACE CONDITIONS, SEE SECTION B FOR DETAILS.



TRUEGRID PRO NOTES:

1. FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF TRUEGRID PRODUCT
2. USE 5/8\"/>

TRUEGRID PRO PAVING SECTION
SCALE: NONE




NOTES:

1. FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION OF GEI WORKS WOVEN 315 OR EQUIVALENT GEOFABRIC PRODUCT.

GRAVEL SECTION
SCALE: NONE

SITE PLAN
SCALE: 1" = 10'-0"
0 10 20 Feet

CONCEPTUAL DESIGN



NAME	DATE	COMPANY
S. MOORE	10/2023	USFS
D. NELSON	1/2024	USFS
J. PIERCE	1/2024	USFS
J. WILSON	1/2024	USFS
E. LLOYD	1/2024	USFS

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
BURIAL AREA #1
SITE PLAN


DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS						
NEXT USED ON										

REV	ENG NO	SCALE	SHOWN	EST	SHEET 1 OF 1
F	VFS-EPM-000-DWG-C-210				G

VFS-EPM-000-DWG-C-210 SH 1 OF 1 REV G

8 7 6 5 4 3 2 1

F
E
D
C
B
A



GENERAL NOTES:

1. ALL SOIL COMPACTION REQUIREMENTS SHALL BE DETERMINED BY GEOTECHNICAL INVESTIGATION.
2. ALL STRUCTURAL FILL SHALL MEET GEOTECHNICAL ENGINEERS REQUIREMENTS.
3. COMMUNICATION AND ELECTRICAL LINE FOR INJECTION SKID NOT SHOWN. DESIGN BY OTHERS.
4. CONSTRUCTION OF ALL SITE UTILITIES SHALL CONFORM TO LOCAL JURISDICTION REQUIREMENTS AND APPROVED CONSTRUCTION SPECIFICATIONS.
5. COORDINATE WITH BMCD-GWREMED-C006 FOR UTILITIES AND PROCESS LINE INTERFACE.

SITE ELECTRICAL NOTES:

- 1 ELECTRICAL CONNECTION AT EXISTING POLE AND POLE MOUNTED TRANSFORMERS BY OTHERS.
- 2 METERING RACK AND DISCONNECT SWITCHES PROVIDED BY OTHERS. POINT OF CONNECTION FOR PUMP POWER IS AT LOAD SIDE OF DISCONNECT SWITCH.


SITE COMMUNICATION NOTES:

- 1 COMMUNICATION PULL BOX. DESIGN AND INSTALLATION BY OTHERS.
- 2 CONNECT FIBER OPTIC CABLE TO POWER DISTRIBUTION RACK. DESIGN OF CONDUIT AND FIBER OPTIC CABLE BY OTHERS.


EDGE OF DRIVING SURFACE

SITE PLAN

SCALE: 1" = 10'-0"



CONCEPTUAL DESIGN



**CIMARRON
PUMP AND TREAT SYSTEM PROJECT
BURIAL AREA #1
SITE UTILITY PLAN**

NAME	DATE	COMPANY
S. MOORE	REVISION	VNSFS
B. NELSON	REVISION	VNSFS
J. PIERCE	REVISION	VNSFS
J. WILSON	REVISION	VNSFS
E. ELLOYD	REVISION	VNSFS


REV	DWG NO	SCALE	SHOWN	EXT	SHEET	1	OF	1
F	VFS-EPM-000-DWG-C-220							

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							


VFS-EPM-000-DWG-C-220 SH 1 OF 1 REV D

GENERAL NOTES:


- SEE VFS-EPM-000-DWG-C-201 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.




1 CHAIN-LINK FENCE WITH GATE DETAIL
C-210 SCALE: NONE




2 CHAIN-LINK FENCE WITH PERSONNEL GATE DETAIL
C-210 SCALE: NONE



3 EXTERIOR BOLLARD DETAIL
C-210 SCALE: NONE



A SECTION
SCALE: NONE



(CURB ONLY REQUIRED IN LOCATIONS INDICATED ON CIVIL LAYOUTS)
4 MISCELLANEOUS EQUIPMENT PAD
C-210 SCALE: NONE

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS						

CONCEPTUAL DESIGN

VEOLIA
VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	STATUS
S. MOORE	10/15/13	ISSUED
D. NELSON	10/15/13	ISSUED
J. PIERCE	10/15/13	ISSUED
K. ROBERTSON	10/15/13	ISSUED
J. WILSON	10/15/13	ISSUED
K. ROBERTSON	10/15/13	ISSUED
E. LLOYD	10/15/13	ISSUED

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

BURIAL AREA #1
CIVIL DETAILS

SCALE	DATE	REV
NONE	10/15/13	1

VFS-EPM-000-DWG-C-230

SHEET 1 OF 1

8 7 6 5 4 3 2 1

LINES: SYMBOLS: (CONTINUED) ABBREVIATIONS: INSTRUMENT/FUNCTION SYMBOLS: GENERAL NOTES:

ONE-LINE CONDUCTOR/CONDUIT
UNDERGROUND CONDUIT
- G - GROUNDING CONDUCTOR
EMBEDDED REBAR

SPD SURGE PROTECTION DEVICE, INTERNAL
Duplex RECEPTACLE
DOUBLE DUPLEX RECEPTACLE
GFCI
GFCI WP
A 1' X 4' LUMINAIRE
A = FIXTURE TYPE
A 2' X 4' LUMINAIRE
A = FIXTURE TYPE
A 1' X 4' LUMINAIRE W/ EMERGENCY BATTERY PACK
A = FIXTURE TYPE
A 2' X 4' LUMINAIRE W/ EMERGENCY BATTERY PACK
A = FIXTURE TYPE
HA WALL MOUNTED LUMINAIRE
A = FIXTURE TYPE

A AMPERES
BA1 BURIAL AREA 1
CBL CABLE
CKT CIRCUIT
CTRL CONTROL
DP DISTRIBUTION PANEL
DS DISCONNECT SWITCH
EGC EQUIPMENT GROUNDING CONDUCTOR
F.O. FIBER OPTIC
FVNR FULL VOLTAGE NON REVERSING
G GROUND
GEC GROUNDING ELECTRODE CONDUCTOR
GES GROUNDING ELECTRODE SYSTEM
GFCI GROUND FAULT CIRCUIT INTERRUPTER
GFEP GROUND FAULT EQUIPMENT PROTECTOR
GND GROUNDING CONDUCTOR
HMI HUMAN MACHINE INTERFACE
HP HORSE POWER
HVAC HEATING, VENTILATION & AIR CONDITIONING
HZ HERTZ
IO INPUT/OUTPUT
IX ION EXCHANGE
KV KILO-VOLT
KVA KILO-VOLT AMPERES
KW KILO-WATT
KWH KILO-WATT HOUR
LED LIGHT EMITTING DIODE
LP LIGHTING PANEL
MCC MOTOR CONTROL CENTER
MLO MAIN LUGS ONLY
N NEUTRAL
NEC NATIONAL ELECTRICAL CODE
P PUMP/POLE BREAKER
PLC PROGRAMMABLE LOGIC CONTROLLER
PLG PLUG
PP POWER PANEL
PWR POWER
RCPT RECEPTACLE
SKD SKID
SPD SURGE PROTECTIVE DEVICE
SWBD SWITCHBOARD
V VOLTS
VA VOLT AMPERES
VFD VARIABLE FREQUENCY DRIVE
W WATTS/WIRE
WAF WESTERN AREA TREATMENT FACILITY
WP WEATHERPROOF
XFMR TRANSFORMER
XO TRANSFORMER SECONDARY NEUTRAL

PRIMARY LOCATION
NORMALLY ACCESSIBLE TO
OPERATOR
XXX DISCRETE INSTRUMENTS
XXX SHARED DISPLAY,
SHARED CONTROL

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE, 2017 EDITION.

SYMBOLS:

CORD & PLUG/RECEPTACLE

NON-FUSED DISCONNECT SWITCH
FUSED DISCONNECT SWITCH
FUSE
LINE BREAK
CONNECTION POINT/ GROUND ROD
EXOTHERMIC BOND OR COMPRESSION FITTING CONNECTION
CIRCUIT BREAKER (TRIP)
CIRCUIT BREAKER (TRIP/FRAME)
CURRENT TRANSFORMER
MOTOR X=HP
TRANSFORMER
GROUND
KILOWATT HOUR METER
POWER PANEL, MAIN BREAKER
LIGHTING PANEL, MLO, NUMBER INDICATES PANEL SIZE
ENCLOSURE/SKID
VARIABLE FREQUENCY DRIVE
SURGE PROTECTION DEVICE, EXTERNAL
DIGITAL POWER METER
FULL VOLTAGE NON REVERSING STARTER
AVAILABLE 3Ø FAULT CURRENT (RMS, SYM. AMPS)

DWG NO	TITLE	REF NUMBER	TITLE	REV NO	DESCRIPTION	REV DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS				

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	DESCRIPTION
D. KING		
D. KING		
S. MOORE		
R. JENSEN		
E. LLOYD		

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

ELECTRICAL
SYMBOLS, NOTES, AND
ABBREVIATIONS

REV	BY	DATE	DESCRIPTION
F			

SEE DWG NO: VFS-EPM-000-DWG-E-201

SCALE: NONE EST

sheet 1 of 1

VFS-EPM-000-DWG-E-201 SH 1 OF 1 REV C

8

7

6

5

4

3

2

1

F

E

D


C

B

A

GENERAL NOTES:

1. SEE VFS-EPM-000-DWG-E-201 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.
2. GROUNDING SHALL BE IN ACCORDANCE WITH THE 2017 NATIONAL ELECTRICAL CODE.
3. INSTALL GROUNDING ELECTRODE CONDUCTOR, SIZED BASED ON NEC TABLE 250.66 USING THE SERVICE PHASE CONDUCTOR SIZE.
4. SEE DRAWING VFS-EPM-000-DWG-210 FOR CONDUCTOR SIZES.
5. INSTALL TWO 8" X 5/8" GROUND RODS SIX FEET APART, ADJACENT TO POWER DISTRIBUTION RACK FOR GROUNDING ELECTRODE SYSTEM.
6. LOW VOLTAGE GROUNDING AT UTILITY TRANSFORMER POLE.



BA1 GROUNDING DIAGRAM
SCALE: NOT TO SCALE

CONCEPTUAL DESIGN



NAME	DATE	COMPANY
D. KING		VEOLIA
S. MOORE		VEOLIA
R. JENSON		VEOLIA
E. LLOYD		VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
BURIAL AREA #1
GROUNDING DIAGRAM

VEOLIA
VFS-EPM-000-DWG-E-205

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	DESCRIPTION
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS					

VFS-EPM-000-DWG-E-205 BH 1 OF 1 REV B

8

7

6

5

4

3

2


1

A

B

8 7 6 5 4 3 2 1

- GENERAL NOTES:**
- SEE VFS-EPM-000-DWG-E-201 FOR SYMBOLS, NOTES, AND ABBREVIATIONS.
 - SEE BMCD-GWREMED-E-102 FOR SINGLE LINE DIAGRAM.



BA1 SINGLE LINE DIAGRAM
SCALE: NOT TO SCALE

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

<table border="1" style="width: 100%; border-collapse: collapse;"> <tr><th>NAME</th><th>DATE</th><th>COMPANY</th></tr> <tr><td>DRYDEN</td><td>11/13/2013</td><td>USPS</td></tr> <tr><td>D KING</td><td></td><td>USPS</td></tr> <tr><td>IS MOORE</td><td></td><td>USPS</td></tr> <tr><td>IR JENSON</td><td></td><td>USPS</td></tr> <tr><td>E LLOYD</td><td></td><td>USPS</td></tr> </table>	NAME	DATE	COMPANY	DRYDEN	11/13/2013	USPS	D KING		USPS	IS MOORE		USPS	IR JENSON		USPS	E LLOYD		USPS	<p style="text-align: center;">CIMARRON PUMP AND TREAT SYSTEM PROJECT</p> <p style="text-align: center;">BURIAL AREA #1 SINGLE LINE DIAGRAM</p>								
NAME	DATE	COMPANY																									
DRYDEN	11/13/2013	USPS																									
D KING		USPS																									
IS MOORE		USPS																									
IR JENSON		USPS																									
E LLOYD		USPS																									
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr><th>DWG NO</th><th>TITLE</th><th>REF NUMBER</th><th>TITLE</th><th>DESCRIPTION</th><th>REV</th><th>DATE</th><th>BY</th><th>CHKD</th><th>APPV</th></tr> <tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr> </table>	DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV	DATE	BY	CHKD	APPV											<table border="1" style="width: 100%; border-collapse: collapse;"> <tr><td>SCALE</td><td>NONE</td><td>SPT</td></tr> <tr><td>SHEET</td><td>1</td><td>OF 1</td></tr> </table>	SCALE	NONE	SPT	SHEET	1	OF 1
DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV	DATE	BY	CHKD	APPV																		
SCALE	NONE	SPT																									
SHEET	1	OF 1																									

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV	DATE	BY	CHKD	APPV

VFS-EPM-000-DWG-E-210 | SHEET 1 OF 1 | REV D

8

7

6

5

4

3


2

1




GENERAL NOTES:

1. SEE DRAWING VFS-EPM-000-DWG-E-210 FOR SINGLE LINE DIAGRAM.
2. SEE DRAWING VFS-EPM-000-DWG-E-231 FOR CONDUIT SCHEDULE..
3. UNDERGROUND CONDUIT ROUTING IS SHOWN DIAGRAMMATICALLY. FIELD ROUTE AS REQUIRED TO AVOID INTERFERENCES WITH STRUCTURAL FOUNDATIONS AND EQUIPMENT.
4. MINIMUM CONDUIT DEPTH SHALL BE PER NEC REQUIREMENTS.
5. INSTALL COMMUNICATION PULLBOXES AS REQUIRED TO MAINTAIN FIBER OPTIC CABLE PULLS UNDER MAXIMUM ALLOWED CABLE TENSION.
6. SEE BMCD DRAWINGS FOR COMMUNICATIONS AND POWER STUB-UP LOCATIONS AT INJECTION SKID.
7. INSTALL 30A HEAVY DUTY NEMA-3R UNFUSED DISCONNECT SWITCH IN APPROXIMATE LOCATION SHOWN.
8. TRANSITION PVC CONDUIT BELOW GRADE TO RMC ABOVE GRADE USING 90 DEGREE RMC SWEEPS.
9. SEE DRAWING VFS-EPM-000-DWG-M-210 FOR LOCATIONS OF ELECTRICAL PANELS AND EQUIPMENT IN PUMP SKID.



ELECTRICAL UTILITY PLAN
SCALE: 1" = 5'-0"



CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>NAME</th> <th>DATE</th> <th>COMPANY</th> </tr> </thead> <tbody> <tr> <td>S. MOORE</td> <td>08/20/23</td> <td>VEOLIA</td> </tr> <tr> <td>D. KING</td> <td></td> <td>VEOLIA</td> </tr> <tr> <td>J. PIERCE</td> <td></td> <td>VEOLIA</td> </tr> <tr> <td>R. JENSEN</td> <td></td> <td>VEOLIA</td> </tr> <tr> <td>E. ELLOYD</td> <td></td> <td>VEOLIA</td> </tr> </tbody> </table>	NAME	DATE	COMPANY	S. MOORE	08/20/23	VEOLIA	D. KING		VEOLIA	J. PIERCE		VEOLIA	R. JENSEN		VEOLIA	E. ELLOYD		VEOLIA	<p style="text-align: center;">CIMARRON PUMP AND TREAT SYSTEM PROJECT</p> <p style="text-align: center;">BURIAL AREA #1 ELECTRICAL UTILITY PLAN</p> <p style="text-align: center;">DWG NO: VFS-EPM-000-DWG-E-211</p>
NAME	DATE	COMPANY																	
S. MOORE	08/20/23	VEOLIA																	
D. KING		VEOLIA																	
J. PIERCE		VEOLIA																	
R. JENSEN		VEOLIA																	
E. ELLOYD		VEOLIA																	

DWG NO	TITLE	REF NUMBER	TITLE	REV	REV DATE	DESCRIPTION	REV	REV DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES							

DWG NO VFS-EPM-000-DWG-E-211 SH 1 OF 1 REV C

8

7

6

5

4


3

2

1

GENERAL NOTES:

1. DIMENSIONS ARE IN INCHES.
TOLERANCE = ± 1/4"




1 POWER SERVICE INSTALLATION
SCALE: NOT TO SCALE

PARTS LIST/MATERIAL LIST

QTY REQ'D	PARTS/DASH NUMBER			NOMENCLATURE/DESCRIPTION	MATERIAL/REFERENCE	SHEET	ITEM NO
	-000	-020	-010				
			-010	POWER SERVICE INSTALLATION		1	1
		1	-020	POWER POLE DISTRIBUTION ASSEMBLY		2	2
		1	-030	POWER DISTRIBUTION RACK INSTALLATION		2	3
		1	VFS-EPM-000-DWG-E-221-010	POWER DISTRIBUTION RACK ASSEMBLY			4
							5
1			19L551	SERVICE ENTRANCE HEAD, 1 1/2", RIGID	RACO		6
1			H363NDS	DISCONNECT SWITCH, 100A, FUSED	SQUARE D		7
1			HU363DS	DISCONNECT SWITCH, 100A, NON-FUSED	SQUARE D		8
1				SERVICE DROP BRACKET (FURNISHED BY OKLAHOMA GAS & ELECTRIC)			9
1				METER, 100 AMP (FURNISHED BY OKLAHOMA GAS & ELECTRIC)			10
1			281047	METER BASE (FURNISHED BY OKLAHOMA GAS & ELECTRIC)			11
2			AMPOLEMNT12	POLE MOUNT KIT, 12" WIDE (KIT CONTAINS 2 MOUNTS)	ALLIED MOULDED PRODUCTS, INC.		12
AR				CHANNEL CONDUIT CLAMP, 1 1/2", GALVANIZED	COMMERCIAL		13
AR	AR		ST5	CONDUIT HUB, 1 1/2"	CROUSE-HINDS		14
2	1			GROUND ROD CLAMP, UL LISTED	COMMERCIAL		15
AR	AR			GROUNDING ELECTRODE CONDUCTOR, #6 AWG, BARE COPPER	COMMERCIAL		16
2	1			GROUND ROD, 5/8"Ø X 8'-0" LONG, COPPER CLAD STEEL	(COPPER OR COPPER CLAD)		17
AR	AR			CONDUIT, 1 1/2", RIGID METAL, GALVANIZED	COMMERCIAL		18
1			YCHC2C2	IRREVERSIBLE SPLICE, #2-6 RUN, #6-2 TAP	BURNDY		19

CONCEPTUAL DESIGN



NAME	DATE	COMMENTS
S. MOORE	REVISION	
J. PIERCE	VSFS	
D. KING	VSFS	
R. JENSEN	VSFS	
E. LLOYD	VSFS	


CIMARRON
PUMP AND TREAT SYSTEM PROJECT
BURIAL AREA #1
ELECTRICAL
INSTALLATION DETAILS

VFS-EPM-000-DWG-E-220


DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	BY	CHKD	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS						

VFS-EPM-000-DWG-E-220 SHEET 1 OF 2 REV C

- NOTES:**
1. DISCONNECT CABINET TO BE LOCKED BY OKLAHOMA GAS & ELECTRIC.
 2. OKLAHOMA GAS & ELECTRIC TO SECURE ENERGIZED PARTS AND SWITCH POSITION WITH SERIES 1 LOCK (301236).
 3. INSTALL GROUNDING ELECTRODE SYSTEM CONSISTING OF TWO GROUND RODS, 5/8"Ø X 8'-0" MINIMUM LENGTH, 6'-0" APART, WITH LISTED GROUND ROD CLAMPS. INSTALL A CONTINUOUS BARE SOLID COPPER GROUNDING ELECTRODE CONDUCTOR (SIZED PER NEC ARTICLE 250) FROM GROUND RODS TO SERVICE DISCONNECT SWITCHES AS SHOWN ON RACK. BOND CONDUCTOR TO RACK WITH LISTED CLAMP. SPLICE CONNECTIONS TO GROUNDING ELECTRODE CONDUCTOR SHALL BE BY IRREVERSIBLE COMPRESSION CLAMP.
 4. INSTALL AUXILIARY GROUNDING TO POWER POLE SECONDARY DISCONNECT SWITCH AS SHOWN.



2 POWER POLE SERVICE ELECTRICAL ASSEMBLY
SCALE: 1 1/2" = 1'-0"



3 POWER DISTRIBUTION RACK INSTALLATION
SCALE: 1 1/2" = 1'-0"

CONCEPTUAL DESIGN

VEOLIA VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMPL.
S. MOORE	11/15/20	VSFS
D. KING		VSFS
J. PIERCE		VSFS
R. JENSON		VSFS
E. LLOYD		VSFS

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

BURIAL AREA #1
ELECTRICAL
ASSEMBLY AND DETAILS

VFS-EPM-000-DWG-E-220

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	ENGR	COMPANY	SCALE	SHOWN	EST	SHEET	OF
	DRAWING TRACEABILITY LIST		REFERENCES								2	2

DWG NO VFS-EPM-000-DWG-E-220 SH 2 OF 2 REV B

8

7

6

5

4


3

2

1

GENERAL NOTES:

- 1. NOZZLE LOCATIONS SHOWN ON TANKS ARE FOR INFORMATION ONLY, ACTUAL NOZZLE LOCATIONS TO BE DETERMINED BY VENDOR'S FINAL SUBMITTAL.
- 2. FOR PIPE SUPPORT SUPPORT DETAILS SEE DRAWING VFS-EPM-000-DWG-S-210. INSTALL PER SPECIFICATION SECTION 22 05 29 - HANGERS AND SUPPORTS FOR PIPING AND EQUIPMENT.
- 3. PUMP ENCLOSURE SHALL BE HUBBELL HOT BOX MODEL NUMBER DF4FEH, PART NUMBER HD041041045 WITH 1000W HEATER AND VENTILATION FAN. CENTER ENCLOSURE OVER CENTER OF PUMP AND ATTACH TO CONCRETE PAD USING SUPPLIED HARDWARE. ENSURE THAT THERE IS 12" OF CLEARANCE FROM INSIDE DIMENSIONS OF ENCLOSURE TO EDGE OF CONCRETE FOR ENCLOSURE MOUNTING. CONTRACTOR TO CUT HOLES IN SIDES OF ENCLOSURE FOR PIPE, HOLES SHALL BE 1/2" LARGER THAN PIPE SIZE. AFTER INSTALLATION APPLY EXPANDING FOAM AROUND THE PERIMETER OF THE PENETRATIONS.
- 4. INTERFACE FLANGE TO BE 12" ABOVE GRADE, CENTER CONNECTION POINT PIPE IN 18" SONNET TUBE X 30" DEEP. FILL SONNET TUBE WITH SAND OR CRUSHED ROCK AFTER HEAT TRACE HAS BEEN INSTALLED.



TANK EQUIPMENT AND ACCESSORIES ASSEMBLY

SCALE 1/4" = 1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	ENGR	COMPANY

CONCEPTUAL DESIGN

VEOLIA
NUCLEAR SOLUTIONS - FEDERAL SERVICES
 295 Bradley Blvd, Suite 300
 Richland, VA 99352
 www.nuclearsolutions.veolia.com

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT

MECHANICAL
 BURIAL AREA #1
 GENERAL ARRANGEMENT

VFS-EPM-000-DWG-G-200

SCALE SHOWN SHEET 1 OF 1

DWG NO VFS-EPM-000-DWG-G-200 SHEET 1 OF 1

8

7

6

5

4


3

2

1

NOTES:


- 1. SEE DRAWING VFS-EPM-000-DWG-G-200 FOR NOTES.
- 2. INTERFACE FLANGE TO BE 12" ABOVE GRADE. CENTER CONNECTION POINT PIPE IN 18" SONNET TUBE X 30" DEEP. FILL SONNET TUBE WITH SAND OR CRUSHED ROCK AFTER HEAT TRACE HAS BEEN INSTALLED.



SECTION A
G-200.1 SCALE: 1/2" = 1'-0"



CONCEPTUAL DESIGN



NAME	DATE	COMPANY
J. PIERCE	10/2011	VEOLIA
E. LLOYD		VEOLIA
S. MOORE		VEOLIA
J. WILSON		VEOLIA
E. LLOYD		VEOLIA

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
 MECHANICAL
 BURIAL AREA #1
 GENERAL ARRANGEMENT

VFS-EPM-000-DWG-G-220
 SHEET 1 OF 2

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS						

VFS-EPM-000-DWG-G-220 SHEET 1 OF 2

A

D

8

7

6

5

4


3

2


1

NOTES:

1. SEE DRAWING VFS-EPM-000-DWG-G-200 FOR NOTES.



B SECTION
G-200.1 SCALE: 1/2" = 1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
	DRAWING TRACEABILITY LIST		REFERENCES					

CONCEPTUAL DESIGN

VEOLIA VEOLIA
NUCLEAR SOLUTIONS - FEDERAL SERVICES
295 Bradley Blvd, Suite 300
Richland, WA 99352
www.nuclearsolutions.veolia.com

NAME	DATE	COMPANY
J. PIERCE	10/20/11	VEOLIA
E. LLOYD	11/20/11	VEOLIA
S. MOORE	11/20/11	VEOLIA
J. WILSON	11/20/11	VEOLIA
E. LLOYD	11/20/11	VEOLIA

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

MECHANICAL
BURIAL AREA #1
GENERAL ARRANGEMENT

SCALE	DRAWING NO	REV
1/2" = 1'-0"	F	D

VFS-EPM-000-DWG-G-220 SHEET 2 OF 2

DWG NO VFS-EPM-000-DWG-G-220 SHEET 2 OF 2 REV D

8

7

6

5

4

3

2

1



GENERAL NOTES:


- 1. SEE CONSTRUCTION SPECIFICATION 28 2000 FOR SECURITY SYSTEM INSTALLATION AND INTERCONNECTION DETAILS.

SYMBOLS LEGEND:

- DM DOOR POSITION SWITCH
- EL ELECTRIFIED LOCK, DOOR POSITION SWITCH, REX
- CR CARD READER - PEDESTAL MOUNTED
- FC FIXED DOME CAMERA - POLE MOUNTED
- C-XX CAMERA NUMBER/TYPE (DEFINED IN SPECIFICATION SECTION 282000)
- AFG ABOVE FINISHED GRADE

SECURE ALL ACCESS DOORS WITH PADLOCK, KEY TO BE LOCATED IN KEY CABINET IN CONTROL ROOM. PROVIDE DOOR POSITION SWITCHES AT ALL INJECTION SKID DOORS (QUANTITY AND LOCATION TO BE DETERMINED).

SECURITY GATE WITH PADLOCK, KEY TO BE LOCATED IN KEY CABINET IN CONTROL ROOM.



**BURIAL AREA #1
SITE SECURITY PLAN**
SCALE: 1/4" = 1'-0"



DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST										
NEXT USED ON										
REVISIONS										

CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

**CIMARRON
PUMP AND TREAT SYSTEM PROJECT
BURIAL AREA #1
SITE SECURITY
PLAN**

NAME	DATE	REVISION
S MOORE	10/20/20	1
D KING	10/20/20	2
J PIERCE	10/20/20	3
J WILSON	10/20/20	4
E LLOYD	10/20/20	5

SCALE	SHOWN	DATE	SHEET 1 OF 1
F			C

DWG NO VFS-EPH-000-DWG-J-211 SH 1 OF 1 REC

8

7

6

5

4


3

2


1

GENERAL NOTES:

1 BYPASS PIPING TO BE BUILT INTO SKID DESIGN.



CONCEPTUAL DESIGN



NAME	DATE	REVISION
IS MOORE	8/1/20	1
J PIERCE	8/1/20	2
J WILSON	8/1/20	3
B GARRETT	8/1/20	4
E LLOYD	8/1/20	5

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
BURIAL AREA #1
PROCESS FLOW DIAGRAM

DWG NO	TITLE	REF NUMBER	TITLE	REF	REV	DATE	DESCRIPTION	REV	BY	DATE	ENGR	COMPANY
DRAWING TRACEABILITY LIST		REFERENCES		REV	REV			REVISIONS				

SCALE	NONE	EST		DWG NO	VFS-EPM-000-DWG-P-210	REV	C
				SHEET	1	OF	2

DWG NO VFS-EPM-000-DWG-P-210 SH 1 OF 2 REC

8

7

6

5

4

3

2

1

	STREAM NO	20
	DESCRIPTION	BLENDED IX FEED
PARAMETER	UNITS	
LIQUID STREAMS		
FLOW	GPM	100
	GPD	-
LIQUID CONCENTRATIONS		
NITRATE (AS N)	PPM	-
URANIUM (TOTAL)	PPB	1000
SUSPENDED SOLIDS	PPM (DRY)	-
SOLID STREAMS		
FLOW		
UNUSED IX RESIN	CUFT/YR	-
EXHAUSTED IX RESIN	CUFT/YR	-

NOTES:

1. STREAM TABLE BASED ON DESIGN CONDITIONS; ACTUAL CONDITIONS WILL VARY OVER THE COURSE OF REMEDIATION.

F

F

E

E

D

D

C

C

B

B

A

A

CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

NAME	DATE	COMMENTS
S. MOORE	08/11/2010	ISSUED
J. PIERCE		ISSUED
L. WILSON		ISSUED
B. GARRETT		ISSUED
R. HODGSON		ISSUED
E. ELLOYD		ISSUED

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
BURIAL AREA #1
 PROCESS FLOW DIAGRAM

VEOLIA PROJECT NO: VFS-EPM-000-DWG-P-210

DWG NO	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY	REVISIONS
	DRAWING TRACEABILITY LIST								

DWG NO VFS-EPM-000-DWG-P-210
 SH 2 OF 2
 REV B

8

7

6

5

4

3

2


1

SCALE: NONE
 SHEET 2 OF 2

8 7 6 5 4 3 2 1

F
E
D
C
B
A

F
E
D
C
B
A



- GENERAL NOTES:**
- 1. ADDED FOR FUTURE SYSTEM BYPASS ONCE MCL IS ACHIEVED FOR URANIUM.
 - 2. HIGH ALARM SIGNAL SENT TO WELL FIELD HMI.
 - 3. DETECTED LEAK (LDA-201) SHUT DOWN SIGNAL SENT TO WELL FIELD HMI.
 - 4. STOP WELL FIELD PUMPS.
 - 5. SEE DRAWING P-115 SHEET 1 FOR INTERLOCK LIST.

CONCEPTUAL DESIGN

VEOLIA

VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
285 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	DESCRIPTION
V. DAVISON	5/14/2023	ENGR
S. MOORE	5/14/2023	ENGR
J. WILSON	5/14/2023	ENGR
D. SMITH	5/14/2023	ENGR
R. WOODEN	5/14/2023	ENGR
E. ELLOYD	5/14/2023	ENGR

CIMARRON
PUMP AND TREAT SYSTEM PROJECT

BURIAL AREA #1
PROCESS P&ID

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	ENGR	COMPANY	SCALE	SHEET	OF
									NONE	1	2

VFS-EPM-000-DWG-P-215
SHEET 1 OF 2
REV E

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	ENGR	COMPANY

8 7 6 5 4 3 2 1

8

7

6

5

4

3

2

1

F

F

E

E

D

D

C

C

B

B

A


A

TK-202
EFFLUENT TANK
12,000 GAL

P-203
EFFLUENT PUMP

FROM BA1
URANIUM IX TRAIN
P-115 SHEET 4
ZONE C1

BMCD VNSFS



GENERAL NOTES:

- 1 ADDED FOR FUTURE SYSTEM BYPASS ONCE MCL IS ACHIEVED FOR URANIUM.
- 2 SEE VFS-EPM-000-DWG-P-115, SHEET 2 FOR ***SAMPLE DETAIL.
- 3 SIGNAL BASED ON TANK LEVEL TO CONTROL P-203.

DWG NO	TITLE	REF NUMBER	TITLE	REV	REV DATE	DESCRIPTION	REV BY	REV DATE	BY/CHK	DATE
DRAWING TRACEABILITY LIST										
NEXT USED ON		REFERENCES								
REVISIONS										

CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, WA 99352

NAME	DATE	COMMENTS
V DAVISON	04/14/2023	ISSUED
S MOORE		ISSUED
J WILSON		ISSUED
B GARRETT		ISSUED
H MOORE		ISSUED
E LLOYD		ISSUED

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
BURIAL AREA #1
PROCESS P&ID

SCALE	NONE	EST	
SHEET	2	OF	2

VFS-EPM-000-DWG-P-215 SH 2 OF 2 REV F

8 7 6 5 4 3 2 1

GENERAL NOTES:

- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE 2015 EDITION OF THE INTERNATIONAL BUILDING CODE (IBC), LOCAL RULES AND STANDARDS OF GOVERNING AGENCIES HAVING JURISDICTION.
- CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF SITE CONDITIONS, INSTALLATION STANDARDS AND CONSTRUCTION CONDITIONS. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS PRIOR TO SHOP FABRICATION AND/OR FIELD ERECTION. DISCREPANCIES BETWEEN SITE CONDITIONS AND THE CONSTRUCTION DRAWINGS SHALL BE CALLED TO THE ATTENTION OF THE ENGINEER. WORK DONE WITHOUT THE ENGINEERS APPROVAL IS THE RESPONSIBILITY OF THE CONTRACTOR.
- ALL SPECIAL INSPECTION AND TESTING SHALL BE PERFORMED BY AN INDEPENDENT INSPECTION AND TESTING AGENCY HIRED BY THE OWNER. CONTRACTOR TO COORDINATE WITH INSPECTION AND TESTING AGENCY FOR REQUIRED CONSTRUCTION INSPECTIONS AND MATERIAL TESTING.
- THIS BUILDING SHALL BE CONSTRUCTED USING THE STANDARD DETAILS CONTAINED WITHIN THIS DRAWING SET UNLESS NOTED OTHERWISE. WHERE NO DETAIL IS NOTED IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO CHOOSE THE APPROPRIATE STANDARD DETAIL FROM THOSE PROVIDED.
- PRIOR TO DIGGING VERIFY LOCATION AND DEPTH OF UTILITIES AND OTHER UNDERGROUND INTERFERENCES. CALL TWO BUSINESS DAYS BEFORE YOU DIG AT 811.

FOUNDATION NOTES:

- FOR SLAB ON GRADE AND FOUNDATION SUBGRADE PREPARATION THE CONTRACTOR SHALL REFERENCE RECOMMENDATIONS OF THE GEOTECHNICAL ENGINEERING REPORT.
- FOUNDATION DESIGN BASED ON AN ALLOWABLE SOIL BEARING OF 2,000 PSF.
- EXCAVATE FOOTING TRENCHES AND AREA BELOW SLABS TWO FEET WIDER THAN FOOTING WIDTH AND ONE FOOT DEEPER THAN DESIGN FOOTING GRADE. PROOF ROLL THE EXPOSED TRENCH BOTTOM TO 95% OF MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D-1557. PLACE MIRAFI 500X ON COMPACTED NATIVE SOIL. PLACE A 12" THICK LAYER OF 3/4" MINUS CRUSHED ROCK OVER FABRIC.

CONCRETE NOTES:

- CONCRETE SLABS SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI AT 28 DAYS WITH A WATER TO CEMENT RATIO OF 0.45. ALL OTHER CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI AT 28 DAYS WITH A WATER TO CEMENT RATIO OF 0.5. CONCRETE DESIGN IS BASED UPON ACI 318-08 COMPRESSIVE STRENGTH OF 2500 PSI WITH NO SPECIAL INSPECTION REQUIRED PER IBC 1705.3 REQUIRED.
- CAST IN PLACE CONCRETE SHALL MEET THE FOLLOWING REQUIREMENTS:
ACI 117 - STANDARD SPECIFICATIONS FOR TOLERANCES FOR CONCRETE CONSTRUCTION AND MATERIALS.
ACI 301 - SPECIFICATIONS FOR STRUCTURAL CONCRETE.
ACI 302 - GUIDE FOR CONCRETE FLOOR AND SLAB CONSTRUCTION.
ACI 305 - HOT WEATHER CONCRETING.
ACI 306 - COLD WEATHER CONCRETING.
- UNLESS NOTED OTHERWISE, ALL CONCRETE FLAT WORK SHALL CONFORM TO THE FOLLOWING FINISHING TOLERANCES 1/8" GAP UNDER A 10'-0" STRAIGHT EDGE MEASURED AS PER ASTM E1155:
OVERALL FLATNESS NUMBER, F_L ≥ 20
MINIMUM LOCAL FLATNESS NUMBER, F_L ≥ 15
OVERALL LEVELNESS NUMBER, F_L ≥ 15
MINIMUM LOCAL LEVELNESS NUMBER, F_L ≥ 10
- ALL REINFORCING STEEL SHALL BE GRADE 60 DEFORMED BARS COMPLYING WITH ASTM SECTION A615. REINFORCING STEEL WHICH IS INDICATED ON THE PLANS AS BEING WELDED SHALL COMPLY WITH ASTM A706, AND SHALL ALSO BE DEFORMED. WELDING OF REINFORCING BARS SHALL BE PER AWS D1.4. SPECIAL INSPECTION SHALL BE PREPARED PER AWS D1.1 AND IBC 1705.2.2.1
- ANCHOR RODS SHALL CONFORM TO ASTM F1554 F_y=36 KSI WITH HEAVY HEX HEADED END OR THREADED WITH NUT UNLESS NOTED OTHERWISE ON PLANS. TACK WELD NUT TO ANCHOR ROD.
- REINFORCEMENT LAP HOOKS, ETC.; SHALL BE PER THE REINFORCEMENT TABLE UNLESS NOTED OTHERWISE.
- THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCEMENT: (MIN. COVER LISTED)
(A) CONCRETE CAST AGAINST AND PERMANENTLY PERMANENTLY EXPOSED TO EARTH: 3"
(B) CONCRETE EXPOSED TO EARTH OR WEATHER:
#6 THROUGH #18 BARS: 2"
#5 BAR, W31 OR D31 WIRE AND SMALLER: 1 1/2"
- CONCRETE ADHESIVE ANCHORS SHALL USE A36 ALL-THREAD ROD WITH HILTI HIT HY 200 ADHESIVE OR SIMPSON SET ADHESIVE, OR ENGINEER APPROVED. SPECIAL INSPECTION OF ADHESIVE ANCHORS IS REQUIRED.
- CONCRETE EXPANSION ANCHORS SHALL BE HILTI KWIK BOLT TZ OR SIMPSON STRONG BOLT OR ENGINEER APPROVED. STAINLESS STEEL ANCHORS SHALL BE USED AT ALL EXTERIOR APPLICATIONS. SPECIAL INSPECTION OF EXPANSION ANCHORS REQUIRED.
- REINFORCING DOWEL ADHESIVE SHALL BE HILTI HIT HY 200 ADHESIVE, OR SIMPSON SET-XP ADHESIVE. SPECIAL INSPECTION OF ADHESIVE DOWELS IS REQUIRED.
- ALL EXPOSED CORNERS OF CONCRETE SHALL BE FORMED INTO A 3/4" x 45 DEGREE CHAMFER, OR SCRIBED WITH A CONCAVE TOOLING DEVICE UNLESS NOTED OTHERWISE PER ACI 318.
- THOROUGHLY CLEAN FORMS AND ADJACENT SURFACES TO RECEIVE CONCRETE. REMOVE CHIPS, WOOD, SAWDUST, DIRT, OR ANY OTHER DEBRIS PRIOR TO CONCRETE PLACEMENT.
- CLEAN REINFORCING OF LOOSE RUST, MILL SCALE, DIRT, OR ANY OTHER FOREIGN MATERIAL. ACCURATELY POSITION, SUPPORT AND SECURE REINFORCEMENT PER ACI 302.
- PROPORTION AND DESIGN MIXES TO RESULT IN CONCRETE SLUMP AT POINT OF PLACEMENT NOT LESS THAN 3" AND NOT MORE THAN 5" PRIOR TO SUPERPLASTICIZER. ADDITION OF WATER TO READY-MIX CONCRETE IN THE FIELD SHALL BE ALLOWED IF ON TRIP TICKET BEFORE DISCHARGE AND TESTING.
- DEPOSIT CONCRETE IN A CONTINUOUS OPERATION UNTIL THE PLACING OF CONCRETE IS COMPLETE. IF THE POUR IS TO BE DISCONTINUOUS, CONTRACTOR SHALL USE CONSTRUCTION JOINTS, AS DETAILED ON THE DRAWINGS OR APPROVED BY THE ENGINEER.
- UNLESS NOTED OTHERWISE, REINFORCING IS NOT TO EXTEND THROUGH CONSTRUCTION JOINTS OF FLOOR SLABS-ON-GRADE.
- REPAIR ALL SURFACE DEFECTS INCLUDING TIE HOLES, MINOR HONEYCOMBING AND OTHER VISUAL IRREGULARITIES WITH CEMENT MORTAR. MORTAR FOR PATCHING SHALL BE THE SAME COMPOSITION AS THAT USED IN THE CONCRETE. PATCHING SHALL BE DONE AS SOON AS THE FORMS ARE REMOVED.
- PROVIDE (1) 2'-0" LONG #4 REBAR AT ALL RE-ENTRANT CORNERS FOR SLABS, PITS, RECESSES, OR SLAB THICKNESS CHANGES IN THE TOP 1/3 OF THE SLAB-ON-GRADE.
- REINFORCEMENT SHALL BE CONTINUOUS BENT AROUND CORNERS, OR CORNER BARS OF THE SAME SIZE MAY BE INSTALLED WITH MINIMUM LEG LENGTH THAT CONFORMS TO ACI 318-11, CLASS "B" SPLICES.
- AVOID HOT AND WINDY CONDITIONS FOR CURING SLABS. SLABS MUST BE SEALED WITH CURING COMPOUND OR "WATER CURED".

CONCRETE - ADHESIVE ANCHORED REINFORCEMENT AND THREADED RODS NOTES:

- SPECIAL INSPECTION IS REQUIRED AND SHALL BE PER IBC APPROVED ESR REPORT.
- MATERIALS:
ADHESIVE: HILTI-HIT-HY-200
- INSTALLATION:
A. INSTALL PER ESR REPORT IN CLEAN HOLES.
- DO NOT INSTALL REINFORCEMENT OR ANCHORS IN CONCRETE THAT IS LESS THAN 7 DAYS OLD.

CONCRETE - EXPANSION ANCHORS NOTES:

- SPECIAL INSPECTION IS REQUIRED AND SHALL BE PER ICC ESR 1917.
- MATERIALS:
HILTI ANCHORS: KWIK-BOLT TZ
- INSTALLATION:
A. USE CARBIDE-TIPPED DRILL BITS CONFORMING TO ANSI B212.15-1994. DRILL BIT SIZE IS EQUAL TO ANCHOR DIAMETER.
B. CLEAN HOLES OF DUST AND DEBRIS USING OIL-FREE COMPRESSED AIR AND A NYLON BRUSH. HOLE DEPTH TO EXCEED EMBEDMENT DEPTH BY TWO ANCHOR DIAMETERS.
- DO NOT INSTALL ANCHORS IN CONCRETE THAT IS LESS THAN 7 DAYS OLD.
- PROVIDE STAINLESS STEEL ANCHORS OR MECHANICALLY GALVANIZED ANCHORS (PER ASTM B-695) WHERE ANCHORS ARE USED IN EXTERIOR CONDITIONS.

ANCHOR RODS NOTES:

- ANCHOR RODS SHALL BE ASTM F1554 GRADE 36 WITH CLASS 1A THREADS, UNLESS NOTED OTHERWISE.
- FURNISH ANCHOR RODS PREFABRICATED WITH MATCHING DOUBLE HEAVY HEX NUTS JAMMED AT THE END EMBEDDED IN CONCRETE.
- FURNISH HARDENED PLATE WASHERS AND MATCHING HEAVY HEX NUTS FOR SECURING THE BASE PLATE TO THE ANCHOR RODS.
- A RIGID TEMPLATE SHALL BE USED TO LOCATE ANCHOR RODS WHILE PLACING CONCRETE.
- NO HEATING OR BENDING OF THE ANCHOR RODS IS PERMITTED.
- HOLES IN THE BASE MATERIAL SHALL NOT BE ENLARGED BY BURNING.

STATEMENT OF SPECIAL INSPECTION NOTES:

- IN ACCORDANCE WITH THE 2015 INTERNATIONAL BUILDING CODE SECTION 1704, THE OWNER SHALL EMPLOY ONE OR MORE APPROVED AGENCIES TO PERFORM INSPECTIONS DURING CONSTRUCTION ON THE TYPES OF WORK AND AS SPECIFIED BELOW. CONTRACTOR SHALL COORDINATE WITH INSPECTION AND TESTING AGENCY(S) FOR REQUIRED CONSTRUCTION INSPECTIONS AND MATERIAL TESTING. SPECIAL INSPECTION REPORTS SHALL BE SUBMITTED TO THE ARCHITECT/ENGINEER AND THE AUTHORITY HAVING JURISDICTION WEEKLY FOR REVIEW.
- CONCRETE CONSTRUCTION: SPECIAL INSPECTION PER SECTION 1705.3 AND TABLE 1705.3 OF THE IBC. EXCEPTIONS: NO SPECIAL INSPECTION IS REQUIRED FOR THE FOUNDATIONS IF THE DESIGN STRENGTH OF THE FOUNDATIONS IS BASED ON A COMPRESSIVE STRENGTH OF 2500 PSI.
- SEISMIC RESISTANCE: SPECIAL INSPECTION FOR SEISMIC RESISTANCE SHALL BE PER SECTION 1705.11 OF THE IBC AND AISC 341.
- POST INSTALLED ANCHORS: SPECIAL INSPECTION SHALL BE PER THE ANCHORS ASSOCIATED ICC-ES ESR.

SYMBOLS:

NEW CMU WALL
 SHEAR WALL
 METAL DECK SPAN DIRECTION
 STEEL COLUMN
 NEW CONCRETE SLAB
 BRACED FRAME

EXPANSION ANCHOR SCHEDULE						
ANCHOR DIAMETER	HILTI KWIK BOLT TZ			SIMPSON STRONG BOLT		
	SHALLOW	STANDARD	DEEP	SHALLOW	STANDARD	DEEP
1/2"	2"	3 1/4"	-	2 3/4"	3 7/8"	5"
5/8"	3 1/8"	4"	-	3 3/8"	5 1/8"	6 1/8"
3/4"	3 3/4"	5"	-	4 1/8"	5 3/4"	7 1/2"
1"	-	-	-	-	5 1/4"	9 3/4"

CONCEPTUAL DESIGN

VEOLIA
 VEOLIA NUCLEAR SOLUTIONS
 FEDERAL SERVICES, LLC
 295 Bradley, Suite 300
 Richland, WA 99352

NAME: S. MOORE
 DATE: 11/25/2016
 COMPANY: VEOLIA
 CHECKED: J. PIERCE
 DATE: 11/25/2016
 COMPANY: VEOLIA
 DESIGNED: D. NELSON
 DATE: 11/25/2016
 COMPANY: VEOLIA
 ENGINEER: J. WILLIAMS
 DATE: 11/25/2016
 COMPANY: VEOLIA
 CHECKED: E. ELLOYD
 DATE: 11/25/2016
 COMPANY: VEOLIA

PROJECT: CIMARRON PUMP AND TREAT SYSTEM PROJECT
 DRAWING: STRUCTURAL NOTES AND ABBREVIATIONS
 FILE: VFS-EPM-000-DWG-S-201
 SCALE: NONE
 SHEET: 1 OF 1

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	BY	DATE	ENGR	COMPANY

VFS-EPM-000-DWG-S-201 SH 1 OF 1 (REV. B)


A

B


8 7 6 5 4 3 2 1

8 7 6 5 4 3 2 1

- NOTES:**
- SEE VFS-EPM-000-DWG-C-201 FOR CIVIL SYMBOLS, NOTES, AND ABBREVIATIONS.
 - SEE VFS-EPM-000-DWG-S-201 FOR NOTES, ABBREVIATIONS AND SCHEDULE.
 - 8" THICK CONCRETE SLAB.
 - USE #5 REBAR AT 12" EACH WAY, C/C OVER 4" OF 5/8" CRUSHED MINUS COMPACTED FILL OVER 12" OF COMPACTED SUBGRADE WITH BROOM FINISH 1 TO 12 SLOPE.
 - SEE VFS-EPM-000-DWG-C-210 FOR FOUNDATION LOCATIONS.




BURIAL AREA - INJECTION SKID - PLAN VIEW
 SCALE: 1/4" = 1'-0"



SECTION
 SCALE: 3/4" = 1'-0"

CONCEPTUAL DESIGN



NAME	DATE	CONTR
S. MOORE	10/21/2010	ENGR
J. PIERCE		ENGR
D. NELSON		ENGR
J. WILSON		ENGR
E. LLOYD		ENGR

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
BURIAL AREA #1
STRUCTURAL
FOUNDATION PLAN VIEWS

VFS-EPM-000-DWG-S-210
 SHEET 1 OF 3


DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	ENGR	COMP
DRAWING TRACEABILITY LIST		REFERENCES		REVISIONS				

VFS-EPM-000-DWG-S-210 SH 1 OF 2 REV C


8 7 6 5 4 3 2 1

8 7 6 5 4 3 2 1

- NOTES:**
1. SEE VFS-EPM-000-DWG-C-201 FOR CIVIL SYMBOLS, NOTES, AND ABBREVIATIONS.
 2. SEE VFS-EPM-000-DWG-S-201 FOR NOTES, ABBREVIATIONS AND SCHEDULE.
 3. SEE VFS-EPM-000-DWG-C-210 FOR FOUNDATION LOCATIONS




3 12K TANK FOUNDATIONS
 C-210 SCALE: 3/4" = 1'-0"



B SECTION
 SCALE: 1 1/2" = 1'-0"

CONCEPTUAL DESIGN



NAME	DATE	DESCRIPTION
S. MOORE	03/11/21	ENGR
J. PIERCE		ENGR
D. NELSON		ENGR
J. WILSON		ENGR
F. WOODRICK		ENGR
E. LLOYD		ENGR

CIMARRON
 PUMP AND TREAT SYSTEM PROJECT
BURIAL AREA #1
 STRUCTURAL
 FOUNDATION PLAN VIEWS

FILE	DESIGN	SCALE	SHOWN	EST	SHEET 2	OF 3
F					B	

DWG NO	TITLE	REF NUMBER	TITLE	REV	DATE	DESCRIPTION	BY	DATE	REVISIONS
	DRAWING TRACEABILITY LIST		REFERENCES						
			NEXT USED ON						

VFS-EPM-000-DWG-S-210 SH 2 OF 2 REV B

8 7 6 5 4 3 2 1

8

7

6

5

4


3

2


1

NOTES:

- 1. SEE VFS-EPM-000-DWG-C-201 FOR CIVIL SYMBOLS, NOTES, AND ABBREVIATIONS.
- 2. SEE VFS-EPM-000-DWG-S-201 FOR NOTES, ABBREVIATIONS AND SCHEDULE.





OPTION 1



OPTION 2

4 DETAIL - PIPE SUPPORT EXTERIOR
SCALE: 1" = 1'-0"



5 DETAIL - PIPE SUPPORT EXTERIOR
SCALE: 1 1/2" = 1'-0"

CONCEPTUAL DESIGN



VEOLIA NUCLEAR SOLUTIONS
FEDERAL SERVICES, LLC
295 Bradley, Suite 300
Richland, VA 99352

NAME	DATE	COMMENTS
S. MOORE	10/21/2011	UNSTB
J. PIERCE		UNSTB
D. NELSON		UNSTB
J. WILSON		UNSTB
F. ELLOYD		UNSTB

CIMARRON
PUMP AND TREAT SYSTEM PROJECT
BURIAL AREA #1
STRUCTURAL
FOUNDATION PLAN VIEWS

VFS-EPM-000-DWG-S-210

DWG NO	TITLE	REF NUMBER	TITLE	REF NUMBER	TITLE	DESCRIPTION	REV BY	DATE	ENGR	COMPANY	
DRAWING TRACEABILITY LIST											
NEXT USED ON				REVISIONS							

VFS-EPM-000-DWG-S-210 SH 2 OF 2 REV B