



Global Nuclear Fuel

Kent Halac
Global Nuclear Fuel Americas, LLC
Senior Engineer
3901 Castle Hayne Road
Wilmington, NC 28401
USA
T 910 819-5307
kent.halac@ge.com

M220152
November 30, 2022
U.S. Nuclear Regulatory Commission
Document Control Desk
Washington, D.C. 20555-0001

Subject: Part 21 60-Day Final Report Notification: GNF3 Raised Water Rod (SC-22-04 Revision 2)

This letter provides Global Nuclear Fuel's (GNF) final report regarding a 10 CFR Part 21 evaluation. This is the final report for Reference 1.

One GNF3 bundle with a raised water rod was found during core verification. The GNF3 bundle was in its first cycle of operation. The water rod remained constrained within the envelope of the fuel bundle, which was discharged to the spent fuel pool for examinations. The examinations concluded that no fuel leaks were present, and all hardware was intact with no visible wear or damage. The cause was identified as the water rod not being rotated into its proper orientation during assembly.

The information required for this GNF Final Report Notification per §21.21 (a)(2) is attached as Enclosures 1 through 4.

Please contact Dr. Brian Moore, General Manager of Core and Fuel Engineering (brian.moore@gnf.com) if there are any questions.

Sincerely,

A handwritten signature in black ink that reads 'Kent E. Halac'.

Kent E. Halac
Senior Engineer
Global Nuclear Fuels Americas, LLC
kent.halac@ge.com

References

1. Global Nuclear Fuels, M220124, Revision 1, Part 21 60-Day Interim Report Notification: GNF Raised Water Rod (SC-22-04 R1)

Enclosures:

Summary Letter

1. Final Report
2. List of Potentially Affected Plants
3. Recent GE Hitachi Nuclear Energy 10 CFR Part 21 Communications
4. GNF's Assessment of 06.07 Scope of Operability Determinations

cc: E Lenning, NRC
L Dudes, NRC Region II Administrator
J. Giessner, NRC Region III Administrator
M Catts, GEH Wilmington, NC
L Trosman, GEH Wilmington, NC
B Moore, GNF Wilmington, NC
PLM Specification 007N3317 Revision 2



Global Nuclear Fuel

10 CFR Part 21 Communication

SC 22-04 R2

November 30, 2022

To: *Affected and Potentially Affected Plants (Enclosure 2)*

Subject: *GNF3 Raised Water Rod – Final Notification*

- | | |
|---|--|
| <input checked="" type="checkbox"/> Reportable Condition [21.21(d)] | <input type="checkbox"/> 60 Day Interim Report [21.21(a)(2)] |
| <input type="checkbox"/> Transfer of Information [21.21(b)] | <input checked="" type="checkbox"/> Safety Information Communication |

Summary:

One GNF3 bundle with a raised water rod was found during core verification at a US-based nuclear power plant. The GNF3 bundle was in its first cycle of operation. The water rod remained constrained within the envelope of the fuel bundle, which was discharged to the spent fuel pool for examinations. The examinations concluded that no fuel leaks were present, and all hardware was intact with no visible wear or damage. The cause was identified as the water rod not being rotated into its proper orientation during assembly.

It is determined that GNF3 bundles fabricated between March 1, 2021, and August 1, 2022, that have not already undergone an enhanced fuel receipt inspection may be susceptible to an infrequent occurrence of this defect.

Analysis of the susceptible GNF3 population concludes that the subject condition has not created a potential for a Substantial Safety Hazard (SSH) nor contributed to exceeding a Safety Limit, as defined in the Technical Specifications of a license for operation issued under 10 CFR Part 50. However, if the condition were to go uncorrected and a bundle with an unlocked water rod were operated beyond a single cycle, it has the potential to contribute to the exceedance of a Technical Specification Safety Limit for bundle critical power and create a potential for a SSH due to a potential loss of structural integrity under design basis loads (i.e., coolability cannot be assured).

GNF has completed the evaluation of the condition described above and determined that the subject condition is reportable under 10 CFR Part 21(d).

Please contact Dr. Brian Moore, General Manager of Core and Fuel Engineering (brian.moore@gnf.com) if there are any questions.

Kent Halac
Issued by: Kent Halac, Safety Evaluation Program Manager Delegate
 Global Nuclear Fuel
 3901 Castle Hayne Rd., Wilmington, NC 28402

Notice: This 10 CFR Part 21 Notification pertains only to the plants or facilities specifically indicated as being affected. Global Nuclear Fuel (GNF) has not considered or evaluated the applicability, if any, of this information to any plants or facilities other than those specifically indicated as being affected and for which GNF supplied the equipment or services addressed in the Notification. Determination of applicability of this information to a particular plant or facility, and the decision of whether or not to take action based on the Notification, are the responsibilities of the Owner of that plant or facility. This 10 CFR Part 21 Notification, its attachments and enclosures may contain proprietary information of GNF that is maintained in confidence by GNF and is subject to withholding from public disclosure under 10 CFR 2.390 and 9.17. Such GNF proprietary information is furnished in confidence solely for the purpose(s) stated in the attached transmittal letter. No other use, direct or indirect, of this GNF proprietary information is authorized, absent the prior written permission of GNF.

Background

During a mid-cycle outage at a US-based BWR/6, a first cycle GNF3 bundle (designated “GEX290”) was discovered to have a raised water rod during core verification inspection (Figure 1).

After the GEX290 discovery, a second GNF3 bundle was found with a water rod not rotated during fabrication oversight with interim additional quality control verification during manufacturing. This GNF3 bundle did not leave GNF’s manufacturing facility and the condition was corrected.

During the bundle assembly process for GNF3 fuel products, the water rod is locked into place via manual rotation of the water rod engaging a proprietary mechanism in the Lower Tie Plate (LTP). A number of spacers are distributed axially where each spacer is engaged by a set of tabs on the water rod that positively locate each spacer for height and separation.

The primary functions of the spacers are to hold the fuel rods in their proper locations and to improve fuel performance during operation by mixing the water such that the fuel rods maintain the water film responsible for the heat transfer out of the rod and into the coolant. The relevant metric for this thermal-hydraulic behavior and associated limit is the critical power of the assembly, which varies throughout operation of the core.

Figure 2 shows a photo taken during the outage at the discovery of the raised water rod and the unengaged water rod tabs.




Figure 1: Raised Water Rod




Figure 2: Closeup of Spacer 8 Water Rod Tab

After the initial discovery, further inspection of bundle GEX290 indicated that the water rod capture mechanism in the LTP was never engaged. The cause was identified as the water rod not being rotated into its proper orientation during bundle assembly due to human error.

Until March 2021, the bundle assembly process involved at least three individuals: two operators and a Quality Control (QC) inspector. From March 1, 2021, the QC inspector function was replaced with each operator as the designated quality checker for the other operator. QC inspectors continued to perform quality inspections during final inspection (after the bundle is assembled); however, a check of the WR

orientation was not explicitly required in the final inspection procedure. On August 1, 2022, because of the GEX290 discovery, QC inspectors at final inspection were required to perform an in-process check for water rod orientation and the QC procedure was updated to assure clarity of the water rod inspection requirement. In addition, fuel receipt inspectors were instructed to assure proper water rod orientation (spacers engaged with water rod tabs) as part of their receipt inspection.

Discussion

Based on the water rod installation process and the root cause analysis that was performed, a probability of the water rod being improperly installed and not being detected by inspections was calculated based on industry accepted human reliability analyses methods for the various time periods described above. The conclusion from the reliability analyses was that the susceptible population consists of GNF3 bundles manufactured between March 1, 2021, and August 1, 2022, that have not already undergone additional inspection(s) to confirm water rod orientation. Within this population, while unlikely, it cannot be precluded that a bundle within a reload may have an unlocked water rod. As added confirmation that this condition is isolated, none of the past GNF3 fuel inspections (including for fuel failures) have identified such a condition.

Currently, the susceptible population does not include any bundles operating beyond their first cycle of operation. For a GNF3 bundle with an unlocked water rod operating in its first cycle, analysis shows insignificant impact to operation. During this single cycle irradiation period, normal operation hydraulic lift forces are sufficient to overcome the weight of an unlocked (and misoriented) water rod and the spacer spring friction restraining forces, given the relaxation of the spacer springs on the water rod. The spacers, which are normally fixed in place by the tabs on the water rod, are held in place by spacer spring forces. That spring force also experiences relaxation, but there is margin to the point where spacers can initially lift (i.e., where drag forces overcome friction and gravity) including both the drag forces for anticipated operational occurrence conditions and the uncertainties in the methodology used to calculate the associated forces.

If an unlocked water rod is raised up through the upper tie plate, but within the envelope of the fuel assembly, there is a change in the location of moderator within the lattice, and an effect of the altered geometry on the hydraulic resistance of the spacers, water rod exit, and upper tie plate. The net impact of the changes in local loss characteristics and void fraction reduction on bundle flow is insignificant.

Analyses of isolated instances of GNF3 assemblies with an unlocked and raised water rod established the potential impact of the subject condition on mechanical performance (including seismic events), thermal margins, transients, LOCA, and core stability. All analyses demonstrated acceptable performance for first cycle operation for bundles with the raised water rod condition.

At some irradiation time after an initial cycle of operation, spring forces on the spacers undergo sufficient relaxation that it is not possible to conclude that they remain at their initial axial locations. Spacers and their location are sufficiently important to critical power performance and to providing structural support for the fuel rods that margin to fuel mechanical or Tech Specification safety limits cannot be shown if such a condition were to exist.

Actions that GNF has already taken since the discovery of the condition include the following:

- GNF initiated Condition Report (CR) 40108 on July 27, 2022, to document this issue. The initiation of this CR under GNF's corrective action program prompted a 10 CFR Part 21 evaluation.
- A formal root cause analysis was performed on this issue per the GNF corrective action program to identify root causes and contributing causes. Due to the root cause analysis completion date going

beyond 60 days from the Part 21 evaluation initiation, GNF issued a 60-Day Interim Notification in accordance with 10 CFR Part 21.21(a)(2).

- After the apparent cause (that the water rod was not rotated during bundle assembly) was determined, on August 1, 2022, GNF manufacturing released QCII-5.2.8 Rev. 103 for final bundle inspection of GNF3 bundles to include looking down the upper tie plate opening to ensure the water rod tabs are aligned in the proper direction.
- For GNF3 bundles that were built and packed but not yet installed in reactor or spent fuel pool, QCII-0032 was updated for new fuel receipt to include an inspection of the water rod tab orientation prior to insertion into operation in the reactor.
- On September 8, 2022, QN-02484 was released to implement an additional check during the bundle build process for the final bundle inspectors to verify that the water rod is rotated prior to proceeding to the next step.

Conclusions

Analysis of the susceptible GNF3 population concludes that the subject condition has not created a potential for a Substantial Safety Hazard (SSH) nor contributed to exceeding a Safety Limit, as defined in the Technical Specifications of a license for operation issued under 10 CFR Part 50. However, if the condition were to go uncorrected and a bundle with an unlocked water rod were operated beyond a single cycle, it has the potential to contribute to the exceedance of a Technical Specification Safety Limit for bundle critical power and create a potential for a SSH due to a potential loss of structural integrity under design basis loads (i.e., coolability cannot be assured).

Recommended Actions

The following action is recommended for licensees when receiving GNF3 fuel.

- Receipt inspection of the GNF3 fuel should be augmented to include visual inspection for the proper water rod orientation. GNF has already provided supplemental instructions to inspection procedures to be used during new fuel receipt of GNF3 fuel bundles at licensees' facilities. These instructions provide a receipt inspection method for licensees to independently verify that the GNF3 water rod is in the correct orientation prior to insertion of the bundle in the fuel pool. These inspections have already been undertaken at some plants to disposition some or all of the susceptible population as being unaffected.

The following action is recommended for licensees with GNF3 fuel in the remaining susceptible population.

- Inspection of the GNF3 susceptible population should be performed prior to the second cycle of operation to identify if any bundles in that population have an unlocked water rod and take appropriate corrective action. This recommendation only applies to bundles that were not receipt inspected for an unlocked WR.

Enclosure 2

List of Potentially Affected Plants

BWR Plants and Associated Facilities

<u>Utility</u>	<u>Plant</u>
<u> X </u>	Clinton
<u> </u>	Dresden 2-3
<u> X </u>	FitzPatrick
<u> X </u>	LaSalle 1
<u> </u>	LaSalle 2
<u> X </u>	Limerick 1
<u> </u>	Limerick 2
<u> </u>	Nine Mile Point 1
<u> X </u>	Nine Mile Point 2
<u> X </u>	Peach Bottom 2-3
<u> </u>	Quad Cities 1-2
<u> X </u>	Fermi 2
<u> </u>	Columbia
<u> X </u>	Grand Gulf
<u> X </u>	River Bend
<u> </u>	Pilgrim
<u> </u>	Perry 1
<u> </u>	Duane Arnold
<u> </u>	Oyster Creek
<u> </u>	Cooper
<u> </u>	Vermont Yankee
<u> </u>	Millstone
<u> </u>	Susquehanna 1-2
<u> </u>	Brunswick 1-2
<u> </u>	Hope Creek
<u> X </u>	Hatch 1-2
<u> </u>	Browns Ferry 1-3
<u> </u>	Monticello

Non-Domestic BWR Plants

<u>Utility</u>	<u>Plant</u>
_____ BKW-FMB, Ltd	Mühleberg
_____ Chubu Electric Power Co.	Hamaoka 1-4
_____ Chubu Electric Power Co.	Hamaoka 5
_____ Chugoku Electric Power Co.	Shimane 1-2
_____ Chugoku Electric Power Co.	Shimane 3
_____ Comision Federal de Electricidad	Laguna Verde 1-2
_____ Forsmark Kraftgrupp AB	Forsmark 1-3
_____ Hokuriku Electric Power Co.	Shika 1
_____ Hokuriku Electric Power Co.	Shika 2
_____ Iberdrola SA	Cofrentes
_____ Japan Atomic Power Co.	Tokai 2
_____ Japan Atomic Power Co.	Tsuruga 1
_____ Kernkraftwerk Gundremmingen GmbH	Gundremmingen B, C
_____ Kernkraftwerk Brunsbuettel GmbH	Brunsbuettel
_____ Kernkraftwerk Kruemmel GmbH	Kruemmel
_____ Kernkraftwerk Philippsburg	Philippsburg
_____ Kernkraftwerk Leibstadt AG	Leibstadt
_____ Kraftgrupp AB	Forsmark
_____ Kraftgrupp AB	Ringhals 1
_____ Nuclenor SA	Santa Maria De Garoña
_____ OKG Aktiebolag	Oskarshamn 1-3
_____ Taiwan Power Company	Chinshan 1-2
_____ Taiwan Power Company	Kuosheng 1-2
_____ Taiwan Power Company	Lungmen 1-2*
_____ Teollisuuden Voima Oy	Olkiluoto 1-2
_____ Tokyo Electric Power Company	Fukushima Daiichi 1-6
_____ Tokyo Electric Power Company	Fukushima Daini 1-4
_____ Tokyo Electric Power Corporation	Kashiwazaki 1-5
_____ Tokyo Electric Power Corporation	Kashiwazaki 6-7
_____ Tohoku Electric Power Company	Higashidori 1
_____ Tohoku Electric Power Company	Onagawa 1-3

US PWR Plants

<u>Utility</u>	<u>Plant</u>
_____ AmerenUE	Callaway
_____ Arizona Public Service	Palo Verde 1-3
_____ Constellation Energy Generation	Braidwood 1-2
_____ Constellation Energy Generation	Byron 1-2
_____ Constellation Energy Generation	Calvert Cliffs 1-2
_____ Constellation Energy Generation	Fort Calhoun
_____ Constellation Energy Generation	GINNA
_____ Constellation Energy Generation	Three Mile Island 1
_____ Dominion	Kewaunee
_____ Dominion	Millstone 2
_____ Dominion	Millstone 3
_____ Dominion	North Anna 1-2
_____ Dominion	Surry 1-2
_____ Duke Energy Corporation	Catawba 1-2
_____ Duke Energy Corporation	Crystal River 3
_____ Duke Energy Corporation	McGuire 1-2
_____ Duke Energy Corporation	Oconee 1-3
_____ Duke Energy Corporation	Robinson
_____ Duke Energy Corporation	Shearon Harris
_____ Entergy	Arkansas Nuclear One 1-2
_____ Entergy	Indian Point 2-3
_____ Entergy	Palisades
_____ Entergy	Waterford 3
_____ FirstEnergy Nuclear Operations Co.	Beaver Valley 1-2
_____ FirstEnergy Nuclear Operating Co.	Davis-Besse
_____ Florida Power & Light	Seabrook
_____ Florida Power & Light	St. Lucie 1-2
_____ Florida Power & Light	Turkey Point 3-4
_____ Florida Power & Light	Point Beach 1-2
_____ Indiana Michigan Power Corp	D C Cook 1-2
_____ Northern States Power	Prairie Island 1-2
_____ Pacific Gas & Electric Co.	Diablo Canyon 1-2
_____ PSEG Nuclear LLC	Salem 1
_____ PSEG Nuclear LLC	Salem 2
_____ South Carolina Electric & Gas Co.	Summer
_____ South Texas Project Nuclear Operating Co.	South Texas Project 1-2
_____ Southern California Edison Co.	San Onofre 2-3
_____ Southern Nuclear Operating Co.	Farley 1-2
_____ Southern Nuclear Operating Co.	Vogtle 1-2
_____ Tennessee Valley Authority	Sequoyah 1-2
_____ Tennessee Valley Authority	Watts Bar 1
_____ Tennessee Valley Authority	Watts Bar 2
_____ TXU Electric Generation Co.	Comanche Peak 1-2
_____ Wolf Creek Nuclear Operating Corp.	Wolf Creek

Enclosure 3 – Recent GE Hitachi Nuclear Energy 10 CFR Part 21 Communications

The following is a list of recent 10 CFR Part 21 communications that GE Hitachi Nuclear Energy (GEH) and Global Nuclear Fuel (GNF) have provided to affected licensees as Reportable Conditions (RC), Transfers of Information (TI), 60-Day Interim Reports (60 Day) and/or Safety Information Communications (SC).

<u>Number</u>	<u>Ref.</u>	<u>Subject</u>	<u>Date</u>
SC 22-01	PRC 22-01	Inadequately sized / rated equipment used to perform dedication testing on a safety related transformer	5/26/2022
SC 22-02	PRC 22-03	Design Change Implemented by Manufacturer Impacts Qualification	6/8/2022
SC 22-03	PRC 22-02	Updated Lifetime Limits for Marathon-C+ Control Rods	6/16/2022
SC-22-04	PRC 22-04	Part 21 60-Day Interim Report Notification: GNF3 Raised Water Rod (SC-22-04)	9/28/2022
SC 22-04	PRC 22-04	GNF3 Raised Water Rod – Final Notification	11/30/2022

Enclosure 4

GNF's Assessment of 06.07 Scope of Operability Determinations

Item	Point to Address	GNF Assessment
a.	Possible elements of an operability determination include:	
(1)	The SSC affected by the condition,	Fuel assemblies with the potential condition are affected. Specifically, GNF3 fuel produced between March 1, 2021, and August 1, 2022, are the susceptible population.
(2)	The extent of condition for all similarly affected SSCs,	There are no other affected SSCs.
(3)	The current licensing basis requirements or commitments established for the affected SSC,	The current licensing basis requirement is the SSC's ability to perform its specified safety function (i.e., operate within defined Specified Acceptable Fuel Design Limits or SAFDLs).
(4)	The specified safety function(s) performed by the affected SSCs,	In general, most SSCs (e.g., control blades, safety relief valves, etc.) have a function that protects nuclear fuel assemblies, which are the SSCs of concern. As long as fuel is operated within applicable limits, such as the Technical Specification Safety Limit MCPR and thermal-mechanical limits, fuel cladding integrity is maintained.
(5)	The effect or potential effect of the condition on the affected SSC's ability to perform its specified safety function(s), and	The condition does not have a significant effect on the SSC's ability to perform its specified safety function (i.e., operate within SAFDLs). Operability is not challenged for bundles in the susceptible population for their first cycle of operation. However, if uncorrected, the condition could result in reduced margin to the Technical Specification Safety Limit MCPR if a limiting Anticipated Operational Occurrence (AOO) were to occur.
(6)	Whether there is a reasonable assurance of operability, including the basis for the determination and any compensatory measures put in place to establish or restore operability.	Implementation of the recommended actions is enough to assure that fuel can be operated as normal. The recommended measures assure adequate margin for operability.

Item	Point to Address	GNF Assessment
b.	The following things should be considered when reviewing operability determinations:	
(1)	Design basis events are plant-specific, and plant-specific TS, bases, and safety evaluations may contain plant-specific considerations related to operability,	Plant-specific safety evaluations are unaffected by this issue. Recommended actions will preserve the existing TS and bases as well as assure adequate margin to the existing TS and bases.
(2)	An SSC's operability requirements are based on safety analyses of specific design basis events for one mode or specified condition of operation and may not be the same for other modes or conditions of operation; therefore, all applicable modes and conditions of operation should be considered,	Recommended actions will assure conformance to existing bases, which includes all applicable licensed modes of operation. The recommended actions will assure adequate margin to the existing limits and bases, which includes all applicable modes of operation.
(3)	The operability requirements for an SSC encompass all necessary support systems (per the TS definition of operability) regardless of whether the TS explicitly specifies operability requirements for the support functions,	The recommended actions will assure adequate margin to the existing bases and TS requirements.
(4)	In order to evaluate conditions, it is assumed in the OD that the design basis event occurs. The occurrence of multiple simultaneous design basis events should be considered only to the extent that they are required as a part of the plant's CLB, and	The recommended actions will assure adequate margin to limits and supports conformance to the plant's CLB including the design basis events.
(5)	Compensatory measures may be established to restore or maintain operability of an SSC. See section 06.08 of this IMC for additional guidance on compensatory measures.	The identified recommended action assures adequate margin to support operation.