



South Texas Project Electric Generating Station P.O. Box 289 Wadsworth, Texas 77483

April 5, 2000
NOC-AE-000817
File No.: G20.02,
G21.02
10CFR50.36
STI: 31082969

U.S. Nuclear Regulatory Commission
Attention: Document Control Desk
Washington, DC 20555

South Texas Project
Unit 2
Docket Nos. STN 50-499
Unit 2 Cycle 8 Core Operating Limits Report, Revision 1

In accordance with Technical Specification 6.9.1.6.d, the attached Revision 1 to the Core Operating Limits Report is submitted for South Texas Project Unit 2 Cycle 8.

If there are any questions concerning this report, please contact Mr. A. W. Harrison at (361) 972-7298, or me at (361) 972-7795.

David Leazar
for David A. Leazar
Director,
Nuclear Fuel & Analysis

kaw

Attachment: Unit 2 Cycle 8 Core Operating Limits Report, Revision 1

cc: Licensing Library
RMS (w/o attachment)

cc:

Ellis W. Merschoff
Regional Administrator, Region IV
U.S. Nuclear Regulatory Commission
611 Ryan Plaza Drive, Suite 400
Arlington, Texas 76011-8064

John A. Nakoski
Project Manager, Mail Code 0-4D3
U. S. Nuclear Regulatory Commission
Washington, DC 20555-0001

Cornelius F. O'Keefe
c/o U. S. Nuclear Regulatory Commission
P. O. Box 910
Bay City, TX 77404-0910

A. H. Gutterman, Esquire
Morgan, Lewis & Bockius
1800 M. Street, N.W.
Washington, DC 20036-5869

M. T. Hardt/W. C. Gunst
City Public Service
P. O. Box 1771
San Antonio, TX 78296

A. Ramirez/C. M. Canady
City of Austin
Electric Utility Department
721 Barton Springs Road
Austin, TX 78704

Jon C. Wood
Matthews & Branscomb
One Alamo Center
106 S. St. Mary's Street, Suite 700
San Antonio, TX 78205-3692

Institute of Nuclear Power
Operations - Records Center
700 Galleria Parkway
Atlanta, GA 30339-5957

Richard A. Ratliff
Bureau of Radiation Control
Texas Department of Health
1100 West 49th Street
Austin, TX 78756-3189

D. G. Tees/R. L. Balcom
Houston Lighting & Power Co.
P. O. Box 1700
Houston, TX 77251

Central Power and Light Company
ATTN: G. E. Vaughn/C. A. Johnson
P. O. Box 289, Mail Code: N5012
Wadsworth, TX 77483

U. S. Nuclear Regulatory Commission
Attention: Document Control Desk
Washington, D.C. 20555-0001



**SOUTH TEXAS PROJECT
ELECTRIC GENERATING STATION
UNIT 2 CYCLE 8
CORE OPERATING LIMITS REPORT
Rev. 1**

March 2000



1.0 CORE OPERATING LIMITS REPORT

This Core Operating Limits Report for STPEGS Unit 2 Cycle 8 has been prepared in accordance with the requirements of Technical Specification 6.9.1.6. The core operating limits have been developed using the NRC-approved methodologies specified in Technical Specification 6.9.1.6.

The Technical Specifications affected by this report are:

- | | | |
|----|-----------|--|
| 1) | 2.1 | SAFETY LIMITS |
| 2) | 2.2 | LIMITING SAFETY SYSTEM SETTINGS |
| 3) | 3/4.1.1.3 | MODERATOR TEMPERATURE COEFFICIENT LIMITS |
| 4) | 3/4.1.3.5 | SHUTDOWN ROD INSERTION LIMITS |
| 5) | 3/4.1.3.6 | CONTROL ROD INSERTION LIMITS |
| 6) | 3/4.2.1 | AFD LIMITS |
| 7) | 3/4.2.2 | HEAT FLUX HOT CHANNEL FACTOR |
| 8) | 3/4.2.3 | NUCLEAR ENTHALPY RISE HOT CHANNEL FACTOR |
| 9) | 3/4.2.5 | DNB PARAMETERS |

2.0 OPERATING LIMITS

The cycle-specific parameter limits for the specifications listed in Section 1.0 are presented below.

COLR Section 2.8 provides for an alternate Minimum Measured Reactor Coolant System Flow limit consistent with plugging up to 10% of steam generator tubes and Departure from Nucleate Boiling (DNB) requirements. When using the alternate minimum flow limit, the T_{avg} limit is reduced for RCS flow no less than 380,500 gpm. Setpoint and constant values for $OP\Delta T$ and $OT\Delta T$ are also revised accordingly when this alternate mode of operation is entered.

2.1 SAFETY LIMITS (Specification 2.1):

- 2.1.1 The combination of THERMAL POWER, pressurizer pressure, and the highest operating loop coolant temperature (T_{avg}) shall not exceed the limits shown in Figure 1, or in Figure 2 when operating under alternate operating criteria consistent with reduced Reactor Coolant System Flow as addressed in COLR Section 2.8.

2.2 LIMITING SAFETY SYSTEM SETTINGS (Specification 2.2):

2.2.1 The Loop design flow for Reactor Coolant Flow-Low is 95,400 gpm (or 92,500 gpm for alternate operation with reduced RCS flow).

2.2.2 The Over-temperature ΔT and Over-power ΔT setpoint parameter values are listed below:

Over-temperature ΔT Setpoint Parameter Values

- τ_1 measured reactor vessel ΔT lead/lag time constant, $\tau_1 = 8$ sec
- τ_2 measured reactor vessel ΔT lead/lag time constant, $\tau_2 = 3$ sec
- τ_3 measured reactor vessel ΔT lag time constant, $\tau_3 = 0$ sec
- τ_4 measured reactor vessel average temperature lead/lag time constant, $\tau_4 = 28$ sec
- τ_5 measured reactor vessel average temperature lead/lag time constant, $\tau_5 = 4$ sec
- τ_6 measured reactor vessel average temperature lag time constant, $\tau_6 = 0$ sec
- K_1 Overtemperature ΔT reactor trip setpoint, $K_1 = 1.14$ or $K_1 = 1.13$ for alternate operation with reduced RCS flow
- K_2 Overtemperature ΔT reactor trip setpoint T_{avg} coefficient, $K_2 = 0.028/^\circ F$
- K_3 Overtemperature ΔT reactor trip setpoint pressure coefficient, $K_3 = 0.00143/psig$
- T' Nominal full power T_{avg} , $T' \leq 589.0$ °F (including alternate operation with reduced RCS flow)
- P' Nominal RCS pressure, $P' = 2235$ psig
- $f_1(\Delta I)$ is a function of the indicated difference between top and bottom detectors of the power-range neutron ion chambers; with gains to be selected based on measured instrument response during plant startup tests such that;
- (1) For $q_t - q_b$ between -70% and +8%, or +6% for alternate operation with reduced RCS flow, $f_1(\Delta I) = 0$, where q_t and q_b are percent RATED THERMAL POWER in the top and bottom halves of the core respectively, and $q_t + q_b$ is total THERMAL POWER in percent of RATED THERMAL POWER;
 - (2) For each percent that the magnitude of $q_t - q_b$ exceeds -70%, the ΔT Trip Setpoint shall be automatically reduced by 0.0% of its value at RATED THERMAL POWER; and
 - (3) For each percent that the magnitude of $q_t - q_b$ exceeds +8%, or +6% for alternate operation with reduced RCS flow, the ΔT Trip Setpoint shall be automatically reduced by 2.65% of its value at RATED THERMAL POWER.



Over-power ΔT Setpoint Parameter Values

- τ_1 measured reactor vessel ΔT lead/lag time constant, $\tau_1 = 8$ sec
- τ_2 measured reactor vessel ΔT lead/lag time constant, $\tau_2 = 3$ sec
- τ_3 measured reactor vessel ΔT lag time constant, $\tau_3 = 0$ sec
- τ_6 measured reactor vessel average temperature lag time constant, $\tau_6 = 0$ sec
- τ_7 Time constant utilized in the rate-lag compensator for T_{avg} , $\tau_7 = 10$ sec
- K_4 Overpower ΔT reactor trip setpoint, $K_4 = 1.08$ or $K_4 = 1.07$ for alternate operation with reduced RCS flow)
- K_5 Overpower ΔT reactor trip setpoint T_{avg} rate/lag coefficient, $K_5 = 0.02/^\circ F$ for increasing average temperature, and $K_5 = 0$ for decreasing average temperature
- K_6 Overpower ΔT reactor trip setpoint T_{avg} heatup coefficient $K_6 = 0.002/^\circ F$ for $T > T''$ and, $K_6 = 0$ for $T \leq T''$
- T'' Indicated full power T_{avg} , $T'' \leq 589.0$ °F (including alternate operation with reduced RCS flow)
- $f_2(\Delta I) = 0$ for all (ΔI)

2.3 MODERATOR TEMPERATURE COEFFICIENT (Specification 3.1.1.3):

- 2.3.1 The BOL, ARO, MTC shall be less positive than the limits shown in Figure 3.
- 2.3.2 The EOL, ARO, HFP, MTC shall be less negative than $-6.12 \times 10^{-4} \Delta k/k/^\circ F$.
- 2.3.3 The 300 ppm, ARO, HFP, MTC shall be less negative than $-5.22 \times 10^{-4} \Delta k/k/^\circ F$ (300 ppm Surveillance Limit).

where: BOL stands for Beginning-of-Cycle Life
 EOL stands for End-of-Cycle Life
 ARO stands for All Rods Out
 HFP stands for Hot Full Power (100% RATED THERMAL POWER)
 HFP vessel average temperature is 589 °F

2.4 ROD INSERTION LIMITS (Specification 3.1.3.5 and 3.1.3.6):

- 2.4.1 All banks shall have the same Full Out Position (FOP) of at least 250 steps withdrawn but not exceeding 259 steps withdrawn.
- 2.4.2 The Control Banks shall be limited in physical insertion as specified in Figure 4.
- 2.4.3 Individual Shutdown bank rods are fully withdrawn when the Bank Demand Indication is at the FOP and the Rod Group Height Limiting Condition for Operation is satisfied (T.S. 3.1.3.1).



2.5 AXIAL FLUX DIFFERENCE (Specification 3.2.1):

- 2.5.1 AFD limits as required by Technical Specification 3.2.1 are determined by CAOC Operations with an AFD target band of +3, -12%.
- 2.5.2 The AFD shall be maintained within the ACCEPTABLE OPERATION portion of Figure 5, as required by Technical Specifications.

2.6 HEAT FLUX HOT CHANNEL FACTOR (Specification 3.2.2):

- 2.6.1 $F_Q^{RTP} = 2.55$.
- 2.6.2 $K(Z)$ is provided in Figure 6.
- 2.6.3 The F_{xy} limits for RATED THERMAL POWER (F_{xy}^{RTP}) within specific core planes shall be:
 - 2.6.3.1 Less than or equal to 2.102 for cycle burnups less than 9000 MWD/MTU and less than or equal to 1.903 for cycle burnups greater than or equal to 9000 MWD/MTU for all core planes containing Bank "D" control rods, and
 - 2.6.3.2 Less than or equal to the appropriate core height-dependent value from Table I for all unrodded core planes.
 - 2.6.3.3 $PF_{xy} = 0.2$.

These F_{xy} limits were used to confirm that the heat flux hot channel factor $F_Q(Z)$ will be limited by Technical Specification 3.2.2 assuming the most-limiting axial power distributions expected to result for the insertion and removal of Control Banks C and D during operation, including the accompanying variations in the axial xenon and power distributions, as described in WCAP-8385. Therefore, these F_{xy} limits provide assurance that the initial conditions assumed in the LOCA analysis are met, along with the ECCS acceptance criteria of 10 CFR 50.46.

For Unit 2 Cycle 8, the $L(Z)$ penalty is not applied (i.e., $L(Z) = 1.0$ for all core elevations).

2.7 ENTHALPY RISE HOT CHANNEL FACTOR (Specification 3.2.3):

	<u>Standard Fuel*</u>	<u>VANTAGE 5H / RFA Fuel**</u>
2.7.1	<u>WITHOUT RCS Loop-specific Temperature Calibrations:</u>	<u>WITHOUT RCS Loop-specific Temperature Calibrations:</u>
	$F_{\Delta H}^{RTP} = 1.46$.	$F_{\Delta H}^{RTP} = 1.53$.
	<u>WITH RCS Loop-specific Temperature Calibrations:</u>	<u>WITH RCS Loop-specific Temperature Calibrations:</u>
	$F_{\Delta H}^{RTP} = 1.49$.	$F_{\Delta H}^{RTP} = 1.557$.
2.7.2	$PF_{\Delta H} = 0.3$.	$PF_{\Delta H} = 0.3$.

*Applies to fuel regions 1 and 2.

**Applies to fuel regions 8A, 8B, 9A, 9B, 10A, and 10B.

**2.8 DNB PARAMETERS (Specification 3.2.5):**

2.8.1**** The following DNB-related parameters shall be maintained within the following limits:

- a. Reactor Coolant System T_{avg} , ≤ 595 °F*,
(or ≤ 593 °F* with reduced RCS flow of COLR 2.8.1.c)
- b. Pressurizer Pressure, > 2214 psig**,
- c. Minimum Measured Reactor Coolant System Flow $\geq 392,300$ gpm***,
(or $\geq 380,500$ gpm*** with reduced RCS T_{avg} of COLR 2.8.1.a)

* Includes a 1.9 °F measurement uncertainty.

** Limit not applicable during either a Thermal Power ramp in excess of 5% of RTP per minute or a Thermal Power step in excess of 10% RTP. Includes a 22.5 psi measurement uncertainty as read on the QDPS display.

*** Includes a 2.8% flow measurement uncertainty.

**** A discussion of the processes to be used to take these readings is provided in the basis for Technical Specification 3.2.5

3.0 REFERENCES

- 3.1 Letter from R. A. Wiley (Westinghouse) to D. F. Hoppes (STPNOC), "Unit 2 Cycle 8 Core Operating Limits Report," 99TG-G-0100 (ST-UB-NOC-1978), October 15, 1999.
- 3.2 NUREG-1346, Technical Specifications, South Texas Project Unit Nos. 1 and 2.
- 3.3 STPNOC Calculation ZC-7035, Rev. 1, "Loop Uncertainty Calculation for RCS T_{avg} Instrumentation," October 19, 1998.
- 3.4 STPNOC Calculation ZC-7032, Rev. 1, "Loop Uncertainty Calculation for Narrow Range Pressurizer Pressure Monitoring Instrumentation," June 10, 1999.



Figure 1
Reactor Core Safety Limit - Four Loops in Operation






Figure 2
 Reactor Core Safety Limit - Four Loops in Operation (Alternate)




Figure 3
MTC versus Power Level







Figure 4
Control Rod Insertion Limits versus Power Level



Control Bank A is already withdrawn to Full Out Position. Fully withdrawn region shall be the condition where shutdown and control banks are at a position within the interval of 250 and ≤ 259 steps withdrawn, inclusive.



Figure 5
AFD Limits versus Rated Thermal Power






Figure 6
 K(Z) - Normalized $F_0(Z)$ versus Core Height






Table 1 (Part 1 of 2)
Unrodded F_{xy} for Each Core Height*
for Cycle Burnups Less Than 9000 MWD/MTU

<u>Core Height</u> <u>(Ft.)</u>	<u>Axial</u> <u>Point</u>	<u>Unrodded</u> <u>F_{xy}</u>	<u>Core Height</u> <u>(Ft.)</u>	<u>Axial</u> <u>Point</u>	<u>Unrodded</u> <u>F_{xy}</u>
14.0	1	4.899	6.8	37	1.916
13.8	2	4.198	6.6	38	1.900
13.6	3	3.497	6.4	39	1.888
13.4	4	2.796	6.2	40	1.878
13.2	5	2.315	6.0	41	1.867
13.0	6	2.096	5.8	42	1.856
12.8	7	2.045	5.6	43	1.850
12.6	8	2.012	5.4	44	1.844
12.4	9	1.995	5.2	45	1.840
12.2	10	1.984	5.0	46	1.835
12.0	11	1.976	4.8	47	1.832
11.8	12	1.970	4.6	48	1.831
11.6	13	1.973	4.4	49	1.831
11.4	14	1.977	4.2	50	1.828
11.2	15	1.981	4.0	51	1.825
11.0	16	1.985	3.8	52	1.830
10.8	17	1.987	3.6	53	1.833
10.6	18	1.987	3.4	54	1.832
10.4	19	1.987	3.2	55	1.835
10.2	20	1.986	3.0	56	1.834
10.0	21	1.984	2.8	57	1.836
9.8	22	1.983	2.6	58	1.835
9.6	23	1.981	2.4	59	1.836
9.4	24	1.979	2.2	60	1.834
9.2	25	1.976	2.0	61	1.831
9.0	26	1.971	1.8	62	1.830
8.8	27	1.967	1.6	63	1.831
8.6	28	1.962	1.4	64	1.851
8.4	29	1.963	1.2	65	1.850
8.2	30	1.963	1.0	66	1.860
8.0	31	1.961	0.8	67	2.077
7.8	32	1.960	0.6	68	2.491
7.6	33	1.959	0.4	69	3.012
7.4	34	1.955	0.2	70	3.532
7.2	35	1.946	0.0	71	4.053
7.0	36	1.931			

For Unit 2 Cycle 8, the L(Z) penalty is not applied (i.e., L(Z) = 1.0 for all core elevations).



Table 1 (Part 2 of 2)
Unrodded F_{xy} for Each Core Height*
for Cycle Burnups Greater Than or Equal to 9000 MWD/MTU.

<u>Core Height</u> <u>(Ft.)</u>	<u>Axial</u> <u>Point</u>	<u>Unrodded</u> <u>F_{xy}</u>	<u>Core Height</u> <u>(Ft.)</u>	<u>Axial</u> <u>Point</u>	<u>Unrodded</u> <u>F_{xy}</u>
14.0	1	5.204	6.8	37	2.045
13.8	2	4.509	6.6	38	2.052
13.6	3	3.768	6.4	39	2.056
13.4	4	2.993	6.2	40	2.057
13.2	5	2.450	6.0	41	2.054
13.0	6	2.200	5.8	42	2.050
12.8	7	2.137	5.6	43	2.046
12.6	8	2.097	5.4	44	2.043
12.4	9	2.074	5.2	45	2.038
12.2	10	2.056	5.0	46	2.031
12.0	11	2.037	4.8	47	2.019
11.8	12	2.017	4.6	48	2.004
11.6	13	2.022	4.4	49	1.990
11.4	14	2.020	4.2	50	1.978
11.2	15	2.020	4.0	51	1.969
11.0	16	2.021	3.8	52	1.956
10.8	17	2.024	3.6	53	1.939
10.6	18	2.027	3.4	54	1.919
10.4	19	2.030	3.2	55	1.903
10.2	20	2.028	3.0	56	1.891
10.0	21	2.024	2.8	57	1.882
9.8	22	2.018	2.6	58	1.869
9.6	23	2.021	2.4	59	1.855
9.4	24	2.028	2.2	60	1.839
9.2	25	2.039	2.0	61	1.833
9.0	26	2.039	1.8	62	1.825
8.8	27	2.033	1.6	63	1.820
8.6	28	2.023	1.4	64	1.839
8.4	29	2.020	1.2	65	1.843
8.2	30	2.020	1.0	66	1.858
8.0	31	2.021	0.8	67	2.075
7.8	32	2.022	0.6	68	2.473
7.6	33	2.022	0.4	69	2.958
7.4	34	2.024	0.2	70	3.417
7.2	35	2.027	0.0	71	3.828
7.0	36	2.035			

For Unit 2 Cycle 8, the L(Z) penalty is not applied (i.e., L(Z) = 1.0 for all core elevations).