

TYPE: OPEN REFERENCE

KA VALUE RO: 2.7 SRO: 3.2 KA REFERENCE: 2.3.11

**REFERENCES: OP2104.014, LRW and BMS Operations Rev 031-03-1,
Supplement 2, Step 1.**

RO EXAM -- SUBJECT A.3

QUESTION 1:

A liquid release is in progress on Waste Condensate Tank 2T21A. Unit 1 experiences a loss of 6900V Bus H1. What action(s) should be performed?

ANSWER:

Terminate the liquid release from 2T21A.

Note to Examiner:

H1 and H2 are the power supplies for the Unit 1 Main Circulating Water Pumps. These pumps provide the dilution flow rates used to calculate the permissible release rates for the Unit 2 liquid release.

COMMENTS:

EXAMINEE'S COPY

TYPE: OPEN REFERENCE

RO EXAM -- SUBJECT A.3

QUESTION 1:

A liquid release is in progress on Waste Condensate Tank 2T21A. Unit 1 experiences a loss of 6900V Bus H1. What action(s) should be performed?