



UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
WASHINGTON, D. C. 20555

METROPOLITAN EDISON COMPANY

JERSEY CENTRAL POWER AND LIGHT COMPANY

PENNSYLVANIA ELECTRIC COMPANY

DOCKET NO. 50-289

THREE MILE ISLAND NUCLEAR STATION, UNIT NO. 1

AMENDMENT TO FACILITY OPERATING LICENSE

Amendment No. 68  
License No. DPR-50

1. The Nuclear Regulatory Commission (the Commission) has found that:
  - A. The application for amendment by Metropolitan Edison Company, Jersey Central Power and Light Company and Pennsylvania Electric Company (the licensees), dated April 24, 1981 and June 15, 1981, complies with the standards and requirements of the Atomic Energy Act of 1954, as amended (the Act), and the Commission's rules and regulations set forth in 10 CFR Chapter I;
  - B. The facility will operate in conformity with the application, the provisions of the Act, and the rules and regulations of the Commission;
  - C. There is reasonable assurance (i) that the activities authorized by this amendment can be conducted without endangering the health and safety of the public, and (ii) that such activities will be conducted in compliance with the Commission's regulations;
  - D. The issuance of this amendment will not be inimical to the common defense and security or to the health and safety of the public; and
  - E. The issuance of this amendment is in accordance with 10 CFR Part 51 of the Commission's regulations and all applicable requirements have been satisfied.


2. Accordingly, the license is amended by changes to the Technical Specifications as indicated in the attachment to this license amendment, and paragraph 2.c.(2) of Facility Operating License No. DPR-50 is hereby amended to read as follows:

(2) Technical Specifications

The Technical Specifications contained in Appendices A and B, as revised through Amendment No. 63, are hereby incorporated in the license. The licensee shall operate the facility in accordance with the Technical Specifications.

3. This license amendment is effective as of the date of its issuance.

FOR THE NUCLEAR REGULATORY COMMISSION



John F. Stolz, Chief  
Operating Reactors Branch #4  
Division of Licensing

Attachment:  
Changes to the Technical  
Specifications

Date of Issuance: July 20, 1981

ATTACHMENT TO LICENSE AMENDMENT NO. 68

FACILITY OPERATING LICENSE NO. DPR-50

DOCKET NO. 50-289

Revise Appendix A as follows:

<u>Remove</u>	<u>Insert</u>
4-7	4-7
4-8	4-8
4-39	4-39
4-41	4-41
4-42	4-42
4-44	4-44
4-46	4-46
4-55	4-55
4-55b	4-55b

The changes on the revised page are shown by marginal lines.

TABLE 4.1-1 (Continued)

<u>CHANNEL DESCRIPTION</u>	<u>CHECK</u>	<u>TEST</u>	<u>CALIBRATE</u>	<u>REMARKS</u>
38. Steam Generator Water Level	W	NA	R	
39. Turbine Overspeed Trip	NA	R*	NA	
40. Sodium Thiosulfate Tank Level Indicator	NA	NA	R	
41. Sodium Hydroxide Tank Level Indicator	NA	NA	R	
42. Diesel Generator Protective Relaying	NA	NA	R	
43. 4 KV ES Bus Undervoltage Relays (Diesel Start)	NA	M(1)	R	(1) Relay operation will be checked by local test pushbuttons.
44. Reactor Coolant Pressure DH Valve Interlock Bistable	S(1)	M	R	(1) When reactor coolant system is pressurized above 300 psig or Taves is greater than 200°F.

S - Each Shift

T/W - Twice per week

R - Each Refueling Period

D - Daily

B/M - Every 2 months

NA - Not Applicable

W - Weekly

Q - Quarterly

B/W - Every two weeks

M - Monthly

P - Prior to each startup  
if not done previous week

\*Test to be performed prior to exceeding 20% power during Cycle 5 start up only.

TABLE 4.1-2

MINIMUM EQUIPMENT TEST FREQUENCY

<u>Item</u>	<u>Test</u>	<u>Frequency</u>
1. Control Rods	Rod drop time of all full length rods	Each refueling shutdown
2. Control Rod Movement	Movement of each rod	Every two weeks, when reactor is critical
3. Pressurizer Safety Valves	Setpoint*	50% each refueling period
4. Main Steam Safety Valves	Setpoint	25% each refueling** period
5. Refueling System Interlocks	Functional	Start of each refueling period
6. Main Steam Isolation Valves	(See Section 4.8)	-
7. Reactor Coolant System Leakage	Evaluate	Daily, when reactor coolant system temperature is greater than 525°F
8. Air Treatment Systems	See Section 3.15	See Section 4.12
9. Spent Fuel Cooling System	Functional	Each refueling period prior to fuel handling
10. Intake Pump House Floor (Elevation 262 ft. 6 in.)	(a) Silt Accumulation-Visual inspection of Intake Pump House Floor	Each refueling period
	(b) Silt Accumulation Measurement of Pump House Flow	Quarterly

\*The setpoint of the pressurizer code safety valves shall be in accordance with ASME Boiler and Pressurizer Vessel Code, Section III, Article 9, Winter, 1968.

\*\* The required percentage of Main Steam Safety Valves will be tested prior to Cycle 5 criticality.

4.5 EMERGENCY LOADING SEQUENCE AND POWER TRANSFER, EMERGENCY CORE COOLING SYSTEM AND REACTOR BUILDING COOLING SYSTEM PERIODIC TESTING

4.5.1 EMERGENCY LOADING SEQUENCE

Applicability

Applies to periodic testing requirements for safety actuation systems.

Objective

To verify that the Emergency loading sequence and automatic power transfer is operable.

Specifications

4.5.1.1\* Sequence and Power Transfer Test

- a. During each refueling interval, a test shall be conducted to demonstrate that the emergency loading sequence and power transfer is operable.
- b. The test will be considered satisfactory if the following pumps and fans have been successfully started and the following valves have completed their travel on preferred power and transferred to the emergency power as evidenced by the control board component operating lights, and either the station computer or pressure/flow indication.
  - M. U. Pump
  - D. H. Pump and D. H. Injection Valves and D. H. Supply Valves
  - R. B. Cooling Pump
  - R. B. Ventilators
  - D. H. Closed Cycle Cooling Pump
  - N. S. Closed Cycle Cooling Pump
  - D. H. River Cooling Pump
  - N. S. River Cooling Pump
  - D. H. and N. S. Pump Area Cooling Fan
  - Screen House Area Cooling Fan
  - Spray Pump. (Initiated in coincidence with a 2 out of 3 R. B. 30 psi Pressure Test Signal.)

\*This test shall be performed prior to Cycle 5 criticality.

4.5.1.2 Sequence Test

- a. At intervals not to exceed 3 months, a test shall be conducted to demonstrate that the emergency loading sequence is operable, this test shall be performed on either preferred power or emergency power.
- b. The test will be considered satisfactory if the pumps and fans listed in 4.5.1.1b have been successfully started and the valves listed in 4.5.1.1b have completed their travel as evidenced by the control board component operating lights, and either the station computer or pressure/flow indication.

Bases

The Emergency loading sequence and automatic power transfer controls the operation of the pumps associated with the emergency core cooling system and Reactor Building cooling system.

## 4.5.2 EMERGENCY CORE COOLING SYSTEM

### Applicability

Applies to periodic testing requirement for emergency core cooling systems.

### Objective

To verify that the emergency core cooling systems are operable.

### Specification

#### 4.5.2.1 High Pressure Injection

- a. During each refueling interval and following maintenance or modification that affects system flow characteristics, system pumps and system high point vents shall be vented, and a system test shall be conducted to demonstrate that the system is operable.\*

The M. U. Pump and its required supporting auxiliaries will be started manually by the operator and a test signal will be applied to the high pressure injection valves MU-V-16A, B, C, D to demonstrate actuation of the high pressure injection system for emergency core cooling operation.

- b. The test will be considered satisfactory if the valves have completed their travel and the M. U. Pumps are running as evidenced by the control board component operating lights. Minimum acceptable injection flow must be greater than or equal to 500 gpm per HPI pump when pump discharge pressure is 600 psig or greater (the pressure between the pump and flow limiting device) and when the RC pressure is equal to or less than 600 psig.
- c. Testing which requires HPI flow thru MU-V16A, B, C, D shall be conducted only under either of the following conditions:
  - 1) T avg. shall be greater than 320°F.
  - 2) Head of the Reactor Vessel shall be removed.

\*The High Pressure Injection Test shall be performed prior to Cycle 5 criticality.

#### 4.5.2.2 Low Pressure Injection

- a. During each refueling period and following maintenance or modification that affects system flow characteristics, system pumps and high point vents shall be vented, and a system test shall be conducted to demonstrate that the system is operable. The auxiliaries required for low pressure injection are all included in the emergency loading sequence specified in 4.5.1.\*\*
- b. The test will be considered satisfactory if the decay heat pumps listed in 4.5.1.1b have been successfully started and the decay heat injection valves and the decay heat supply valves have completed their travel as evidenced by the control board component operating lights. Flow shall be verified to be equal or greater than the flow assumed in the Safety Analysis for the single corresponding RCS pressure used in the test.

- c. When the Decay Heat System is required to be operable, the correct position of DH-V-19A/B shall be verified by observation within four hours of each valve stroking operation or valve maintenance, which effects the position indicator.

**\*\*The Low Pressure System test shall be performed prior to Cycle 5 criticality.**

#### 4.5.2.3 Core Flooding

- a. During each refueling period, a system test shall be conducted to demonstrate proper operation of the system. **\*\*\*During depressurization of the Reactor Coolant System, verification shall be made that the check and isolation valves in the core cooling flooding tank discharge lines operate properly.**
- b. The test will be considered satisfactory if control board indication of core flooding tank level verifies that all valves have opened.

**\*\*\*The Core Flooding Test shall be performed prior to Cycle 5 criticality.**

#### 4.5.2.4 Component Tests

- a. At intervals not to exceed 3 months, the components required for emergency core cooling will be tested.
- b. The test will be considered satisfactory if the pumps and fans have been successfully started and the valves have completed their travel as evidenced by the control board component operating lights, and either the station computer or pressure/flow indication.

#### Bases

The emergency core cooling systems are the principal reactor safety features in the event of a loss of coolant accident. The removal of heat from the core provided by these systems is designed to limit core damage.

The low pressure injection pumps are tested singularly for operability by opening the borated water storage tank outlet valves and the bypass valves in the borated water storage tank fill line. This allows water to be pumped from the borated water storage tank through each of the injection lines and back to the tank.

The minimum acceptable HPI/LPI flow assures proper flow and flow split between injection legs.

With the reactor shutdown, the valves in each core flooding lines are checked for operability by reducing the reactor coolant system pressure until the indicated level in the core flood tanks verify that the check and isolation valves have opened.

b. Reactor Building Cooling and Isolation System

1. During each refueling period, a system test shall be conducted to demonstrate proper operation of the system.\* A test signal will actuate the R.B. emergency cooling system valves to demonstrate operability of the coolers.
2. The test will be considered satisfactory if the valves have completed their expected travel as evidenced by the control board component operating lights, and either the station computer or local verification.

\*The system test shall be conducted prior to heatup following Cycle 4 refueling.

4.5.3.2 Component Tests

- a. At intervals not to exceed three months, the components required for reactor building cooling and isolation will be tested.
- b. The test will be considered satisfactory if the valves have completed their expected travel as evidenced by the control board component operating lights, and either the station computer or local verification.

Bases

The reactor building cooling and isolation systems and reactor building spray system are designed to remove the heat in the containment atmosphere to prevent the building pressure from exceeding the design pressure.

The delivery capability of one reactor building spray pump at a time can be tested by opening the valve in the line from the borated water storage tank, opening the corresponding valve in the test line, and starting the corresponding pump.

With the pumps shut down and the borated water storage tank outlet closed, the reactor building spray injection valves can each be opened and closed by the operator action. With the reactor building spray inlet valves closed, low pressure air can be blown through the test connections of the reactor building spray nozzles to demonstrate that the flow paths are open.

The equipment, piping, valves and instrumentation of the reactor building cooling system are arranged so that they can be visually inspected. The cooling units and associated piping are located outside the secondary concrete shield. Personnel can enter the reactor building during power operations to inspect and maintain this equipment.

The reactor building fans are normally operating periodically, constituting the test that these fans are operable.

Reference

- (1) FSAR, Section 6

## 4.6 EMERGENCY POWER SYSTEM PERIODIC TESTS

### Applicability

Applies to periodic testing and surveillance requirement of the emergency power system.

### Objective

To verify that the emergency power system will respond promptly and properly when required.

### Specification

The following tests and surveillance shall be performed as stated:

#### 4.6.1 Diesel Generators

- a. Manually-initiated start of the diesel generator, followed by manual synchronization with other power sources and assumption of load by the diesel generator up to the name-plate rating (3000 kw). This test will be conducted every month on each diesel generator. Normal plant operation will not be affected.
- b. Automatic start of each diesel generator and restoration to operation of particular vital equipment, initiated by an actual loss of normal a-c station service power supply together with a simulated engineered safeguards actuation signal. This test will be conducted during reactor shutdown for refueling to assure that the diesel-generator will start assuming load in ten seconds and assume the load of all safe-guards equipment listed in 4.5.1.1b within 60 seconds after the initial starting signal.\*
- c. Each diesel generator shall be given an inspection at least annually in accordance with the manufacturer's recommendations for this class of stand-by service.

\*This testing shall be performed prior to Cycle 5 criticality.

#### 4.6.2 Station Batteries

- a. The voltage, specific gravity, and liquid level of each cell will be measured and recorded monthly.
- b. The voltage and specific gravity of a pilot cell will be measured and recorded weekly.
- c. Each time data are recorded, new data shall be compared with old to detect signs of abuse or deterioration.

## 4.12 AIR TREATMENT SYSTEMS

### 4.12.1 EMERGENCY CONTROL ROOM AIR TREATMENT SYSTEM

#### Applicability

Applies to the emergency control room air treatment system and associated components.

#### Objective

To verify that this system and associated components will be able to perform its design functions.

#### Specification

- 4.12.1.1 At least every refueling interval or once every 18 months, whichever comes first, the pressure drop across the combined HEPA filters and charcoal adsorber banks of AH-F3A and 3B shall be demonstrated to be less than 6 inches of water at system design flow rate ( $\pm 10\%$ ).
- 4.12.1.2 a.\* The tests and sample analysis required by Specification 3.15.1.2 shall be performed initially and at least once per year for standby service or after every 720 hours of system operation and following significant painting, steam, fire or chemical release in any ventilation zone communicating with the system that could contaminate the HEPA filters or charcoal adsorbers.
- b.\* DOP testing shall be performed after each complete or partial replacement of the HEPA filter bank or after any structural maintenance on the system housing which could affect the HEPA filter bank bypass leakage.
- c.\* Halogenated hydrocarbon testing shall be performed after each complete or partial replacement of the charcoal adsorber bank or after any structural maintenance on the system housing which could affect the charcoal adsorber bank bypass leakage.
- d. Each AH-E18A and B (AH-F3A and B) fan/filter circuit shall be operating at least 10 hours every month.
- 4.12.1.3 At least once per refueling interval or once every 18 months, whichever comes first, automatic initiation of the Control Building isolation and recirculation Dampers AH-D28, 37, 39, and 36 shall be demonstrated as operable.
- 4.12.1.4 An air distribution test shall be performed on the HEPA filter bank initially, and after any maintenance or testing that could affect the air distribution within the system. The air distribution across the HEPA filter bank shall be uniform within  $\pm 20\%$ . The test shall be performed at 40,000 cfm ( $\pm 10\%$ ) flow rate.

\*Surveillance to be performed prior to Cycle 5 criticality in lieu of once per refueling interval or once per 18 months.

## 4.12.2 REACTOR BUILDING PURGE AIR TREATMENT SYSTEM

### Applicability

Applies to the reactor building purge air treatment system and associated components.

### Objective

To verify that this system and associated components will be able to perform its design functions.

### Specification

- 4.12.2.1 At least once per refueling interval or once per 18 months, whichever comes first it shall be demonstrated that the pressure drop across the combined HEPA filters and charcoal adsorber banks is less than 6 inches of water at system design flow rate ( $\pm 10\%$ ).
- 4.12.2.2
- a.\* The tests and sample analysis required by Specification 3.15.2.2, shall be performed initially, once per refueling interval or 18 months, whichever comes first, or after each 720 hours of operation and following significant painting, steam, fire, or chemical release in any ventilation zone communicating with the system that could contaminate the HEPA filters or charcoal adsorbers.
  - b.\* DOP testing shall be performed after each complete or partial replacement of a HEPA filter bank or after any structural maintenance on the system housing which could affect HEPA frame bypass leakage.
  - c.\* Halogenated hydrocarbon testing shall be performed after each complete or partial replacement of a charcoal adsorber bank or after any structural maintenance on the system housing which could affect the charcoal adsorber bank bypass leakage.
  - d.\* The DOP and halogenated hydrocarbon testing shall be performed at the maximum available flow considering physical restrictions, i.e., purge valve position, and gaseous radioactive release criteria.
  - e. The Reactor Building purge exhaust fans AH-E7A and B shall be operated at least 10 hours every month, either during actual purging or using makeup air.
- 4.12.2.3 An air distribution test shall be performed on the HEPA filter bank initially and after any maintenance or testing that could affect the air distribution within the system. The air distribution across the HEPA filter bank shall be uniform within  $\pm 20\%$ . The test shall be performed at 25,000 cfm ( $\pm 10\%$ ) flow rate.

\*Surveillance to be performed prior to Cycle 5 criticality in lieu of once per refueling interval or once per 18 months.

### Bases

Pressure drop across the combined HEPA filters and charcoal adsorbers of less than 6 inches of water at the system design flow rate will indicate that the filters and adsorbers are not clogged by excessive amounts of foreign matter. Pressure drop should be determined at least once every refueling interval to show system performance capability.

4-55b