

Docket File

DISTRIBUTION

April 9, 1984

Docket File
ORB #1 Rdg.
C Parrish
E Jordan
T Barnhardt (4)
R Diggs

NRC PDR
D Eisenhut
L Harmon
W Jones
D Brinkman
JN Grace

L PDR
R Pedersen
OELD
ACRS (10)
C Miles, OPA

Docket No. 50-247

Mr. John D. O'Toole, Vice President
Nuclear Engineering and Quality Assurance
Consolidated Edison Company of New York, Inc.
4 Irving Place
New York, New York 10003

Dear Mr. O'Toole:

By letter dated March 14, 1984 we transmitted to you Amendment No. 89 to Facility Operating License No. DPR-26, for Indian Point Unit 2, which included Revised Technical Specifications. Through an oversight in processing your amendment request, Amendment No. 89 is incomplete. In consonance with the Safety Evaluation that accompanied Amendment No. 89 the flowrate specified for the Fuel Storage Building Air Filtration System should have been changed in all locations of subparagraph F to Surveillance Requirement 4.5. Therefore, F.6 should also specify 20,000 cfm \pm 10%. Likewise the addition of the flowrate for the Post Accident Containment Venting System (4.5.G) should have been made in all locations in subparagraph G. Therefore, G.3.a should also read 200 cfm \pm 10%. Enclosed are revised Technical Specification pages 4.5-8 and 4.5-9 for your use.

Sincerely,

ORIGINAL SIGNED BY

Roger L. Pedersen, Project Manager
Operating Reactors Branch No. 1
Division of Licensing

Enclosures:
As stated

cc w/enclosures:
See attached list

ORB #1 *CP*
CParrish
4/9 /84

ORB #1 *RP*
RPedersen/jm
4/9 /84

ORB #1
SV Varga
4/9 /84

8404240492 840409
PDR ADOCK 05000247
P PDR

~~Mr. John D. O'Toole~~
Consolidated Edison Company
of New York, Inc.

~~Indian Point Station, Unit 1~~
Indian Point Nuclear Generating Unit 2

cc: Mayor, Village of Buchanan
236 Tate Avenue
Buchanan, New York 10511

Joseph D. Block, Esquire
Executive Vice President
Administrative
Consolidated Edison Company
of New York, Inc.
4 Irving Place
New York, New York 10003

Robert L. Spring
Nuclear Licensing Engineer
Consolidated Edison Company
of New York, Inc.
4 Irving Place
New York, New York 10003

Ms. Ellyn Weiss
Sheldon, Harmon and Weiss
1725 I Street, N.W., Suite 506
Washington, DC 20006

Senior Resident Inspector
U.S. Nuclear Regulatory Commission
Post Office Box 38
Buchanan, NY 10511

Brent L. Brandenburg
Assistant General Counsel
Consolidated Edison Company
of New York, Inc.
4 Irving Place - 1822
New York, NY 10003

Regional Administrator - Region I
U.S. Nuclear Regulatory Commission
631 Park Avenue
King of Prussia, PA 19406

Carl R. D'Alvia, Esquire
Attorney for the Village of
Buchanan, New York
395 South Riverside Avenue
Croton-on-Hudson, NY 10520

Regional Radiation Representative
EPA Region II
26 Federal Plaza
New York, New York 10007

Director, Technical Development
Programs
State of New York Energy Office
Agency Building 2
Empire State Plaza
Albany, New York 12223

Dr. Lawrence R. Quarles
Apartment 51
Kendal at Longwood
Kennett Square, PA 19346

Thomas J. Farrelly, Esquire
Law Department
Consolidated Edison Company
of New York, Inc.
4 Irving Place
New York, New York 10003

Mr. Charles W. Jackson
Vice President, Nuclear Power
Consolidated Edison Company
of New York, Inc.
Broadway and Bleakley Avenues
Buchanan, New York 10511

Mr. Frank Matra
Resident Construction Manager
Consolidated Edison Company
of New York, Inc.
Broadway and Bleakley Avenues
Buchanan, New York 10511

Ezra I. Bialik
Assistant Attorney General
Environmental Protection Bureau
New York State Department of Law
2 World Trade Center
New York, New York 10047

5. After each complete or partial replacement of a HEPA filter bank by verifying that the HEPA filter banks remove greater than or equal to 99% of the DOP when they are tested in-place in accordance with ANSI N510-1975 while operating the system at ambient conditions and at a flow rate of 20,000 cfm \pm 10%.
6. After each complete or partial replacement of a charcoal adsorber bank by verifying that the charcoal adsorbers remove greater than or equal to 99.95% of a halogenated hydrocarbon refrigerant test gas when they are tested in-place in accordance with ANSI N510-1975 while operating the system at ambient conditions and at a flow rate of 20,000 cfm \pm 10%.

G. Post Accident Containment Venting System

The post accident containment venting system shall be demonstrated operable:

1. At least once per 18 months or (1) after any structural maintenance on the HEPA filter or charcoal adsorber housings, or (2) at any time painting, fire or chemical releases could alter filter integrity by:
 - a) Verifying no flow blockage by passing flow through the filter system.
 - b) Verifying that the system satisfies the in-place testing acceptance criteria and uses the test procedures of Regulatory Positions C.5.a, C.5.c and C.5.d of Regulatory Guide 1.52, Revision 2, March 1978, at ambient conditions and at a flow rate of 200 cfm \pm 10%.
 - c) Verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide

- 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978.
2. After every 720 hours of charcoal adsorber operation by verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978.
 3. At least once per 18 months by:
 - a) Verifying that the pressure drop across the combined HEPA filters and charcoal adsorber banks is less than 6 inches Water Gauge while operating the system at ambient conditions and at a flow rate of 200 cfm \pm 10%.
 - b) Verifying that the system valves can be manually opened.
 4. After each complete or partial replacement of a HEPA filter bank by verifying that the HEPA filter banks remove greater than or equal to 99% of the DOP when they are tested in-place in accordance with ANSI-N510-1975 while operating the system at ambient conditions and at a flow rate of 200 cfm \pm 10%.
 5. After each complete or partial replacement of a charcoal adsorber bank by verifying that the charcoal adsorbers remove greater than or equal to 99.95% of a halogenated hydrocarbon refrigerant test gas when they are tested in-place in accordance with ANSI N510-1975 while operating the system at ambient conditions and at a flow rate of 200 cfm \pm 10%.