



## H. B. Robinson Steam Electric Plant, Unit No. 2

# Meeting with NRC to Discuss Refueling Outage 20

March 26, 2001



**CP&L**

A Progress Energy Company

Enclosure 2

# Agenda

---

- Introduction.....John Moyer
- Schedule Overview.....Tim Cleary
- Outage Goals.....Tim Cleary
- Major Activities.....Tim Cleary
- Reactor Pressure Vessel  
Inservice Inspection.....Dan Stoddard
- Closing Remarks.....John Moyer


# Introduction



- Purpose

- ▶ Introduce key Robinson Nuclear Plant (RNP) department managers
- ▶ Provide year 2000 results
- ▶ To discuss key Refueling Outage 20 (RO-20) activities, including Reactor Pressure Vessel (RPV) Inservice Inspection (ISI)


## H. B. Robinson Plant, Unit No. 2 Key Department Managers



# Year 2000 Results



<b>Capacity Factor</b>	<b>103.96%</b>
<b>Forced Outage Rate</b>	<b>0.38%</b>
<b>Radiation Dose</b>	<b>8.4 Rem</b>
<b>Personnel Contaminations</b>	<b>5</b>
<b>Maintenance Backlog</b>	<b>176</b>



# **Tim Cleary**

## **Plant General Manager**

# Schedule Overview

- Current RO-20 Critical Path is ~34 Days

- Major Milestones

▶ Unit Off Line	4/7
▶ Mode 5	4/7
▶ Core Offloaded	4/16
▶ RPV ISI Completed	4/22
▶ Core Reloaded	4/30
▶ Mode 4	5/7
▶ Unit On Line	5/10
▶ 100% Power	5/14



# Outage Goals

Human Performance Events	≤ 2 Events
OSHA Recordable Injuries	≤ 4 Events
Radiation Exposure	≤ 100 Rem
Duration (Business Plan)	≤ 37 Days
Budget (Business Plan)	≤ \$18 Million



# Major Activities



- Steam Generator Inspections
- Reactor Protection Relay Replacements
- Turbine Project
- Component Cooling Water (CCW) Heat Exchanger Service Water Piping Upgrade
- RPV Inservice Inspection

# Major Activities (Cont'd)

- Fuel Transfer System Upgrade
- 1 Reactor Coolant Pump (RCP) Motor, 2 RCP Seal Replacements
- RCP Oil Level Monitoring Enhancement
- Condenser Tube Leak Repair
- Secondary Piping Replacement (Flow Accelerated Corrosion Program)
- Rod Position Indication Upgrade

# Major Activities (Cont'd)

- Steam Generator Inspections
  - ▶ Eddy current examination (B and C)
  - ▶ Sludge lancing (A, B, and C)
    - ◆ In-bundle using “CECIL” for collar scale removal
  - ▶ Tube support plate visual inspection

# Major Activities (Cont'd)

---

- Reactor Protection Relay Replacements
  - ▶ Replacements based on operating experience and aging management concerns (297 relays)
    - ◆ No safety or operability concerns
  - ▶ Dedicated team of CP&L Technicians
    - ◆ Emphasis on human performance
    - ◆ Shop expectations established
    - ◆ Utilizing RO-19 lessons learned
  - ▶ Tested for operability prior to Mode 4




# Major Activities (Cont'd)

- Turbine Project

- ▶ Low pressure turbine inspections
- ▶ Lube oil cooler cleaning
- ▶ Turbine EH oil system upgrade
  - ◆ Fatigue failure in June 2000 resulted in non-isolable leak
    - ▼ Manual reactor trip initiated by Operators
    - ▼ Only Licensee Event Report in 2000
  - ◆ Replacing control piping, fittings, and tubing

## Simplified Diagram of CCW Heat Exchanger Service Water Piping Upgrade



# **Dan Stoddard**

## **Manager - Engineering**

# RPV Inservice Inspection

- Final Period of Ten-Year ISI Interval
- Significant RPV Inspections Scheduled for RO-20
- Incorporating Lessons Learned from V.C. Summer



# V.C. Summer Lessons Learned


---

- Team of Plant and Corporate Personnel Formed to Address Implications for Robinson
  - ▶ Materials issues
  - ▶ Inspection techniques
  - ▶ Industry issues
  - ▶ Operational considerations and contingencies


## V.C. Summer Lessons Learned (Cont'd)

- Materials Issues

- ▶ Robinson vessel has stainless “safe-ends” welded to reactor vessel nozzles
- ▶ Nozzle-to-safe ends were shop welded and heat treated with vessel; safe end-to-piping field weld is stainless-to-stainless
  - ◆ Reduced susceptibility to similar failure
- ▶ Inconel alloys used in reactor coolant system (RCS) have been identified for awareness during walkdowns/inspections



HOT LEG NOZZLE ASSEMBLY



COLD LEG NOZZLE ASSEMBLY

# V.C. Summer Lessons Learned (Cont'd)

- Inspection Techniques
  - ▶ Reviewed previous inspection history
  - ▶ Evaluated weld accessibility
  - ▶ Worked with industry (PWR Materials Reliability Program) to identify best available techniques
    - ◆ Ultrasonic testing (UT) determined to be the best available and only viable, qualified volumetric inspection technique

## V.C. Summer Lessons Learned (Cont'd)

- Inspection Techniques (Cont'd)
  - Observed qualification of vendor UT technique
    - ◆ Electric Power Research Institute (EPRI) concurrence using performance demonstration
    - ◆ Identified and compensated for areas of potential lift-off
    - ◆ Optimized transducers for maximum coverage
  - Providing enhanced guidance for boric acid walkdowns/inspections
  - Developed bounding flaw analysis


# V.C. Summer Lessons Learned (Cont'd)




- Inspection Techniques (Cont'd)

- Inspection Plan


- ◆ Inner diameter UT on all nozzle welds
    - ◆ Outer diameter VT-2 visual examination on accessible areas of nozzle-to-safe end welds
      - ▼ Relief Request No. 32




PLAN VIEW



ENLARGED END VIEW  
28" MANWAY COVER, PLATE, AND ELASTOMER



END VIEW




SIDE VIEW







# Access Area Mock-Up



# Access Area Mock-Up



# Access Area Mock-Up



## V.C. Summer Lessons Learned (Cont'd)

- Industry Issues

- ▶ Working closely with PWR Materials Reliability Program and plants with spring Ten-Year Inservice Inspections
- ▶ Reviewing available industry operating experience and technical information

## V.C. Summer Lessons Learned (Cont'd)

- Operational Considerations and Contingencies
  - Operations and Chemistry sensitivity
  - Walkdown/inspection sensitivity
  - Contingency plans to evaluate and act upon findings (boric acid deposits, etc.)

# Closing Remarks