

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE	FREQUENCY
<p>SR 3.6.1.3.6 -----NOTE----- Only required to be met in MODES 1, 2 and 3. -----</p> <p>Perform leakage rate testing for each primary containment purge valve with resilient seals.</p>	<p>184 days</p>
<p>SR 3.6.1.3.7 Verify the isolation time of each MSIV is <math>\geq 3</math> seconds and <math>\leq 5</math> seconds.</p>	<p>In accordance with the Inservice Testing Program</p>
<p>SR 3.6.1.3.8 Verify each automatic PCIV actuates to the isolation position on an actual or simulated isolation signal.</p>	<p>24 months</p>
<p>SR 3.6.1.3.9 Verify a representative sample of reactor instrumentation line EFCVs actuate to check flow on a simulated instrument line break.</p>	<p>24 months</p>
<p>SR 3.6.1.3.10 Remove and test the explosive squib from each shear isolation valve of the TIP System.</p>	<p>24 months on a STAGGERED TEST BASIS</p>

(continued)

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE		FREQUENCY
SR 3.6.1.3.6	<p>-----NOTE----- Only required to be met in MODES 1, 2 and 3. -----</p> <p>Perform leakage rate testing for each primary containment purge valve with resilient seals.</p>	184 days
SR 3.6.1.3.7	Verify the isolation time of each MSIV is $\geq 3$ seconds and $\leq 5$ seconds.	In accordance with the Inservice Testing Program
SR 3.6.1.3.8	Verify each automatic PCIV actuates to the isolation position on an actual or simulated isolation signal.	24 months
SR 3.6.1.3.9	Verify a representative sample of reactor instrumentation line EFCVs actuate to check flow on a simulated instrument line break.	24 months

(continued)