



South Texas Project Electric Generating Station P.O. Box 289 Wadsworth, Texas 77483

April 17, 2001  
NOC-AE-01001084  
File No.: G20.02.02  
G21.02.02  
10CFR50.59  
STI: 31273080

U. S. Nuclear Regulatory Commission  
Attention: Document Control Desk  
Washington, DC 20555

South Texas Project  
Units 1 and 2  
Docket Nos. STN 50-498, STN 50-499  
Technical Specification Bases Change

The South Texas Project Technical Specification Bases Section 3/4.2.5 "DNB Parameters" has been changed pursuant to 10CFR50.59. This change revises the methodology for calculating Reactor Coolant System flow. This change in methodology results in an increase to the Baseline Calorimetric Flow that is used to calculate Reactor Coolant System Flow using the elbow tap methodology.

If there are any questions, please contact S. M. Head at (361) 972-7136 or me at (361) 972-7795.

  
D. A. Leazar  
Director  
Nuclear Fuel and  
Analysis

mkj

Attachment: Revised Technical Specification Bases Page 3/4 2-6 (1 page)

IE47

cc:

Ellis W. Merschoff  
Regional Administrator, Region IV  
U.S. Nuclear Regulatory Commission  
611 Ryan Plaza Drive, Suite 400  
Arlington, Texas 76011-8064

John A. Nakoski  
Addressee Only  
U. S. Nuclear Regulatory Commission  
Project Manager, Mail Stop OWFN/7-D-1  
Washington, DC 20555-0001

Mohan C. Thadani  
Addressee Only  
U. S. Nuclear Regulatory Commission  
Project Manager, Mail Stop OWFN/7-D-1  
Washington, DC 20555

Cornelius F. O'Keefe  
c/o U. S. Nuclear Regulatory  
Commission  
P. O. Box 910  
Bay City, TX 77404-0910

A. H. Gutterman, Esquire  
Morgan, Lewis & Bockius  
1800 M. Street, N.W.  
Washington, DC 20036-5869

M. T. Hardt/W. C. Gunst  
City Public Service  
P. O. Box 1771  
San Antonio, TX 78296

A. Ramirez/C. M. Canady  
City of Austin  
Electric Utility Department  
721 Barton Springs Road  
Austin, TX 78704

Jon C. Wood  
Matthews & Branscomb  
112 East Pecan, Suite 1100  
San Antonio, Texas 78205-3692

Institute of Nuclear Power  
Operations - Records Center  
700 Galleria Parkway  
Atlanta, GA 30339-5957

Richard A. Ratliff  
Bureau of Radiation Control  
Texas Department of Health  
1100 West 49th Street  
Austin, TX 78756-3189

R. L. Balcom/D. G. Tees  
Reliant Energy, Inc.  
P. O. Box 1700  
Houston, TX 77251

C. A. Johnson/R. P. Powers  
AEP - Central Power and Light  
Company  
P. O. Box 289, Mail Code: N5012  
Wadsworth, TX 77483

U. S. Nuclear Regulatory Commission  
Attention: Document Control Desk  
Washington, D.C. 20555-0001

## POWER DISTRIBUTION LIMITS

### BASES

---

#### 3/4.2.5 DNB PARAMETERS (continued)

The value for thermal design RCS flow rate presented in Technical Specification 3.2.5 is an analytical limit. The minimum thermal design RCS flow rate with Model E Steam Generators is 370,000 gpm, and with Model Delta 94 Steam Generators is 392,000 gpm. To provide additional operating margin, a higher value for thermal design flow rate may be used if supported by cycle specific analysis. The minimum measured flow in the Core Operating Limits Report is the thermal design flow rate assumed for a particular cycle plus RCS flow measurement uncertainties. The RCS flow measurement uncertainty is 2.8% using the precision heat balance method or 2.1% using the elbow tap methods described in WCAP 15287, "RCS Flow Measurement for the South Texas Projects Using Elbow Tap Methodology", dated August, 1999. The elbow tap Dp measurement uncertainty presumes that elbow tap Dp measurements are obtained from either QDPS or the plant process computer. Based on instrument uncertainty assumptions, RCS flow measurements using either the precision heat balance or the elbow tap Dp measurement methods are to be performed at greater than or equal to 90% RTP at the beginning of a new fuel cycle.

The 12-hour periodic surveillance of these parameters through instrument readout is sufficient to ensure that the parameters are restored within their limits following load changes and other expected transient operation.