

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
<p>SR 3.5.3.1 Verify the RCIC System piping is filled with water from the pump discharge valve to the injection valve.</p>	<p>31 days</p>
<p>SR 3.5.3.2 Verify each RCIC System manual, power operated, and automatic valve in the flow path, that is not locked, sealed, or otherwise secured in position, is in the correct position.</p>	<p>31 days</p>
<p>SR 3.5.3.3 -----NOTE----- Not required to be performed until 12 hours after reactor steam pressure and flow are adequate to perform the test.</p> <p>Verify, with RCIC steam supply pressure ≤ 1045 psig and ≥ 920 psig, the RCIC pump can develop a flow rate ≥ 600 gpm against a system head corresponding to reactor pressure.</p>	<p>92 days</p>
<p>SR 3.5.3.4 -----NOTE----- Not required to be performed until 12 hours after reactor steam pressure and flow are adequate to perform the test.</p> <p>-----</p> <p>Verify, with RCIC steam supply pressure ≤ 150 psig and ≥ 135 psig, the RCIC pump can develop a flow rate ≥ 600 gpm against a system head corresponding to reactor pressure.</p>	<p>18 months</p>

(continued)