

Docket No. 50-293

MAR 11 1977

Boston Edison Company  
ATTN: Mr. G. Carl Andognini  
800 Boylston Street  
Boston, Massachusetts 02199

Gentlemen:

RE: PILGRIM STATION UNIT NO. 1

DISTRIBUTION

Docket	BScharf (10)
NRC PDR	DEisenhut
Local PDR	OPA - Clare Miles
ORB #2 Reading	JRBuchanan
BRusche	TBAbernathy
ECASE	ACRS (16)
KRGoller	WMcDonald, MIPC
VStello	
TJCarter	
DLZiemann	
RMDiggs	
PO'Connor	
RPSnaider	
OELD	
OI&E (5)	
BJones	

The enclosed Order of Modification pertains to Facility Operating License No. DPR-35 issued for Pilgrim Nuclear Power Station Unit No. 1. The Order corrects errors and reflects changes in the methods of analysis in the ECCS performance evaluation submitted in accordance with 10 CFR §50.46.

The errors detected were of the nature of inputs to computer codes used in the analyses or were due to numerical errors in the calculations performed. The total impact of the errors and model changes is conservative and no reduction of plant operating limits is required to accommodate the presence of the errors.

This Order confirms the appropriateness of Boston Edison's voluntary action of agreeing to submit, on a timely basis, an ECCS re-evaluation using a General Electric ECCS evaluation model approved by the staff.

A copy of the Order is being filed with the Office of the Federal Register for publication.

Sincerely,

Original Signed by:  
Dennis L. Ziemann

Dennis L. Ziemann, Chief  
Operating Reactors Branch #2  
Division of Operating Reactors

Enclosure:  
Order for Modification  
of License

NOTE: SEE ATTACHED YELLOW FOR PREVIOUS CONCURRENCES.

cc w/enclosure:	DOR:AD/OT	NRR:D/DIR	NRR:DIR
See next page	DEisenhut	EGCase	BRusche
	3/ 1/77	3/ 1/77	3/ 1/77

OFFICE >	DOR:ORB #2	DOR:ORB #2	DOR:ORB #2	OELD	DOR:AD/OT	DOR:DIR
SURNAME >	RMDiggs;ro	PO'Connor;ro	DLZiemann	<i>D. Ziemann</i>	KRGoller	VStello
DATE >	3/10/77	3/10/77	3/11/77	3/11/77	3/10/77	3/11/77

DATE	SURNAME	OFFICE
3/1/77	P O'Connor	DOR:ORB #2
3/1/77	DLZiemann	DOR:ORB #2
3/1/77	KRGotler	DOR:AD/OR
3/1/77	WS-Kuro	DOR:DIR
3/1/77	EGCase	NRR:D/DIR

Enclosures:  
 Order for Modification  
 of License  
 cc/enclosure:  
 See next page

Dennis L. Ziemann, Chief  
 Operating Reactors Branch #2  
 Division of Operating Reactors

Sincerely,

The enclosed Order of Modification pertains to Facility Operating License No. DPE-35 issued for Pilgrim Nuclear Power Station Unit No. 1. The Order corrects errors and reflects changes in the methods of analysis in the ECCS performance evaluation submitted in accordance with 10 CFR § 50.46. The errors detected were of the nature of inputs to computer codes used in the analyses or were due to numerical errors in the calculations performed. The total impact of the errors and model changes is conservative and no reduction of plant operating limits is required to accommodate the presence of the errors. This Order confirms the appropriateness of Boston Edison's voluntary action of agreeing to submit, on a timely basis, an ECCS re-evaluation using a General Electric ECCS evaluation model approved by the staff. A copy of the Order is being filed with the office of the Federal Register for publication.

RE: PILGRIM STATION UNIT NO. 1

Gentlemen:

Boston Edison Company  
 ATTN: Mr. G. Carl Andognini  
 800 Boylston Street  
 Boston, Massachusetts 02199

Docket No. 50-293

- DISTRIBUTION
- Docket
  - NRC PDR
  - Local PDR
  - ORB #2 Reading
  - Brusche
  - EGCase
  - KRGotler
  - TJCarter
  - DLZiemann
  - RMDiggs
  - P O'Connor
  - RPSnider
  - OELD
  - OIAE (5)
  - Bjones
  - Bscharf (10)
  - DEisenhut
  - OPA - Clare Miles
  - JRBuchanan
  - TBabernathy
  - ACRS (16)
  - WMcDonald, MIP

cc w/enclosure:

Mr. Paul J. McGuire  
Pilgrim Station Acting Manager  
Boston Edison Company  
RFD #1, Rocky Hill Road  
Plymouth, Massachusetts 02360

Anthony Z. Roisman, Esquire  
Roisman, Kessler and Cashdan  
1025 15th Street, N. W., 5th Floor  
Washington, D. C. 20005

Henry Herrmann, Esquire  
Massachusetts Wildlife Federation  
151 Tremont Street  
Boston, Massachusetts 02111

Plymouth Public Library  
North Street  
Plymouth, Massachusetts 02360

Mr. David F. Tarantino  
Chairmen, Board of Selectmen  
11 Lincoln Street  
Plymouth, Massachusetts 02360

Chief, Energy Systems  
Analyses Branch (AW-459)  
Office of Radiation Programs  
U. S. Environmental Protection Agency  
Room 645, East Tower  
401 M Street, S. W.  
Washington, D. C. 20460

U. S. Environmental Protection Agency  
Region I Office  
ATTN: EIS COORDINATOR  
JFK Federal Building  
Boston, Massachusetts 02203

Massachusetts Department of Public  
Health  
ATTN: Commissioner of Public Health  
600 Washington Street  
Boston, Massachusetts 02111

UNITED STATES OF AMERICA  
NUCLEAR REGULATORY COMMISSION

In the Matter of )  
Boston Edison Company ) Docket No. 50-293  
Pilgrim Nuclear Power Station )  
Unit No. 1 )

ORDER FOR MODIFICATION OF LICENSE

I.

The Boston Edison Company (the licensee), is the holder of Facility Operating License No. DPR-35 which authorizes the operation of the nuclear power reactor known as Pilgrim Nuclear Power Station Unit No. 1 (the facility) at steady state reactor power levels not in excess of 1998 megawatts thermal (rated power). The facility consists of a boiling water reactor (BWR) located at the licensee's site in the town of Plymouth, Plymouth County, Massachusetts.

II.

In conformance with evaluations of the performance of the Emergency Core Cooling System (ECCS) of the facility submitted by the licensee on July 9, 1975, and a supplement thereto dated October 3, 1975, the Technical Specifications issued for the facility on May 21, 1976, limit the Average Planar Linear Heat Generation Rates to the values shown on Technical Specification Figures 3.11-1 through 3.11-7. The ECCS performance evaluation submitted by the licensee was based upon a previously approved ECCS evaluation model developed by General Electric Company (General Electric), the designer of the facility. This model has been found to conform to

the requirements of the Commission's ECCS Acceptance Criteria, 10 CFR Part 50 § 50.46 and Appendix K. The evaluation indicated that with the average planar linear heat generation rate limited as set forth above, and with the other limits set forth in the facility's Technical Specifications, the ECCS cooling performance for the facility would conform with the criteria contained in 10 CFR § 50.46(b) which govern calculated peak clad temperature, maximum cladding oxidation, maximum hydrogen generation, coolable geometry and long term cooling.

Recently, the NRC staff was informed by General Electric that several errors had been discovered in the computer codes used to calculate peak clad temperature and the clad oxidation percentage in the General Electric evaluation model. These errors have been discovered by General Electric during a continuing internal Quality Assurance (QA) audit of their LOCA evaluation model codes. This audit is still under way and the errors reported reflect those found to date. The additional effort expended by the vendor to enhance the assurance of the quality of its evaluation model, the staff believes, was prudent and desirable. Identification of additional errors of a minor nature may still develop during the ongoing QA checks. Nonetheless, the staff believes it appropriate to order the correction of those uncovered thus far. While some of these errors discussed herein have either no significant effect or a conservative effect on the evaluation results, one or more of the errors included in the Pilgrim ECCS evaluation leads to non-conservative values. Based on a preliminary assessment, including information and supportive calculations by General Electric, the NRC staff has determined that the

combined effect of the following code errors would, when corrected, result in an ECCS evaluation requiring no reduction in operating limits for Pilgrim Unit No. 1.

(1) Pressure Rule

The LAMB code is used to calculate system pressure during the LOCA. This calculated pressure is then used as an input to the REFLOOD code which calculates the water level vs time relationship in the core. General Electric used an approximation of the pressure response of the LAMB code that was thought, at the time of approval, to be an acceptable representation of the physical phenomena involved. Later application of this approximation to certain cases showed it to be non-conservative. General Electric proposes to correct this nonconservatism by utilizing a conservative approximation to the pressure rule for input into REFLOOD. This correction increases reflood time by 0 to 50 seconds and decreases MAPLHGR by 0 to 5%.

(2) Bundle Vaporization

General Electric has used incorrect coefficients in the calculation of the amount of vaporization occurring during core spray. The vapor formation in the bundle is a prime determinant of the amount of spray water that can get through the upper tie plate and reflood the core. The vapor formation was under-calculated by approximately 4% resulting in a 20-second increase in reflooding time and about a 2% decrease in the MAPLHGR.

(3) Discharge Break Modeling

General Electric proposes to take credit for an approved model for suction line friction (from the vessel nozzle to the discharge side of the

recirculation pump) that improves reflooding time for the discharge break by approximately 15 seconds. This increases the MAPLHGR for discharge break limited plants by about 1.5%. This error does not apply to Pilgrim Unit No. 1.

(4) Structural Absorption of Gamma Heat

General Electric has erroneously taken double credit for power generation in non-fuel structural material. Correction of this error results in approximately a 4% decrease in the MAPLHGR for certain plants. This error does not apply to Pilgrim Unit No. 1.

(5) Increased Counter Current Flow Limiting (CCFL) Differential Pressure

Some experimental evidence exists that the differential pressure in a fuel assembly during periods of CCFL may be higher than previously assumed. This could cause a delay in reflood time. Correction of this error reduces the Pilgrim MAPLHGR by 1 to 2%.

(6) Others

Several small changes of inputs to the evaluation codes were identified as being necessary to correct errors. They included:

- (a) The use of actual plant specific break areas for the LOCA;
- (b) A reduced core plate weight;
- (c) An increase in the peripheral bypass area used in the counter current flooding calculations;
- (d) The correction of a decimal point error in the assumed guide tube thickness; and
- (e) Credit is no longer assumed for recirculation loop discharge valve closure during blowdown.

Due to the errors in the ECCS analysis currently approved by NRC for Pilgrim Unit No. 1, the staff requested the licensee to submit an estimate of the impact of these errors on the peak clad temperature that would result from the worst break, if the errors were corrected. The revised ECCS calculations indicated that the MAPLHGR is conservative by approximately 1% considering the cumulative effect of these errors. Although GE model changes under review by the staff generically show that MAPLHGR limits even higher than those presently set forth in the Technical Specifications for Pilgrim Unit No. 1 would still satisfy ECCS limits, no credit for such increase was considered by the NRC.

The staff expects that when final revised calculations for the facility are submitted using the revised and corrected model, they will demonstrate that operation with the linear heat generation rates set forth in this Order will conform to the Criteria of 10 CFR § 50.46(b). Such revised calculations fully conforming to the requirements of 10 CFR § 50.46 are to be provided for the facility as soon as possible.

As discussed herein, the present MAPLHGR limits for this facility are such that they assure that the ECCS will conform to the performance requirements of 10 CFR § 50.46. Accordingly, such limits provide reasonable assurance that the public health and safety will not be endangered.

Upon notification by the NRC staff on February 14, 1977, the licensee committed to submit a re-evaluation of the ECCS performance of Pilgrim on a timely basis. The staff believes that the licensee's action, under the circumstances, is appropriate and that this action should be confirmed by NRC Order.



III.


Copies of the following documents are available for inspection at the Commission's Public Document Room at 1717 H Street, Washington, D. C. 20555 and are being placed in the Commission's local public document room at the Plymouth Public Library, North Street, Plymouth, Massachusetts 02360:

- (1) Letters from General Electric to NRC dated February 14, 1977, and January 26, 1977;
- (2) Letters from Boston Edison Company to the Director of Nuclear Reactor Regulation dated January 19, 1977, February 18 and 24, 1977;
- (3) Letter dated July 9, 1975, from Boston Edison Company to NRC and a supplement thereto dated October 3, 1975;
- (4) This Order for Modification of License in the matter of Boston Edison Company (Pilgrim Nuclear Power Station Unit No. 1).

Accordingly, pursuant to the Atomic Energy Act of 1954, as amended, and the Commission's Rules and Regulations in 10 CFR Parts 2 and 50, IT IS ORDERED THAT Facility Operating License No. DPR-35 is hereby amended by adding the following new provision:

- (1) As soon as possible, the licensee shall submit a re-evaluation of ECCS cooling performance calculated in accordance with General Electric Company's Evaluation Model approved by the NRC staff and corrected for the errors described herein and any other corrections in the Model of which the licensee is aware at the time the calculations are performed.

FOR THE NUCLEAR REGULATORY COMMISSION

  
Ben C. Rusche, Director  
Office of Nuclear Reactor Regulation

Dated in Bethesda, Maryland  
this 11th day of March, 1977.