

March 24, 1994

Docket Nos. 50-269, 50-270
and 50-287

Mr. J. W. Hampton
Vice President, Oconee Site
Duke Power Company
P. O. Box 1439
Seneca, South Carolina 27679

Dear Mr. Hampton:

DISTRIBUTION

~~Docket File~~
NRC/Local PDRs
PDII-3 Reading
S.Varga
C.Grimes
D.Matthews
L.Wiens
L.Berry
OGC

ACRS (10)
G.Hill (6)
PA 17F2
OC/LFMB MNBB4702
D.Hagan MNBB4702

J.Johnson (Acting) RII

SUBJECT: CORRECTION TO TECHNICAL SPECIFICATION PAGE
OCONEE UNITS 1, 2, AND 3

On May 3, 1993, Duke Power Company (DPC) requested amendments to the Oconee Nuclear Station, Units 1, 2, and 3 Technical Specifications (TS) revising requirements for the Low Pressure Service Water system. The NRC approved the amendments by letter dated January 13, 1994.

No changes to page 4.5.1 of the TS were included with your submittal for this amendment request. Upon review by DPC, it was noticed that the words "Reactor Coolant" shifted from page 4.5.2 to page 4.5.1, apparently as a result of retyping the specification. The enclosed page corrects this error.

Please remove page 4.5.1 from the Oconee TS and replace it with the enclosed corrected page. Since this is a correction of an administrative error, it is not considered an amendment to the TS.

Sincerely,

(Original Signed By)

L. A. Wiens, Project Manager
Project Directorate II-3
Division of Reactor Projects - I/II
Office of Nuclear Reactor Regulation

Enclosure:
Corrected TS page

cc w/enclosure:
See next page

OFFICE	PDII-3/LA	PDII-3/PM	PDII-3/D		
NAME	L. BERRY	L. WIENS	D. MATTHEWS		
DATE	3/22/94	3/23/94	3/24/94		

OFFICIAL RECORD COPY
FILE NAME: G:\OCONEE\LPSCOR.LTR

280014

9403310201 940324
PDR ADDCK 05000269
P PDR

DF01

Mr. J. W. Hampton
Duke Power Company

Oconee Nuclear Station

cc:

A. V. Carr, Esquire
Duke Power Company
422 South Church Street
Charlotte, North Carolina 28242-0001

J. Michael McGarry, III, Esquire
Winston and Strawn
1400 L Street, NW.
Washington, DC 20005

Mr. Robert B. Borsum
Babcock & Wilcox
Nuclear Power Division
Suite 525
1700 Rockville Pike
Rockville, Maryland 20852

Manager, LIS
NUS Corporation
2650 McCormick Drive, 3rd Floor
Clearwater, Florida 34619-1035

Senior Resident Inspector
U. S. Nuclear Regulatory Commission
Route 2, Box 610
Seneca, South Carolina 29678

Regional Administrator, Region II
U. S. Nuclear Regulatory Commission
101 Marietta Street, NW. Suite 2900
Atlanta, Georgia 30323

Max Batavia, Chief
Bureau of Radiological Health
South Carolina Department of Health
and Environmental Control
2600 Bull Street
Columbia, South Carolina 29201

Office of Intergovernmental
Relations
116 West Jones Street
Raleigh, North Carolina 27603

County Supervisor of Oconee County
Walhalla, South Carolina 29621

Mr. Steve Benesole
Compliance
Duke Power Company
Oconee Nuclear Site
P. O. Box 1439
Seneca, South Carolina 29679

Mr. Mark Lesser, Section Chief
Project Branch #3
U. S. Nuclear Regulatory Commission
101 Marietta Street, NW. Suite 2900
Atlanta, Georgia 30323

Ms. Karen E. Long
Assistant Attorney General
North Carolina Department of
Justice
P. O. Box 629
Raleigh, North Carolina 27602

Mr. G. A. Copp
Licensing - EC050
Duke Power Company
526 South Church Street
Charlotte, North Carolina 28242-0001

4.5 EMERGENCY CORE COOLING SYSTEMS AND REACTOR BUILDING COOLING SYSTEM PERIODIC TESTING

4.5.1 Emergency Core Cooling Systems

Applicability

Applies to periodic testing requirements for the Emergency Core Cooling Systems.

Objective

To verify that the Emergency Core Cooling Systems are operable.

Specification

4.5.1.1 System Tests

4.5.1.1.1 High Pressure Injection System

- a. During each refueling outage, a system test shall be conducted to demonstrate that the system is operable. A test signal will be applied to demonstrate actuation of the High Pressure Injection System for emergency core cooling operation.
- b. The test will be considered satisfactory if control board indication verifies that all components have responded to the actuation signal properly; all appropriate pump breakers shall have opened or closed and all valves shall have completed their travel.

4.5.1.1.2 Low Pressure Injection System

- a. During each refueling outage, a system test shall be conducted to demonstrate that the system is operable. The test shall be performed in accordance with the procedure summarized below:
 - (1) A test signal will be applied to demonstrate actuation of the Low Pressure Injection System for emergency core cooling operation.
 - (2) Verification of the engineered safety features function of the Low Pressure Service Water System which supplies cooling water to the low pressure coolers shall be made to demonstrate operability of the coolers.
- b. The test will be considered satisfactory if control board indication verifies that all components have responded to the actuation signal properly; all appropriate pump breakers shall have opened or closed, and all valves shall have completed their travel.

4.5.1.1.3 Core Flooding System

- a. During each refueling outage, a system test shall be conducted to demonstrate proper operation of the system. During pressurization of the Reactor Coolant