NUCLEAR REGULATORY COMMISSION NOT REMOVE

April 28, 1989

50-270 50-269 Docket Nos.: 50-287 and

Mr. H. B. Tucker, Vice President Nuclear Production Department Duke Power Company 422 South Church Street Charlotte, North Carolina 28242 POSTED ______

OCONEE 2 C-AMENDMENT NO.16 TO DPR-47

Dear Mr. Tucker:

SUBJECT: CORRECTION TO FACILITY OPERATING LICENSE AMENDMENTS (TACS 61377/61378/61379)

Ms. Helen Pastis's April 30, 1987, letter forwarded Amendments 158, 158, and 155 to Facility Operating Licenses DPR-38, DPR-47, and DPR-55 for the Oconee Nuclear Station, Units 1, 2, and 3. Enclosed with the amendments were revised Technical Specification pages. Please replace pages 4.4-17 and 4.4-18 which were forwarded with that letter with the enclosed revised pages.

Ms. Pastis's December 11, 1987, letter forwarded Amendment Nos. 165, 165, and 162 to Facility Operating Licenses DPR-38, DPR-47, and DPR-55. Please replace page 4.1-3 which was forwarded with that letter with the enclosed revised page.

Sincerely,

APL HOOT

Darl S. Hood, Project Manager Project Directorate II-3 Division of Reactor Projects - I/II Office of Nuclear Reactor Regulation

Enclosures: As stated

cc w/encl: See next page

Mr. H. B. Tucker Duke Power Company

cc:

Mr. A. V. Carr, Esq. Duke Power Company P. O. Box 33189 422 South Church Street Charlotte, North Carolina 28242

J. Michael McGarry, III, Esq. Bishop, Liberman, Cook, Purcell & Reynolds 1400 L Street, N.W. Washington, D.C. 20005

Mr. Robert B. Borsum Babcock & Wilcox Nuclear Power Generation Division Suite 525 1700 Rockville Pike Rockville, Maryland 20852

Manager, LIS NUS Corporation 2536 Countryside Boulevard Clearwater, Florida 33515

Senior Resident Inspector U.S. Nuclear Regulatory Commission Route 2, Box 610 Seneca, South Carolina 29678

Regional Administrator, Region II U.S. Nuclear Regulatory Commission 101 Marietta Street, N.W., Suite 2900 Atlanta, Georgia 30323

Mr. Heyward G. Shealy, Chief Bureau of Radiological Health South Carolina Department of Health and Environmental Control 2600 Bull Street Columbia, South Carolina 29201

Office of Intergovernmental Relations 116 West Jones Street Raleigh, North Carolina 27603

Honorable James M. Phinney County Supervisor of Oconee County Walhalla, South Carolina 29621 Oconee Nuclear Station Units Nos. 1, 2 and 3

Mr. Paul Guill Duke Power Company Post Office Box 33189 422 South Church Street Charlotte, North Carolina 28242

Mr. Alan R. Herdt, Chief Project Branch #3 U.S. Nuclear Regulatory Commission 101 Marietta Street, NW, Suite 2900 Atlanta, Georgia 30323 4.4.3 CONTAINMENT HYDROGEN CONTROL SYSTEMS

Applicability

Applies to the Containment Hydrogen Control Systems.

Objective

To verify that the Containment Hydrogen Control Systems are operable.

Specifications

4.4.3.1 Containment Hydrogen Control System Piping

During each refueling, the permanent piping for the Containment Hydrogen Control System shall be tested as follows:

- a. The post-LOCA flow paths shall be verified by connecting and operating either the Hydrogen Purge Unit or the Hydrogen Recombiner through each flow path as follows:
 - 1. The hydrogen Recombiner flow path circulates Reactor Building atmosphere at a flow greater than 50 SCFM.
 - 2. The Hydrogen Purge flow path removes Reactor Building atmosphere and discharges to the Unit vent stack at a flow greater than or equal to 45 SCFM.
- b. The blind isolation flanges on the Containment Hydrogen Control System permanent piping shall be leak tested after each installation to ensure adequate isolation.
- 4.4.3.2 Containment Hydrogen Recombiner System Operational Performance Testing
 - a. The testing requirement of this section may be performed without connecting the system to either of the Reactor Buildings.
 - b. At a refueling frequency:
 - 1. Visual inspection of the unit.
 - - 3. Operate a recombiner unit at design flow rate 10% and allow unit to reach recombination temperature.
- 4.4.3.3 Reactor Building Hydrogen Purge System, Pre-Operational Testing

a. Prior to declaring this system operable, a Pre-operational system test shall be performed.

OCONEE - UNITS 1, 2, & 3

4.4-17

Amendment No. 158 (Unit 1) Amendment No. 158 (Unit 2) Amendment No. 155 (Unit 3)

4-28-81

Collection letter of

- b. This pre-operational test shall consist of:
 - 1. Visual inspection of the system.
 - Installation of new carbon and HEPA filters and in-place filter leakage test per ANSI-N510-1975 (minimum DOP efficiency 99%, minimum halogenated hydrocarbon removal 99%).
 - 3. Flow measurement using flow instruments in the portable purging station.
 - 4. Verification that the pressure drop across the combined HEPA filters and charcoal absorber banks is less than six inches of water at the system design flow rate (±10%).
 - 5. Verification of the operability of the heater at rated power when tested in accordance with ANSI N510-1975.

Bases

The control panel mounted near the recombiner enables the operator to control and monitor system parameters for all functions of the recombiner system except containment isolation valve operation. The control and monitor functions include: process temperature indications, temperature control, flow indication, start/stop switch, low temperature timer and various annunciators. Therefore, the operational performance testing ensures operability.

The penetrations to and from the hydrogen recombiner are shared with the gaseous radiation monitoring pump. Since this pump is normally in operation and since there is no system 1. Jlation valve on the supply branch to the recombiner, the blind flanges are the only means of system isolation. Therefore, these flange joints should be leak tested after each removal and installation to ensure adequate isolation.

The hydrogen recombiner unit operational performance test should be conducted with full flow and with the heaters energized. The capability of the recombiner to achieve the required recombination temperature and flow rate is considered an adequate test of recombination efficiency. Gas inlet and outlet sampling is not required.

The pre-operational testing requirements for the Reactor Building Hydrogen Purge System are applicable only when the system is required to be operable as required by. Technical Specification 3.16.1.c. Requirements for interim surveillance testing of the Reactor Building Hydrogen Purge System during any period of its required operability will be reported to the NRC as described in Technical Specification 3.16.1.d.

New carbon and HEPA filters are installed during pre-operational testing. HEPA filters are installed before the charcoal adsorbers to prevent clogging of the iodine adsorbers. The charcoal adsorbers are installed to reduce the potential release of radioiodine. Bypass leakage for the charcoal adsorbers and particulate removal efficiency for HEPA filters are determined by halogenated hydrocarbon and DOP, respectively.

OCONEE - UNITS 1, 2, & 3

Amendment No. 158 (Unit 1) Amendment No. 158 (Unit 2) Amendment No. 155 (Unit 3)

Correction little of 4-28-89

han	nel Description	Check	Test	Calibrate	Remarks
1.	Protective Channel Coincidence Logic	NA	МО	NA	
2.	Control Rod Drive Trip Breaker	NA	МО	NA	
3.	Power Range Amplifier	ES(1)	NA	(1)	(1) Heat balance check each shift. Heat balance calibration whenever indi- cated core thermal power exceeds neutron power by more than 2 percent.
4.	Power Range	ES	MO	MO(1)(2)	 Using incore instrumentation. Axial offset upper and lower chambers after each startup if not done pre- vious week.
5.	Intermediate Range	ES(1)	PS	NA	(1) When in service.
6.	Source Range	ES(1)	PS	NA	(1) When in service.
7.	Reactor Coolant Temperature	ES	МО	RF	
8.	High Reactor Coolant Pressure	ES	MO	RF	
9.	Low Reactor Coolant Pressure	ES	MO	RF	
0.	Flux-Reactor Coolant Flow Comparator	ES	MO	RF	I
11.	Reactor Coolant Pressure Temperature Comparator	ES	MO	RF	

ł

.

.

, ;

4.1-3

Amendment No. 165 (Unit 1) Amendment No. 165 (Unit 2) Amendment Np. 162 (Unit 3)