

September 18, 2001

Mr. David A. Christian
Senior Vice President - Nuclear
Virginia Electric and Power Company
5000 Dominion Blvd.
Glen Allen, Virginia 23060

SUBJECT: NORTH ANNA POWER STATION UNITS 1 AND 2 RE: REQUEST TO USE
RISK INFORMED INSERVICE INSPECTION PROGRAM (TAC NOS. MB1871
AND MB1872)

Dear Mr. Christian:

By letter dated April 26, 2001, as supplemented July 25, 2001, Virginia Electric and Power Company (VEPCO) requested approval of a risk-informed inservice inspection (RI-ISI) program for Class 1 piping welds as an alternative to the current ISI program at the North Anna Power Station, Units 1 and 2 (NAPS). Your proposed RI-ISI program was developed in accordance with Westinghouse Owners Group topical report WCAP-14572, Revision 1-NP-A. The results of our review indicate that your proposed RI-ISI program is an acceptable alternative to the requirements of the American Society of Mechanical Engineers (ASME) Boiler and Pressure Vessel Code, Section XI for ISI of Code Class 1 piping, Categories B-F and B-J welds because the alternative provides an acceptable level of quality and safety. Therefore, VEPCO's request for relief is authorized for the third 10-year ISI interval pursuant to Title 10 of the *Code of Federal Regulations* (10 CFR) Section 50.55a(a)(3)(i).

In addition, VEPCO submitted Relief Request RR-1 for NAPS, which requested performance of visual VT-2 examinations each refueling outage as an alternative to the volumetric examinations specified in Code Case N-577 and in WCAP-14572, Revision 1-NP-A, for those high safety significant ASME Code Class 1 socket welds identified in the RI-ISI program. The staff concurs that volumetric examination of socket welds is inconclusive and impractical due to the geometric limitations imposed by a socket weld. The staff also concurs that it is not necessary to perform the Code-required surface examination of socket welds in the absence of an environment that would cause outside surface-initiated flaws. The proposed alternative provides reasonable assurance of structural integrity. Therefore, VEPCO's proposed alternative examination method is authorized for the third 10-year ISI interval pursuant to 10 CFR 50.55a(a)(3)(ii) on the basis that performing either the volumetric or the surface examinations of these socket welds would result in unusual difficulty without a compensatory increase in the level of quality and safety.

David A. Christian

- 2 -

Our detailed evaluation and conclusions are documented in the enclosed Safety Evaluation, and we are closing TAC Nos. MB1871 and MB1872.

Sincerely,

/RA by Leonard N. Olshan for/

Richard L. Emch Jr., Chief, Section 1
Project Directorate II
Division of Licensing Project Management
Office of Nuclear Reactor Regulation

Docket Nos. 50-338 and 50-339

Enclosure: As stated

cc w/encl: See next page

Our detailed evaluation and conclusions are documented in the enclosed Safety Evaluation, and we are closing TAC Nos. MB1871 and MB1872.

Sincerely,

/RA by Leonard N. Olshan for/

Richard L. Emch Jr., Chief, Section 1
Project Directorate II
Division of Licensing Project Management
Office of Nuclear Reactor Regulation

Docket Nos. 50-338 and 50-339

Enclosure: As stated

cc w/encl: See next page

Distribution

SMonarque (paper copy)
RidsNrrDlpmLpdii (HBerkow)
RidsOgcRp
RidsRgn2MailCenter
MRubin

PDII-1 R/F
G. Hill (2)
RidsAcrcsAcnwMailCenter
EDunnington (paper copy)

PPatnaik
PUBLIC
SDinsmore
TChan

Accession Number: ML012470437

| | | | | |
|--------|------------|-------------|------------|------------|
| OFFICE | PM:PDII/S1 | LA:PDII/S2 | OGC* (NLO) | SC/PDII/S1 |
| NAME | SMonarque | EDunnington | AFernandes | REmch |
| DATE | 9/18/01 | 9/18/01 | 9/12/01 | 9/18/01 |
| COPY | Yes/No | Yes/No | Yes/No | Yes/No |

OFFICIAL RECORD COPY

Mr. David A. Christian
Virginia Electric and Power Company

North Anna Power Station
Units 1 and 2

cc:

Mr. C. Lee Lintecum
County Administrator
Louisa County
P.O. Box 160
Louisa, Virginia 23093

Mr. David A. Heacock
Site Vice President
North Anna Power Station
P.O. Box 402
Mineral, Virginia 23117-0402

Mr. Donald P. Irwin, Esquire
Hunton and Williams
Riverfront Plaza, East Tower
951 E. Byrd Street
Richmond, Virginia 23219

Mr. Richard H. Blount, II
Site Vice President
Surry Power Station
Virginia Electric and Power Company
5570 Hog Island Road
Surry, Virginia 23883-0315

Dr. W. T. Lough
Virginia State Corporation
Commission
Division of Energy Regulation
P.O. Box 1197
Richmond, Virginia 23209

Robert B. Strobe, M.D., M.P.H.
State Health Commissioner
Office of the Commissioner
Virginia Department of Health
P. O. Box 2448
Richmond, Virginia 23218

Old Dominion Electric Cooperative
4201 Dominion Blvd.
Glen Allen, Virginia 23060

Mr. William R. Matthews
Vice President - Nuclear Operations
Virginia Electric and Power Company
Innsbrook Technical Center
5000 Dominion Boulevard
Glen Allen, Virginia 23060-6711

Mr. Stephen P. Sarver, Director
Nuclear Licensing & Operations Support
Virginia Electric and Power Company
Innsbrook Technical Center
5000 Dominion Blvd.
Glen Allen, Virginia 23060-6711

Office of the Attorney General
Commonwealth of Virginia
900 East Main Street
Richmond, Virginia 23219

Senior Resident Inspector
North Anna Power Station
U.S. Nuclear Regulatory Commission
1024 Haley Drive
Mineral, Virginia 23117

SAFETY EVALUATION BY THE OFFICE OF NUCLEAR REACTOR REGULATION

RISK-INFORMED INSERVICE INSPECTION PROGRAM

NORTH ANNA POWER STATION, UNITS 1 AND 2

VIRGINIA ELECTRIC AND POWER COMPANY

DOCKET NOS. 50-338 AND 50-339

1.0 INTRODUCTION

In a submittal dated April 26, 2001, as supplemented on July 25, 2001 (Refs. 1 and 2), the Virginia Electric and Power Company (the licensee) proposed a risk-informed inservice inspection (RI-ISI) program as an alternative to a portion of their current ISI program for North Anna Power Station, Units 1 and 2. The scope of the RI-ISI program is limited to the American Society of Mechanical Engineers (ASME) Code Class 1 piping (Categories B-F and B-J welds) only. The licensee's RI-ISI program was developed in accordance with the methodology contained in the Westinghouse Owners' Group Topical Report, WCAP-14572, Revision 1-NP-A (Ref. 3), which was previously reviewed and approved by the staff. The RI-ISI program proposed by the licensee was reviewed pursuant to Title 10 of the *Code of Federal Regulations* (10 CFR) Section 50.55a(a)(3)(i). In addition, the licensee submitted Relief Request RR-1, which requested performance of visual VT-2 examinations each refueling outage as an alternative to the volumetric examinations specified in Code Case N-577 and in WCAP-14572, Rev. 1-NP-A, for those high safety significant ASME Code Class 1 socket welds identified in the RI-ISI program. This relief request was reviewed pursuant to 10 CFR 50.55a(a)(3)(ii).

2.0 BACKGROUND

2.1 Applicable Requirements

10 CFR 50.55a(g) requires that ISI of the ASME Code Class 1, 2, and 3 components be performed in accordance with Section XI of the ASME Boiler and Pressure Vessel Code, "Rules for Inservice Inspection of Nuclear Power Plant Components" (hereinafter called Code) and applicable addenda, except where specific written relief has been granted by the Commission pursuant to 10 CFR 50.55a(g)(6)(i). 10 CFR 50.55a(a)(3) states in part that alternatives to the requirements of paragraph (g) may be used, when authorized by the NRC, if the proposed alternatives would provide an acceptable level of quality and safety or if the specified requirement would result in hardship or unusual difficulty without a compensating increase in the level of quality and safety.

Pursuant to 10 CFR 50.55a(g)(4), ASME Code Class 1, 2, and 3 components (including supports) shall meet the requirements set forth in the Code, to the extent practical within the limitations of design, geometry, and materials of construction of the components.

Enclosure

The regulations require that ISI of components conducted during the first 10-year interval and subsequent intervals comply with the requirements in the latest edition and addenda of the Code incorporated by reference in 10 CFR 50.55a(b) 12 months prior to the start of the 120-month interval, subject to the limitations and modifications listed therein.

For North Anna Units 1 and 2, the applicable editions of the Code for the third 10-year ISI interval are the 1989 Edition and the 1995 Edition through 1996 Addenda of ASME Section XI, respectively. North Anna Unit 1 is currently in the first period of the third 10-year ISI interval and Unit 2 will enter the third 10-year interval on December 14, 2001.

The Code requires in part that for each successive 10-year ISI interval, 100% of Category B-F welds and 25% of Category B-J welds for the Code Class 1 piping greater than 1-inch in nominal diameter be selected for volumetric and/or surface examination, based on existing stress analyses and cumulative usage factors.

2.2 Summary of Proposed Approach

In the licensee's proposed RI-ISI program, piping failure potential estimates were determined using a software program contained in Supplement 1 to Reference 3, entitled "Westinghouse Structural Reliability and Risk Assessment (SRRA) Model for Piping Risk-Informed Inservice Inspection," which utilizes probabilistic fracture mechanics technology, industry piping failure history, plant-specific piping failure history, and other relevant information. Using the failure potential and supporting insights on piping failure consequences from the licensee's probabilistic risk assessment (PRA), safety significance ranking of piping segments was established to determine inspection locations. The program maintains the fundamental requirements of the Code, such as the examination technique, frequency, and acceptance criteria. The RI-ISI program is intended to reduce the number of required examination locations significantly while maintaining an acceptable level of quality and safety.

The licensee has planned for complete implementation of the RI-ISI program in the third ISI interval beginning with the first inspection period. Other non-related portions of the Code requirements, as well as the ongoing augmented inspection programs at both units of North Anna, will remain unchanged. The RI-ISI program follows a previously approved methodology delineated in Reference 3.

3.0 EVALUATION

Pursuant to 10 CFR 50.55a(a)(3), the staff has reviewed and evaluated the licensee's proposed RI-ISI program, including those portions related to the applicable methodology and processes contained in Ref. 3, based on guidance and acceptance criteria provided in Regulatory Guides (RGs) 1.174 (Ref. 4) and 1.178 (Ref. 5) and in Standard Review Plan (SRP) Chapter 3.9.8 (Ref. 6).

3.1 Proposed Changes to the ISI Program

The scope of the licensee's proposed RI-ISI program is limited to ASME Class 1 piping only, which consists of Category B-J piping welds and Category B-F dissimilar metal vessel nozzle welds. The RI-ISI program was proposed as an alternative to the existing ISI program, which is based on the requirements of the Code. A general description of the proposed changes to the ISI program was provided in Sections 3 and 5 of the licensee's submittal (Ref. 1).

During the course of its review, the staff reviewed the proposed RI-ISI program against the guidelines contained in previously approved WCAP-14572, Rev. 1-NP-A, which states in part that the SRRA computer models are to be used to estimate the failure probabilities of the structural elements most likely to fail in each of the piping segments. In Reference 2, the licensee states that the failure probabilities for North Anna piping segments were all derived using the SRRA software program. This is consistent with the guidelines in previously approved WCAP-14572, Rev. 1-NP-A. The staff also notes that the same RI-ISI methodology has been implemented at Surry, Units 1 and 2, which have been previously reviewed and approved. Thus, the staff concludes that the licensee's application of WCAP-14572, Rev. 1-NP-A approach at North Anna is an acceptable alternative to the current piping ISI requirements with regard to the number, locations, and methods of inspections and, hence, provides an acceptable level of quality and safety pursuant to 10 CFR 50.55a(a)(3)(i).

In Table 5-1 of Reference 1, a comparison of inspection location selection between the current ISI program and the proposed RI-ISI program is provided. The staff finds that the information submitted adequately defines the proposed changes to the RI-ISI program.

3.2 Engineering Analysis

In accordance with the guidance provided in RGs 1.174 and 1.178 (Refs. 4 and 5), the licensee provided the results of an engineering analysis of the proposed changes, using a combination of traditional engineering analysis and PRA. The licensee stated that the results of the engineering analysis demonstrate that the proposed changes are consistent with the principles of defense-in-depth and that adequate safety margins will be maintained. This is accomplished by evaluating a location's susceptibility to each potential degradation mechanism that may be a precursor to leak or rupture and then performing an independent assessment of the consequence of a failure at that location.

The licensee stated that the first seven of the nine step WCAP-14572, Rev. 1-NP-A process was applied to each unit and that the results, as well as similar Class 1 piping configurations, supported completion of the final three steps using data from only North Anna, Unit 2, as a typical representation. Steps applied to each unit include segment definition, consequence evaluation, failure assessment, and the safety classification of each segment. Reference 1 provides a discussion of a few differences in segment definitions between the two units, and Table 3.1-1 further illustrates some minor differences in the number of segments in each system. The staff finds that the identification and discussion of the differences between the two units provides reasonable assurance that the licensee's decision to apply the last two steps to Unit 2 as the representative unit is technically defensible and acceptable. The proposed RI-ISI program will result in the volumetric inspection of 56 ASME Class 1 butt welds in each North Anna unit in each interval. An additional 44 ASME Class 1 welds (Ref. 1, Table 5-1) will be visually inspected at North Anna, Unit 2, and a similar number at Unit 1.

The licensee stated that the applicable aspects of the ASME Code not affected by the proposed alternative RI-ISI program and the ongoing augmented inspection programs will be retained. This is consistent with approved WCAP-14572, Rev. 1-NP-A; therefore, it is acceptable.

The licensee requested performing visual VT-2 examinations during each refueling outage as an alternative to the volumetric examinations specified in Code Case N-577 and in WCAP-14572, Rev. 1-NP-A, for those high safety significant (HSS) ASME Code Class 1 socket welds identified in the RI-ISI program. The licensee indicated that Code Case N-577 has been revised to allow the substitution of the VT-2 examination method for all damage

mechanisms on socket welds selected as HSS. This request is reasonable because the volumetric examination is inconclusive and impractical due to the geometric limitations imposed by a socket weld. However, the staff notes that Table IWB-2500-1 of the Code requires surface examination, not volumetric examination, at the socket welds, and surface examination (i.e., liquid penetration examination) is an effective method for discovery of potential surface flaws on the outside surface, and specifically, flaws induced by low-cycle, high-bending stress thermal fatigue or by external chloride stress corrosion cracking (ECSCC). The licensee indicated that the Code Class 1 socket weld piping is not located in areas that are subject to an environment promoting ECSCC, and an outside surface-initiated flaw has a very low probability of occurrence due to the inclusion of thermal cyclic loads in the piping design. Therefore, these conditions do not exist in the Code Class 1 piping at North Anna. As for a potential outside surface flaw caused by vibration-induced fatigue, such a flaw is likely to take a long period for initiation. After the initiation phase, the flaw will likely propagate rapidly and cause the pipe to leak. Hence, the staff concludes that performance of a VT-2 visual examination is sufficiently effective and therefore acceptable. The staff notes that the revised Code Case N-577 has neither been issued nor been reviewed and approved by the NRC. Thus, the approval of this request is based on the technical soundness of applying VT-2 visual examination to specific conditions at North Anna, and should not be considered as an endorsement of the Code case. Pursuant to 10 CFR 50.55a(a)(3)(ii), the staff concurs that performing volumetric or surface examinations of these socket welds would result in unusual difficulty without a compensating increase in the level of quality and safety. Therefore, the request to conduct VT-2 examinations as an alternative in each refueling outage for Category B-J socket welds is acceptable.

Piping systems within the scope of the proposed RI-ISI program were divided into piping segments. A pipe segment is defined as a portion of pipe length whose failure at any location within the segment will lead to the same consequence. Pipe segments are separated by flow splits and locations of pipe size changes, and include piping to a point at which a pipe break could be isolated. The licensee reported no deviations from the identification and definition of segments in WCAP-14572, Rev. 1-NP-A, and their process is therefore acceptable.

Piping failure mechanisms identified by the licensee include fatigue, stress corrosion cracking, thermal striping/stratification, and vibratory fatigue. The failure probabilities for the North Anna piping segments were all derived using the Westinghouse SRRA software program. This is consistent with the guidelines in previously approved WCAP-14572, Rev. 1-NP-A, and in conformance with SRP 3.9.8. The licensee reported one deviation in the WCAP-14572, Rev. 1-NP-A methodology regarding credit taken for leak detection when calculating pipe failure probabilities. WCAP-14572, Rev. 1-NP-A allows credit for detecting (and isolating, repairing, or otherwise terminating a potential accident sequence) a leak before it develops into a pipe break for piping inside of containment. In Reference 2, the licensee stated that all Class 1 piping, including Class 1 pipe segments outside of containment, are extensively monitored for leakage. Therefore, the licensee credited leak detection for all Class 1 piping in their initial evaluation. The licensee subsequently performed a sensitivity study where leak detection was not credited for pipe segments outside of containment, and determined that there was no change in the locations selected for inspections.

The licensee developed the consequence of each segment break based on the direct and indirect effects of the segment failure. The licensee reported no deviations from the consequence characterization methodology in WCAP-14572, Rev. 1-NP-A, and their analyses are therefore acceptable.

3.3 Probabilistic Risk Assessment

The licensee used the March 1998 version of its Level 1 and Level 2 PRA (N7B) to support the RI-ISI submittal. The current estimates of core damage frequency (CDF) and large early release frequency (LERF) are $3.50\text{E-}5/\text{yr}$ and $4.66\text{E-}6/\text{yr}$, respectively. The two unit Surry Power Station is a similar design to the two unit North Anna Power Station. The Surry PRA model was reviewed during the Westinghouse Owner's Group peer review certification process. The North Anna PRA was created using the same standards as the Surry PRA model and the licensee stated that the two PRAs have the same level of quality. WCAP-14572, Rev. 1-NP-A requires that functions relied upon to mitigate external events and fires and to mitigate transients during operation modes outside the scope of the PRA be systematically included in the categorization by the engineering team members and the expert panel. The licensee did not report a deviation in this area and therefore the use of a PRA derived from an internal event, full-power operation Individual Plant Examination (IPE) is acceptable.

The staff evaluation report, dated December 14, 1992, concluded that the North Anna IPE satisfied the intent of Generic Letter 88-20. However, the report noted that human error related to the calibration of equipment was not well treated. In Reference 2, the licensee provided a list of calibration errors included in the current model, indicating that the current model has addressed the earlier staff concern. Since the IPE, the PRA models have been updated on an 18-month interval that coincides with the refueling outages to ensure that the risk analyses performed in support of plant operation reflect the current plant configuration and operational practices. The updates to the models are documented and reviewed in accordance with the licensee's administrative procedures. The continuous use and well-documented maintenance of the PRA provides further opportunities to identify inaccuracies and inappropriate assumptions, if any, in the PRA models.

The staff did not review the PRA analysis to assess the accuracy of the quantitative estimates. Quantitative results of the PRA are used, in combination with a quantitative characterization of the pipe segment failure likelihood, to support the assignment of segments into broad safety significance categories reflecting the relative importance of pipe segment failures on CDF and LERF. Inaccuracies in the models or assumptions large enough to invalidate the broad categorizations developed to support RI-ISI should have been identified in the licensee's or in the staff's review. Minor errors or inappropriate assumptions will only affect the consequence categorization of a few segments and will not invalidate the general results or conclusions. The staff finds that the quality of the PRA is sufficient to support the submittal.

The licensee stated in Reference 2 that the risk ranking and change in risk calculations were performed according to the guidance provided in Section 4.4.2 of WCAP-14572, Rev. 1-NP-A, aside from the one deviation discussed in Section 3.2 of this Safety Evaluation. The submittal included estimates for North Anna Unit 2 on the change in CDF and LERF associated with replacing the current ASME Section XI weld inspection locations for Code Class 1 piping with the proposed RI-ISI inspection locations. The change in CDF is estimated to be about $-5.4\text{E-}7/\text{yr}$ with and $-5.0\text{E-}6/\text{yr}$ without operator action. The change in LERF is estimated to be $-7.8\text{E-}8/\text{yr}$ with operator action and $-8.5\text{E-}7/\text{yr}$ without operator action. The licensee did not submit estimates for the other risk change criteria in Section 4.4.2 of WCAP-14572, Rev. 1-NP-A, but stated in Reference 2 that all four criteria were applied and no re-evaluation of the results was required. Based on the use of the approved methodology and on the reported results, the staff finds that any increase in risk associated with the implementation of

the RI-ISI program is small and consistent with the intent of the Commission's Policy Statement (Ref. 7) and, therefore, is consistent with RG 1.178.

3.4 Integrated Decisionmaking

The proposed RI-ISI program presents an integrated approach that considers in concert the traditional engineering analysis, risk evaluation, and the implementation and performance monitoring of piping. This is consistent with the guidelines of RG 1.178.

The selection of pipe segments to be inspected is described in Section 3.8 of Reference 1 using the results of the risk category rankings and other operational considerations. Table 5-1 of Reference 1 provides a summary table comparing the number of inspections required under the existing ASME Section XI ISI program at North Anna Unit 2 (North Anna Unit 1 is similar to Unit 2) with the alternative RI-ISI program. The licensee stated that it used the methodology described in WCAP-14572, Rev. 1-NP-A to guide the selection of the number and the location of examination elements within the piping segments. The staff finds the location selection process to be acceptable since it is consistent with the process approved for WCAP-14572, Rev. 1-NP-A, and takes into account defense-in-depth.

WCAP-14572, Rev. 1-NP-A describes targeted examination volumes (typically associated with welds) and methods of examination based on the type(s) of degradation expected. The staff has reviewed these guidelines and has determined that, if implemented as described, the RI-ISI examinations should result in improved discovery of service-related discontinuities over that currently provided by the Code.

The objective of ISI required by the Code is to identify conditions (i.e., flaw indications) that are precursors to leaks and ruptures in the pressure boundary that may impact plant safety. Therefore, the RI-ISI program must meet this objective to be found acceptable for use. Further, since the RI program is based on inspection for cause, element selection should target specific degradation mechanisms.

Section 4 of WCAP-14572, Rev. 1-NP-A provides guidelines for the areas and/or volumes to be inspected as well as the examination method, acceptance standard, and evaluation standard for each degradation mechanism. Based on a review of the cited portion of WCAP-14572, Rev. 1-NP-A, the staff concludes that the examination methods are appropriate since they are selected based on specific degradation mechanisms, pipe sizes, and materials of concern. The licensee reported no deviations in this area from the WCAP-14572, Rev. 1-NP-A methodology and, therefore, its evaluation is acceptable.

3.5 Implementation and Monitoring

Implementation and performance monitoring strategies require careful consideration by the licensee and are addressed in Element 3 of RG 1.178 and SRP 3.9.8. The objective of Element 3 is to assess performance of the affected piping systems under the proposed RI-ISI program by implementing monitoring strategies that confirm the assumptions and analyses used in the development of the RI-ISI program. To approve an alternative pursuant to 10 CFR 50.55a(a)(3)(i), implementation of the RI-ISI program, including inspection scope, examination methods, and methods of evaluation of examination results, must provide an adequate level of quality and safety.

In Reference 1, the licensee stated that upon approval of the RI-ISI program, procedures that comply with the WCAP-14572, Rev. 1-NP-A guidelines will be prepared to implement and

monitor the RI-ISI program. The licensee confirmed that the applicable portions of the Code not affected by the change, such as inspection methods, acceptance guidelines, pressure testing, corrective measures, documentation requirements, and quality control requirements would be retained.

The licensee stated in Section 4 of Reference 1 that the RI-ISI program is a living program and its implementation will require feedback of new relevant information to ensure the appropriate identification of HSS piping locations. Reference 1 also stated that as a minimum, risk ranking of piping segments will be reviewed and adjusted on an ASME Code-defined ISI period basis and that significant changes may require more frequent adjustment as directed by NRC Bulletin or Generic Letter requirements or by industry and plant-specific feedback.

The proposed periodic reporting requirements meet existing ASME Code requirements and applicable regulations and therefore are considered acceptable. The staff finds that the proposed process for RI-ISI program updates meets the guidelines of RG 1.174 that risk-informed applications should include performance monitoring and feedback provisions; therefore, the process for program updates is acceptable.

4.0 CONCLUSION

10 CFR 50.55a(a)(3)(i) permits alternatives to regulatory requirements when authorized by the NRC if the applicant demonstrates that the alternative provides an acceptable level of quality and safety. In this case, the licensee's proposed alternative is to use the RI process described in the NRC-approved report WCAP-14572, Rev. 1-NP-A. The licensee reported one deviation discussed in Section 3.2, but a sensitivity study performed by the licensee indicated that the deviation did not affect the proposed RI-ISI program. As discussed in Section 3.0 above, the staff concludes that the licensee's proposed RI-ISI program, as described in the submittal, will provide an acceptable level of quality and safety with regard to the number of inspections, locations of inspections, and methods of inspection.

The staff finds that the results of different elements of the engineering analysis are considered in an integrated decisionmaking process. The impact of the proposed changes in the ISI program is founded on the adequacy of the engineering analysis and acceptable estimation of changes in plant risk in accordance with RG 1.174 and RG 1.178 guidelines.

The North Anna methodology also considers implementation and performance monitoring strategies. Inspection strategies ensure that failure mechanisms of concern have been addressed and there is adequate assurance of detecting damage before structural integrity is affected. The risk significance of piping segments is taken into account in defining the inspection scope for the RI-ISI program.

System pressure tests and visual examination of piping structural elements will continue to be performed on all Code Class 1 systems in accordance with the ASME Code Section XI program. The RI-ISI program applies the same performance measurement strategies as existing ASME Code requirements.

The North Anna risk-informed methodology provides for conducting an analysis of the proposed changes using a combination of engineering analysis with supporting insights from a PRA. Defense-in-depth and quality are not degraded in that the methodology provides reasonable confidence that any reduction in existing inspections will not lead to degraded piping performance when compared to existing performance levels. Inspections are focused

on locations with active degradation mechanisms as well as selected locations that monitor the performance of system piping.

In addition, the licensee submitted Relief Request RR-1, which requested performance of visual VT-2 examinations each refueling outage as an alternative to the volumetric examinations specified in Code Case N-577 and in WCAP-14572, Rev. 1-NP-A for those HSS ASME Code Class 1 socket welds identified in the RI-ISI program. The staff concurs that volumetric examination of socket welds is inconclusive and impractical due to the geometric limitations imposed by a socket weld. The staff also concurs that to perform Code-required surface examination of socket welds is not useful due to the absence of an environment that would cause outside surface-initiated flaws. Therefore, the licensee's proposed alternative examination method is authorized pursuant to 10 CFR 50.55a(a)(3)(ii) on the basis that performing either volumetric or surface examinations of these socket welds would result in unusual difficulty without a compensating increase in the level of quality and safety, and that the licensee's proposed alternative provides reasonable assurance of structural integrity.

As discussed above, the staff's review of the licensee's proposed RI-ISI program concludes that the program is an acceptable alternative to the current ISI program, which is based on ASME Code, Section XI requirements for Code Class 1, Categories B-F and B-J welds. Therefore, the licensee's proposed RI-ISI program is authorized for the third 10-year ISI interval pursuant to 10 CFR 50.55a(a)(3)(i) on the basis that the request provides an acceptable level of quality and safety.

5.0 REFERENCES

1. Letter, dated April 26, 2001, L. N. Hartz (Virginia Electric and Power Company, Vice President - Nuclear Engineering and Services) to U.S. Nuclear Regulatory Commission, containing *Risk-Informed Inservice Inspection Program - North Anna Power Station Units 1 and 2*.
2. Letter, dated July 25, 2001, L. N. Hartz (Virginia Electric and Power Company, Vice President - Nuclear Engineering and Services) to U.S. Nuclear Regulatory Commission, containing *Virginia Electric Power Company North Anna Power Station Units 1 and 2 Response to Request for Additional Information Risk-Informed Inservice Inspection Program*.
3. WCAP-14572, Revision 1-NP-A, *Westinghouse Owners Group Application of Risk-Informed Methods to Piping Inservice Inspection Topical Report*, February 1999.
4. NRC Regulatory Guide 1.174, *An Approach for Using Probabilistic Risk Assessment in Risk-Informed Decisions on Plant-Specific Changes to the Licensing Basis*, July 1998.

5. NRC Regulatory Guide 1.178, *An Approach for Plant-Specific Risk-Informed Decision Making: Inservice Inspection of Piping*, September 1998.
6. NRC NUREG-0800, Chapter 3.9.8, *Standard Review Plan for Trial Use for the Review of Risk-Informed Inservice Inspection of Piping*, May 1998.
7. USNRC, "Use of Probabilistic Risk Assessment Methods in Nuclear Regulatory Activities; Final Policy Statement," *Federal Register*, Vol. 60, p. 42622, August 16, 1995.

Principal Contributors: S. Dinsmore
P. Patnaik

Date: September 18, 2001