

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. One required offsite circuit inoperable.</p>	<p>A.1 Perform SR 3.8.1.1 for required OPERABLE offsite circuit.</p> <p><u>AND</u></p> <p>-----NOTE----- In MODES 1, 2 and 3, the TDAFW pump is considered a required redundant feature. -----</p>	<p>1 hour</p> <p><u>AND</u></p> <p>Once per 8 hours thereafter</p>
	<p>A.2 Declare required feature(s) with no offsite power available inoperable when its redundant required feature(s) is inoperable.</p>	<p>24 hours from discovery of no offsite power to one train concurrent with inoperability of redundant required feature(s)</p>
	<p><u>AND</u></p> <p>A.3 Restore required offsite circuit to OPERABLE status.</p>	<p>72 hours</p> <p><u>AND</u></p> <p>6 days from discovery of failure to meet LCO</p> <p><u>OR</u></p> <p>21 days for a one time preventive maintenance outage on Startup Transformer XST2 to be completed by February 28, 2002</p>

(continued)