



AGENCY AUTHORITY FILE COPY
UNITED STATES
NUCLEAR REGULATORY COMMISSION
WASHINGTON, D. C. 20555

DO NOT REMOVE

June 29, 1989

Docket Nos. 50-280
and 50-281

POSTED

50-281
SURRY 2

~~CONFIDENTIAL~~
TO DPR-37

Mr. W. R. Cartwright
Vice President - Nuclear
Virginia Electric and Power Company
5000 Dominion Blvd.
Glen Allen, Virginia 23060

Dear Mr. Cartwright:

SUBJECT: SURRY UNITS 1 AND 2 - CORRECTIONS TO AMENDMENT NOS. 128 AND 128 AND
AMENDMENT NOS. 130 AND 130 (TAC NOS. 56910, 56911, 72811 AND 72812)

On May 24, 1989, the Commission issued Amendment Nos. 128 and 128 for the Surry Power Station, Units 1 and 2. These amendments removed obsolete inservice inspection and testing requirements and replaced them with more up-to-date NRC-approved requirements specified in 10 CFR 50.55a(g). Also, Amendment Nos. 130 and 130 were issued for the Surry Power Station, Units 1 and 2 on June 9, 1989. These amendments revised the Technical Specifications (TS) relating to the canal level, canal safety-related actuation instrumentation and the emergency service water pumps. Recently you informed us of administrative errors in these amendments.

In Amendment Nos. 128 and 128, page TS 4.5-1 contained a footnote which required that the inside containment recirculation spray pump be dry tested at least once a month. However, this footnote should have been deleted. Also, the attachment to the amendments which provided the instructions for removing and inserting the new TS pages should have noted that pages TS 4.2-8 through TS 4.2-35 should have been removed from the Surry TS as well as pages TS 4.11-3 and TS 4.11-4. The corrected page TS 4.5-1 and the attachment page are enclosed.

In addition, Amendment Nos. 130 and 130 contained an administrative error on page TS 3.7-9b. The paragraph concerning the Control Room Chlorine Detection System was previously deleted in Amendment Nos. 124 and 124, and therefore should not have been included. Table 4.1-1 also contained a reference to the Control Room Chlorine Detection System which should have been deleted.

Mr. W. R. Cartwright

- 2 -

June 29, 1989

Finally, the attachment to the amendments incorrectly instructed you to remove page TS 4.1-8aa. However, since TS 4.1-8aa was a new page to be added, there was no page to remove. The corrected page TS 3.7-9b, Table 4.1-1 and the attachment page are also enclosed.

We apologize for any inconvenience these errors may have caused.

Sincerely,

Original signed by

Bart C. Buckley, Senior Project Manager
Project Directorate II-2
Division of Reactor Projects-I/II
Office of Nuclear Reactor Regulation

Enclosures:
As stated

cc w/enclosures:
See next page

LM:PD2A
D. Berkow
6/29/89

BCB
PM:PD22
BBuckley
6/29/89

D:PD2
HBerkow
6/29/89

Mr. W. R. Cartwright
Virginia Electric and Power Company

Surry Power Station

cc:

Michael W. Maupin, Esq.
Hunton and Williams
Post Office Box 1535
Richmond, Virginia 23212

Attorney General
Supreme Court Building
101 North 8th Street
Richmond, Virginia 23219

Mr. Michael Kansler, Manager
Surry Power Station
Post Office Box 315
Surry, Virginia 23883

Resident Inspector
Surry Power Station
U.S. Nuclear Regulatory Commission
Post Office Box 166, Route 1
Surry, Virginia 23883

Mr. Sherlock Holmes, Chairman
Board of Supervisors of Surry County
Surry County Courthouse
Surry, Virginia 23683

Mr. W. T. Lough
Virginia Corporation Commission
Division of Energy Regulation
Post Office Box 1197
Richmond, Virginia 23209

Regional Administrator, Region II
U.S. Nuclear Regulatory Commission
101 Marietta Street N.W., Suite 2900
Atlanta, Georgia 30323

C. M. G. Buttery, M.D., M.P.H.
Department of Health
109 Governor Street
Richmond, Virginia 23219

ATTACHMENT TO LICENSE AMENDMENT

AMENDMENT NO. 128 FACILITY OPERATING LICENSE NO. DPR-32

AMENDMENT NO. 128 FACILITY OPERATING LICENSE NO. DPR-37

DOCKET NOS. 50-280 AND 50-281

Revise Appendix A as follows:

<u>Remove Pages</u>	<u>Insert Pages</u>
TS ii	TS ii
TS iii	TS iii
TS 3.1-4	TS 3.1-4
TS 3.6-1	TS 3.6-1
TS 3.6-2	TS 3.6-2
---	TS 3.6-7
TS 4.0-1	TS 4.0-1
---	TS 4.0-2
---	TS 4.0-3
---	TS 4.0-4
TS 4.1-9b	TS 4.1-9b
TS 4.1-11	TS 4.1-11
TS 4.1-12	TS 4.1-12
TS 4.2-1	TS 4.2-1
TS 4.2-2	TS 4.2-2
TS 4.2-3	TS 4.2-3
TS 4.2-4	TS 4.2-4
TS 4.2-5	TS 4.2-5
TS 4.2-6	TS 4.2-6
TS 4.2-7	TS 4.2-7
TS 4.2-8	TS 4.2-8
TS 4.3-1	TS 4.3-1
TS 4.3-2	TS 4.3-2
TS 4.3-3	TS 4.3-3
TS 4.3-4	---
TS 4.5-1	TS 4.5-1
TS 4.5-2	TS 4.5-2
TS 4.5-3	TS 4.5-3
TS 4.5-4	TS 4.5-4
TS 4.5-5	---
TS 4.5-6	---
TS 4.11-1	TS 4.11-1
TS 4.11-2	TS 4.11-2

4.5 SPRAY SYSTEMS TESTS

Applicability

Applies to the testing of the Spray Systems.

Objective

To verify that the Spray Systems will respond promptly and perform their design function, if required.

Specification

- A. Each containment spray subsystem shall be demonstrated operable:
1. By verifying, that on recirculation flow, each containment spray pump performs satisfactorily when tested in accordance with Specification 4.0.3.
 2. By verifying that each motor-operated valve in the containment spray flow path performs satisfactorily when tested in accordance with Specification 4.0.3.
 3. At least once per 5 years, coincident with the closest refueling outage, by performing an air or smoke flow test and verifying each spray nozzle is unobstructed.
 4. Coincident with the containment spray pump test described in Specification 4.5.A.1, by verifying that no particulate material clogs the test spray nozzles in the refueling water storage tank.
- B. Each recirculation spray subsystem shall be demonstrated operable:
1. By verifying each recirculation spray pump performs satisfactorily when tested in accordance with Specification 4.0.3.*

* Except that each inside containment recirculation spray pump shall be dry tested at least once per month. The dry test of a recirculation spray pump shall be considered satisfactory if the motor and pump shaft rotates, starts on signal, and the ammeter readings for the motor are comparable to the original dry test ammeter readings.

ATTACHMENT TO LICENSE AMENDMENT

AMENDMENT NO. 130 FACILITY OPERATING LICENSE NO. DPR-32

AMENDMENT NO. 130 FACILITY OPERATING LICENSE NO. DPR-37

DOCKET NOS. 50-280 AND 50-281

Revise Appendix A as follows:

Remove Pages

TS 3.7-9b
TS 3.7-16
TS 3.7-19
TS 3.14-1
TS 3.14-2
TS 3.14-3
TS 3.14-4
TS 4.1-8a
--
TS 4.1-9c

Insert Pages

TS 3.7-9b
TS 3.7-16
TS 3.7-19
TS 3.14-1
TS 3.14-2
TS 3.14-3
TS 3.14-4
TS 4.1-8a
TS 4.1-8aa
TS 4.1-9c

control room.

The supply lines installed from the containment penetrations to the hydrogen analyzers have Category I Class IE heat tracing applied. The heat tracing system receives the same transferable emergency power as is provided to the containment hydrogen analyzers. The heat trace system is de-energized during normal system operation. Upon receipt of a safety injection signal (Train A or Train B), the system is automatically started, after a preset time delay, to bring the piping process temperature to $250^{\circ}\text{F} \pm 10^{\circ}\text{F}$ within 20 minutes. Each heat trace circuit is equipped with an RTD to provide individual circuit readout, over temperature alarm and cycles the circuit to maintain the process temperatures via the solid state control modules.

The hydrogen analyzer heat trace system is equipped with high temperature, loss of D.C. power, loss of A.C. power, loss of control power and failure of automatic initiation alarms.

Non-Essential Service Water Isolation System

The operability of this functional system ensures that adequate intake canal inventory can be maintained by the emergency service water pumps. Adequate intake canal inventory provides design service water flow to the recirculation spray heat exchangers and other essential loads (e.g., control room area chillers, charging pump lube oil coolers) following a design basis loss of coolant accident with a coincident loss of offsite power. This system is common to both units in that each of the two trains will actuate equipment on each unit.

TABLE 4.1-1
MINIMUM FREQUENCIES FOR CHECK, CALIBRATIONS, AND
TEST OF INSTRUMENT CHANNELS

<u>Channel Description</u>	<u>Check</u>	<u>Calibrate</u>	<u>Test</u>	<u>Remarks</u>
33. Loss of Power				
a. 4.16 KV Emergency Bus Under-voltage (Loss of Voltage)	N.A.	R	M	
b. 4.16 KV Emergency Bus Under-voltage (Degraded Voltage)	N.A.	R	M	
34. Deleted				
35. Manual Reactor Trip	N.A.	N.A.	R	The test shall independently verify the operability of the undervoltage and shunt trip attachments for the manual reactor trip function. The test shall also verify the operability of the bypass breaker trip circuit.
36. Reactor Trip Bypass Breaker	N.A.	N.A.	M(1), R(2)	(1) Local manual undervoltage trip prior to placing breaker in service. (2) Automatic shunt trip.
37. Safety Injection Input from ESF	N.A.	N.A.	R	
38. Reactor Coolant Pump Breaker Position Trip	N.A.	N.A.	R	