1/2/27

Dockets Nos. 50-250 and 50-251

> Florida Power and Light Company ATTN: Dr. Robert E. Uhrig Vice President P. O. Box 013100 Miami, Florida 33101

**DISTRIBUTION:** Docket NRC PDR Local PDR ORB#3 Rdq KRGoller **TJCarter JMcGough** GLear DElliott CParrish OEL D OI&E(5)DEisenhut BJones (8) **TBAbernathy** JRBuchanan ACRS (16) File

Gentlemen:

By letter dated January 14, 1977, we transmitted to you Amendments Nos. 22 and 21 to Facility Licenses Nos. DPR-31 and DPR-41. Due to a typographical error, Technical Specifications pages 3.2-3 and B3.2-4 for both Units Nos. 3 and 4 contained incorrect information.

Please replace pages 3.2-3 and B3.2-4 of Amendments Nos. 22 and 21 to Licenses Nos. DPR-31 and DPR-41 with the enclosed corrected pages 3.2-3 and B3.2-4.

Sincerely,

George Lear, Chief Operating Reactors Branch #3 Division of Operating Reactors

Enclosures: Pages 3.2-3 and B3.2-4 of Amendments Nos. 22 and 21



OFFICE	ORB#3	0 <b>8</b> B#3	ORB#3	 	
SURNAME	CParrish	DElliott:acr	GLear	 	
DATE	1//77	1./			

Form AEC-318 (Rev. 9-53) AECM 0240

X U. S. GOVERNMENT PRINTING OFFICE: 1974-526-166

Florida Power & Light Company

\_ 2

cc:

Mr. Jack R. Newman, Esquire Lowenstein, Newman, Reis & Axelrad 1025 Connecticut Avenue, N. W. Suite 1214 Washington, D. C. 20036

Mr. Ed Maroney Bureau of Intergovernmental Relations 725 South Bronough Street Tallahassee, Flordia 32304

Honorable Dewey Knight County Manager of Metropolitan Dade County Miami, Florida 33130

Florida Power & Light Company ATTN: Mr. Henry Yaeger Plant Manager Turkey Point Plant P. O. Box 013100 Miami, Florida 33101

Chief, Energy Systems Analysis Branch (AW-459) Office of Radiation Programs U. S. Environmental Protection Agency Room 645, East Tower 401 M Street, S. W. Washington, D. C. 20460

U. S. Environmental Protection Agency Region VI Office ATTN: EIS COORDINATOR 345 Courtland Street, N. E. Atlanta, Georgia 30308

Environmental & Urban Affairs Library Florida International University Miami, Florida 33199

1400

reactivity insertion upon ejection greater than 0.3%  $\Delta$  k/k at rated power. Inoperable rod worth shall be determined within 4 weeks.

- b. A control rod shall be considered inoperable if
  - (a) the rod cannot be moved by the CRDM, or
  - (b) the rod is misaligned from its bank by more than 15 inches, or
  - (c) the rod drop time is not met.
- c. If a control rod cannot be moved by the drive mechanism, shutdown margin shall be increased by boron addition to compensate for the withdrawn worth of the inoperable rod.

## 5. CONTROL ROD POSITION INDICATION

If either the power range channel deviation alarm or the rod deviation monitor alarm are not operable rod positions shall be logged once per shift and after a load change greater than 10% of rated power. If both alarms are inoperable for two hours or more, the nuclear overpower trip shall be reset to 93% of rated power.

## 6. POWER DISTRIBUTION LIMITS

- a. At all times except during low power physics tests, the hot channel factors defined in the basis must meet the following limits:  $F_q(Z) \leq (2.22/P) \ge K(Z)$  for  $P \geq .5$  $F_q(Z) \leq (4.44) \ge K(Z)$  for  $P \leq .5$  $F_{\Delta H} \leq 1.55$  [1 + 0.2 (1-P)] where P is the fraction of rated power at which the core is operating. K(Z) is the function given in Figure 3.2-3 and Z is the core height location of  $F_q$ .
- b. Following initial loading before the reactor is operated above 75% of rated power and at regular effective full rated power monthly intervals thereafter, power distribution maps, using the movable detector system shall be made, to conform that the hot channel factor limits of the specification are satisfied. For the purpose of this comparison,

UNIT 3

3.2-3

An upper bound envelope of 2.22 times the normalized peaking factor axial dependence of Figure 3.2-3 has been determined to be consistent with the technical specifications on power distribution control as given in Section 3.2.

When an  $F_q$  measurement is taken, both experimental error and manufacturing tolerance must be allowed for. Five percent is the appropriate experimental uncertainty allowance for a full core map taken with the movable incore detector flux mapping system and three percent is the appropriate allowance for manufacturing tolerance.

In the specified limit of  $F_{\Delta H}^{N}$ , there is an 8 percent allowance for uncertainties which means that normal operation of the core is expected to result in  $F_{\Delta H}^{N} < 1.55/1.08$ . The logic behind the larger uncertainty in this case is that (a) normal perturbations in the radial power shape (e.g., rod misalignment) affect  $F_{\Delta H}^{N}$ , in most cases without necessarily affecting  $F_{q}$ , (b) the operator has a direct influence on  $F_{q}$  through movement of rods, and can limit it to the desired value, he has no direct control over  $F_{\Delta H}^{N}$  and (c) an error in the predictions for radial power shape, which may be detected during startup physics tests can be compensated for in  $P_{q}$  by tighter axial control, but compensation for  $F_{\Delta H}^{N}$  is less readily available. When a measurement of  $F_{\Delta H}^{N}$  is taken, experimental error must be allowed for and 4% is the appropriate allowance for a full core map taken with the movable incore detector flux mapping system.

Measurements of the hot channel factors are required as part of start-up physics tests, at least once each full rated power month of operation, and whenever abnormal power distribution conditions require a reduction of core power to a level based on measured hot channel factors. The incore map taken following initial loading provides confirmation of the basic nuclear

UNIT 3

B3.2-4

Amendment No. 22

## UNIT 3

reactivity insertion upon ejection greater than  $0.3\% \Delta k/k$  at rated power. Inoperable rod worth shall be determined within 4 weeks.

- b. A control rod shall be considered inoperable if
  - (a) the rod cannot be moved by the CRDM, or
  - (b) the rod is misaligned from its bank by more than 15 inches, or
  - (c) the rod drop time is not met.
- c. If a control rod cannot be poved by the drive mechanism, shutdown margin shall be increased by boron addition to compensate for the withdrawn worth of the inoperable rod.

5. CONTROL ROD POSITION INDICATION

If either the power range channel deviation alarm or the rod deviation monitor alarm are not operable rod positions shall be logged once per shift and after a load change greater than 10% of rated power. If both alarms are inoperable for two hours or more, the nuclear overpower trip shall be reset to 93% of rated power.

- 6. POWER DISTRIBUTION LIMITS
  - a. At all times except during low power physics tests,
    the hot channel factors defined in the basis must
    meet the following limits:

 $F_q(Z) \leq (2.22/P) \times K(Z) \text{ for } P > .5$ 

 $F_q(Z) \leq (4.44) \times K(Z)$  for  $P \leq .5$ 

 $F_{AH}^{N} \leq 1.55 [1 + 0.2 (1-P)]$ 

where P is the fraction of rated power at which the core is operating. K(Z) is the function given in Figure 3.2-3 and Z is the core height location of  $F_q$ .

b. Following initial loading before the reactor is operated above 75% of rated power and at regular effective full rated power conthly intervals thereafter, power distribution maps, using the movable detector system shall be made, to conform that the hot channel factor limits of the specification are satisfied. For the purpose of this comparis me An upper bound envelope of 2.22 times the normalized peaking factor axial dependence of Figure 3.2-3 has been determined to be consistent with the technical specifications on power distribution control as given in Section 3.2.

When an  $F_q$  measurement is taken, both experimental error and manufacturing solerance must be allowed for. Five percent is the appropriate experimental uncertainty allowance for a full core map taken with the movable incore detector flux mapping system and three percent is the appropriate allowance for manufacturing tolerance.

In the specified limit of  $F_{\Delta H}^{N}$ , there is an 8 percent allowance for uncertainties which means that normal operation of the core is expected to result in  $F_{\Delta H}^{N}$  (1.55/1.08. The logic behind the larger uncertainty in this case is that (a) normal perturbations in the radial power shape (e.g., rod misalignment) affect  $F_{\Delta H}^{N}$ , in most cases without necessarily affecting  $F_{q}$ . (b) the operator has a direct influence on  $F_{q}$  through movement of rods, and can limit it to the desired value, he has no direct control over  $F_{\Delta H}^{N}$  and (c) an error in the predictions for radial power shape, which may be detected during startup physics tests can be compensated for in  $P_{q}$  by tighter axial control, but compensation for  $F_{\Delta H}^{N}$  is less readily available. When a measurement of  $F_{\Delta H}^{N}$  is taken, experimental error must be allowed for and 4% is the appropriate allowance for a full core map taken with the movable incore detector flux mapping system.

Measurements of the hot channel factors are required as part of start-up physics tests, at least once each full rated power month of operation, and whenever abnormal power distribution conditions require a reduction of core power to a level based on measured hot channel factors. The incore map taken following initial loading provides confirmation of the basic nuclear

UNIT 3

B3.2-4

Amendment No. 21