

Docket Nos. 50-259/260/296

Mr. Hugh G. Parris
Manager of Power
Tennessee Valley Authority
500A Chestnut Street, Tower II
Chattanooga, Tennessee 37401

Dear Mr. Parris:

On April 5, 1985 we issued Amendment Nos. 116, 111 and 86 to Facility Operating License Nos. DPR-33, DPR-52 and DPR-68 in response to your application dated October 19, 1984.

Those amendments contained errors. Changes made by Amendments Nos. 114, 108 and 86 were inadvertently omitted, and footers did not indicate previous amendments. Corrected pages are enclosed. Certain pages have been revised for improved legibility. Only the pages marked "corrected (date)" have corrected Technical Specifications.

Sincerely,



Richard J. Clark, Project Manager
Operating Reactors Branch #2
Division of Licensing

Enclosures:
As stated

cc w/enclosures:
See next page

DISTRIBUTION

Docket File
NRC PDR
Local PDR
ORB#2 Reading
HThompson

JPartlow
SNorris
RClark
WLong
OELD
LJHarmon

ELJordan
BGrimes
TBarnhart (12)
WJones
EButcher

ACRS (10)
OPA, CMiles
RDiggs
Gray File
Extra - 5

DL:ORB#2
SNorris:rc
04/19/85

DL:ORB#2
WLong
04/19/85

DL:ORB#2
RClark
04/19/85

JTB
DL:ORB#2
DVassallo
04/22/85

B505060120 B50422
PDR ADDOCK 05000259
PDR

Mr. Hugh G. Parris
Tennessee Valley Authority
Browns Ferry Nuclear Plant, Units 1, 2 and 3

cc:

H. S. Sanger, Jr., Esquire
General Counsel
Tennessee Valley Authority
400 Commerce Avenue
E 11B 330
Knoxville, Tennessee 37902

James A. Coffey
Site Director, BFNP
Tennessee Valley Authority
Post Office Box 2000
Decatur, Alabama 35602

Mr. Ron Rogers
Tennessee Valley Authority
400 Chestnut Street, Tower II
Chattanooga, Tennessee 37401

Resident Inspector
U. S. Nuclear Regulatory Commission
Route 2, Box 311
Athens, Alabama 35611

Mr. Charles R. Christopher
Chairman, Limestone County Commission
Post Office Box 188
Athens, Alabama 35611

Mr. Donald L. Williams, Jr.
Tennessee Valley Authority
400 West Summit Hill Drive, W10B85
Knoxville, Tennessee 37902

Ira L. Meyers, M.D.
State Health Officer
State Department of Public Health
State Office Building
Montgomery, Alabama 36130

George Jones, Manager, BFNP
Tennessee Valley Authority
Post Office Box 2000
Decatur, Alabama 35602

Mr. H. N. Culver
249A HBD
400 Commerce Avenue
Tennessee Valley Authority
Knoxville, Tennessee 37902

Mr. Oliver Havens
U. S. Nuclear Regulatory Commission
Reactor Training Center
Osborne Office Center, Suite 200
Chattanooga, Tennessee 37411

J. Nelson Grace
Regional Administrator
Region II Office
U. S. Nuclear Regulatory Commission
101 Marietta Street, Suite 3100
Atlanta, Georgia 30303

ATTACHMENT TO LICENSE AMENDMENT NO. 116

FACILITY OPERATING LICENSE NO. DPR-33

DOCKET NO. 50-259

Revise Appendix A as follows:

1. Remove the following pages and replace with identically numbered pages.

57, 58, 59, 60, 61, 86, 88, 109

2. The marginal lines on these pages denote the area being changed.

8505060129 850422
PDR ADDCK 05000259
P PDR

TABLE 3.2.A
PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

Minimum No. of Instrument Channels Operable per Trip System (1) (11)	<u>Function</u>	<u>Trip Level Setting</u>	<u>Action</u>	<u>Remarks</u>
1	Reactor Building Isolation Timer (refueling floor)	0.5 t ± 2 secs	H or F	1. Below trip setting prevents spurious trips and system per- turbations from init- iating isolation
1	Reactor Building Isolation Timer (reactor zone)	0.5 t ± 2 secs	G or A or H	1. Below trip setting prevents spurious trips and system per- turbations from init- iating isolation
2 (10)	Group 1 (Initiating) Logic	N/A	A	1. Refer to Table 3.7.A for list of valves.
1	Group 1 (Actuation) Logic	N/A	B	1. Refer to Table 3.7.A for list of valves

Amendment No. 85, 116

57

TABLE 3.2.A
PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

Minimum No. Instrument Channels Operable per Trip Sys(1)(1)	Function	Trip Level Setting	Action (1)	Remarks
2	Group 2 (Initiating) Logic	N/A	A or (B and E)	1. Refer to Table 3.7.A for list of valves.
1	Group 2 (RHR Isolation- Actuation) Logic	N/A	D	
1	Group 8 (Tip-Actuation) Logic	N/A	J	
1	Group 2 (Drywell Sump Drains-Actuation) Logic	N/A	K	
1	Group 2 (Reactor Building & Refueling Floor, and Dry- well Vent and Purge- Actuation) Logic	N/A	F and G	1. Part of Group 6 Logic.
2	Group 3 (Initiating) Logic	N/A	C	1. Refer to Table 3.7.A for list of valves.
1	Group 3 (Actuation) Logic	N/A	C	
1	Group 6 Logic	N/A	F and G	1. Refer to Table 3.7.A for list of valves.
1	Group 8 (Initiating) Logic	N/A	J	1. Refer to Table 3.7.A for list of valves. 2. Same as Group 2 initiating logic.
1	Reactor Building Isolation (refueling floor) Logic	N/A	H or F	
1	Reactor Building Isolation (reactor zone) Logic	N/A	H or G or A	

Amendment No. 85, 116

TABLE 3.2.A
PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

Minimum No. Instrument Channels Operable per Trip Sys(1)(11)	Function	Trip Level Setting	Action (1)	Remarks
1(7) (8)	SGTS Train A Logic	N/A	L or (A and F)	
1(7) (8)	SGTS Train B Logic	N/A	L or (A and F)	
1(7) (8)	SGTS Train C Logic	N/A	L or (A and F)	

Refer to Table 3.2.B for RCIC and RPCI functions including Groups 4, 5, and 7 valves.

NOTES FOR TABLE 3.2.A

1. Whenever the respective functions are required to be operable there shall be two operable or tripped trip systems for each function. If the first column cannot be met for one of the trip systems, that trip system or logic for that function shall be tripped (or the appropriate action listed below shall be taken). If the column cannot be met for all trip systems, the appropriate action listed below shall be taken.
 - A. Initiate an orderly shutdown and have the reactor in Cold Shutdown in 24 hours.
 - B. Initiate an orderly load reduction and have Main Steam Lines isolated within eight hours.
 - C. Isolate Reactor Water Cleanup System.
 - D. Isolate Shutdown Cooling.
 - E. Initiate primary containment isolation within 24 hours.
 - F. The handling of spent fuel will be prohibited and all operations over spent fuels and open reactor wells shall be prohibited.
 - G. Isolate the reactor building and start the standby gas treatment system.
 - H. Immediately perform a logic system functional test on the logic in the other trip systems and daily thereafter not to exceed 7 days.
 - I. DELETE
 - J. Withdraw TIP.
 - K. Manually isolate the affected lines. Refer to section 4.2.E for the requirements of an inoperable system.
 - L. If one SGTS train is inoperable take actions H or A and F. If two SGTS trains are inoperable take actions A and F.
2. When it is determined that a channel is failed in the unsafe condition, the other channels that monitor the same variable shall be functionally tested immediately before the trip system or logic for that function is tripped. The trip system or the logic for that function may remain untripped for short periods of time to allow functional testing of the other trip system or logic for that function.
3. There are four sensors per steam line of which two must be operable.
4. Only required in Run Mode (Interlocked with Mode Switch).
5. Not required in Run Mode (bypassed by mode switch).

6. Channel shared by RPS and Primary Containment & Reactor Vessel Isolation Control Systems. A channel failure may be a channel failure in each system.
 7. A train is considered a trip system.
 8. Two out of three SGTS trains required. A failure of more than one will require action A and F.
 9. DELETED
 10. Refer to Table 3.7.A and its notes for a listing of Isolation Valve Groups and their initiating signals.
 11. A channel may be placed in an inoperable status for up to four hours for required surveillance without placing the trip system in the tripped condition provided at least one OPERABLE channel in the same trip system is monitoring that parameter.
 12. A channel contains four sensors, all of which must be operable for the channel to be operable.
- Power operations permitted for up to 30 days with 15 of the 16 temperature switches operable.

In the event that normal ventilation is unavailable in the main steam line tunnel, the high temperature channels may be bypassed for a period of not to exceed four hours. During periods when normal ventilation is not available, such as during the performance of secondary containment leak rate tests, the control room indicators of the affected space temperatures shall be monitored for indications of small steam leaks. In the event of rapid increases in temperature (indicative of steam line break), the operator shall promptly close the main steam line isolation valves.

13. The nominal setpoints for alarm and reactor trip (1.5 and 3.0 times background, respectively) are established based on the normal background at full power. The allowable setpoints for alarm and reactor trip are 1.2 - 1.8 and 2.4 - 3.6 times background, respectively.
14. Requires two independent channels from each physical location, there are two locations.

TABLE 4.2.A
 SURVEILLANCE REQUIREMENTS FOR PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

<u>Function</u>	<u>Functional Test</u> (1) (14) (22)	<u>Calibration Frequency</u>	<u>Instrument Check</u> once/day (8)
Instrument Channel - Reactor Building Ventilation High Radiation - Refueling Zone		once/3 months	
Instrument Channel - SGTS Train A Heaters	(4)	(9)	N/A
Instrument Channel - SGTS Train B Heaters	(4)	(9)	N/A
Instrument Channel - SGTS Train C Heaters	(4)	(9)	N/A
Reactor Building Isolation Timer (refueling floor)	(4)	once/operating cycle	N/A
Reactor Building Isolation Timer (reactor zone)	(4)	once/operating cycle	N/A

TABLE 4.2.A

SURVEILLANCE REQUIREMENTS FOR PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

<u>Function</u>	<u>Functional Test</u>	<u>Calibration Frequency</u>	<u>Instrument Check</u>
Group 6 Logic	once/operating cycle (18)	N/A	N/A
Group 8 (Initiating Logic)	Checked during channel functional test. No further test required	N/A	N/A
Reactor Building Isolation (refueling floor) Logic	once/6 months (18)	(6)	N/A
Reactor Building Isolation (reactor zone) Logic	once/6 months (18)	(6)	N/A
SGTS Train A Logic	once/6 months (19)	N/A	N/A
SGTS Train B Logic	once/6 months (19)	N/A	N/A
SGTS Train C Logic	once/6 months (19)	N/A	N/A
Instrument Channel- Reactor Cleanup System Floor Dr. Hi. Temp	(1)	once/operating cycle	N/A
Instrument Channel- Reactor Cleanup System Space High Temp	(1)	once/operating cycle	N/A

Amendment No. 114, 116

88

Corrected

NOTES FOR TABLES 4.2.A THROUGH 4.2.H

1. Functional tests shall be performed once per month.
2. Functional tests shall be performed before each startup with a required frequency not to exceed once per week.
3. This instrumentation is excepted from the functional test definition. The functional test will consist of injecting a simulated electrical signal into the measurement channel.
4. Tested during logic system functional tests.
5. Refer to Table 4.1.B.
6. The logic system functional tests shall include a calibration once per operating cycle of time delay relays and timers necessary for proper functioning of the trip systems.
7. The functional test will consist of verifying continuity across the inhibit with a volt-ohmmeter.
8. Instrument checks shall be performed in accordance with the definition of Instrument Check (see Section 1.0, Definitions). An instrument check is not applicable to a particular setpoint, such as Upscale, but is a qualitative check that the instrument is behaving and/or indicating in an acceptable manner for the particular plant condition. Instrument check is included in this table for convenience and to indicate that an Instrument Check will be performed on the instrument. Instrument checks are not required when these instruments are not required to be operable or are tripped.
9. Calibration frequency shall be once/year.
10. DELETE
11. Portion of the logic is functionally tested during outage only.
12. The detector will be inserted during each operating cycle and the proper amount of travel into the core verified.
13. Functional test will consist of applying simulated inputs (see note 3). Local alarm lights representing upscale and downscale trips will be verified, but no rod block will be produced at this time. The inoperative trip will be initiated to produce a rod block (SRM and IRM inoperative also bypassed with the mode switch in RUN). The functions that cannot be verified to produce a rod block directly will be verified during the operating cycle.

ATTACHMENT TO LICENSE AMENDMENT NO. 111

FACILITY OPERATING LICENSE NO. DPR-52

DOCKET NO. 50-260

Revise Appendix A as follows:

1. Remove the following pages and replace with identically numbered pages.
57, 58, 59, 60, 61, 86, 88, 109
2. The marginal lines on these pages denote the area being changed.

TABLE 3.2.A
PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

Minimum No. of Instrument Channels Operable per Trip System (1) (11)	Function	Trip Level Setting	Action	Remarks
1	Reactor Building Isolation Timer (refueling floor)	0.5 ± 2 secs	H or F	1. Below trip setting prevents spurious trips and system per- turbations from init- iating isolation
1	Reactor Building Isolation Timer (reactor zone)	0.5 ± 2 secs	G or A or H	1. Below trip setting prevents spurious trips and system per- turbations from init- iating isolation
2 (10)	Group 1 (Initiating) Logic	N/A	A	1. Refer to Table 3.7.A for list of valves.
1	Group 1 (Actuation) Logic	N/A	B	1. Refer to Table 3.7.A for list of valves

TABLE 3.2.A
PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

Minimum No. Instrument Channels Operable per Trip Sys(1)(11)	Function	Trip Level Setting	Action (1)	Remarks
2	Group 2 (Initiating) Logic	N/A	A or (B and E)	1. Refer to Table 3.7.A for list of valves.
1	Group 2 (RHR Isolation-Actuation) Logic	N/A	D	
1	Group 8 (Tip-Actuation) Logic	N/A	J	
1	Group 2 (Drywell Sump Drains-Actuation) Logic	N/A	K	
1	Group 2 (Reactor Building & Refueling Floor, and Drywell Vent and Purge-Actuation) Logic	N/A	F and G	1. Part of Group 6 Logic.
2	Group 3 (Initiating) Logic	N/A	C	1. Refer to Table 3.7.A for list of valves.
1	Group 3 (Actuation) Logic	N/A	C	
1	Group 6 Logic	N/A	F and G	1. Refer to Table 3.7.A for list of valves.
1	Group 8 (Initiating) Logic	N/A	J	1. Refer to Table 3.7.A for list of valves. 2. Same as Group 2 initiating logic.
1	Reactor Building Isolation (refueling floor) Logic	N/A	H or F	
1	Reactor Building Isolation (reactor zone) Logic	N/A	H or G or A	

TABLE 3.2.A
PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

Minimum No. Instrument Channels Operable per Trip Sys(1)(11)	Function	Trip Level Setting	Action (1)	Remarks
1(7) (8)	SGTS Train A Logic	N/A	L or (A and F)	
1(7) (8)	SGTS Train B Logic	N/A	L or (A and F)	
1(7) (8)	SGTS Train C Logic	N/A	L or (A and F)	

Refer to Table 3.2.B for RCIC and MPCV functions including Groups 4, 5, and 7 valves.

NOTES FOR TABLE 3.2.A

1. Whenever the respective functions are required to be operable there shall be two operable or tripped trip systems for each function. If the first column cannot be met for one of the trip systems, that trip system or logic for that function shall be tripped (or the appropriate action listed below shall be taken). If the column cannot be met for all trip systems, the appropriate action listed below shall be taken.
 - A. Initiate an orderly shutdown and have the reactor in Cold Shutdown in 24 hours.
 - B. Initiate an orderly load reduction and have Main Steam Lines isolated within eight hours.
 - C. Isolate Reactor Water Cleanup System.
 - D. Isolate Shutdown Cooling.
 - E. Initiate primary containment isolation within 24 hours.
 - F. The handling of spent fuel will be prohibited and all operations over spent fuels and open reactor wells shall be prohibited.
 - G. Isolate the reactor building and start the standby gas treatment system.
 - H. Immediately perform a logic system functional test on the logic in the other trip systems and daily thereafter not to exceed 7 days.
 - I. DELETE
 - J. Withdraw TIP.
 - K. Manually isolate the affected lines. Refer to section 4.2.E for the requirements of an inoperable system.
 - L. If one SGTS train is inoperable take actions H or A and F. If two SGTS trains are inoperable take actions A and F.
2. When it is determined that a channel is failed in the unsafe condition, the other channels that monitor the same variable shall be functionally tested immediately before the trip system or logic for that function is tripped. The trip system or the logic for that function may remain untripped for short periods of time to allow functional testing of the other trip system or logic for that function.
3. There are four sensors per steam line of which two must be operable.
4. Only required in Run Mode (Interlocked with Mode Switch).
5. Not required in Run Mode (bypassed by mode switch).

6. Channel shared by RPS and Primary Containment & Reactor Vessel Isolation Control Systems. A channel failure may be a channel failure in each system.
7. A train is considered a trip system.
8. Two out of three SGTS trains required. A failure of more than one will require action A and F.
9. DELETED
10. Refer to Table 3.7.A and its notes for a listing of Isolation Valve Groups and their initiating signals.
11. A channel may be placed in an inoperable status for up to four hours for required surveillance without placing the trip system in the tripped condition provided at least one OPERABLE channel in the same trip system is monitoring that parameter.
12. A channel contains four sensors, all of which must be operable for the channel to be operable.

Power operations permitted for up to 30 days with 15 of the 16 temperature switches operable.

In the event that normal ventilation is unavailable in the main steam line tunnel, the high temperature channels may be bypassed for a period of not to exceed four hours. During periods when normal ventilation is not available, such as during the performance of secondary containment leak rate tests, the control room indicators of the affected space temperatures shall be monitored for indications of small steam leaks. In the event of rapid increases in temperature (indicative of steam line break), the operator shall promptly close the main steam line isolation valves.

13. The nominal setpoints for alarm and reactor trip (1.5 and 3.0 times background, respectively) are established based on the normal background at full power. The allowable setpoints for alarm and reactor trip are 1.2 - 1.8 and 2.4 - 3.6 times background, respectively.
14. Requires two independent channels from each physical location, there are two locations.

TABLE 4.2.A
 SURVEILLANCE REQUIREMENTS FOR PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

<u>Function</u>	<u>Functional Test</u>	<u>Calibration Frequency</u>	<u>Instrument Check</u>
Instrument Channel - Reactor Building Ventilation High Radiation - Refueling Zone	(1) (14) (22)	once/3 months	once/day (8)
Instrument Channel - SGTS Train A Heaters	(4)	(9)	N/A
Instrument Channel - SGTS Train B Heaters	(4)	(9)	N/A
Instrument Channel - SGTS Train C Heaters	(4)	(9)	N/A
Reactor Building Isolation Timer (refueling floor)	(4)	once/operating cycle	N/A
Reactor Building Isolation Timer (reactor zone)	(4)	once/operating cycle	N/A

TABLE 4.2.A
SURVEILLANCE REQUIREMENTS FOR PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

<u>Function</u>	<u>Functional Test</u>	<u>Calibration Frequency</u>	<u>Instrument Check</u>
Group 6 Logic	once/operating cycle (18)	N/A	N/A
Group 8 (Initiating Logic)	Checked during channel functional test. No further test required	N/A	N/A
Reactor Building Isolation (refueling floor) Logic	once/6 months (18)	(6)	N/A
Reactor Building Isolation (reactor zone) Logic	once/6 months (18)	(6)	N/A
SGTS Train A Logic	once/6 months (19)	N/A	N/A
SGTS Train B Logic	once/6 months (19)	N/A	N/A
SGTS Train C Logic	once/6 months (19)	N/A	N/A
Instrument Channel- Reactor Cleanup System Floor Dr. Hi. Temp	(1)	once/operating cycle	N/A
Instrument Channel- Reactor Cleanup System Space High Temp	(1)	once/operating cycle	N/A

NOTES FOR TABLES 4.2.A THROUGH 4.2.H

1. Functional tests shall be performed once per month.
2. Functional tests shall be performed before each startup with a required frequency not to exceed once per week.
3. This instrumentation is excepted from the functional test definition. The functional test will consist of injecting a simulated electrical signal into the measurement channel.
4. Tested during logic system functional tests.
5. Refer to Table 4.1.B.
6. The logic system functional tests shall include a calibration once per operating cycle of time delay relays and timers necessary for proper functioning of the trip systems.
7. The functional test will consist of verifying continuity across the inhibit with a volt-ohmmeter.
8. Instrument checks shall be performed in accordance with the definition of Instrument Check (see Section 1.0, Definitions). An instrument check is not applicable to a particular setpoint, such as Upscale, but is a qualitative check that the instrument is behaving and/or indicating in an acceptable manner for the particular plant condition. Instrument check is included in this table for convenience and to indicate that an Instrument Check will be performed on the instrument. Instrument checks are not required when these instruments are not required to be operable or are tripped.
9. Calibration frequency shall be once/year.
10. DELETE
11. Portion of the logic is functionally tested during outage only.
12. The detector will be inserted during each operating cycle and the proper amount of travel into the core verified.
13. Functional test will consist of applying simulated inputs (see note 3). Local alarm lights representing upscale and downscale trips will be verified, but no rod block will be produced at this time. The inoperative trip will be initiated to produce a rod block (SRM and IRM inoperative also bypassed with the mode switch in RUN). The functions that cannot be verified to produce a rod block directly will be verified during the operating cycle.

ATTACHMENT TO LICENSE AMENDMENT NO. 86

FACILITY OPERATING LICENSE NO. DPR-68

DOCKET NO. 50-296

Revise Appendix A as follows:

1. Remove the following pages and replace with identically numbered pages.

59, 60, 61, 62, 63, 89, 91, 106

2. The marginal lines on these pages denote the area being changed.

TABLE 3.2.A
PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

Minimum No. of Instrument Channels Operable per Trip System (1) (11)	Function	Trip Level Setting	Action	Remarks
1	Reactor Building Isolation Timer (refueling floor)	0.4 ± 2 secs	H or F	1. Below trip setting prevents spurious trips and system per- turbations from init- iating isolation
1	Reactor Building Isolation Timer (reactor zone)	0.4 ± 2 secs	G or A or H	1. Below trip setting prevents spurious trips and system per- turbations from init- iating isolation
2 (10)	Group 1 (Initiating) Logic	N/A	A	1. Refer to Table 3.7.A for list of valves.
1	Group 1 (Actuation) Logic	N/A	B	1. Refer to Table 3.7.A for list of valves

TABLE 3.2.A
PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

Minimum No. Instrument Channels Operable per Trip Sys(1)(11)	Function	Trip Level Setting	Action (1)	Remarks
2	Group 2 (Initiating) Logic	N/A	A or (B and E)	1. Refer to Table 3.7.A for list of valves.
1	Group 2 (RRR Isolation- Actuation) Logic	N/A	D	
1	Group 8 (Tip-Actuation) Logic	N/A	J	
1	Group 2 (Drywell Sump Drains-Actuation) Logic	N/A	K	
1	Group 2 (Reactor Building & Refueling Floor, and Dry- well Vent and Purge- Actuation) Logic	N/A	F and G	1. Part of Group 6 Logic.
2	Group 3 (Initiating) Logic	N/A	C	1. Refer to Table 3.7.A for list of valves.
1	Group 3 (Actuation) Logic	N/A	C	
1	Group 6 Logic	N/A	F and G	1. Refer to Table 3.7.A for list of valves.
1	Group 8 (Initiating) Logic	N/A	J	1. Refer to Table 3.7.A for list of valves. 2. Same as Group 2 initiating logic.
1	Reactor Building Isolation (refueling floor) Logic	N/A	H or F	
1	Reactor Building Isolation (reactor zone) Logic	N/A	H or G or A	

TABLE 3.2.A
PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

Minimum No. Instrument Channels Operable per Trip Sys(1)(11)	Function	Trip Level Setting	Action (1)	Remarks
1(7) (8)	SGTS Train A Logic	N/A	L or (A and F)	
1(7) (8)	SGTS Train B Logic	N/A	L or (A and F)	
1(7) (8)	SGTS Train C Logic	N/A	L or (A and F)	

Refer to Table 3.2.B for RCIC and EPCI functions including Groups 4, 5, and 7 valves.

NOTES FOR TABLE 3.2.A

1. Whenever the respective functions are required to be operable, there shall be two operable or tripped trip systems for each function.

If the first column cannot be met for one of the trip systems, that trip system or logic for that function shall be tripped (or the appropriate action listed below shall be taken). If the column cannot be met for all trip systems, the appropriate action listed below shall be taken.

- A. Initiate an orderly shutdown and have the reactor in Cold Shutdown Condition in 24 hours.
 - B. Initiate an orderly load reduction and have Main Steam Lines isolated within eight hours.
 - C. Isolate Reactor Water Cleanup System.
 - D. Isolate Shutdown Cooling.
 - E. Initiate primary containment isolation within 24 hours.
 - F. The handling of spent fuel will be prohibited and all operations over spent fuels and open reactor wells shall be prohibited.
 - G. Isolate the reactor building and start the standby gas treatment system.
 - H. Immediately perform a logic system functional test on the logic in the other trip systems and daily thereafter not to exceed 7 days.
 - I. DELETE
 - J. Withdraw TIP.
 - K. Manually isolate the affected lines. Refer to section 4.2.E for the requirements of an inoperable system.
 - L. If one SGTS train is inoperable take actions H or action A and F. If two SGTS trains are inoperable take actions A and F.
2. When it is determined that a channel is failed in the unsafe condition, the other channels that monitor the same variable shall be functionally tested immediately before the trip system or logic for that function is tripped. The trip system or the logic for that function may remain untripped for short periods of time to allow functional testing of the other trip system or logic for that function.

3. There are four channels per steam line of which two must be operable.
 4. Only required in Run Mode (Interlocked with Mode Switch).
 5. Not required in Run Mode (bypassed by mode switch).
 6. Channel shared by RPS and Primary Containment & Reactor Vessel Isolation Control Systems. A channel failure may be a channel failure in each system.
 7. A train is considered a trip system.
 8. Two out of three SGTS trains required. A failure of more than one will require action A and F.
 9. DELETED
 10. Refer to Table 3.7.A and its notes for a listing of Isolation Valve Groups and their initiating signals.
 11. A channel may be placed in an inoperable status for up to four hours for required surveillance without placing the trip system in the tripped condition provided at least one OPERABLE channel in the same trip system is monitoring that parameter.
 12. A channel contains four sensors, all of which must be operable for the channel to be operable.
- Power operations permitted for up to 30 days with 15 of the 16 temperature switches operable.

In the event that normal ventilation is unavailable in the main steam line tunnel, the high temperature channels may be bypassed for a period of not to exceed four hours. During periods when normal ventilation is not available, such as during the performance of secondary containment leak rate tests, the control room indicators of the affected space temperatures shall be monitored for indications of small steam leaks. In the event of rapid increases in temperature (indicative of steam line break), the operator shall promptly close the main steam line isolation valves.

13. The nominal setpoints for alarm and reactor trip (1.5 and 3.0 times background, respectively) are established based on the normal background at full power. The allowable setpoints for alarm and reactor trip are 1.2 - 1.8 and 2.4 - 3.6 times background, respectively.
14. Requires two independent channels from each physical location, there are two locations.

TABLE 4.2.A

SURVEILLANCE REQUIREMENTS FOR PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

<u>Function</u>	<u>Functional Test</u>	<u>Calibration Frequency</u>	<u>Instrument Check</u>
Instrument Channel - Reactor Building Ventilation High Radiation - Refueling Zone	(1) (14) (22)	once/3 months	once/day (8)
Instrument Channel - SGTS Train A Heaters	(4)	(9)	N/A
Instrument Channel - SGTS Train B Heaters	(4)	(9)	N/A
Instrument Channel - SGTS Train C Heaters	(4)	(9)	N/A
Reactor Building Isolation Timer (refueling floor)	(4)	once/operating cycle	N/A
Reactor Building Isolation Timer (reactor zone)	(4)	once/operating cycle	N/A

Amendment No. 86

86

TABLE 4.2.A
SURVEILLANCE REQUIREMENTS FOR PRIMARY CONTAINMENT AND REACTOR BUILDING ISOLATION INSTRUMENTATION

<u>Function</u>	<u>Functional Test</u>	<u>Calibration Frequency</u>	<u>Instrument Check</u>
Group 6 Logic	once/operating cycle (18)	N/A	N/A
Group 8 (Initiating Logic)	Checked during channel functional test. No further test required	N/A	N/A
Reactor Building Isolation (refueling floor) Logic	once/6 months (18)	(6)	N/A
Reactor Building Isolation (reactor zone) Logic	once/6 months (18)	(6)	N/A
SGTS Train A Logic	once/6 months (19)	N/A	N/A
SGTS Train B Logic	once/6 months (19)	N/A	N/A
SGTS Train C Logic	once/6 months (19)	N/A	N/A
Instrument Channel- Reactor Cleanup System Floor Dr. Hi. Temp	(1)	once/operating cycle	N/A
Instrument Channel- Reactor Cleanup System Space High Temp	(1)	once/operating cycle	N/A

NOTES FOR TABLES 4.2.A THROUGH 4.2.H

1. Functional tests shall be performed once per month.
2. Functional tests shall be performed before each startup with a required frequency not to exceed once per week.
3. This instrumentation is excepted from the functional test definition. The functional test will consist of injecting a simulated electrical signal into the measurement channel.
4. Tested during logic system functional tests.
5. Refer to Table 4.1.B.
6. The logic system functional tests shall include a calibration once per operating cycle of time delay relays and timers necessary for proper functioning of the trip systems.
7. The functional test will consist of verifying continuity across the inhibit with a volt-ohmmeter.
8. Instrument checks shall be performed in accordance with the definition of Instrument Check (see section 1.0, Definitions). An instrument check is not applicable to a particular setpoint, such as Upscale, but is a qualitative check that the instrument is behaving and/or indicating in an acceptable manner for the particular plant condition. Instrument check is included in this table for convenience and to indicate that an Instrument Check will be performed on the instrument. Instrument checks are not required when these instruments are not required to be operable or are tripped.
9. Calibration frequency shall be once/year.
10. DELETE
11. Portion of the logic is functionally tested during outage only.
12. The detector will be inserted during each operating cycle and the proper amount of travel into the core verified.
13. Functional test will consist of applying simulated inputs (see note 3). Local alarm lights representing upscale and downscale trips will be verified, but no rod block will be produced at this time. The inoperative trip will be initiated to produce a rod block (SRM and IRM inoperative also bypassed with the mode switch in RUN). The functions that cannot be verified to produce a rod block directly will be verified during the operating cycle.