

Secondary Containment Isolation Instrumentation  
3.3.6.2

Table 3.3.6.2-1 (page 1 of 1)  
Secondary Containment Isolation Instrumentation

FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
1. Reactor Vessel Water Level —Low Level 2	1,2,3,	2	SR 3.3.6.2.1 SR 3.3.6.2.2 SR 3.3.6.2.3 SR 3.3.6.2.4 SR 3.3.6.2.5	≥ 101 inches
2. Drywell Pressure —High	1,2,3	2	SR 3.3.6.2.1 SR 3.3.6.2.2 SR 3.3.6.2.3 SR 3.3.6.2.4 SR 3.3.6.2.5	≤ 1.8 psig
3. Reactor Building Exhaust Radiation —High	1,2,3, (a),(b)	1	SR 3.3.6.2.1 SR 3.3.6.2.2 SR 3.3.6.2.4 SR 3.3.6.2.5	≤ 16 mR/hr

(a) During operations with a potential for draining the reactor vessel.

(b) During movement of recently irradiated fuel assemblies in secondary containment.

3.3 INSTRUMENTATION

3.3.7.1 Control Room Emergency Ventilation (CREV) System Instrumentation

LCO 3.3.7.1 Two channels per trip system of the Control Building Air Intake Radiation—High Function shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3,  
During movement of recently irradiated fuel assemblies in the secondary containment,  
During operations with a potential for draining the reactor vessel (OPDRVs).

ACTIONS

-----NOTE-----  
Separate Condition entry is allowed for each channel.  
-----

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more channels inoperable.	A.1 Place one CREV subsystem in the radiation/smoke protection mode of operation.	7 days
B. CREV System initiation capability not maintained.	B.1 Place one CREV subsystem in the radiation/smoke protection mode of operation.	1 hour

3.6 CONTAINMENT SYSTEMS

3.6.4.1 Secondary Containment

LCO 3.6.4.1 The secondary containment shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3,  
During movement of recently irradiated fuel assemblies in the secondary containment,  
During operations with a potential for draining the reactor vessel (OPDRVs).

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Secondary containment inoperable in MODE 1, 2, or 3.	A.1 Restore secondary containment to OPERABLE status.	8 hours
B. Required Action and associated Completion Time of Condition A not met.	B.1 Be in MODE 3.	12 hours
	<u>AND</u> B.2 Be in MODE 4.	36 hours
C. Secondary containment inoperable during movement of recently irradiated fuel assemblies in the secondary containment, or during OPDRVs.	C.1 -----NOTE----- LCO 3.0.3 is not applicable. ----- Suspend movement of recently irradiated fuel assemblies in the secondary containment.	Immediately
	<u>AND</u>	(continued)

**ACTIONS**

CONDITION	REQUIRED ACTION	COMPLETION TIME
C. (continued)	C.2 Initiate action to suspend OPDRVs.	Immediately

**SURVEILLANCE REQUIREMENTS**

SURVEILLANCE	FREQUENCY
SR 3.6.4.1.1 Verify all secondary containment equipment hatches are closed and sealed.	24 months
SR 3.6.4.1.2 Verify one secondary containment access door is closed in each access opening.	24 months
SR 3.6.4.1.3 Verify each SGT subsystem can maintain $\geq 0.25$ inch of vacuum water gauge in the secondary containment for 1 hour at a flow rate $\leq 3000$ cfm.	24 months on a STAGGERED TEST BASIS

3.6 CONTAINMENT SYSTEMS

3.6.4.2 Secondary Containment Isolation Dampers (SCIDs)

LCO 3.6.4.2 Each SCID shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3,  
During movement of recently irradiated fuel assemblies in the secondary containment,  
During operations with a potential for draining the reactor vessel (OPDRVs).

ACTIONS

- NOTES-----
1. Penetration flow paths may be unisolated intermittently under administrative controls.
  2. Separate Condition entry is allowed for each penetration flow path.
  3. Enter applicable Conditions and Required Actions for systems made inoperable by SCIDs.
- 

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more penetration flow paths with one SCID inoperable.	A.1 Isolate the affected penetration flow path by use of at least one closed and de-activated automatic damper, closed manual damper, or blind flange.	8 hours
	<u>AND</u>	(continued)

**ACTIONS (continued)**

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>D. Required Action and associated Completion Time of Condition A or B not met during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.</p>	<p>D.1 -----NOTE-----                      LCO 3.0.3 is not applicable.                      -----                      Suspend movement of recently irradiated fuel assemblies in the secondary containment.</p>	<p>Immediately</p>
	<p><u>AND</u>                      D.2 Initiate action to suspend OPDRVs.</p>	<p>Immediately</p>

**SURVEILLANCE REQUIREMENTS**

SURVEILLANCE	FREQUENCY
<p>SR 3.6.4.2.1 Verify the isolation time of each automatic SCID is within limits.</p>	<p>24 months</p>
<p>SR 3.6.4.2.2 Verify each automatic SCID actuates to the isolation position on an actual or simulated actuation signal.</p>	<p>24 months</p>

3.6 CONTAINMENT SYSTEMS

3.6.4.3 Standby Gas Treatment (SGT) System

LCO 3.6.4.3 Two SGT subsystems shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3,  
During movement of recently irradiated fuel assemblies in the secondary containment,  
During operations with a potential for draining the reactor vessel (OPDRVs).

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One SGT subsystem inoperable in MODE 1, 2 or 3.	A.1 Restore SGT subsystem to OPERABLE status.	7 days
B. Required Action and associated Completion Time of Condition A not met.  <u>OR</u> Two SGT subsystems inoperable in MODE 1, 2, or 3.	B.1 Be in MODE 3.  <u>AND</u> B.2 Be in MODE 4.	12 hours  36 hours

(continued)

ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>C. One SGT subsystem inoperable during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.</p>	<p>C.1 Restore SGT subsystem to OPERABLE status.</p>	<p>31 days</p>
<p>D. Required Action and associated Completion Time of Condition C not met.</p>	<p>-----NOTE----- LCO 3.0.3 is not applicable. -----</p> <p>D.1 Place OPERABLE SGT subsystem in operation.</p> <p><u>OR</u></p> <p>D.2.1 Suspend movement of recently irradiated fuel assemblies in secondary containment.</p> <p><u>AND</u></p> <p>D.2.2 Initiate action to suspend OPDRVs.</p>	<p>Immediately</p> <p>Immediately</p> <p>Immediately</p>

(continued)



**ACTIONS (continued)**

CONDITION	REQUIRED ACTION	COMPLETION TIME
E. Two SGT subsystems inoperable during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.	E.1 -----NOTE----- LCO 3.0.3 is not applicable. ----- Suspend movement of recently irradiated fuel assemblies in secondary containment.	Immediately
	AND	
	E.2 Initiate action to suspend OPDRVs.	Immediately

**SURVEILLANCE REQUIREMENTS**

SURVEILLANCE	FREQUENCY
SR 3.6.4.3.1 Operate each SGT subsystem for $\geq 10$ continuous hours with heaters operating.	31 days
SR 3.6.4.3.2 Perform required SGT filter testing in accordance with the Ventilation Filter Testing Program (VFTP).	In accordance with the VFTP
SR 3.6.4.3.3 Verify each SGT subsystem actuates on an actual or simulated initiation signal.	24 months

Secondary Containment Isolation Instrumentation  
3.3.6.2

Table 3.3.6.2-1 (page 1 of 1)  
Secondary Containment Isolation Instrumentation

FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
1. Reactor Vessel Water Level —Low Level 2	1,2,3,	2	SR 3.3.6.2.1 SR 3.3.6.2.2 SR 3.3.6.2.3 SR 3.3.6.2.4 SR 3.3.6.2.5	≥ 101 inches
2. Drywell Pressure —High	1,2,3	2	SR 3.3.6.2.1 SR 3.3.6.2.2 SR 3.3.6.2.3 SR 3.3.6.2.4 SR 3.3.6.2.5	≤ 1.8 psig
3. Reactor Building Exhaust Radiation —High	1,2,3, (a),(b)	1	SR 3.3.6.2.1 SR 3.3.6.2.2 SR 3.3.6.2.4 SR 3.3.6.2.5	≤ 16 mR/hr

(a) During operations with a potential for draining the reactor vessel.

(b) During movement of recently irradiated fuel assemblies in secondary containment.

3.3 INSTRUMENTATION

3.3.7.1 Control Room Emergency Ventilation (CREV) System Instrumentation

LCO 3.3.7.1 Two channels per trip system of the Control Building Air Intake Radiation—High Function shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3,  
During movement of recently irradiated fuel assemblies in the secondary containment,  
During operations with a potential for draining the reactor vessel (OPDRVs).

ACTIONS

-----NOTE-----  
Separate Condition entry is allowed for each channel.  
-----

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more channels inoperable.	A.1 Place one CREV subsystem in the radiation/smoke protection mode of operation.	7 days
B. CREV System initiation capability not maintained.	B.1 Place one CREV subsystem in the radiation/smoke protection mode of operation.	1 hour



**ACTIONS**

CONDITION	REQUIRED ACTION	COMPLETION TIME
C. (continued)	C.2 Initiate action to suspend OPDRVs.	Immediately

**SURVEILLANCE REQUIREMENTS**

SURVEILLANCE	FREQUENCY
SR 3.6.4.1.1 Verify all secondary containment equipment hatches are closed and sealed.	24 months
SR 3.6.4.1.2 Verify one secondary containment access door is closed in each access opening.	24 months
SR 3.6.4.1.3 Verify each SGT subsystem can maintain $\geq 0.25$ inch of vacuum water gauge in the secondary containment for 1 hour at a flow rate $\leq 3000$ cfm.	24 months on a STAGGERED TEST BASIS



ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>D. Required Action and associated Completion Time of Condition A or B not met during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.</p>	<p>D.1 -----NOTE----- LCO 3.0.3 is not applicable. -----</p> <p>Suspend movement of recently irradiated fuel assemblies in the secondary containment.</p>	<p>Immediately</p>
	<p><u>AND</u></p> <p>D.2 Initiate action to suspend OPDRVs.</p>	<p>Immediately</p>

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
<p>SR 3.6.4.2.1 Verify the isolation time of each automatic SCID is within limits.</p>	<p>24 months</p>
<p>SR 3.6.4.2.2 Verify each automatic SCID actuates to the isolation position on an actual or simulated actuation signal.</p>	<p>24 months</p>

3.6 CONTAINMENT SYSTEMS

3.6.4.3 Standby Gas Treatment (SGT) System

LCO 3.6.4.3 Two SGT subsystems shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3,  
During movement of recently irradiated fuel assemblies in the secondary containment,  
During operations with a potential for draining the reactor vessel (OPDRVs).

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One SGT subsystem inoperable in MODE 1, 2 or 3.	A.1 Restore SGT subsystem to OPERABLE status.	7 days
B. Required Action and associated Completion Time of Condition A not met.  <u>OR</u>  Two SGT subsystems inoperable in MODE 1, 2, or 3.	B.1 Be in MODE 3.  <u>AND</u>  B.2 Be in MODE 4.	12 hours  36 hours

(continued)



ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>C. One SGT subsystem inoperable during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.</p>	<p>C.1 Restore SGT subsystem to OPERABLE status.</p>	<p>31 days</p>
<p>D. Required Action and associated Completion Time of Condition C not met.</p>	<p>-----NOTE----- LCO 3.0.3 is not applicable. -----</p> <p>D.1 Place OPERABLE SGT subsystem in operation.</p> <p><u>OR</u></p> <p>D.2.1 Suspend movement of recently irradiated fuel assemblies in secondary containment.</p> <p><u>AND</u></p> <p>D.2.2 Initiate action to suspend OPDRVs.</p>	<p>Immediately</p> <p>Immediately</p> <p>Immediately</p>

(continued)

ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
E. Two SGT subsystems inoperable during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.	E.1 -----NOTE----- LCO 3.0.3 is not applicable. -----  Suspend movement of recently irradiated fuel assemblies in secondary containment.	Immediately
	<u>AND</u> E.2 Initiate action to suspend OPDRVs.	Immediately

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
SR 3.6.4.3.1 Operate each SGT subsystem for $\geq 10$ continuous hours with heaters operating.	31 days
SR 3.6.4.3.2 Perform required SGT filter testing in accordance with the Ventilation Filter Testing Program (VFTP).	In accordance with the VFTP
SR 3.6.4.3.3 Verify each SGT subsystem actuates on an actual or simulated initiation signal.	24 months