Table 3.3.6.2-1 (page 1 of 1)
Secondary Containment Isolation Instrumentation

FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	SURVEILLANCE REQUIREMENTS	ALLOMABLE VALUE
. Reactor Vessel Water Level —Low Level 2	1,2,3,	2	SR 3.3.6.2.1 SR 3.3.6.2.2 SR 3.3.6.2.3 SR 3.3.6.2.4 SR 3.3.6.2.5	≥ 101 inches
Drywell Pressure —High	1,2,3	2	SR 3.3.6.2.1 SR 3.3.6.2.2 SR 3.3.6.2.3 SR 3.3.6.2.4 SR 3.3.6.2.5	≤ 1.8 psig
. Reactor Building Exhaust Radiation —High	1,2,3, (a),(b)	1	SR 3.3.6.2.1 SR 3.3.6.2.2 SR 3.3.6.2.4 SR 3.3.6.2.5	≤ 16 mR/hr

⁽a) During operations with a potential for draining the reactor vessel.

⁽b) During movement of recently irradiated fuel assemblies in secondary containment.

3.3 INSTRUMENTATION

3.3.7.1 Control Room Emergency Ventilation (CREV) System Instrumentation

LCO 3.3.7.1 Two channels per trip system of the Control Building Air Intake Radiation—High Function shall be OPERABLE.

APPLICABILITY:

MODES 1, 2, and 3,

During movement of recently irradiated fuel assemblies in

the secondary containment,

During operations with a potential for draining the reactor

vessel (OPDRVs).

	-	•	^		_
AC		1	"	N	
nu		1	u	13	

Separate Condition entry is allowed for each channel.

	CONDITION	REQUIRED ACTION		COMPLETION TIME
Α.	One or more channels inoperable.	A.1	Place one CREV subsystem in the radiation/smoke protection mode of operation.	7 days
В.	CREV System initiation capability not maintained.	B.1	Place one CREV subsystem in the radiation/smoke protection mode of operation.	1 hour

3.6 CONTAINMENT SYSTEMS

3.6.4.1 Secondary Containment

LCO 3.6.4.1 The secondary containment shall be OPERABLE.

APPLICABILITY: MOD

MODES 1, 2, and 3,

During movement of recently irradiated fuel assemblies in

the secondary containment,

During operations with a potential for draining the reactor

vessel (OPDRVs).

ACTIONS

	CONDITION		REQUIRED ACTION	COMPLETION TIME
Α.	Secondary containment inoperable in MODE 1, 2, or 3.	A.1	Restore secondary containment to OPERABLE status.	8 hours
asso Time	Required Action and associated Completion Time of Condition A not met.	B.1 AND	Be in MODE 3.	12 hours
		B.2	Be in MODE 4.	36 hours
C.	Secondary containment inoperable during movement of recently irradiated fuel assemblies in the secondary containment, or during OPDRVs.	C,1	Suspend movement of recently irradiated fuel assemblies in the secondary containment.	Immediately
		AND		
				(continued)

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME	_
C. (continued)	C.2	Initiate action to suspend OPDRVs.	Immediately	l

		FREQUENCY	
SR	3.6.4.1.1	Verify all secondary containment equipment hatches are closed and sealed.	24 months
SR	3.6.4.1.2	Verify one secondary containment access door is closed in each access opening.	24 months
SR	3.6.4.1.3	Verify each SGT subsystem can maintain ≥ 0.25 inch of vacuum water gauge in the secondary containment for 1 hour at a flow rate ≤ 3000 cfm.	24 months on a STAGGERED TEST BASIS

3.6 CONTAINMENT SYSTEMS

3.6.4.2 Secondary Containment Isolation Dampers (SCIDs)

LCO 3.6.4.2 Each SCID shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3,

During movement of recently irradiated fuel assemblies in

the secondary containment,

During operations with a potential for draining the reactor

vessel (OPDRVs).

ACTIONS

-----NOTES-----

- 1. Penetration flow paths may be unisolated intermittently under administrative controls.
- 2. Separate Condition entry is allowed for each penetration flow path.
- 3. Enter applicable Conditions and Required Actions for systems made inoperable by SCIDs.

CONDITION		REQUIRED ACTION		COMPLETION TIME	
Α.	One or more penetration flow paths with one SCID inoperable.	A.1	Isolate the affected penetration flow path by use of at least one closed and de-activated automatic damper, closed manual damper, or blind flange.	8 hours	
		AND			
				(continued)	

ACTIONS (continued)

CONDITION		TION REQUIRED ACTION		
D.	Required Action and associated Completion Time of Condition A or B not met during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.	D.1	LCO 3.0.3 is not applicable. Suspend movement of recently irradiated fuel assemblies in the secondary containment.	Immediately
		AND		
		D.2	Initiate action to suspend OPDRVs.	Immediately

		FREQUENCY	
SR	3.6.4.2.1	Verify the isolation time of each automatic SCID is within limits.	24 months
SR	3.6.4.2.2	Verify each automatic SCID actuates to the isolation position on an actual or simulated actuation signal.	24 months

3.6 CONTAINMENT SYSTEMS

3.6.4.3 Standby Gas Treatment (SGT) System

Two SGT subsystems shall be OPERABLE. LCO 3.6.4.3

APPLICABILITY:

MODES 1, 2, and 3, During movement of recently irradiated fuel assemblies in

the secondary containment,

During operations with a potential for draining the reactor

vessel (OPDRVs).

ACTI	ONS			
CONDITION			REQUIRED ACTION	COMPLETION TIME
Α.	One SGT subsystem inoperable in MODE 1, 2 or 3.	A.1	Restore SGT subsystem to OPERABLE status.	7 days
В.	Required Action and associated Completion Time of Condition A not met.	B.1 <u>AND</u> B.2	Be in MODE 3. Be in MODE 4.	12 hours
	<u>OR</u>		DE 111 MODE 4.	30 11001 3
	Two SGT subsystems inoperable in MODE 1, 2, or 3.			

ACTIONS	(continued)
ACILUNA	1 CON CHIMCA

	CONDITION		REQUIRED ACTION	COMPLETION TIME	-
c.	One SGT subsystem inoperable during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.	C.1	Restore SGT subsystem to OPERABLE status.	31 days	-
D.	D. Required Action and associated Completion Time of Condition C not met.	D.1	NOTE	Immediately	
		OR D.2.1	Suspend movement of recently irradiated fuel assemblies in secondary containment.	Immediately	l
		<u>ANC</u> D.2.2	•	Immediately	

ACTIONS	(continued)
TO LIGHT	1 CON CINCLE

	CONDITION		REQUIRED ACTION	COMPLETION TIME	-
Ε.	Two SGT subsystems inoperable during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.	E.1	Suspend movement of recently irradiated fuel assemblies in secondary containment.	Immediately	
		AND			1
		E.2	Initiate action to suspend OPDRVs.	Immediately	l

		FREQUENCY	
SR	3.6.4.3.1	Operate each SGT subsystem for ≥ 10 continuous hours with heaters operating.	31 days
SR	3.6.4.3.2	Perform required SGT filter testing in accordance with the Ventilation Filter Testing Program (VFTP).	In accordance with the VFTP
SR	3.6.4.3.3	Verify each SGT subsystem actuates on an actual or simulated initiation signal.	24 months

Table 3.3.6.2-1 (page 1 of 1)
Secondary Containment Isolation Instrumentation

FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
. Reactor Vessel Water Level —Low Level 2	1,2,3,	2	SR 3.3.6.2.1 SR 3.3.6.2.2 SR 3.3.6.2.3 SR 3.3.6.2.4 SR 3.3.6.2.5	≥ 101 inches
. Drywell Pressure —High	1,2,3	2	SR 3.3.6.2.1 SR 3.3.6.2.2 SR 3.3.6.2.3 SR 3.3.6.2.4 SR 3.3.6.2.5	≤ 1.8 psig
. Reactor Building Exhaust Radiation —High	1,2,3, (a),(b)	1	SR 3.3.6.2.1 SR 3.3.6.2.2 SR 3.3.6.2.4 SR 3.3.6.2.5	≤ 16 mR/hr

⁽a) During operations with a potential for draining the reactor vessel.

⁽b) During movement of recently irradiated fuel assemblies in secondary containment.

ı

1

3.3 INSTRUMENTATION

3.3.7.1 Control Room Emergency Ventilation (CREV) System Instrumentation

LCO 3.3.7.1 Two channels per trip system of the Control Building Air Intake Radiation—High Function shall be OPERABLE.

APPLICABILITY:

MODES 1, 2, and 3,

During movement of recently irradiated fuel assemblies in

the secondary containment,

During operations with a potential for draining the reactor

vessel (OPDRVs).

ACTIONS

Separate Condition entry is allowed for each channel.

	CONDITION		REQUIRED ACTION	COMPLETION TIME	
Α.	One or more channels inoperable.	A.1	Place one CREV subsystem in the radiation/smoke protection mode of operation.	7 days	
В.	CREV System initiation capability not maintained.	B.1	Place one CREV subsystem in the radiation/smoke protection mode of operation.	1 hour	

3.6 CONTAINMENT SYSTEMS

3.6.4.1 Secondary Containment

The secondary containment shall be OPERABLE. LCO 3.6.4.1

APPLICABILITY:

MODES 1, 2, and 3,

During movement of recently irradiated fuel assemblies in

the secondary containment,

During operations with a potential for draining the reactor vessel (OPDRVs).

ACTIONS

	CONDITION		REQUIRED ACTION	COMPLETION TIME	
Α.	Secondary containment inoperable in MODE 1, 2, or 3.	A.1	Restore secondary containment to OPERABLE status.	8 hours	
В.	Required Action and associated Completion Time of Condition A	B.1	Be in MODE 3.	12 hours	
	not met.	B.2	Be in MODE 4.	36 hours	
c.	Secondary containment inoperable during movement of recently irradiated fuel assemblies in the secondary containment, or during OPDRVs.	C.1	Suspend movement of recently irradiated fuel assemblies in the secondary containment.	Immediately	1
		AND			
				(continued)	

	^-	•	\sim	ы	•
л			ก	N	•
n		1	u	11	-

CONDITION		REQUIRED ACTION	COMPLETION TIME	
C. (continued)	C.2	Initiate action to suspend OPDRVs.	Immediately	

		FREQUENCY	
SR	3.6.4.1.1	Verify all secondary containment equipment hatches are closed and sealed.	24 months
SR	3.6.4.1.2	Verify one secondary containment access door is closed in each access opening.	24 months
SR	3.6.4.1.3	Verify each SGT subsystem can maintain ≥ 0.25 inch of vacuum water gauge in the secondary containment for 1 hour at a flow rate ≤ 3000 cfm.	24 months on a STAGGERED TEST BASIS

3.6 CONTAINMENT SYSTEMS

3.6.4.2 Secondary Containment Isolation Dampers (SCIDs)

LCO 3.6.4.2 Each SCID shall be OPERABLE.

APPLICABILITY:

MODES 1, 2, and 3,

During movement of recently irradiated fuel assemblies in

the secondary containment,

During operations with a potential for draining the reactor

vessel (OPDRVs).

ACTIONS

- 1. Penetration flow paths may be unisolated intermittently under administrative controls.
- 2. Separate Condition entry is allowed for each penetration flow path.
- 3. Enter applicable Conditions and Required Actions for systems made inoperable by SCIDs.

	CONDITION		REQUIRED ACTION	COMPLETION TIME
Α.	One or more penetration flow paths with one SCID inoperable.	A.1	Isolate the affected penetration flow path by use of at least one closed and de-activated automatic damper, closed manual damper, or blind flange.	8 hours
		AND		
				(continued)

ACT1	ONS	(continued)
AL. I	CIUI	I CON CINGON

	CONDITION		REQUIRED ACTION	COMPLETION TIME
D.	Required Action and associated Completion Time of Condition A or B not met during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.	D.1	NOTF LCO 3.0.3 is not applicable. Suspend movement of recently irradiated fuel assemblies in the secondary containment.	Immediately
		AND		
		D.2	Initiate action to suspend OPDRVs.	Immediately

		FREQUENCY	
SR	3.6.4.2.1	Verify the isolation time of each automatic SCID is within limits.	24 months
SR	3.6.4.2.2	Verify each automatic SCID actuates to the isolation position on an actual or simulated actuation signal.	24 months

3.6 CONTAINMENT SYSTEMS

3.6.4.3 Standby Gas Treatment (SGT) System

Two SGT subsystems shall be OPERABLE. LCO 3.6.4.3

APPLICABILITY:

MODES 1, 2, and 3,

During movement of recently irradiated fuel assemblies in

the secondary containment, During operations with a potential for draining the reactor

vessel (OPDRVs).

ACTIONS

CONDITION		REQUIRED ACTION		COMPLETION TIME	
Α.	One SGT subsystem inoperable in MODE 1, 2 or 3.	A.1	Restore SGT subsystem to OPERABLE status.	7 days	
В.	Required Action and associated Completion Time of Condition A not met.	B.1	Be in MODE 3.	12 hours	
		B.2	Be in MODE 4.	36 hours	
	Two SGT subsystems inoperable in MODE 1, 2, or 3.				

ACTIONS	(continued)
---------	-------------

<u>ACTI</u>		<u> </u>		2010 57701 7715
	CONDITION	REQUIRED ACTION		COMPLETION TIME
c.	One SGT subsystem inoperable during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.	C.1	Restore SGT subsystem to OPERABLE status.	31 days
D.	Required Action and associated Completion Time of Condition C not met.	D.1 Place OPERABLE SGT subsystem in operation.		Immediately
		<u>OR</u>	·	Tunna di ada 311
		D.2.1	Suspend movement of recently irradiated fuel assemblies in secondary containment.	Immediately
		AN	<u>D</u>	
		D.2.2	Initiate action to suspend OPDRVs.	Immediately

ACTIONS	(continued)
AC LIUNS	(CONCINCE)

CONDITION		REQUIRED ACTION		COMPLETION TIME	
Ε.	Two SGT subsystems inoperable during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.	E.1	Suspend movement of recently irradiated fuel assemblies in secondary containment.	Immediately	1
		AND E.2	Initiate action to suspend OPDRVs.	Immediately	1

		FREQUENCY	
SR	3.6.4.3.1	Operate each SGT subsystem for ≥ 10 continuous hours with heaters operating.	31 days
SR	3.6.4.3.2	Perform required SGT filter testing in accordance with the Ventilation Filter Testing Program (VFTP).	In accordance with the VFTP
SR	3.6.4.3.3	Verify each SGT subsystem actuates on an actual or simulated initiation signal.	24 months