

SURVEILLANCE REQUIREMENTS

SURVEILLANCE		FREQUENCY								
SR 3.4.4.1	<p>Verify the safety function lift setpoints of the required S/RVs are as follows:</p> <table><thead><tr><th><u>Number of S/RVs</u></th><th><u>Setpoint (psig)</u></th></tr></thead><tbody><tr><td>7</td><td>1165 ± 34.9</td></tr><tr><td>5</td><td>1180 ± 35.4</td></tr><tr><td>4</td><td>1190 ± 35.7</td></tr></tbody></table> <p>Following testing, lift settings shall be within ± 1%.</p>	<u>Number of S/RVs</u>	<u>Setpoint (psig)</u>	7	1165 ± 34.9	5	1180 ± 35.4	4	1190 ± 35.7	In accordance with the Inservice Testing Program
<u>Number of S/RVs</u>	<u>Setpoint (psig)</u>									
7	1165 ± 34.9									
5	1180 ± 35.4									
4	1190 ± 35.7									
SR 3.4.4.2	<p>-----NOTE----- Valve actuation may be excluded. -----</p> <p>Verify each required relief function S/RV actuates on an actual or simulated automatic initiation signal.</p>	18 months								
SR 3.4.4.3	<p>-----NOTE----- Not required to be performed until 12 hours after reactor steam pressure and flow are adequate to perform the test. -----</p> <p>Verify each required S/RV actuator strokes when manually actuated.</p>	18 months								

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE	FREQUENCY
<p>SR 3.5.1.5 -----NOTE----- Vessel injection/spray may be excluded. -----</p> <p>Verify each ECCS injection/spray subsystem actuates on an actual or simulated automatic initiation signal.</p>	18 months
<p>SR 3.5.1.6 -----NOTE----- Valve actuation may be excluded. -----</p> <p>Verify the ADS actuates on an actual or simulated automatic initiation signal.</p>	18 months
<p>SR 3.5.1.7 -----NOTE----- Not required to be performed until 12 hours after reactor steam pressure and flow are adequate to perform the test. -----</p> <p>Verify each ADS valve actuator strokes when manually actuated.</p>	18 months
<p>SR 3.5.1.8 -----NOTE----- ECCS actuation instrumentation is excluded. -----</p> <p>Verify the ECCS RESPONSE TIME for each ECCS injection/spray subsystem is within limits.</p>	18 months

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
<p>SR 3.6.1.6.1 -----NOTE----- Not required to be performed until 12 hours after reactor steam pressure and flow are adequate to perform the test. -----</p> <p>Verify each LLS valve actuator strokes when manually actuated.</p>	<p>18 months</p>
<p>SR 3.6.1.6.2 -----NOTE----- Valve actuation may be excluded. -----</p> <p>Verify the LLS System actuates on an actual or simulated automatic initiation signal.</p>	<p>18 months</p>