

November 4, 1998

Mr. Oliver D. Kingsley, President  
Nuclear Generation Group  
Commonwealth Edison Company  
Executive Towers West III  
1400 Opus Place, Suite 500  
Downers Grove, IL 60515

SUBJECT: CORRECTION TO AMENDMENT - BYRON STATION AND BRAIDWOOD  
STATION (TAC NOS. M96449, M96450, M96451, M96452, MA0765, MA0766,  
MA0767 AND MA0768)

Dear Mr. Kingsley:

By letter dated October 6, 1998, the U.S. Nuclear Regulatory Commission (Commission) issued Amendment No. 104 to Facility Operating License No. NPF-37 and Amendment No. 104 to Facility Operating License No. NPF-66 for the Byron Station, Unit Nos. 1 and 2, respectively, and Amendment No. 96 to Facility Operating License No. NPF-72 and Amendment No. 96 to Facility Operating License No. NPF-77 for the Braidwood Station, Unit Nos. 1 and 2, respectively. By letter dated October 15, 1998, the Commission issued Amendment No. 105 to Facility Operating License No. NPF-37 and Amendment No. 105 to Facility Operating License No. NPF-66 for the Byron Station, Unit Nos. 1 and 2, respectively, and Amendment No. 97 to Facility Operating License No. NPF-72 and Amendment No. 97 to Facility Operating License No. NPF-77 for the Braidwood Station, Unit Nos. 1 and 2, respectively. Subsequently, some typographical errors were noted in the revised Technical Specification pages that were enclosed with these amendments. The corrected Technical Specification pages are enclosed. We apologize for any inconvenience this may have caused you.

Sincerely,

ORIG. SIGNED BY  
Stewart N. Bailey, Project Manager  
Project Directorate III-2  
Division of Reactor Projects - III/IV  
Office of Nuclear Reactor Regulation

9811170061 981104  
PDR ADDCK 05000454  
P PDR

Docket Nos. STN 50-454, STN 50-455,  
STN 50-456, STN 50-457

Enclosures: Corrected TS pages

cc w/encls: See next page

DISTRIBUTION: ~~Public~~ PUBLIC  
EAdensam, EGA1 PDIII-2 r/f SRichards  
CMoore (2) SBailey JHickman  
OGC, O15B18 GHill (8) WBeckner  
ACRS, T2E26 MJordan, RIII  
GHubbard REMch TMarsh

DOCUMENT NAME: G:\PDIII-2\CM\BRAID-BY\BB96449.LTR

To receive a copy of this document, indicate in the box: "C" = Copy without enclosures "E" = Copy with enclosures "N" = No copy

OFFICE	PM:PDIII-2	<input checked="" type="checkbox"/>	LA:PDIII-2	<input checked="" type="checkbox"/>	PM:PDIII-2	<input checked="" type="checkbox"/>	D:PDIII-2	<input checked="" type="checkbox"/>		
NAME	SBAILEY	SUB	CMOORE		JHICKMAN	JHX	SRICHARDS	SB		
DATE	11/3	/98	11/3	/98	11/4	/98	11/4	/98		

OFFICIAL RECORD COPY

NRG FILE CENTER COPY

1/1  
DFol  
CP-1



UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
WASHINGTON, D.C. 20555-0001

November 4, 1998

Mr. Oliver D. Kingsley, President  
Nuclear Generation Group  
Commonwealth Edison Company  
Executive Towers West III  
1400 Opus Place, Suite 500  
Downers Grove, IL 60515

SUBJECT: CORRECTION TO AMENDMENT - BYRON STATION AND BRAIDWOOD  
STATION (TAC NOS. M96449, M96450, M96451, M96452, MA0765, MA0766,  
MA0767 AND MA0768)

Dear Mr. Kingsley:

By letter dated October 6, 1998, the U.S. Nuclear Regulatory Commission (Commission) issued Amendment No. 104 to Facility Operating License No. NPF-37 and Amendment No. 104 to Facility Operating License No. NPF-66 for the Byron Station, Unit Nos. 1 and 2, respectively, and Amendment No. 96 to Facility Operating License No. NPF-72 and Amendment No. 96 to Facility Operating License No. NPF-77 for the Braidwood Station, Unit Nos. 1 and 2, respectively. By letter dated October 15, 1998, the Commission issued Amendment No. 105 to Facility Operating License No. NPF-37 and Amendment No. 105 to Facility Operating License No. NPF-66 for the Byron Station, Unit Nos. 1 and 2, respectively, and Amendment No. 97 to Facility Operating License No. NPF-72 and Amendment No. 97 to Facility Operating License No. NPF-77 for the Braidwood Station, Unit Nos. 1 and 2, respectively. Subsequently, some typographical errors were noted in the revised Technical Specification pages that were enclosed with these amendments. The corrected Technical Specification pages are enclosed. We apologize for any inconvenience this may have caused you.

Sincerely,

A handwritten signature in black ink, appearing to read "Stewart N. Bailey", with a long, sweeping underline.

Stewart N. Bailey, Project Manager  
Project Directorate III-2  
Division of Reactor Projects - III/IV  
Office of Nuclear Reactor Regulation

Docket Nos. STN 50-454, STN 50-455,  
STN 50-456, STN 50-457

Enclosures: Corrected TS pages

cc w/encls: See next page

O. Kingsley  
Commonwealth Edison Company

Byron/Braidwood Stations

cc:

Ms. C. Sue Hauser, Project Manager  
Westinghouse Electric Corporation  
Energy Systems Business Unit  
Post Office Box 355  
Pittsburgh, Pennsylvania 15230

George L. Edgar  
Morgan, Lewis and Bochiuss  
1800 M Street, N.W.  
Washington, DC 20036

Joseph Gallo  
Gallo & Ross  
1250 Eye St., N.W., Suite 302  
Washington, DC 20005

Attorney General  
500 S. Second Street  
Springfield, Illinois 62701

Michael I. Miller, Esquire  
Sidley and Austin  
One First National Plaza  
Chicago, Illinois 60603

Illinois Department of Nuclear Safety  
Office of Nuclear Facility Safety  
1035 Outer Park Drive  
Springfield, Illinois 62704

Howard A. Learner  
Environmental law and Policy  
Center of the Midwest  
35 East Wacker Dr., Suite 1300  
Chicago, Illinois 60601

Commonwealth Edison Company  
Byron Station Manager  
4450 N. German Church Road  
Byron, Illinois 61010-9794

U.S. Nuclear Regulatory Commission  
Byron Resident Inspectors Office  
4448 N. German Church Road  
Byron, Illinois 61010-9750

Commonwealth Edison Company  
Site Vice President - Byron  
4450 N. German Church Road  
Byron, Illinois 61010-9794

Regional Administrator, Region III  
U.S. Nuclear Regulatory Commission  
801 Warrenville Road  
Lisle, Illinois 60532-4351

U.S. Nuclear Regulatory Commission  
Braidwood Resident Inspectors Office  
RR 1, Box 79  
Braceville, Illinois 60407

Ms. Lorraine Creek  
RR 1, Box 182  
Manteno, Illinois 60950

Mr. Ron Stephens  
Illinois Emergency Services  
and Disaster Agency  
110 E. Adams Street  
Springfield, Illinois 62706

Chairman, Ogle County Board  
Post Office Box 357  
Oregon, Illinois 61061

Chairman  
Will County Board of Supervisors  
Will County Board Courthouse  
Joliet, Illinois 60434

Mrs. Phillip B. Johnson  
1907 Stratford Lane  
Rockford, Illinois 61107

Commonwealth Edison Company  
Braidwood Station Manager  
RR 1, Box 84  
Braceville, Illinois 60407

O. Kingsley  
Commonwealth Edison Company

- 2 -

Byron/Braidwood Stations

Ms. Bridget Little Rorem  
Appleseed Coordinator  
117 N. Linden Street  
Essex, Illinois 60935

Ms. Irene Johnson, Licensing Director  
Nuclear Regulatory Services  
Commonwealth Edison Company  
Executive Towers West III  
1400 Opus Place, Suite 500  
Downers Grove, IL 60515

Document Control Desk-Licensing  
Commonwealth Edison Company  
1400 Opus Place, Suite 400  
Downers Grove, Illinois 60515

Commonwealth Edison Company  
Reg. Assurance Supervisor - Braidwood  
RR 1, Box 79  
Braceville, Illinois 60407

Commonwealth Edison Company  
Site Vice President - Braidwood  
RR 1, Box 84  
Braceville, IL 60407

Commonwealth Edison Company  
Reg. Assurance Supervisor - Byron  
4450 N. German Church Road  
Byron, Illinois 61010-9794

Mr. David Helwig  
Senior Vice President  
Commonwealth Edison Company  
Executive Towers West III  
1400 Opus Place, Suite 300  
Downers Grove, IL 60515

Mr. Michael J. Wallace  
Senior Vice President  
Commonwealth Edison Company  
Executive Towers West III  
1400 Opus Place, Suite 900  
Downers Grove, IL 60515

Mr. Gene H. Stanley  
PWR's Vice President  
Commonwealth Edison Company  
Executive Towers West III  
1400 Opus Place, Suite 900  
Downers Grove, IL 60515

Mr. Steve Perry  
BWR's Vice President  
Commonwealth Edison Company  
Executive Towers West III  
1400 Opus Place, Suite 900  
Downers Grove, IL 60515

Mr. Dennis Farrar  
Regulatory Services Manager  
Commonwealth Edison Company  
Executive Towers West III  
1400 Opus Place, Suite 500  
Downers Grove, IL 60515

9811170073 981104  
PDR ADDCK 05000454  
PDR

TABLE 3.3-4 (Continued)

ENGINEERED SAFETY FEATURES ACTUATION SYSTEM INSTRUMENTATION TRIP SETPOINTS

<u>FUNCTIONAL UNIT</u>	<u>TRIP SETPOINT</u>	<u>ALLOWABLE VALUE</u>
6. Auxiliary Feedwater (Continued)		
f. Division 11 for Unit 1 (Division 21 for Unit 2) ESF Bus Undervoltage- Start Motor-Driven Pump	2870 volts	2730 volts
g. Auxiliary Feedwater Pump Suction Pressure- Low (Transfer to Essential Service Water)	≥18.1 psia	≥17.4 psia
7. Automatic Opening of Containment Sump Suction Isolation Valves		
a. Automatic Actuation Logic and Actuation Relays	N.A.	N.A.
b. RWST Level-Low-Low Coincident with Safety Injection	46.7%	44.7%
See Item 1. above for Safety Injection Trip Setpoints and Allowable Values.		

## PLANT SYSTEMS

### CONDENSATE STORAGE TANK

#### LIMITING CONDITION FOR OPERATION

---

3.7.1.3 The condensate storage tank (CST) shall be OPERABLE with a contained water level of at least 60%\* (75%\*\*).

APPLICABILITY: MODES 1, 2, and 3.

ACTION:

With the CST inoperable, within 4 hours either:

- a. Restore the CST to OPERABLE status or be in at least HOT STANDBY within the next 6 hours and in HOT SHUTDOWN within the following 6 hours, or
- b. Demonstrate the OPERABILITY of the Essential Service Water System as a backup supply to the auxiliary feedwater pumps and restore the CST to OPERABLE status within 7 days or be in at least HOT STANDBY within the next 6 hours and in HOT SHUTDOWN within the following 6 hours.

#### SURVEILLANCE REQUIREMENTS

---

4.7.1.3.1 The CST shall be demonstrated OPERABLE at least once per 12 hours by verifying the contained water level is within its limits when the tank is the supply source for the auxiliary feedwater pumps.

4.7.1.3.2 The Essential Service Water System shall be demonstrated OPERABLE at least once per 12 hours by performing the surveillance specified in Specification 4.7.4a. whenever the Essential Service Water System is the supply source for the auxiliary feedwater pumps.

\*Applicable to Unit 1 and to Unit 2 after Cycle 7.

\*\*Not applicable to Unit 1. Applicable to Unit 2 through Cycle 7.

PLANT SYSTEMS

CONDENSATE STORAGE TANK

LIMITING CONDITION FOR OPERATION

---

3.7.1.3 The condensate storage tank (CST) shall be OPERABLE with a contained water level of at least 57%\* (66%\*\*) {80%\*\*\*}.

APPLICABILITY: MODES 1, 2, and 3.

ACTION:

With the CST inoperable, within 4 hours either:

- a. Restore the CST to OPERABLE status or be in at least HOT STANDBY within the next 6 hours and in HOT SHUTDOWN within the following 6 hours, or
- b. Demonstrate the OPERABILITY of the Essential Service Water System as a backup supply to the auxiliary feedwater pumps and restore the CST to OPERABLE status within 7 days or be in at least HOT STANDBY within the next 6 hours and in HOT SHUTDOWN within the following 6 hours.

SURVEILLANCE REQUIREMENTS

---

4.7.1.3.1 The CST shall be demonstrated OPERABLE at least once per 12 hours by verifying the contained water level is within its limits when the tank is the supply source for the auxiliary feedwater pumps.

4.7.1.3.2 The Essential Service Water System shall be demonstrated OPERABLE at least once per 12 hours by performing the surveillance specified in Specification 4.7.4a. whenever the Essential Service Water System is the supply source for the auxiliary feedwater pumps.

\*Applicable to Unit 1 after Cycle 8 and to Unit 2 after Cycle 8.

\*\*Applicable to Unit 1 after Cycle 7. Applicable to Unit 2.

\*\*\*Applicable to Unit 1 through Cycle 7. Not applicable to Unit 2.

9811180082 981104  
PDR ADDCK 05000454  
P PDR

## PLANT SYSTEMS

### SURVEILLANCE REQUIREMENTS (Continued)

---

- 3) Verifying a system flow rate of 66,900 cfm  $\pm$  10% through the train and 22,300 cfm  $\pm$  10% per bank through the exhaust filter plenum during operation when tested in accordance with ANSI N510-1980; and
  - 4) Verifying that with the system operating at a flow rate of 66,900 cfm  $\pm$  10% through the train and 22,300 cfm  $\pm$  10% per bank and exhausting through the HEPA filter and charcoal adsorbers, the total bypass flow of the system and the damper leakage is less than or equal to 1% when the system is tested by admitting cold DOP at the system intake and the damper leakage rate is determined by either direct measurements or pressure decay measurements at a test pressure of 2 inches of water and the auxiliary building exhaust fans are operating at their rated flow.
- c. After every 720 hours of charcoal adsorber operation, by verifying, within 31 days after removal, that a laboratory analysis of a representative carbon sample obtained from each bank of adsorbers of the train in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978, when the average for a methyl iodide penetration of less than 1% when tested at a temperature of 30°C and a relative humidity of 70%.
- d. At least once per 18 months by:
- 1) Verifying for each filter bank of the train that the pressure drop across the combined HEPA filters and charcoal adsorber banks of less than 6.0 inches Water Gauge while operating the exhaust filter plenum at a flow rate of 66,900 cfm  $\pm$  10% through the train and 22,300 cfm  $\pm$  10% per bank;
  - 2) Verifying that the exhaust filter plenum starts on manual initiation or Safety Injection test signal; and
  - 3) Verifying that the system maintains the ECCS equipment rooms at a negative pressure of greater than or equal to 1/4 in. Water Gauge relative to the outside atmosphere during system operation while operating at a flow rate of 66,900 cfm  $\pm$  10% through the train and 22,300 cfm  $\pm$  10% per bank.
- e. After each complete or partial replacement of a HEPA filter bank, by verifying that the exhaust filter plenum satisfies the in-place penetration testing acceptance criteria of less than 1% in accordance with ANSI N510-1980 for a DOP test aerosol while operating at a flow rate of 66,900 cfm  $\pm$  10% through the train and 22,300 cfm  $\pm$  10% per bank; and