FRAMATOME ANP

Fuel Performance Meeting - NRC and Framatome ANP

April 9 and 10, 2002



FUEL PERFORMANCE MEETING - APRIL 9 and 10 NRC and FRAMATOME ANP

AGENDA

- •Introduction and Purpose
- •Description of Framatome ANP (Organization, Facilities, and Services
- •Description of Current Fuel Designs and Key Features
 - •PWR
 - •BWR
- •Recent Fuel Performance Experience
- •Corrosion Experience Update
- •Lead Test Assemblies
- •Description of Recent Post-Irradiation Examinations
- •Emerging Issues

Fuel Performance, April 2002, JSH

•Plans for Future Topical Reports



Framatome ANP: 13,000 Employees Worldwide









Framatome ANP in the U.S.





Advanced Mark-B Design Features



Fuel Performance, April 2002, JSH

Mark-B10K/B12

TRAPPER[™] debris filter lower end fitting
Heavy loaded fuel rod (0.430")
M5[™] advanced alloy cladding & guide tubes
Cruciform 6-leaf holddown spring
Optional quick disconnect upper end fitting

Mark-B11

Plug-in-grid debris filter Reduced diameter (0.416") fuel rod M5[™] advanced alloy cladding High thermal margin flow mixing grids Cruciform 6-leaf holddown spring Quick disconnect upper end fitting

M5TM Design Features

Fuel Rods - Spring 2000 Guide Tubes - Fall 2001 Intermediate Grids - 2004





Mark-BW (17x17) Spacer Grid Design



- •High CHF performance
- •Floating intermediate grids
- •Keyed spacer grids

A FRAMATOME ANP

TRAPPER™ Bottom Nozzle



Fuel Performance, April 2002, JSH

> Provides superior debris protection

- No debris failures since introduction for more than 2,000 fuel assemblies
- Pressure drop equivalent to traditional debris filters





High Thermal Performance (HTP) Spacer

> All Zircaloy

Fuel Performance, April 2002, JSH

- > Channels for flow mixing
- > Low flow resistance
- > Optimum rod contacts
- > Robust construction













ATRIUM[™]-10 Fuel Assembly: Advanced Fuel Channel



Fuel Performance, April 2002, JSH







Framatome ANP PWR Fuel Burnup Summary As Of 12/01



Framatome ANP PWR Fuel Burnup Summary As Of 12/01



Framatome ANP PWR Fuel Burnup Summary As Of 12/01



Burnup Distribution of Framatome ANP PWR Fuel (former SPC) (Status 8/2001)



Burnup Distribution of Framatome ANP PWR Fuel with HTP Spacers (Status 8/2001)



Burnup Distribution of Framatome ANP BWR Fuel (Status 8/2001) (U.S. & German)



Burnup Distribution of Framatome ANP BWR ATRIUM[™]-10 Fuel (Status 8/2001) (U.S. & German)



Framatome ANP PWR Fuel Performance Status As Of 3/02



Framatome ANP BWR Fuel Performance Status As Of 3/02





Year Failure ð Rate Manufacture for Mark-B (15x15) Fuel By

Failure Rate for Mark-BW (17x17) Fuel By Year Of Manufacture



Failure Rate for former SPC PWR Fuel (bi-metallic spacers, no HTP failures)





Current PWR Fuel Performance Summary

- > ANO-1, Crystal River-3, Oconee-2
 - Currently Termed "Weak Indications"
- > Davis-Besse

Puel Performance, April 9, 2002, JSH:02:002

- 2nd Cycle Discharged B10 Fuel Assembly
 - Interior rod, possible manufacturing defect, not fretting or debris
- 3rd Cycle Discharged B10 Fuel Assembly
 - Edge rod, confirmed grid fretting
- > Millstone-2, St. Lucie-1
 - Low-power assemblies
 - Experience shows fretting near baffle seam
 - Fuel assemblies do not have HTP spacers



Current BWR Fuel Performance Summary

> Quad Cities

Fuel Performance, April 9, 2002, JSH:02:002

- Confirmed during outage; cause unknown
- Clad cracking observed, but <u>NO</u> large split of the fuel rod [Fe-enhanced liner]
- > LaSalle-1, LaSalle-2
 - 1st-cycle assemblies
 - No root cause as cycles are still operating
 - Design does not have FUELGUARDTM LTP [Fe-enhanced liner]


Improvement actions

- > For PWR fretting-related failures at Millstone-2, St. Lucie-1
 - Batches of HTP introduced when failures recognized
- > For PWR fretting-related failures at Davis-Besse, ANO-1
 - Formed the Fuel Integrity Quality Improvement Team (FIQIT II) to investigate spacer grid fretting failures
 - Review manufacturing and design changes
 - Review production data and processes
 - Recommend future work

Fuel Performance, April 9, 2002, JSH-02:002

- Evaluating integration of HTP grid
- > PCI failure at Kuosheng in previous cycle
 - Modified ramp rate procedures for deconditioned fuel









M5 Cladding (Zr 1.0 Nb) Provides Outstanding Corrosion Performance

- > Low corrosion rate, oxidation kinetic exhibits no acceleration at high burnup.
- > Hydrogen pickup fraction of M5 cladding is low, limiting overall hydrogen pickup.
- > M5 geometric behavior is equal to or improved over Zircaloy-4.
- > M5 has a low sensitivity to reactor duty factors.

Fuel Performance, April 2002, JSH





PWR Hydrogen Performance Of M5™

■M5TM continues to show much lower hydrogen pickup than Zr-4





FRA-ANP Optimized Zircaloy-4

- > Optimized Zircaloy-4 PWR cladding is low-tin high-iron and chromium Zry-4 that is optimized through special processing with respect to corrosion, growth, and mechanical properties
- > Optimized Zircaloy-4 cladding differs from low-Sn Zircaloy-4 cladding and shows better corrosion performance than other low-tin Zircaloy-4 cladding



FRA-ANP Optimized Zircaloy-4

Composition

Sn %	1.2-1.4
Fe %	0.20-0.24
Cr %	0.09-0.13
Si ppm	80-120
ΣA _i =	(15-60) E-18 hrs.

- Annealing parameter
- Fabrication

Evel Performance, April 2002, JSH

- Forge Quench Forge process
- Defined beta quench time and temperature
- Texture control
- High CW final pass



Corrosion of Optimized Zircaloy-4 Cladding in PWR Reactors



BWR Zircaloy 2 - LTP Cladding

 LTP: Low Temperature Process
 Material with an optimized annealing parameter; results in optimal size of Second Phase Particles:

Fuel Performance, April 2002, JSH

- reduction of coarse precipitates reduces nodular corrosion
- avoiding extremely fine precipitates delays accelerated corrosion at high burnup
- LTP tubing (with Liner): optimum PCI resistance due to liner



Corrosion of BWR Fuel Rods with LTP Clad (CWSR) (J.S.) (compared with 9x9)







Objectives

- Confirm operating performance of design features (MSMG's and Quick Disconnect Top Nozzle)
- Provide high/extended burnupp data on M5[™]

■ Scope/Status

Fuel Performance, April 2002, JSH

- 4 LTAs successfully completed 3-18 month cycles of irradiation in North Anna 1 (57 GWd/mtU rod burnup)
- PIE completed January 2002
- Scheduled for re-insertion for a fourth cycle in North Anna 2
- PIE Fall 2004
 - ~73 GWd/mtU fuel rod burnup
- Potential Hot Cell
 - 2003 (3 cycles)
 - 2005-2006 (4 cycles)
- Batch Implementation Spring 2003

A FRAMATOME ANP

50

> Alliance 12-foot – Sequoyah 2

Objectives

- Confirm operating performance of design features
- Additional high burnup data on M5[™]

Scope/Status

Fuel Performance, April 2002, JSH

- 4 LTAs complete 1 cycle of operation in April 2002
 - 20 GWd/mtU fuel assembly burnup
- PIE 2005 (3 cycles) Planned rod burnup of 60 GWd/mtu



> Mark-B11 LTA – Oconee 2

Objectives

• Confirm operating performance of design features

■ Scope/Status

- 4 LTAs Completed 3 cycles of operation
 - 46 GWd/mtu FA burnup
 - Zircaloy material
- Operated on baffle 2nd cycle to confirm FIV performance
- PIE

Fuel Performance, April 2002, JSH

- Performed each cycle
- Last PIE Completed April 2001
- Mark-B11 batches in first cycle of operation at all Oconee plants



52

> M5 High Burnup Fuel Rod – TMI-1

■ Objective

Fuel Performance, April 2002, JSH

Provide extended burnup data on M5[™]

■ Scope/Status

- 4 M5 fuel rods
 - Operated for 3 cycles 48 Gwd/mtU rod burnup
 - Recaged into twice burned fuel assembly
- Planned burnup of 69 GWd/mtU (4 cycles)
- PIE Fall 2003
- Potential Hot Cell 2004-2005 (Fourth Cycle)



> Mark-B10K M5 Structure – Davis-Besse

■ Objective

• Provide high/extended burnup data on design features

■ Scope/Status

- 4 fuel assemblies up to 52 GWd/mtu rod burnup
 - M5 fuel rods and guide tubes
 - Two uppermost intermediate grids with M5
- PIE

Fuel Performance, April 2002, JSH

- Completed March 2002 (1 cycle) 28 GWd/mtU rod burnup
- 2004 (2 cycle)
- Potential 2006 @ +62 Gwd/mtu



VGB Utility Group BWR High Burnup Program

Fuel Performance, April 2002, JSH

Plant	Design	Cladding material	No. of cycles	Rod burnup [MWd/kgU]	No. of (segments)	Main examination
KKP-1	9x9	LTP Fe liner	5	42.2	2 (6)	transient behavior
KKP-1	9x9	LTP Fe liner	8	69.3	2 (6)	transient behavior
KKP-1	10x10	LTP Fe liner	5	57.3	2 (6)	transient behavior shadow corrosion
GUN-B	10x10	LTP Zr liner	8	64.5-73.4	21	fission gas release, shadow corrorosion
KKK	9x9	LTP Zr liner	8	67.3-69.9	2	fuel and cladding behavior



55

FRAMATOME AND

GUN-B High Burnup Program

- > Objective:
 - Burnup 70 MWd/kgU
 - ATRIUMTM-10A design
- > Description:
 - 4.95 % max. U235 enrichment
 - Advanced pellets, cladding and spacer materials
- > Scope:
 - Begin irradiation,
 1999: 8 FA
 2000: 4 FA (large grain fuel)
 - Intermediate pool site examinations after 2, 4, 6 and 7 cycles
 - Final pool site and hot cell examinations after 5 and 8 cycles
- > Status:

Fuel Performance, April 2002, JSH

Intermediate exam performed at 26 GWD/tU









PIE Objectives

- > Continue confirmation of advanced designs and materials
- > Purpose of the latest PIE data is to specifically support:
 - High burnups
 - M5TM
 - Mark-B11 design
 - Advanced Mark-BW design
 - Alliance design



Fuel Performance, April 2002, JSH

Post Irradiation Exams

- > Recently Completed
 - Oconee 2, Cycle 18 B11 LTA
 - TMI-1, Cycle 13 M4/M5TM LTAs
 - North Anna 1, Cycle 15 Mark-BW/X1 LTAs
 - Davis-Besse, Cycle 14 Mark-B10K/B10K Structure Assemblies
- > Upcoming
 - Sequoyah 2, Cycle 11 Alliance LTAs



M5[™] Fuel Rod Growth

> U.S and worldwide M5TM fuel rod growth data are consistent



North Anna Advanced Mark-BW LTAs Continue To Show No Fuel Assembly Growth





Fuel Assembly and Fuel Rod Growth Summary > Fuel Rod Growth Zirc-4 fuel assembly and fuel rod growth supports existing models ■ M5TM fuel rod growth supports existing M5TM model • U.S. data is consistent with worldwide data Rod growth saturates above 40 GWd/mtU > Fuel Assembly Growth ■ Advanced Mark-BW M5TM fuel assembly growth is low ■ Mark-B M5TM fuel assembly growth follows zirc-4 growth for low burnups as expected • M5[™] fuel assembly growth should saturate above 40 GWd/mtU > Fuel Assembly Growth Model ■ UTL - 80% of zirc-4 at 62 GWd/mtU burnup ■ LTL – No fuel assembly growth Alliance LTA data will be incorporated FRAMATOME ANP Fuel Pertormance, April 2002, JSH

PWR Fuel Assembly Growth









Recent US and Important German BWR Exams

- > <u>Reactor</u>
- > TVO-1, Quad Cities
- > Gundremmingen B
- > Susquehanna
- > Dresden

Main evaluation

Failure of Fe-enhanced liner Oxide, growth, hot cell Oxide, growth, creepdown Oxide/CRUD



Post-Irradiation Examination of the First Defective Fuel Rod with Fe-enhanced Zr-Liner Cladding

Reactor

Fuel Assembly Type

Irradiation Time

Burnup

Fuel Performance, April 2002, JSH

Operation with Defect

TVO

ATRIUM[™]-10B

1 Cycle

14 MWd/kgU

<u>></u>9 Month

A FRAMATOME ANP

The Primary Defect has been Caused by Foreign Particle Fretting Below SG 4



Close Look at the Largest Secondary Failure -Open Hydride Blister



Fuel Performance, April 2002, JSH



Cracks Starting at the Hydride Blister Stop Within a Few Millimeters

Fuel Performance, April 2002, JSH





72


Defected Fe-enhanced Liner Clad Behaves the Same as Non-Liner Clad

- > In spite of long-time operation in defect condition the activity release and fuel wash-out were relatively low
- > Secondary defects were limited to local hydride blisters

el Performance, April 2002, JSH

- > No signs of severe secondary degradation such as large cracks and long splits have been observed
- > It is therefore concluded that the Fe-enhanced Liner effectively prevents the development of large axial splits



Dresden Crud/Oxide Measurement

- > 2 Assemblies, 3 cycles to 38 GWD/tU
 - One reference
 - One operated 3rd cycle in NMCA
- > Rods, 12 measured
 - Dual frequency corrosion thickness measurement
 - Crud scrapes
- > Preliminary results

Fuel Performance, April 2002, JSH

- Measurement system appears reliable
- Total thickness increase seen under NMCA



ATRIUM[™] -10 Global Inspection Program

Fuel Performance, April 2002, JSH

<u> </u>	Year	93	94	95	96	97	98	99	00	01	02	03	04
Reactor	FA Type												
GUN-B	10A liner	1	2	3□	4�	5�	5�	6�	7□	8 _ }	H		
	10A non–liner					1∨	2∨	3∨	4	5∨	6□		
KKL	10B liner						1∨	2v	3□	4	5∨	6⊟H	
TVO-1	10B non–liner				1∨	2∨	3□	4					
	10B liner							1∨	2v	Зv	4□	5□	6∨
TVO-2	10B non–liner				1∨	2∨	3□	4					
BRA	10B non-liner					1∨	2	Зv					
OKG–2	10B non–liner							1	2v	3	4	5	
OKG–3	10B non–liner					1	2	Зv	4v		5v		
FMK–1	10B non-liner					1∨	2	3	4				
FMK–3	10B liner							1	2v	3	4□	5	6
RH–1	10B liner							1v	2□	3	4□	5	6
KKP-1	10B/10P liner					1∨	2◇	3◊	4	5 <u></u> H	-		
GUN-C	10–8 liner		1◊	2♦	3□	4�	5◇	6					
∨ Visual	Inspection 🔗 Vi	sual +	Length	I		🗆 Vis	sual, Le	enght, F	R Oxid	le+Dia	m. (out	ter row)	
Visual. I	Length, FR Oxide+Dia	am., W	C Oxide	e+Dime	ensions				H Hot	<u>t Cell E</u>	xamina	ation	
Prelimi	inary Examina	atior	n Scł	nedu	le								
	-											A	

FRAMATOME AND



ATRIUM[™] -10 Fuel Assemblies in GUN-B

- > First time a BWR assembly reached 71 MWd/kgU with maximum rod burnup of 73.4 MWd/kgU.
- > The fuel assemblies, fuel rods and channels showed good behavior.
- > Fuel channels made of Zry-4 show a corrosion acceleration at high burnup.
- > Detailed hot cell examination will be performed in addition to the final pool examination.



ATRIUM[™] -10 Fuel Assembly Growth (German Region)



ATRIUM[™] -10 Assembly Growth (U.S. Region Data) (Comparison with Fuel Channel Growth)



Description of Defects in the Fuel Rod with Fe-enhanced Zr-Liner

Fuel Performance, April 2002, JSH

- > Small primary defect caused by fretting of foreign particle at spacer grid 4
- > One larger secondary defect, an open hydride blister about 100 mm above spacer grid 1
- > Additional small hydride blisters were observed above spacer grids 3 and 6







Long Term PIE Goals

- > Continued confirmation of existing and advanced designs
- > Provide data to validate new designs to burnups above current levels
- > Proactive response to provide information to support future robust fuel data needs
 - Selective assemblies for 3rd and 4th cycle burnups > 65 GWd/mtU
 - Selective reconstitution of M5TM fuel rods to reach rod burnups of 70-75 GWd/mtU





Challenges to BWR Hardware Design

- > Elimination of fuel failures
 - Continue to identify root causes, make change as appropriate
- > Increased Cycle Length
 - Continue monitoring fuel behavior
- > Coolant Chemistry

uel Perjormance, April 2002, JSH

- Currently working with customers
 - Improved fuel corrosion and crud measurement
 - Balance ALARA, plant and fuel requirements





Challenges to BWR Core Design Management

> Plant Uprates in Combination with 2 Year Cycles

- Development of improved fuel performance analysis
 - Statistical approach
- Development of improved bundle CHF performance
 - Design improvements



Challenges to PWR Hardware Design

- > Elimination of fuel failures
 - Continue to identify root causes, make change as appropriate
- > Resistance to Axial Offset Anomalies (AOA) & Distinctive Crud Pattern (DCP)
 - Issue of crud minimize boron concentration and power peaking
- > Reduction in fuel assembly distortion
 - Design and core management issue
- > Increase fuel component dimensional stability
 - Minimize growth of structural components [M5TM]
- > Decrease fuel component corrosion and hydrogen pickup
 - M5TM material has low H pickup



Challenges to PWR Core Design Management

- > Extended length cycles
- > Power level uprates

Fuel Performance, April 2002, JSH

- > Increased discharge burnups
- > Very low leakage fuel management
 - Increased boron concentrations lead to crud, AOA issues
 - High power, long residence time encourages assembly distortion
 - Fresh-to-fresh interface increases likelihood of high power peaking, crud deposition, and boiling
 - Fewer fresh assemblies leads to increased power peaking



Incomplete Rod Insertion Update

- > TMI-1 cycle 13 operated successfully
 - All control rods well within tech specs
 - LER Supplement Report submitted to NRC by utility
 - Corrective actions proved successful
 - Reduction in holddown loads by spring set
 - Cycle design improvements to remove same quadrant core shuffle
 - New fuel design improvements for cycle 14 implemented
 - 6 leaf holddown spring

uel Performance, April 2002, JSh

• Lower growth M5 fuel rods and guide tubes



Incomplete Rod Insertion Update



Latest Mark-B Plant Outages Since July 200

- > 24 month cycle plants
 - TMI-1 Cycle 13
 - Crystal River 3 Cycle 12
 - Davis-Besse Cycle 13
- > 18 month cycle plants
 - ANO-1 Cycle 16
 - Oconee 1 Cycle 19
 - Oconee 2 Cycle 18
 - Oconee 3 Cycle 19

Performance, April 2002, JSH

> All control rods met tech specs



Latest Mark-BW Plant Outages Since July 2000

- > 18 month cycle plants with outages
 - Sequoyah 1 Cycle 11
 - Sequoyah 2 Cycle 10
 - McGuire 1 Cycle 14
 - McGuire 2 Cycle 13
 - Catawba 1 Cycle 12

uel Performance, April 2002, JSH

> All control rods met tech specs



PWR METHODOLOGY VISION

B&W PLANTS

<u>Methodology</u>	<u>Topical Report</u>	<u>Schedule</u>
Neutronics	BAW-10180(A), NEMO Neutronics Code	Approved
News considered as a set of a general set of the set of	BAW-10156(P)(A), LYNXT Core Transient	
Thermal-Hydraulic	Thermal-Hydraulic Code	Approved
-	BAW-10143(P)(A), DNB Correlations for Mark-B	
DNB	designs	Approved
	BAW-X, DNBR Correlation for HTP Correlation in	
DNB	LYNXT	mid-2003
	BAW-10187(P)(A), Statistical Core Design	
Statistical Core Design	Process	Approved
	BAW-10193(P)(A), RELAP5/Mod2-B&W Safety	
Non-LOCA	Analyses	Approved
	BAW-10192(P)(A), Large and Small Break LOCA	
LOCA	Evaluation Model	Approved
	BAW-X, Modifications to LOCA Methodology for	
LOCA	HTP Spacer (if required)	mid-2003
	BAW-10179(P)(A), Safety Criteria and	
	Methodology for Acceptable Cycle Reload	
Design	Analyses	Approved
Design	BAW-10227(P)(A), M5 Cladding	Approved
	BAW-10231(P) COPERNIC Fuel Performance	
Fuel Performance	Code	Under Review





PWR METHODOLOGY VISION

WESTINGHOUSE and COMBUSTION ENGINEERING PLANTS

Fuel Performance

<u>Methodology</u>	Topical Report	Schedule
	EMF-96-029(P)(A) PWR Neutronics Methodology	······································
Neutronics	using SAV95	Approved
	XN-NF-82-21(P)(A), Thermal-Hydraulic and	··········
Thermal-Hydraulic	Mixed Core Analysis	Approved
	EMF-92-153(P)(A), DNBR Correlation for HTP	······································
DNB	Spacer	Approved
	BAW-X, DNBR Correlation for Mark-BW spacer	
DNB	in XCOBRA-IIIC	Nov-02
	EMF-92-081(P)(A), Statistical Setpoint/Transient	· · · · · · · · · · · · · · · · · · ·
Setpoint	Methodology for Westinghouse Type Reactors	Approved
	EMF-1961(P)(A), Statistical Setpoint/Transient	· · · · · · · · · · · · · · · · · · ·
Setpoint	Methodology for CE Type Reactors	Approved
	EMF-2310(P)(A), Non-LOCA Methodology using	
Non-LOCA	S-RELAP5	Approved
Non-LOCA	BAW-X, Coupled Neutronics/System/TH Code	Future Submittal
	EMF-2103(P), Realistic LBLOCA Methodology	
LBLOCA - Realistic	using S-RELAP5	Under Review
SBLOCA - Appendix K	EMF-2328(P)(A), SBLOCA Methodology using S- RELAP5	Approved
	EMF-92-116(P)(A), Generic Mechanical Design	
Design	Criteria	Approved
Design	BAW-10227(P)(A), M5 Cladding	Approved
	BAW-X, M5 Cladding for RODEX2 and S-	
Design	RELAP5 Methodologies	Oct-02
	BAW-10186(P), Extended burnup for M5	
Design	Cladding (62 GWd/MTU)	Under Review
Fuel Performance	BAW-10231 COPERNIC fuel performance code	Under Review

FRAMATOME ANP

BWR METHODOLOGY VISION

<u>Methodology</u>	Topical Report	<u>Schedule</u>	
Neutronics	EMF-2158(P)(A), CASMO4/MICROBURN-B2	Approved	
Thermal-Hydraulic			
CHF	EMF-2209(P)(A), SPCB Correlation for ATRIUM-10	Approved	
CHF	BAW-X, CHF Correlation for Advanced BWR Spacer Spacer	Future Submittal	
Stability	EMF-CC-074(P)(A), STAIF Code for Stability Analysis	Approved	
Safety Limit	XN-NF-80-19(P)(A) Vol 3, Safety Limit Methodology	Approved	
Non-LOCA	BAW-X, S-RELAP5 for BWR Non-LOCA Transients	end of 2004	
LOCA	EMF-2361(P)(A), EXEM BWR-2000 Evaluation Model	Approved	
LOCA	BAW-X, S-RELAP5 for BWR LOCA	Future Submittal	
	ANF-89-98(P)(A), Generic Mechanical Design Criteria	anna a f a na a statu a ta t	
Design	for BWR Fuel Designs	Approved	
Fuel Performance	BAW-X, RODEX4 and Statistical Design Methodology	Dec-02	

Fuel Performance, April 2002, JSH



TOPICAL REPORT SUBMITTALS

B&W Methodology BAW-X, DNBR Correlation for HTP Correlation in DNB LYNXT BAW-X, Modifications to LOCA Methodology for HTP LOCA Spacer (if required) w & CE Methodology EMF-2310 Revision 1, S-RELAP5 for PWR Non-LOCA Non-LOCA modified Boron Dilution Methodology, MOX BAW-10238, MOX Fuel Design MOX BAW-10238, MOX Fuel Design MOX BAW-10238, MOX Fuel Design MOX BAW-3023(P) COPERNIC for MOX Under Review MOX BAW-3023(P) COPERNIC for MOX Under Review MOX BAW-3023(P) COPERNIC for MOX Under Review MOX BAW-3023(P) COPERNIC for MOX Non-LOCA BAW-3023(P) COPERNIC for MOX Under Review BAW-3023(P) COPERNIC for MOX BAW-3023(P) COPERNIC for MOX Under Review BAW-10231(P) COPERNIC for MOX Under Review BAW-3029, Advanced Mark-BW Design Apr-02 Design BAW-10239, Advanced Mark-BW Design Apr-02 Design BAW-10186 Revision 1 Supplement 1, M5 Extended Design Apr-02 BAW-30186 Revision	<u>Methodology</u>	<u>Topical Report</u>	<u>Schedule</u>
BAW Methodology BAW-X, DNBR Correlation for HTP Correlation in DNB LYNXT mid-2003 BAW-X, Modifications to LOCA Methodology for HTP mid-2003 LOCA Spacer (if required) mid-2003 W & CE Methodology mid-2003 W & CE Methodology EMF-2310 Revision 1, S-RELAP5 for PWR Non-LOCA Non-LOCA modified Boron Dilution Methodology, Apr-02 MOX BAW-10238, MOX Fuel Design Apr-02 MOX BAW-10238, MOX Fuel Design Apr-02 MOX BAW-10238, MOX Fuel Design Apr-02 MOX BAW-3X, Modifications to LOCA Methodology for MOX Future Submitta Non-LOCA BAW-3X, Coupled Neutronics/System/TH Code Future Submitta DNB XCOBRA-IIIC Nov-02 LBLOCA - Realistic S-RELAP5 Under Review BAW-3X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design BAW-10239, Advanced Mark-BW Design Apr-02 BAW-10186 Revision 1 Supplement 1, M5 Extended Design BAW-30239, Advanced Mark-BW Design Apr-02 Design BAW-10231(P) COPERNIC for UO2 Under Review BAW-3239, Advanced Mark-BW Design Apr-02 <td></td> <td></td> <td></td>			
BAW-X, DNBR Correlation for HTP Correlation in mid-2003 BAW-X, Modifications to LOCA Methodology for HTP mid-2003 LOCA Spacer (if required) mid-2003 W & CE Methodology mid-2003 EMF-2310 Revision 1, S-RELAP5 for PWR Non-LOCA Mon-LOCA Non-LOCA modified Boron Dilution Methodology, Apr-02 MOX BAW-10238, MOX Fuel Design Apr-02 MOX BAW-X, Modifications to LOCA Methodology for MOX Future Submitta Non-LOCA BAW-X, Coupled Neutronics/System/TH Code Future Submitta Non-LOCA BAW-X, DNBR Correlation for Mark-BW Spacer in Nov-02 DNB XCOBRA-IIIC Nov-02 EMF-2103(P), Realistic LBLOCA Methodology using LBLOCA - Realistic S-RELAP5 Design Methodologies Oct-02 Design BAW-10239, Advanced Mark-BW Design Apr-02 BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design BAW-10231(P) COPERNIC for UO2 Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design BAW-X, S-RELAP5 for BWR Non-LOCA Transients	e programme de la constance de	B&W Methodology	
DNB LYNXT mid-2003 BAW-X, Modifications to LOCA Methodology for HTP mid-2003 LOCA Spacer (if required) mid-2003 W & CE Methodology EMF-2310 Revision 1, S-RELAP5 for PWR Non-LOCA Apr-02 Non-LOCA modified Boron Dilution Methodology, MOX Apr-02 MOX BAW-10238, MOX Fuel Design Apr-02 MOX BAW-1023(P) COPERNIC for MOX Under Review MOX BAW-X, Coupled Neutronics/System/TH Code Future Submitta Non-LOCA BAW-X, Coupled Neutronics/System/TH Code Future Submitta NOX BAW-X, Coupled Neutronics/System/TH Code Future Submitta DNB XCOBRA-IIIC Nov-02 EMF-2103(P), Realistic LBLOCA Methodology using LBLOCA - Realistic S-RELAP5 Design Methodologies Oct-02 Design BAW-10236 (PACM/TU Under Review BAW-10186 Revision 1 Supplement 1, M5 Extended Design Apr-02 Design Methodologies Oct-02 Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Under Review BAW-1023 (P) COPERNIC for UO2 Under Review BAW-31023		BAW-X, DNBR Correlation for HTP Correlation in	
BAW-X, Modifications to LOCA Methodology for HTP LOCA Spacer (if required) w & CE Methodology EMF-2310 Revision 1, S-RELAP5 for PWR Non-LOCA Non-LOCA modified Boron Dilution Methodology, MOX BAW-10238, MOX Fuel Design MOX BAW-10231(P) COPERNIC for MOX MOX BAW-X, Modifications to LOCA Methodology for MOX MOX BAW-X, Modifications to LOCA Methodology for MOX Non-LOCA BAW-X, Modifications to LOCA Methodology for MOX Non-LOCA BAW-X, Coupled Neutronics/System/TH Code Future Submitta BAW-X, Modifications to LOCA Methodology using LBLOCA - Realistic S-RELAP5 DNB XCOBRA-IIIC Nov-02 EMF-2103(P), Realistic LBLOCA Methodology using LBLOCA - Realistic S-RELAP5 Design Methodologies Design BAW-10239, Advanced Mark-BW Design BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Design BAW-X M5 Cladding for RODEX2 and S-RELAP5 Design BAW-X M5 Cladding for RODEX2 and S-RELAP5 Design Methodologies Oct-02 Under Review BAW-X M5 Cladding for RODEX2 and S-RELAP5	· DNB	LYNXT	mid-2003
LOCA Spacer (if required) mid-2003 W & CE Methodology EMF-2310 Revision 1, S-RELAP5 for PWR Non-LOCA Non-LOCA modified Boron Dilution Methodology, Apr-02 MOX BAW-10238, MOX Fuel Design Apr-02 MOX BAW-10231(P) COPERNIC for MOX Under Review MOX BAW-X, Coupled Neutronics/System/TH Code Future Submitta Non-LOCA BAW-X, Coupled Neutronics/System/TH Code Future Submitta Non-LOCA BAW-X, Modifications to LOCA Methodology for MOX Future Submitta Non-LOCA BAW-X, Coupled Neutronics/System/TH Code Future Submitta DNB XCOBRA-IIIC Nov-02 EMF-2103(P), Realistic LBLOCA Methodology using Under Review LBLOCA - Realistic S-RELAP5 Under Review BAW-X0239, Advanced Mark-BW Design Apr-02 Design Methodologies Oct-02 Design Apr-02 BAW-10186 Revision 1 Supplement 1, M5 Extended Design BAW-10231(P) COPERNIC for UO2 Under Review BAW-30168 Revision 1 Supplement 1, M5 Extended Design Methodologies Oct-02 Loca BAW-10231(P) COPERNIC for UO2 Under Review DAW-X, MS Cladding for RODEX2 and		BAW-X, Modifications to LOCA Methodology for HTP	
W & CE Methodology EMF-2310 Revision 1, S-RELAP5 for PWR Non-LOCA Non-LOCA modified Boron Dilution Methodology, Apr-02 MOX BAW-10238, MOX Fuel Design Apr-02 MOX BAW-10231(P) COPERNIC for MOX Under Review MOX BAW-X, Modifications to LOCA Methodology for MOX Future Submitta Non-LOCA BAW-X, Modifications to LOCA Methodology for MOX Future Submitta Non-LOCA BAW-X, Coupled Neutronics/System/TH Code Future Submitta Non-LOCA BAW-X, DNBR Correlation for Mark-BW Spacer in Nov-02 EMF-2103(P), Realistic LBLOCA Methodology using LBLOCA - Realistic S-RELAP5 Design Methodologies Oct-02 Design BAW-10239, Advanced Mark-BW Design Apr-02 BAW-10186 Revision 1 Supplement 1, M5 Extended Design BaW-3023, Advanced Mark-BW Design Apr-02 Design Bumup to 62 GWd/MTU Under Review BAW-3, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design Methodologies Oct-02 Under Review Design Apr-02 Design Burburb to 62 GWd/MTU Under Review Design Apr-02 EMEN-30231(P) COPERNIC for	LOCA	Spacer (if required)	mid-2003
EMF-2310 Revision 1, S-RELAP5 for PWR Non-LOCA modified Boron Dilution Methodology, MOXApr-02 Apr-02MOXBAW-10238, MOX Fuel DesignApr-02MOXBAW-10231(P) COPERNIC for MOXUnder ReviewMOXBAW-X, Modifications to LOCA Methodology for MOXFuture SubmitteNon-LOCABAW-X, Coupled Neutronics/System/TH CodeFuture SubmitteDNBXCOBRA-IIICNov-02EMF-2103(P), Realistic LBLOCA Methodology usingLBLOCA - RealisticS-RELAP5DesignMethodologiesOct-02DesignBAW-X, M5 Cladding for RODEX2 and S-RELAP5Oct-02DesignBAW-10239, Advanced Mark-BW DesignApr-02BAW-X, M5 Cladding for RODEX2 and S-RELAP5DesignOct-02DesignBAW-10231(P) COPERNIC for UO2Under ReviewBAW-X, M5 Cladding for RODEX2 and S-RELAP5Oct-02DesignBAW-10231(P) COPERNIC for UO2Under ReviewBAW-X M5 Cladding for RODEX2 and S-RELAP5Oct-02DesignMethodologiesOct-02Under ReviewBAW-X, M5 Cladding for RODEX2 and S-RELAP5DesignMethodologiesOct-02Under ReviewBAW-X, S-RELAP5 for BWR Non-LCCA Transientsend of 2004LOCABAW-X, S-RELAP5 for BWR Non-LCCAFuture SubmittaNon-LOCABAW-X, S-RELAP5 for BWR LOCAFuture SubmittaNon-LOCABAW-X, RODEX4 and Statistical Design MethodologyDec-02		W & CE Methodology	
Non-LOCAmodified Boron Dilution Methodology, BAW-10238, MOX Fuel DesignApr-02 Apr-02MOXBAW-10231(P) COPERNIC for MOXUnder ReviewMOXBAW-X, Modifications to LOCA Methodology for MOXFuture Submitte Future SubmitteNon-LOCABAW-X, Coupled Neutronics/System/TH CodeFuture Submitte Future SubmitteDNBXCOBRA-IIICNov-02EMF-2103(P), Realistic LBLOCA Methodology using LBLOCA - RealisticS-RELAP5Under ReviewDesignMethodologiesOct-02DesignBAW-X, M5 Cladding for RODEX2 and S-RELAP5Oct-02DesignBAW-10239, Advanced Mark-BW DesignApr-02Baw-X, M5 Cladding for RODEX2 and S-RELAP5Under ReviewDesignBAW-10186 Revision 1 Supplement 1, M5 ExtendedUnder ReviewBaw-X, M5 Cladding for RODEX2 and S-RELAP5Oct-02DesignMethodologiesOct-02Under ReviewBAW-X, M5 Cladding for RODEX2 and S-RELAP5DesignMethodologiesOct-02Under ReviewBAW-X, M5 Cladding for RODEX2 and S-RELAP5DesignMethodologiesOct-02Under ReviewBAW-X, SC131(P) COPERNIC for UO2Under ReviewMCHBAW-X, CHF Correlation for Advanced BWR SpacerFuture SubmittaNon-LOCABAW-X, S-RELAP5 for BWR Non-LOCAFuture SubmittaNon-LOCABAW-X, S-RELAP5 for BWR Non-LOCAFuture SubmittaFuel PerformanceBAW-X, RODEX4 and Statistical Design MethodologyDec-02	y construction of second se	EMF-2310 Revision 1, S-RELAP5 for PWR Non-LOCA	
MOX BAW-10238, MOX Fuel Design Apr-02 MOX BAW-10231(P) COPERNIC for MOX Under Review MOX BAW-X, Modifications to LOCA Methodology for MOX Future Submitta Non-LOCA BAW-X, Coupled Neutronics/System/TH Code Future Submitta DNB XCOBRA-IIIC Nov-02 EMF-2103(P), Realistic LBLOCA Methodology using Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Under Review BAW-10239, Advanced Mark-BW Design Apr-02 Design BAW-10239, Advanced Mark-BW Design Apr-02 Design BAW-10239, Advanced Mark-BW Design Apr-02 Design BAW-10186 Revision 1 Supplement 1, M5 Extended Under Review BAW-10186 Revision 1 Supplement 1, M5 Extended Under Review BAW-10231(P) COPERNIC for UO2 Under Review BAW-10231(P) COPERNIC for UO2 Under Review BAW-10231(P) COPERNIC for UO2 Under Review BAW-3000gies Oct-02 Under Review BAW-10231(P) COPERNIC for UO2 Under Review BAW-10231(P) COPERNIC for UO2 Under Review BAW-3 S-RELAP5 for BWR Non-LOCA Transients end of 2004 Non-	Non-LOCA	modified Boron Dilution Methodology,	Apr-02
MOX BAW-10231(P) COPERNIC for MOX Under Review MOX BAW-X, Modifications to LOCA Methodology for MOX Future Submitta Non-LOCA BAW-X, Coupled Neutronics/System/TH Code Future Submitta DNB XCOBRA-IIIC Nov-02 EMF-2103(P), Realistic LBLOCA Methodology using Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Under Review BAW-10239, Advanced Mark-BW Design Apr-02 Design BAW-10239, Advanced Mark-BW Design Apr-02 Baw-10239, Advanced Mark-BW Design Apr-02 BAW-10186 Revision 1 Supplement 1, M5 Extended Design BAW-10186 Revision 1 Supplement 1, M5 Extended Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design BAW-10239, Advanced Mark-BW Design Apr-02 Baw-10231(P) COPERNIC for UO2 Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design Methodologies Oct-02 Baw-10231(P) COPERNIC for UO2 Under Review BAW-10231(P) COPERNIC for UO2 Under Review BAW-X, S-RELAP5 for BWR Non-LOCA Transients end of 2004 Non-LOCA BAW-X, S-RELAP5 for BWR LOCA <td< td=""><td>MOX</td><td>BAW-10238, MOX Fuel Design</td><td>Apr-02</td></td<>	MOX	BAW-10238, MOX Fuel Design	Apr-02
MOX BAW-X, Modifications to LOCA Methodology for MOX Future Submitta Non-LOCA BAW-X, Coupled Neutronics/System/TH Code Future Submitta DNB XCOBRA-IIIC Nov-02 EMF-2103(P), Realistic LBLOCA Methodology using Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Under Review Design Methodologies Oct-02 Design BAW-10239, Advanced Mark-BW Design Apr-02 BAW-10186 Revision 1 Supplement 1, M5 Extended Burnup to 62 GWd/MTU Under Review Design Burnup to 62 GWd/MTU Under Review BAW-X, CHF Correlation for Advanced BWR Spacer Oct-02 Under Review BAW-X, S-RELAP5 for BWR Non-LOCA Transients end of 2004 LOCA Burnup to 62 GWd/MTU Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design Burnup to 62 GWd/MTU Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 CHF BAW-X, SCladding for RODEX2 and S-RELAP5 Oct-02 Under Review BAW-X, SCladding for RODEX2 and S-RELAP5 Oct-02 Under Review BAW-X, SCladding for RODEX2 and S-RELAP5 Oct-02 Under Review <	MOX	BAW-10231(P) COPERNIC for MOX	Under Review
Non-LOCABAW-X, Coupled Neutronics/System/TH CodeFuture SubmittsDNBXCOBRA-IIICNov-02EMF-2103(P), Realistic LBLOCA Methodology using S-RELAP5Under ReviewDesignMethodologiesOct-02DesignBAW-10239, Advanced Mark-BW DesignApr-02BAW-10186 Revision 1 Supplement 1, M5 ExtendedDesignBAW-X, M5 Cladding for RODEX2 and S-RELAP5DesignBAW-10186 Revision 1 Supplement 1, M5 ExtendedUnder ReviewBAW-X, M5 Cladding for RODEX2 and S-RELAP5Oct-02DesignBAW-10186 Revision 1 Supplement 1, M5 ExtendedUnder ReviewDesignBurnup to 62 GWd/MTUUnder ReviewBAW-X, M5 Cladding for RODEX2 and S-RELAP5Oct-02DesignBurnup to 62 GWd/MTUUnder ReviewBAW-X, M5 Cladding for RODEX2 and S-RELAP5Oct-02DesignBaW-X, CIF Correlation for Advanced BWR SpacerFuture SubmittaNon-LOCABAW-X, S-RELAP5 for BWR Non-LOCA Transientsend of 2004LOCABAW-X, S-RELAP5 for BWR LOCAFuture SubmittaFuel PerformanceBAW-X, RODEX4 and Statistical Design MethodologyDec-02	MOX ·	BAW-X, Modifications to LOCA Methodology for MOX	Future Submittal
BAW-X, DNBR Correlation for Mark-BW Spacer in Nov-02 DNB XCOBRA-IIIC Nov-02 EMF-2103(P), Realistic LBLOCA Methodology using Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Under Review Design Methodologies Oct-02 Design BAW-10239, Advanced Mark-BW Design Apr-02 BaW-10186 Revision 1 Supplement 1, M5 Extended Burnup to 62 GWd/MTU Under Review Design BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Design Apr-02 Baw-10186 Revision 1 Supplement 1, M5 Extended Burnup to 62 GWd/MTU Under Review Design Methodologies Oct-02 Under Review BaW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Under Review Design Methodologies Oct-02 Under Review Gestign Methodology Ct-02 Under Review Fuel Performance BAW-X, CHF Correlation for Advanced BWR Spacer Future Submitta Non-LOCA BAW-X, S-RELAP5 for BWR Non-LOCA Transients end of 2004 LOCA BAW-X, S-RELAP5 for BWR LOCA Future Submitta	Non-LOCA	BAW-X, Coupled Neutronics/System/TH Code	Future Submittal
DNBXCOBRA-IIICNov-02LBLOCA - RealisticEMF-2103(P), Realistic LBLOCA Methodology using S-RELAP5Under ReviewDesignBAW-X, M5 Cladding for RODEX2 and S-RELAP5Oct-02DesignBAW-10239, Advanced Mark-BW DesignApr-02DesignBAW-10186 Revision 1 Supplement 1, M5 Extended Burrup to 62 GWd/MTUUnder ReviewDesignBAW-X, M5 Cladding for RODEX2 and S-RELAP5Oct-02DesignBAW-10186 Revision 1 Supplement 1, M5 Extended Burrup to 62 GWd/MTUUnder ReviewDesignBAW-X, M5 Cladding for RODEX2 and S-RELAP5Oct-02Under ReviewBAW-10231(P) COPERNIC for UO2Under ReviewEWR MethodologyCt-02Under ReviewCHFBAW-X, CHF Correlation for Advanced BWR SpacerFuture SubmittaNon-LOCABAW-X, S-RELAP5 for BWR Non-LOCA Transientsend of 2004LOCABAW-X, S-RELAP5 for BWR LOCAFuture SubmittaFuel PerformanceBAW-X, RODEX4 and Statistical Design MethodologyDec-02	Sannya pangangan kanya kany	BAW-X, DNBR Correlation for Mark-BW Spacer in	ar i shifi a chara anna anna a aranna shanna a anna a sh
EMF-2103(P), Realistic LBLOCA Methodology using Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design Methodologies Oct-02 Design BAW-10239, Advanced Mark-BW Design Apr-02 BAW-10186 Revision 1 Supplement 1, M5 Extended Design Under Review BAW-10186 Revision 1 Supplement 1, M5 Extended Design Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Under Review Design BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design Methodologies Oct-02 Fuel Performance BAW-10231(P) COPERNIC for UO2 Under Review BAW-X, CHF Correlation for Advanced BWR Spacer Future Submitta Non-LOCA BAW-X, S-RELAP5 for BWR Non-LOCA Transients end of 2004 LOCA BAW-X, RODEX4 and Statistical Design Methodology Dec-02	DNB	XCOBRA-IIIC	Nov-02
LBLOCA - Realistic S-RELAP5 Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design Methodologies Oct-02 Design BAW-10239, Advanced Mark-BW Design Apr-02 BAW-10186 Revision 1 Supplement 1, M5 Extended Under Review Design Burnup to 62 GWd/MTU Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design Methodologies Oct-02 Busing Methodologies Oct-02 Verify BAW-10231(P) COPERNIC for UO2 Under Review BWR Methodology Oct-02 Under Review CHF BAW-X, CHF Correlation for Advanced BWR Spacer Future Submitta Non-LOCA BAW-X, S-RELAP5 for BWR Non-LOCA Transients end of 2004 LOCA BAW-X, RODEX4 and Statistical Design Methodology Dec-02		EMF-2103(P), Realistic LBLOCA Methodology using	an i sudul dun ton salad di mana mana a dan da
BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design BAW-10239, Advanced Mark-BW Design Apr-02 BAW-10186 Revision 1 Supplement 1, M5 Extended Baw-10186 Revision 1 Supplement 1, M5 Extended Design Bumup to 62 GWd/MTU Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Oct-02 Design Methodologies Oct-02 Besign Methodologies Oct-02 Under Review BAW-10231(P) COPERNIC for UO2 Under Review BWR Methodology Under Review CHF BAW-X, CHF Correlation for Advanced BWR Spacer Future Submitta Non-LOCA BAW-X, S-RELAP5 for BWR Non-LOCA Transients end of 2004 LOCA BAW-X, S-RELAP5 for BWR LOCA Future Submitta Fuel Performance BAW-X, RODEX4 and Statistical Design Methodology Dec-02	LBLOCA - Realistic	S-RELAP5	Under Review
DesignMethodologiesOct-02DesignBAW-10239, Advanced Mark-BW DesignApr-02BAW-10186 Revision 1 Supplement 1, M5 ExtendedBurnup to 62 GWd/MTUUnder ReviewDesignBAW-X, M5 Cladding for RODEX2 and S-RELAP5Oct-02DesignMethodologiesOct-02Fuel PerformanceBAW-10231(P) COPERNIC for UO2Under ReviewBWR MethodologyEWR MethodologyCHFNon-LOCABAW-X, CHF Correlation for Advanced BWR SpacerFuture SubmittaNon-LOCABAW-X, S-RELAP5 for BWR Non-LOCA Transientsend of 2004LOCABAW-X, RODEX4 and Statistical Design MethodologyDec-02		BAW-X, M5 Cladding for RODEX2 and S-RELAP5	nanan kara mana mana kara kara kara kara kara kara kara k
DesignBAW-10239, Advanced Mark-BW DesignApr-02BAW-10186 Revision 1 Supplement 1, M5 ExtendedBurnup to 62 GWd/MTUUnder ReviewDesignBAW-X, M5 Cladding for RODEX2 and S-RELAP5Oct-02DesignMethodologiesOct-02Fuel PerformanceBAW-10231(P) COPERNIC for UO2Under ReviewBWR MethodologyBWR MethodologyUnder ReviewCHFBAW-X, CHF Correlation for Advanced BWR SpacerFuture SubmittaNon-LOCABAW-X, S-RELAP5 for BWR Non-LOCA Transientsend of 2004LOCABAW-X, S-RELAP5 for BWR LOCAFuture SubmittaFuel PerformanceBAW-X, RODEX4 and Statistical Design MethodologyDec-02	Design	Methodologies	Oct-02
BAW-10186 Revision 1 Supplement 1, M5 Extended Under Review Design BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Under Review Design Methodologies Oct-02 Fuel Performance BAW-10231(P) COPERNIC for UO2 Under Review BWR Methodology Under Review CHF BAW-X, CHF Correlation for Advanced BWR Spacer Future Submitta Non-LOCA BAW-X, S-RELAP5 for BWR Non-LOCA Transients end of 2004 LOCA BAW-X, S-RELAP5 for BWR LOCA Future Submitta Fuel Performance BAW-X, RODEX4 and Statistical Design Methodology Dec-02	Design	BAW-10239, Advanced Mark-BW Design	Apr-02
Design Bumup to 62 GWd/MTU Under Review BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Design Oct-02 Design Methodologies Oct-02 Fuel Performance BAW-10231(P) COPERNIC for UO2 Under Review BWR Methodology Employ and the second se		BAW-10186 Revision 1 Supplement 1, M5 Extended	
BAW-X, M5 Cladding for RODEX2 and S-RELAP5 Design Methodologies Oct-02 Fuel Performance BAW-10231(P) COPERNIC for UO2 Under Review BWR Methodology Empty comparison Empty comparison CHF BAW-X, CHF Correlation for Advanced BWR Spacer Future Submitta Non-LOCA BAW-X, S-RELAP5 for BWR Non-LOCA Transients end of 2004 LOCA BAW-X, S-RELAP5 for BWR LOCA Future Submitta Fuel Performance BAW-X, RODEX4 and Statistical Design Methodology Dec-02	Design	Bumup to 62 GWd/MTU	Under Review
Design Methodologies Oct-02 Fuel Performance BAW-10231(P) COPERNIC for UO2 Under Review BWR Methodology BWR Methodology Under Review CHF BAW-X, CHF Correlation for Advanced BWR Spacer Future Submitta Non-LOCA BAW-X, S-RELAP5 for BWR Non-LOCA Transients end of 2004 LOCA BAW-X, S-RELAP5 for BWR LOCA Future Submitta Fuel Performance BAW-X, RODEX4 and Statistical Design Methodology Dec-02		BAW-X, M5 Cladding for RODEX2 and S-RELAP5	
Fuel Performance BAW-10231(P) COPERNIC for UO2 Under Review BWR Methodology BWR Methodology Euler Submitta CHF BAW-X, CHF Correlation for Advanced BWR Spacer Future Submitta Non-LOCA BAW-X, S-RELAP5 for BWR Non-LOCA Transients end of 2004 LOCA BAW-X, S-RELAP5 for BWR LOCA Future Submitta Fuel Performance BAW-X, RODEX4 and Statistical Design Methodology Dec-02	Design	Methodologies	Oct-02
BWR MethodologyFuture SubmittalCHFBAW-X, CHF Correlation for Advanced BWR SpacerFuture SubmittalNon-LOCABAW-X, S-RELAP5 for BWR Non-LOCA Transientsend of 2004LOCABAW-X, S-RELAP5 for BWR LOCAFuture SubmittalFuel PerformanceBAW-X, RODEX4 and Statistical Design MethodologyDec-02	Fuel Performance	BAW-10231(P) COPERNIC for UO2	Under Review
CHFBAW-X, CHF Correlation for Advanced BWR SpacerFuture SubmittaNon-LOCABAW-X, S-RELAP5 for BWR Non-LOCA Transientsend of 2004LOCABAW-X, S-RELAP5 for BWR LOCAFuture SubmittaFuel PerformanceBAW-X, RODEX4 and Statistical Design MethodologyDec-02		BWR Methodology	
Non-LOCABAW-X, S-RELAP5 for BWR Non-LOCA Transientsend of 2004LOCABAW-X, S-RELAP5 for BWR LOCAFuture SubmittaFuel PerformanceBAW-X, RODEX4 and Statistical Design MethodologyDec-02	CHF	BAW-X. CHF Correlation for Advanced BWR Spacer	Future Submitta
LOCA BAW-X, S-RELAP5 for BWR LOCA Future Submitta Fuel Performance BAW-X, RODEX4 and Statistical Design Methodology Dec-02	Non-LOCA	BAW-X S-RELAP5 for BWR Non-LOCA Transients	end of 2004
Fuel Performance BAW-X, RODEX4 and Statistical Design Methodology Dec-02	LOCA	BAW-X, S-RELAP5 for BWR LOCA	Future Submitta
	Fuel Performance	BAW-X RODEX4 and Statistical Design Methodology	Dec-02

L. FRAMATOME ANP