

Nuclear Fuel Update

Palo Verde Nuclear Generating Station

**May 30, 2002
Meeting with US NRC**

1



Review of 2001

- ◆ **March 2001 Meeting with NRR**
- ◆ **Approval of new MDNBR Limit**
- ◆ **Progress with Clad Performance**
- ◆ **Alloy A LFA Approved For 4th Burn**
- ◆ **CENTS Code Added to COLR**
- ◆ **Begin Transition to Westinghouse Rod**
- ◆ **Zirlo Tech Spec Submitted**

2



Agenda Today

- ◆ **Review of Unit 2 Cycle 11**
- ◆ **CENTS Implementation & Licensing**
- ◆ **Integrated Clad Performance Strategy**
- ◆ **Update on CEA Investigation**
- ◆ **Dry Cask Storage Update**

3



Unit 2 Cycle 11

**Activities Incorporated in the
Reload Safety Analyses**

4



U2C11 Reload Analyses

- ◆ **Implementation of New MDNBR Limit**
- ◆ **Manufacturing Transition to Columbia**
- ◆ **Implementation of Zirlo Clad & New LOCA Methodology**
- ◆ **Implementation of New CENTS AORs**

5



CENTS System Code

Implementation & Licensing

6



CENTS Implementation Plan

- ◆ **Generic Letter 83-11 Supplement 1**
- ◆ **All UFSAR Chapter 15 Analyses**
- ◆ **Two Events Remain In Progress**
 - **Steam Generator Tube Rupture**
 - **CEA Ejection Dose Consequences**

7



Steam Generator Tube Rupture

- ◆ **Consequences Increase > Minimal**
- ◆ **Principal Contributors**
 - **Timing of Aux FW & ADV opening**
 - **New Limiting SG Level**
- ◆ **Retain Current CESEC AOR Until CENTS Analysis Reviewed & Approved**
- ◆ **Consistent With RSG/PUR Submittal**

8



CEA Ejection Dose Consequences

- ◆ **Evaluating CENTS Applicability**
- ◆ **Will Submit if Required**
- ◆ **Retain Current CESEC AOR Until
CENTS Implemented**
- ◆ **Will Not Impact RSG/PUR
Submittal**

9



Palo Verde Integrated Clad Performance Strategy

**Review of Recent Capabilities
U2 Uprate Corrosion Strategy**

10



Integrated Fuel Clad Strategy

- ◆ **Advanced Clad Alloys**
- ◆ **Primary System Chemistry**
- ◆ **Higher Order Modeling**
- ◆ **Low Duty Core Designs**

11



Advanced Clad Alloys

- ◆ **Full Batch Zirlo starting U2C11 (Spring 2002)**
- ◆ **Alloy A LTA in U3C10 (Spring 2003)**
- ◆ **Continuing Discussions with Westinghouse**

12



Primary Chemistry

- ◆ Additional RCS Cleaning at EOC Shutdown
- ◆ Early Lithium Injection During Startups
- ◆ Elevated-Coordinated Lithium Strategy
 - Currently 7.1 pH
 - Inspection U1R10 (Fall 2002)
 - Gradual Increase to ≥ 7.2 pH

13



Higher Order Modeling

- ◆ Uncertainty in Behaviors \Rightarrow Multiple Models
- ◆ Steaming Rate Function in Design Tools
 - U3C9 Benchmark
- ◆ APS CRUD/Oxide Model
 - Pin x Pin Colorset and Coarse Mesh Octant
- ◆ Vendor Fuel Duty Model
 - Oxide and FDI for all Clads

14




Low Duty Core Designs

- ◆ Increase Feed Batch Size
 - 104 vs 96 Assemblies
- ◆ Minimal Feed-Face-Feed
- ◆ U2 Uprate Corrosion Strategy
 - 3% Power and 2°F Coolant Temperature
 - Zirlo Clad
 - Re-design Lattice Pattern

15



Total Core Crud Volume - Predicted



16



Palo Verde CEA Replacement

Update on CEA Investigation

17



Review of CEA Replacement

- ◆ **CEA Finger Failures Observed - all Units**
 - Significant Cracks in High Fluence CEAs
 - Boron Loss in U1 Lead Group
 - Some Medium Fluence CEA Cracking
 - U2R8 CEA Found Cracked (Jan. 2002)
- ◆ **All Full Length CEAs Replaced**
 - Two Different Tip Designs
 - Replaced by Design with Smallest Pellet

18



Apparent Cause of Failures

- ◆ **IASCC of Cladding**
 - Irradiation Sensitized Inconel
 - Swelling-induced Strain
- ◆ **Less than Adequate Design Testing**
 - Fuelmetal Properties Unverified at High Duty
 - Pellet-Fuelmetal Interaction
- ◆ **Lifetime Predictive Software**
 - Models Not Fully Benchmarked

19



Remaining Actions

- ◆ **Determine Conservative Estimate of Life**
 - 2 Cycle Fingers OK
 - Possible YGN Inspections
 - Possible Hot Cell Exams
 - 2×10^{21} n/cm² Threshold?
- ◆ **CEA re-Design for the Future**

20



Palo Verde Dry Cask Storage

Plan Overview

21




Project Schedule

- ◆ Concrete Cask fab completed 3/31/02
- ◆ First Canister delivery 6/28/02
- ◆ ISFSI Construction complete 8/19/02
- ◆ Security features installed 9/15/02
- ◆ Dry run practice begins 8/1/02
- ◆ NRC dry run observations mid November
- ◆ First system on the pad by Christmas



Completed VCCs




3/7/2002



Palo Verde Dry Cask Storage Principal Components

(Cut-away View)



Dimensions:

Transfer cask	Ht. 16 ft. 11 in. Dia. 7 ft. 1 in.
Loaded canister	Ht. 15 ft. 11 in. Dia. 5 ft. 7 in.
VCC	Ht. 18 ft. 10 in. Dia. 11 ft. 4 in.

Weight:

Transfer cask	60 tons
Loaded canister	35 tons
VCC	119 tons
Loaded system	154 tons

