

June 12, 1990

Docket No. 50-458

Gulf States Utilities
ATTN: Mr. James C. Deddens
Senior Vice President (RBNG)
Post Office Box 220
St. Francisville, Louisiana 70775

Dear Mr. Deddens:

SUBJECT: CORRECTION TO AMENDMENT NO. 43 TO FACILITY OPERATING LICENSE
NO. NPF-47

On May 11, 1990, the Commission issued Amendment No. 43 to Facility Operating License No. NPF-47 for the River Bend Station, Unit 1. The amendment modified the Technical Specification (TS) requirement to perform a simulated loss of offsite power test of the diesel generators within 5 minutes of performing a 24-hour run.

One of the TS pages contained some typographical errors. The correct TS page is enclosed. The corresponding overleaf page is also provided to maintain document completeness.

Please accept our apology for any inconvenience this error may have caused you.

Sincerely,

Original signed by:

Claudia M. Abbate, Project Engineer
Project Directorate IV-2
Division of Reactor Projects - III, IV,
V, and Special Projects
Office of Nuclear Reactor Regulation

Enclosure:
Corrected TS Page

cc w/enclosure:
See next page

06222

DISTRIBUTION:

Docket	CGrimes
NRC PDR	OGC
Local PDR	Wanda Jones
PDIV-2 Reading	GPA/PA
GHolahan	EPeyton (2)
WPaulson	DHagan
CAbbate	JCalvo
GHill	ARM/LFMB
ACRS (10)	EJordan
PDIV-2 Plant File	

CP-1

OFC	: NRR: PDIV-2	: NRR: PDIV-2	: NRR: PDIV-2	:	:	:
NAME	: EPeyton <i>esp</i>	: CAbbate <i>CHA</i>	: CGrimes <i>WJ</i>	:	:	:
DATE	: 6/11 /90	: 6/11 /90	: 6/12/90	:	:	:

Mr. James C. Deddens

- 2 -

cc w/enclosure:

Mark Wetterhahn, Esq.
Bishop, Cook, Purcell & Reynolds
1401 L Street, N.W.
Washington, D.C. 20005

Ms. H. Anne Plettinger
3456 Villa Rose Drive
Baton Rouge, Louisiana 70806

Mr. Les England
Director - Nuclear Licensing
Gulf States Utilities Company
P. O. Box 220
St. Francisville, Louisiana 70775

Mr. Philip G. Harris
Cajun Electric Power Coop. Inc.
10719 Airline Highway
P. O. Box 15540
Baton Rouge, Louisiana 70895

Senior Resident Inspector
P. O. Box 1051
St. Francisville, Louisiana 70775

President of West Feliciana
Police Jury
P. O. Box 1921
St. Francisville, Louisiana 70775

Regional Administrator, Region IV
U.S. Nuclear Regulatory Commission
611 Ryan Plaza Drive, Suite 1000
Arlington, Texas 76011

Mr. J. E. Booker
Manager-Nuclear Industry Relations
P. O. Box 2951
Beaumont, Texas 77704

Mr. William H. Spell, Administrator
Nuclear Energy Division
Office of Environmental Affairs
P. O. Box 14690
Baton Rouge, Louisiana 70898

Mr. J. David McNeill, III
William G. Davis, Esq.
Department of Justice
Attorney General's Office
P. O. Box 94095
Baton Rouge, Louisiana 70804-9095

ELECTRICAL POWER SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

- 2) Verifying the diesel generator starts** on the auto-start signal, energizes the emergency busses with permanently connected loads within 10 seconds, energizes the auto-connected loads through the sequencing logic, and operates for greater than or equal to 5 minutes while its generator is loaded with the loads. After energization, the steady-state voltage and frequency of the emergency busses shall be maintained at 4160 ± 420 volts and 60 ± 1.2 Hz during this test.
- b) For division III:
 - 1) Verifying de-energization of the emergency bus.
 - 2) Verifying the diesel generator starts** on the auto-start signal, energizes the emergency bus with the permanently connected loads within 10 seconds, energizes the auto-connected loads through the sequence logic, and operates for greater than or equal to 5 minutes while its generator is loaded with the loads. After energization, the steady-state voltage and frequency of the emergency bus shall be maintained at 4160 ± 420 volts and 60 ± 1.2 Hz during this test.
- c) Operating** with the diesel generator loaded to 3000-3100 kW*** for diesel generators 1A and 1B and 2500-2600 kW*** for diesel generator 1C for at least 60 minutes or until operating temperatures have stabilized. Within 5 minutes after completing this test, perform Surveillance Requirement 4.8.1.1.2.f.4.a)2) and b)2).
5. Verifying that, on an ECCS actuation test signal without loss of offsite power, the diesel generator starts on the auto-start signal and operates on standby for greater than or equal to 5 minutes. For diesel generator 1A and 1B, the generator voltage and frequency shall be 4160 ± 420 volts and 60 ± 1.2 Hz within 10 seconds after the auto-start signal. For diesel generator 1C, the generator voltage and frequency shall not exceed a maximum of 5400 volts and 66.75 Hz and shall be greater than 3740 volts and 58.8 Hz within 10 seconds and 4160 ± 420 volts and 60 ± 1.2 Hz within 13 seconds. The steady-state generator voltage and frequency shall be maintained within these limits during this test.
6. Simulating a loss of offsite power in conjunction with an ECCS actuation test signal and:
 - a) For divisions I and II:
 - 1) Verifying deenergization of the emergency busses and load shedding from the emergency busses.

**All diesel generator starts for the purpose of this surveillance test may be preceded by an engine prelube period. Further, all surveillance tests, with the exception of once per 184 days, may also be preceded by warmup procedures and may also include gradual loading (> 150 sec) as recommended by the manufacturer so that the mechanical stress and wear on the diesel engine is minimized.

***Momentary transients due to changing bus loads shall not invalidate the test.

ELECTRICAL POWER SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

- 2) Verifying the diesel generator starts** on the auto-start signal, energizes the emergency busses with permanently connected loads within 10 seconds, energizes the auto-connected loads through the sequencing logic, and operates for greater than or equal to 5 minutes while its generator is loaded with the emergency loads.

**All diesel generator starts for the purpose of this surveillance test may be preceded by an engine prelube period. Further, all surveillance tests, with the exception of once per 184 days, may also be preceded by warmup procedures and may also include gradual loading (> 150 sec) as recommended by the manufacturer so that the mechanical stress and wear on the diesel engine is minimized.

ELECTRICAL POWER SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

After energization, the steady-state voltage and frequency of the emergency busses shall be maintained at 4160 ± 420 volts and 60 ± 1.2 Hz during this test.

b) For division III:

- 1) Verifying de-energization of the emergency bus.
 - 2) Verifying the diesel generator starts** on the auto-start signal, energizes the emergency bus with its permanently connected loads within 10 seconds, energizes the auto-connected loads through the sequencing logic, and operates for greater than or equal to 5 minutes while its generator is loaded with the emergency loads. After energization, the steady-state voltage and frequency of the emergency bus shall be maintained at 4160 ± 420 volts and 60 ± 1.2 Hz during this test.
7. Verifying that, upon an ECCS actuation signal, all automatic diesel generator trips are automatically bypassed except engine overspeed and generator differential current.
 8. Verifying the diesel generator operates for at least 24 hours. Diesel generators 1A and 1B shall be loaded to 3030-3130 kw*** for the duration of the test. Diesel generator 1C shall be loaded to 2750-2850 kw*** for the first 2 hours of the test and to 2500-2600 kw*** for the remaining 22 hours of the test. For diesel generator 1A and 1B, the generator voltage and frequency shall be 4160 ± 420 volts and 60 ± 1.2 Hz within 10 seconds after the start signal. For diesel generator 1C, the generator voltage and frequency shall not exceed a maximum of 5400 volts and 66.75 Hz and shall be greater than 3740 volts and 58.8 Hz within 10 seconds and 4160 ± 420 volts and 60 ± 1.2 Hz within 13 seconds. The steady-state generator voltage and frequency shall be maintained within these limits during this test.
 9. Verifying that the auto-connected loads to each diesel generator do not exceed 3130 kw for diesel generator 1A and 1B and 2600 kw for diesel generator 1C.

**All diesel generator starts for the purpose of this surveillance test may be preceded by an engine prelube period. Further, all surveillance tests, with the exception of once per 184 days, may also be preceded by warmup procedures and may also include gradual loading (> 150 sec) as recommended by the manufacturer so that the mechanical stress and wear on the diesel engine is minimized.

***Momentary transients due to changing bus loads shall not invalidate the test.