## 5.5.2.11 Steam Generator (SG) Tube Surveillance Program (continued)

- e) Imperfection An exception to the dimensions, finish, or contour of a tube from that required by fabrication drawings or specifications. Eddy-current testing indications below 20% of the nominal tube wall thickness, if detectable, may be considered as imperfections;
- f) Repair Limit The imperfection depth at or beyond which the tube shall be removed from service or repaired and is equal to 44% of the nominal tube wall thickness; Sleeves shall be removed from service upon detection of service-induced degradation of the sleeve material or any portion of the sleeve-to-tube weld.
- g) Preservice Inspection - An inspection of the full length of each tube in each SG performed by eddycurrent techniques prior to service to establish a baseline condition of the tubing. This inspection shall be performed prior to initial MODE 1 operating using the equipment and techniques expected to be used during subsequent inservice inspections. These examinations may be performed prior to steam generator installation. Similarly, for tube repair by sleeving, an inspection of the full length of the pressure boundary portion of the sleeved area shall be performed by eddy current techniques prior to service. This includes pressure retaining portions of the parent tube in contact with the sleeve, the sleeve-totube weld, and the pressure retaining portion of the sleeve.
- h) Tube Inspection An inspection of the SG tube from the point of entry (hot leg side) completely around the U-bend to the top support of the cold leg excluding the portion of the tube within the tubesheet (TS) below 5 inches from the secondary face of the TS.\*
- i) Unserviceable The condition of a tube if it leaks or contains a defect large enough to affect its structural integrity in the event of an Operational Basis Earthquake, a loss-of-coolant accident, or a steam line of feedwater line break accident as specified in Specification 5.5.2.11.e.

(continued)

<sup>\*</sup> This exclusion is for Unit 3, Cycle 11 operation only.