

October 10, 1984

Docket No. 50-331

Mr. Lee Liu, Chairman of the Board
and Chief Executive Officer
Iowa Electric Light and Power Company
Post Office Box 351
Cedar Rapids, Iowa 52406

Dear Mr. Liu:

Amendment No. 106 to the Duane Arnold Energy Center Technical Specifications inadvertently deleted the page 3.7-7 approved in the Amendment No. 100. Please replace the enclosed pages 3.7-7 and 3.7-7a in the Technical Specifications to reflect the changes that were approved in Amendment Nos. 100 and 106.

We regret any inconvenience caused by the error.

Sincerely,

Original signed by/

Mohan C. Thadani, Project Manager
Operating Reactors Branch #2
Division of Licensing

Enclosures:
As stated

cc w/enclosures:
See next page

DISTRIBUTION

Docket File
NRC PDR
Local PDR
ORB#2 Reading
DEisenhut
SNorris
MThadani
OELD
LJHarmon
ELJordan

JNGrace
JPartlow
TBarnhart (4)
WJones
DBrinkman
ACRS (10)
OPA, CMiles
RDiggs
Gray File
Extra - 5

DL:ORB#2
SNorris:ajs
10/10/84

MCS
DL:ORB#2
MThadani
10/10/84

MT
DL:ORB#2
DVassallo
10/10/84

8411010095 841010
PDR ADDCK 05000331
PDR

Mr. Lee Liu
Iowa Electric Light and Power Company
Duane Arnold Energy Center

cc:

Jack Newman, Esquire
Harold F. Reis, Esquire
Newman and Holtzinger
1615 L Street, N. W.
Washington, D. C. 20036

Mr. Thomas Houvenagle
Regulatory Engineer
Iowa Commerce Commission
Lucas State Office Building
Des Moines, Iowa 50319

Office for Planning and Programming
523 East 12th Street
Des Moines, Iowa 50319

Chairman, Linn County
Board of Supervisors
Cedar Rapids, Iowa 52406

Iowa Electric Light and Power Company
ATTN: D. L. Mineck
Post Office Box 351
Cedar Rapids, Iowa 52406

U. S. Environmental Protection
Agency
Region VII Office
Regional Radiation Representative
324 East 11th Street
Kansas City, Missouri 64106

U. S. Nuclear Regulatory Commission
Resident Inspector's Office
Rural Route #1
Palo, Iowa 52324

James G. Keppler
Regional Radiation Representative
Region III Office
U. S. Nuclear Regulatory Commission
799 Roosevelt Road
Glen Ellyn, Illinois 60137

LIMITING CONDITIONS FOR OPERATIONSURVEILLANCE REQUIREMENT3) Type C Tests

Type C tests shall be performed during each reactor shutdown for major refueling or other convenient interval but in no case at intervals greater than two years.

4) Additional Periodic Tests

Additional purge system isolation valve leakage integrity testing shall be performed at least once every three months in order to detect excessive leakage of the purge isolation valve resilient seats. The purge system isolation valves will be tested in three groups, by penetration: drywell purge exhaust group (CV-4302 and CV-4303), torus purge exhaust group (CV-4300 and CV-4301), and drywell/torus purge supply group (CV-4307, CV-4308 and CV-4306).

e. Seal Replacement

The T-ring inflatable seals for purge isolation valves CV-4300, CV-4301, CV-4302, CV-4303, CV-4306, CV-4307 and CV-4308 shall be replaced at intervals not to exceed four years.

The baseline for this requirement shall be established during the 1982 refueling outage.

f. Containment Modification

Any major modification, replacement of a component which is part of the primary reactor containment boundary, or resealing a seal-welded door, performed after the preoperational leakage rate test shall be followed by either a Type A, Type B, or Type C test, as applicable, for the area affected by the modification.

8411010101 841010
PDR ADOCK 05000331
PDR

LIMITING CONDITIONS FOR OPERATION

SURVEILLANCE REQUIREMENT

The measured leakage from this test shall be included in the test report. The acceptance criteria as appropriate, shall be met. Minor modifications, replacements, or resealing of seal welded doors, performed directly prior to the conduct of a scheduled Type A test do not require a separate test.

g. Reporting

100

Periodic tests shall be the subject of a summary technical report submitted to the Commission approximately 3 months after the conduct of each test. The report will be titled "Reactor Containment Integrated Leakage Rate Test."

106

The results of the periodic testing performed to satisfy the requirements of 4.7.A.2.d.4 shall be reported with the summary technical report prepared to provide the results of the testing performed in accordance with Section 4.7.A.2.d.3.

100