e. Closure of the containment isolation valves for the purpose of the test shall be accomplished by the means provided for normal operation of the valves.

## 2. Acceptance Criteria

The As Found measured leakage rate shall be less than 1.0 L<sub>a</sub> where L<sub>a</sub> is equal to 0.1 w/o per day of containment steam air atmosphere at 47 psig and 271°F, which are the peak accident pressure and temperature conditions. Prior to entering a mode where containment integrity is required, the As Left leakage rate shall not exceed 0.75 L<sub>a</sub>.

### 3. Frequency

The integrated leakage rate test frequency shall be performed in accordance with 10 CFR 50 Appendix J, Option B as modified by approved exemption and in accordance with guidelines contained in Regulatory Guide 1.163, dated September 1995, with the following exceptions:

Exception 1: The Type A testing frequency specified in NEI 94-01 paragraph 9.2.3 as at-least-once-per-10 years based on acceptable performance history is changed to allow a Type A testing frequency of at-least-once-per-15 years based on acceptable performance history. This is a one-time-only exception that applies only for the interval following the Type A test performed in June 1991.

## B. SENSITIVE LEAKAGE RATE

### 1. Test

A sensitive leakage rate test shall be conducted with the containment penetrations, weld channels, and certain double-gasketed seals and isolation valve interspaces at a minimum pressure of 52 psig and with the containment building at atmospheric pressure.

# 2. <u>Acceptance Criteria</u>

The test shall be considered satisfactory if the leak rate for the containment penetrations, weld channel and other pressurized zones is equal to or less than 0.2% of the containment free volume per day.

#### 3. Frequency

A sensitive leakage rate test shall be performed at every Refueling Interval (R#).