
SYSTEM DATA
DESIGN DATA
HYDROTEST TEMP 60°F
(NOTES CONTINUED)
1 UPSTREAM & DOWNSTREAM VALVES TO 3FI 11900 & 11901 ARE TO BE CLOSED AT THE START OF TESTING. PROCEDURE FOR USING THESE INDICATORS IS:
1 PROVIDE A BLEED SIDE 3FI 1977 FLOW INDICATOR OR DRAIN VALVE 6A OF 3F TO ORDER TO REDUCE PRESSURE TO LESS THAN 240 PSIG ON P3-1918
2 OPEN DOWNSTREAM VALVE (S) (3FS-11900 HR LD OR 3FI 11901 HR LD)
3 OPEN UPSTREAM VALVE (S) (3FI 11900 LR LD OR 3FI 11901 LR-LD)
4 CLOSE BLEED PATH
AFTER FLOW IS READ, UPSTREAM VALVE(S) TO BE CLOSED FIRST & DOWNSTREAM VALVE(S) CLOSED LAST
3FI 11900 LOW RANGE FLOW INDICATOR IS 0 TO READING FROM 3FI 1977 READS A FLOWLESS THAN 1.6 GPM 3FI 11901 LOW RANGE FLOW INDICATOR IS ONLY TO BE USED WHEN 3FI 11900 READS A FLOW LESS THAN 0.6 GPM
NOTES:
1 ALL PIPING TO BE NON-NUCLEAR SAFETY CLASS LINE SIZE EXCEPT 2 CLOSED O.D. x .515 I.D. FLOW RESTRICTOR IS REQUIRED TO ALLOW TRANSITION FROM SAFETY CLASS 1 TO SAFETY CLASS 2A.
3 SPOOL PIECE REQUIRED. SPOOL PIECE REMAINS IN EXCEPT WHEN LINE IS TO DRAINED UP STREAM VALVES ARE LOCKED CLOSED DURING NORMAL OPERATION.
4 VENT LINE FOR SYSTEM FILL WITH DEMINERALIZED WATER PRIOR TO TESTING. NOTED F SERIES OR EQUAL
5 2.250 O.D. x .515 I.D. FLOW RESTRICTOR IS REQUIRED TO ALLOW TRANSITION FROM SAFETY CLASS 1 TO SAFETY CLASS 2A.
6 .75 SW CONN EQUIV TO GOOD-ALL A HALF INCH DRILLED FOR .515 I.D. FLOW RESTRICTOR IS REQUIRED TO ALLOW TRANSITION FROM SAFETY CLASS 1 TO SAFETY CLASS 2A.
(FOR CONTINUATION OF NOTES SEE DRAWING (COORDINATES B 14))
D-99
PLEX Drawing TR00160-002
FSAR Figure 5.2-8
SOUTH CAROLINA ELECTRIC & GAS COMPANY
V.C. SUMMER NUCLEAR STATION
PIPING
SYSTEM FLOW DIAGRAM
ECCS CHECK VALVE TESTING
DESIGN ENGINEERING
SRM
MGR
MRH
D-302-812
16
DRAWING LEGIBILITY CLASS 1
SCE&G CAD ENHANCED
REVISION
REVISED PER CGSS-98-0138
REVISED PER CGSS-97-0579
REVISED PER LTR97-404
REVISED PER MRF-22640
REVISED PER CGSS-94-0722
REVISED PER MRF-21302