1.1 Definitions (continued)

¢

2

•

1

ENGINEERED SAFETY FEATURE (ESF) RESPONSE TIME	The ESF RESPONSE TIME shall be that time interval from when the monitored parameter exceeds its ESF actuation setpoint at the channel sensor until the ESF equipment is capable of performing its safety function (i.e., the valves travel to their required positions, pump discharge pressures reach their required values, etc.). Times shall include diesel generator starting and sequence loading delays, where applicable. The response time may be measured by means of any series of sequential, overlapping, or total steps so that the entire response time is measured. In lieu of measurement, response time may be verified for selected components provided that the components and the methodology for verification have been previously reviewed and approved by the NRC.			
LEAKAGE		LEAKAGE shall be:		
	a.	. Identified LEAKAGE		
		1.	LEAKAGE, such as that from pump seals or valve packing (except reactor coolant pump (RCP) seal water injection or leakoff), that is captured and conducted to collection systems or a sump or collecting tank;	
		2.	LEAKAGE into the containment atmosphere from sources that are both specifically located and known either not to interfere with the operation of leakage detection systems or not to be pressure boundary LEAKAGE; or	
		3.	Reactor Coolant System (RCS) LEAKAGE through a steam generator (SG) to the Secondary System;	
	b.	<u>Uni</u>	dentified LEAKAGE	
			LEAKAGE (except RCP seal water injection or <off) identified="" is="" leakage;<="" not="" td="" that=""></off)>	
	C.	<u>Pre</u>	ssure Boundary LEAKAGE	
		LE/ fau wal	AKAGE (except SG LEAKAGE) through a nonisolable It in an RCS component body, pipe wall, or vessel I.	

1.1 Definitions (continued)

-

. .

,

QUADRANT POWER TILT RATIO (QPTR)	QPTR shall be the ratio of the maximum upper excore detector calibrated output to the average of the upper excore detector calibrated outputs, or the ratio of the maximum lower excore detector calibrated output to the average of the lower excore detector calibrated outputs, whichever is greater.		
RATED THERMAL POWER (RTP)	RTP shall be a total reactor core heat transfer rate to the reactor coolant of 3411 MWt.		
REACTOR TRIP SYSTEM (RTS) RESPONSE TIME	The RTS RESPONSE TIME shall be that time interval from when the monitored parameter exceeds its RTS trip setpoint at the channel sensor until loss of stationary gripper coil voltage. The response time may be measured by means of any series of sequential, overlapping, or total steps so that the entire response time is measured. In lieu of measurement, response time may be verified for selected components provided that the components and the methodology for verification have been previously reviewed and approved by the NRC.		
SHUTDOWN MARGIN (SDM)	SDM shall be the instantaneous amount of reactivity by which the reactor is subcritical or would be subcritical from its present condition assuming:		
	a. All rod cluster control assemblies (RCCAs) are fully inserted except for the single RCCA of highest reactivity worth, which is assumed to be fully withdrawn. With any RCCA not capable of being fully inserted, the reactivity worth of the RCCA must be accounted for in the determination of SDM; and		
	b. In MODES 1 and 2, the fuel and moderator temperatures are changed to the nominal zero power design level		
SLAVE RELAY TEST	A SLAVE RELAY TEST shall consist of energizing each slave relay and verifying the OPERABILITY of each slave relay. The SLAVE RELAY TEST shall include, as a minimum, a continuity check of associated testable actuation devices.		

1.1 Definitions (continued)

.

-

-

STAGGERED TEST BASIS	A STAGGERED TEST BASIS shall consist of the testing of one of the systems, subsystems, channels, or other designated components during the interval specified by the Surveillance Frequency, so that all systems, subsystems, channels, or other designated components are tested during <i>n</i> Surveillance Frequency intervals, where <i>n</i> is the total number of systems, subsystems, channels, or other designated components in the associated function.
THERMAL POWER	THERMAL POWER shall be the total reactor core heat transfer rate to the reactor coolant
TRIP ACTUATING DEVICE OPERATIONAL TEST (TADOT)	A TADOT shall consist of operating the trip actuating device and verifying the OPERABILITY of required alarm, interlock, and trip functions. The TADOT shall include adjustment, as necessary, of the trip actuating device so that it actuates at the required setpoint within the required accuracy.

SURVEILLANCE REQUIREMENTS (continued)

not required if it has been performed within the previous 31 days. Verification of the Trip Setpoint does not have to be performed for this Surveillance Performance of this test will ensure that the turbine trip Function is OPERABLE prior to taking the reactor critical. This test cannot be performed with the reactor at power and must therefore be performed prior to reactor startup.

SR 3.3 1 16 and SR 3.3.1.17

SR 3.3.1 16 and SR 3 3.1.17 verify that the individual channel/train actuation response times are less than or equal to the maximum values assumed in the accident analysis. Response time testing acceptance criteria are included in the UFSAR (Ref. 1). Individual component response times are not modeled in the analyses.

The analyses model the overall or total elapsed time, from the point at which the parameter exceeds the trip setpoint value at the sensor to the point at which the equipment reaches the required functional state (i.e., control and shutdown rods fully inserted in the reactor core).

For channels that include dynamic transfer Functions (e.g., lag, lead/lag, rate/lag, etc.), the response time test may be performed with the transfer Function set to one, with the resulting measured response time compared to the appropriate UFSAR response time. Alternately, the response time test can be performed with the time constants set to their nominal value, provided the required response time is analytically calculated assuming the time constants are set at their nominal values. The response time may be measured by a series of overlapping tests such that the entire response time is measured

Response time may be verified by actual response time tests in any series of sequential, overlapping or total channel measurements, or by the summation of allocated sensor, signal processing and actuation logic response times with actual response time tests on the remainder of the channel. Allocations for sensor response times may be obtained from: (1) historical records based on acceptable response time tests (hydraulic, noise, or power interrupt tests), (2) in place, onsite, or offsite (e.g., vendor) test measurements, or (3) utilizing vendor engineering specifications. WCAP-13632-P-A, Revision 2, "Elimination of Pressure Sensor Response Time Testing Requirements" provides the basis and methodology for using allocated sensor response times in the overall verification of the channel response time for specific sensors identified in the WCAP. Response time verification for other sensor types must be either demonstrated by test, or their equivalency to those listed in WCAP-

SURVEILLANCE REQUIREMENTS (continued)

13632-P-A, Revision 2. Any demonstration of equivalency must have been determined to be acceptable by NRC staff review.

WCAP-14036-P-A, Revision 1, "Elimination of Periodic Protection Channel Response Time Tests' provides the basis and methodology for using allocated signal processing and actuation logic response times in the overall verification of the protection system channel response time The allocations for sensor, signal conditioning, and actuation logic response times must be verified prior to placing the component in operational service and re-verified following maintenance that may adversely affect response time. In general, electrical repair work does not impact response time provided the parts used for repair are of the same type and value. Specific components identified in the WCAP may be replaced without verification testing. One example where response time could be affected is replacing the sensing assembly of a transmitter.

As appropriate, each channel's response must be verified every 18 months on a STAGGERED TEST BASIS. Testing of the final actuation devices is included in the testing. Testing of the RTS RTDs is performed on an 18 month frequency. Response times cannot be determined during unit operation because equipment operation is required to measure response times. Experience has shown that these components usually pass this surveillance when performed at the 18 month Frequency. Therefore, the Frequency was concluded to be acceptable from a reliability standpoint

SR 3.3.1.16 is modified by a Note stating that neutron detectors are excluded from RTS RESPONSE TIME testing. This Note is necessary because of the difficulty in generating an appropriate detector input signal. Excluding the detectors is acceptable because the principles of detector operation ensure a virtually instantaneous response. The response time of the neutron flux signal portion of the channel shall be measured from detector output or input of the first electronic component in the channel.

REFERENCES	1.	UFSAR, Chapter 7

- 2. UFSAR, Chapter 6
- 3 UFSAR, Chapter 15.
- 4 IEEE-279-1971.
- 5. 10 CFR 50 49
- 6. 10 CFR 50.36, Technical Specifications, (c)(2)(II).
- 7 WCAP-10271-P-A, Supplement 2, Rev. 1, June 1990.
- 8. WCAP 13632-P-A, Revision 2, "Elimination of Pressure Sensor Response Time Testing Requirements" Sep., 1995.
- 9. WCAP-14036-P-A, Revision 1, "Elimination of Periodic Protection Channel Response Time Tests" Oct., 1998

SURVEILLANCE REQUIREMENTS (continued)

calibration interval in the determination of the magnitude of equipment drift in the setpoint methodology.

This SR is modified by a Note stating that this test should include verification that the time constants are adjusted to the prescribed values where applicable The applicable time constants are shown in Table 3 3.2-1.

<u>SR 332.9</u>

This SR ensures the individual channel ESF RESPONSE TIMES are less than or equal to the maximum values assumed in the accident analysis. Response Time testing acceptance criteria are included in the UFSAR (Ref. 2). Individual component response times are not modeled in the analyses The analyses model the overall or total elapsed time, from the point at which the parameter exceeds the Trip Setpoint value at the sensor to the point at which the equipment in both trains reaches the required functional state (e.g., pumps at rated discharge pressure, valves in full open or closed position)

For channels that include dynamic transfer functions (e g , lag, lead/lag, rate/lag, etc), the response time test may be performed with the transfer functions set to one with the resulting measured response time compared to the appropriate UFSAR response time. Alternately, the response time test can be performed with the time constants set to their nominal value provided the required response time is analytically calculated assuming the time constants are set at their nominal values. The response time may be measured by a series of overlapping tests such that the entire response time is measured.

Response time may be verified by actual response time tests in any series of sequential, overlapping or total channel measurements, or by the summation of allocated sensor, signal processing and actuation logic response times with actual response time tests on the remainder of the channel. Allocations for sensor response times may be obtained from: (1) historical records based on acceptable response time tests (hydraulic, noise, or power interrupt tests), (2) in place, onsite, or offsite (e.g., vendor) test measurements, or (3) utilizing vendor engineering specifications. WCAP-13632-P-A, Revision 2, "Elimination of Pressure Sensor Response Time Testing Requirements" provides the basis and methodology for using allocated sensor response times in the overall verification of the channel response time for specific sensors identified in the WCAP Response time verification for other sensor types must be either demonstrated by test or their equivalency to those listed in WCAP-13632-P-A, Revision 2. Any demonstration of equivalency must have been determined to be acceptable by NRC staff review.

WCAP-14036-P-A, Revision 1, "Elimination of Periodic Protection Channel Response Time Tests' provides the basis and methodology for using allocated signal processing and actuation logic response times in the overall verification of the protection system channel response time. The allocations for sensor, signal conditioning, and actuation logic response times must be verified prior to placing the component in operational service and re-verified following maintenance that may adversely affect response time. In general, electrical repair work does not impact response time provided the parts used for repair are of the same type and value. Specific components identified in the WCAP may be replaced without verification testing One example where response time could be affected is replacing the sensing assembly of a transmitter.

ESF RESPONSE TIME tests are conducted on an 18 month STAGGERED TEST BASIS. Testing of the final actuation devices, which make up the bulk of the response time, is included in the testing of each channel. The final actuation device in one train is tested with each channel. Therefore, staggered testing results in response time verification of these devices every 18 months. The 18 month Frequency is consistent with the typical refueling cycle and is based on unit operating experience, which shows that random failures of instrumentation components causing serious response time degradation, but not channel failure, are infrequent occurrences.

This SR is modified by a Note that clarifies that the turbine driven AFW pump is tested within 24 hours after reaching 900 psig in the SGs.

REFERENCES 1. UFSAR, Chapter 6

- 2 UFSAR, Chapter 7
- 3 UFSAR, Chapter 15
- 4 IEEE-279-1971.
- 5. 10 CFR 50 49.
- 6 10 CFR 50.36, Technical Specifications, (c)(2)(ii)
- 7 WCAP-10271-P-A, Supplement 1 and Supplement 2, Rev. 1, May 1986 and June 1990
- 8. WCAP 13632-P-A, Revision 2, "Elimination of Pressure Sensor Response Time Testing Requirements" Sep., 1995.
- 9 WCAP-14036-P-A, Revision 1, "Elimination of Periodic Protection Channel Response Time Tests" Oct , 1998