

April 16, 1996

Mr. Gregory M. Rueger
Pacific Gas and Electric Company
NPG - Mail Code A10D
P. O. Box 770000
San Francisco, California 94177

SUBJECT: CORRECTION TO AMENDMENTS 89 AND 88 FOR DIABLO CANYON NUCLEAR POWER PLANT, UNITS 1 (TAC NO. M88522) AND 2 (TAC NO. M88523)

Dear Mr. Rueger:

On March 2, 1994, the Commission issued Amendment No. 89 to Facility Operating License No. DPR-80 and Amendment No. 88 to Facility Operating License No. DPR-82 for Diablo Canyon Nuclear Power Plant, Unit Nos. 1 and 2 (DCPP). The amendments revised the technical specifications (TS) related to engineering safety features actuation system instrumentation and surveillance requirements and clarified containment fan cooling unit (CFCU) configurations.

Page 3/4 3-32 was issued without correctly indicating the changes that were made in amendments 84/83. In amendments 84/83, the surveillance requirements under functional unit item 1.e. for differential pressure between steam lines-high was eliminated. Also in those amendments, item 1.f. was modified to eliminate steam flow in two steam lines-high coincident with either Tavg-low-low or steam line pressure-low, except for the part on steam line pressure-low. The corrected page 3/4 3-32 and its corresponding overleaf page is enclosed. We apologize for any inconvenience.

Sincerely,

Original Signed By

Steven D. Bloom, Project Manager
Project Directorate IV-2
Division of Reactor Projects III/IV
Office of Nuclear Reactor Regulation

Docket Nos. 50-275
and 50-323

Enclosure: Page 3/4 3-32

cc w/encl: See next page

DISTRIBUTION

Docket File
PUBLIC
PDIV-2 Reading
EGA1
LHurley, RIV
WBateman
KPerkins, WCFO
SBloom
JBianchi, RIV (2)
CGrimes, 011E22
JBianchi, WCFO (2)
GHill (4), T5C3
OGC, 015B18
ACRS, T2E26
DChamberlain, RIV
JKilcrease, RIV
EPeyton

DOCUMENT NAME: DC88522.COR

OFC	LA/PDIV-2	PM/PDIV-2
NAME	EPeyton	SBloom
DATE	4/16/96	4/16/96

OFFICIAL RECORD COPY

220019

9604240006 960416
PDR ADOCK 05000275
P PDR

CP-1
DF01
NRC FILE CENTER COPY

Mr. Gregory M. Rueger

- 2 -

cc w/encl:

NRC Resident Inspector
Diablo Canyon Nuclear Power Plant
c/o U.S. Nuclear Regulatory Commission
P. O. Box 369
Avila Beach, California 93424

Regional Administrator, Region IV
U.S. Nuclear Regulatory Commission
Harris Tower & Pavillion
611 Ryan Plaza Drive, Suite 400
Arlington, Texas 76011-8064

Dr. Richard Ferguson, Energy Chair
Sierra Club California
1100 11th Street, Suite 311
Sacramento, California 95814

Christopher J. Warner, Esq.
Pacific Gas & Electric Company
Post Office Box 7442
San Francisco, California 94120

Ms. Nancy Culver
San Luis Obispo
Mothers for Peace
P. O. Box 164
Pismo Beach, California 93448

Mr. Warren H. Fujimoto
Vice President and Plant Manager
Diablo Canyon Nuclear Power Plant
P. O. Box 56
Avila Beach, California 93424

Ms. Jacquelyn C. Wheeler
P. O. Box 164
Pismo Beach, California 93448

Diablo Canyon Independent Safety
Committee
ATTN: Robert R. Wellington, Esq.
Legal Counsel
857 Cass Street, Suite D
Monterey, California 93940

Managing Editor
The County Telegram Tribune
1321 Johnson Avenue
P. O. Box 112
San Luis Obispo, California 93406

Chairman
San Luis Obispo County Board of
Supervisors
Room 370
County Government Center
San Luis Obispo, California 93408

Mr. Truman Burns
Mr. Robert Kinosian
California Public Utilities Commission
505 Van Ness, Room 4102
San Francisco, California 94102

Mr. Steve Hsu
Radiologic Health Branch
State Department of Health Services
Post Office Box 942732
Sacramento, California 94232

TABLE 3.3-5 (Continued)

TABLE NOTATIONS

- (1) Diesel generator starting delay not included because offsite power available.
- (2) Notation deleted.
- (3) Diesel generator starting and loading delays included.
- (4) Diesel generator starting delay not included because offsite power is available. Response time limit includes opening of valves to establish SI path and attainment of discharge pressure for centrifugal charging pumps (where applicable). Sequential transfer of charging pump suction from the VCT to the RWST (RWST valves open, then VCT valves close) is included.
- (5) Diesel generator starting and sequence loading delays included. Offsite power is not available. Response time limit includes opening of valves to establish SI path and attainment of discharge pressure for centrifugal charging pumps. Sequential transfer of charging pump suction from the VCT to the RWST (RWST valves open, then VCT valves close) is included.
- (6) The maximum response time of 48.5 seconds is the time from when the containment pressure exceeds the High-High Setpoint until the spray pump is started and the discharge valve travels to the fully open position assuming off-site power is not available. The time of 48.5 seconds includes the 28-second maximum delay related to ESF loading sequence. Spray riser piping fill time is not included. The 80-second maximum spray delay time does not include the time from LOCA start to "P" signal.
- (7) Diesel generator starting and sequence loading delays included. Sequential transfer of charging pump suction from the VCT to the RWST (RWST valves open, then VCT valves close) is not included. Response time limit includes opening of valves to establish SI flow path and attainment of discharge pressure for centrifugal charging pumps, SI, and RHR pumps (where applicable).
- (8) Does not include Trip Time Delays. Response times include the transmitters, Eagle-21 Process Protection cabinets, Solid State Protection System cabinets and actuation devices only. This reflects the response times necessary for THERMAL POWER in excess of 50% RTP.

TABLE 4.3-2

ENGINEERED SAFETY FEATURES ACTUATION SYSTEM INSTRUMENTATION
SURVEILLANCE REQUIREMENTS

DIABLO CANYON - UNITS 1 & 2 3/4 3-32 Unit 1 - Amendment No. 61, 84, 89 Unit 2 - Amendment No. 60, 83, 88	FUNCTIONAL UNIT	CHANNEL CHECK	CHANNEL CALI- BRATION	ANALOG OPERA- TIONAL TEST	TRIP ACTUATING OPERA- TIONAL TEST	ACTUATION LOGIC TEST	MASTER RELAY TEST	SLAVE RELAY TEST	MODES FOR WHICH SURVEILLANCE IS REQUIRED
	1. Safety Injection, (Reactor Trip Feedwater Isolation, Start Diesel Generators, Containment Fan Cooler Units, and Component Cooling Water)								
	a. Manual Initiation	N.A.	N.A.	N.A.	R	N.A.	N.A.	N.A.	1, 2, 3, 4
	b. Automatic Actuation Logic and Actuation Relays	N.A.	N.A.	N.A.	N.A.	M(1)	M(1)	Q	1, 2, 3, 4
	c. Containment Pressure-High	S	R	Q	N.A.	N.A.	N.A.	N.A.	1, 2, 3, 4
	d. Pressurizer Pressure-Low	S	R	Q	N.A.	N.A.	N.A.	N.A.	1, 2, 3
	e. DELETED								
	f. Steam Line Pressure-Low	S	R	Q	N.A.	N.A.	N.A.	N.A.	1, 2, 3
	2. Containment Spray								
	a. Manual Initiation	N.A.	N.A.	N.A.	R	N.A.	N.A.	N.A.	1, 2, 3, 4
	b. Automatic Actuation Logic and Actuation Relays	N.A.	N.A.	N.A.	N.A.	M(1)	M(1)	Q	1, 2, 3, 4
	c. Containment Pressure-High-High	S	R	Q	N.A.	N.A.	N.A.	N.A.	1, 2, 3, 4