SURVEILLANCE REQUIREMENTS

----------NOTES----------

1. Refer to Table 3.3.6.1-1 to determine which SRs apply for each Primary Containment Isolation Function.

2. When a channel is placed in an inoperable status solely for performance of required Surveillances, entry into associated Conditions and Required Actions may be delayed for up to:

   a. 2 hours for Function 5.a when testing non-redundant circuitry that results in loss of isolation capability associated with this Function, provided Functions 5.b, 5.c, and 5.e are OPERABLE;

   b. 6 hours for Functions 1, 2, 5 (other than non-redundant circuitry of 5.a), and 6, provided the associated Function maintains isolation capability; and

   c. 8 hours for Functions 3 and 4, provided the associated Function maintains isolation capability.

SURVEILLANCE		FREQUENCY
SR 3.3.6.1.1	Perform CHANNEL CHECK.	12 hours
SR 3.3.6.1.2	Perform CHANNEL FUNCTIONAL TEST.	92 days
SR 3.3.6.1.3	Verify the trip unit setpoint.	92 days
SR 3.3.6.1.4	Perform CHANNEL CALIBRATION.	18 months
SR 3.3.6.1.5	Perform LOGIC SYSTEM FUNCTIONAL TEST.	18 months
SR 3.3.6.1.6	Perform CHANNEL FUNCTIONAL TEST.	18 months

(continued)

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE		FREQUENCY
SR 3.3.6.1.7	Verify the Main Steam Line Isolation Instrumentation DC Output Relays response time allows the overall ISOLATION SYSTEM RESPONSE TIME to remain within limits.	18 months on a STAGGERED TEST BASIS

Table 3.3.6.1-1 (page 1 of 4)
Primary Containment Isolation Instrumentation

FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION C.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
1. Main Steam Line Isolation					
a. Reactor Vessel Water Level – Low Low Low, Level 1	1,2,3	2	D	SR 3.3.6.1.1 SR 3.3.6.1.2 SR 3.3.6.1.3 SR 3.3.6.1.4 SR 3.3.6.1.5 SR 3.3.6.1.7	≥ 24.8 inches
b. Main Steam Line Pressure – Low	1	2	E	SR 3.3.6.1.1 SR 3.3.6.1.2 SR 3.3.6.1.3 SR 3.3.6.1.4 SR 3.3.6.1.5	≥ 736 psig
c. Main Steam Line Flow – High	1,2,3	2 per MSL	D	SR 3.3.6.1.1 SR 3.3.6.1.2 SR 3.3.6.1.3 SR 3.3.6.1.4 SR 3.3.6.1.5 SR 3.3.6.1.7	≤ 118.4 psid
d. Condenser Pressure – High	1, 2(a), 3(a)	2	D	SR 3.3.6.1.1 SR 3.3.6.1.2 SR 3.3.6.1.3 SR 3.3.6.1.4 SR 3.3.6.1.5	≤ 7.05 psia
e. Main Steam Tunnel Temperature – High	1,2,3	2 per trip string	D	SR 3.3.6.1.1 SR 3.3.6.1.2 SR 3.3.6.1.3 SR 3.3.6.1.4 SR 3.3.6.1.5	≤ 206°F
f. Main Steam Line Radiation – High	1,2,3	2	D	SR 3.3.6.1.1 SR 3.3.6.1.2 SR 3.3.6.1.4 SR 3.3.6.1.5	≤ 3.6 x full power background
g. Turbine Building Area Temperature – High	1,2,3	4	D	SR 3.3.6.1.1 SR 3.3.6.1.2 SR 3.3.6.1.3 SR 3.3.6.1.4 SR 3.3.6.1.5	≤ 206°F
h. Manual Initiation	1,2,3	1 per valve	G	SR 3.3.6.1.6	NA

(continued)

(a) Except when bypassed during reactor shutdown or for reactor startup under administrative control.