



South Texas Project Electric Generating Station PO Box 289 Wadsworth, Texas 77483

December 2, 2002  
NOC-AE-02001433  
10CFR50.36

U. S. Nuclear Regulatory Commission  
Attention: Document Control Desk  
One White Flint North  
11555 Rockville Pike  
Rockville, MD 20852

South Texas Project  
Unit 2  
Docket No. STN 50-499  
Unit 2 Cycle 10 Core Operating Limits Report

In accordance with Technical Specification 6.9.1.6.d, the attached Core Operating Limits Report is submitted for South Texas Project Unit 2 Cycle 10. This report does not reflect the end of life moderator temperature coefficient amendment (Amendments 144/132), issued on November 26, 2002, because it was completed prior to the amendment date.

If there are any questions concerning this report, please contact Scott Head at (361) 972-7136 or me at (361) 972-7795.

David A. Leazar  
Director,  
Nuclear Fuel & Analysis

kaw

Attachment: Unit 2 Cycle 10 Core Operating Limits Report

cc: Licensing Library  
RMS (w/o attachment)

A001

cc:

(paper copy)

Ellis W. Merschoff  
Regional Administrator, Region IV  
U.S. Nuclear Regulatory Commission  
611 Ryan Plaza Drive, Suite 400  
Arlington, Texas 76011-8064

U. S. Nuclear Regulatory Commission  
Attention: Document Control Desk  
One White Flint North  
11555 Rockville Pike  
Rockville, MD 20852

Richard A. Ratliff  
Bureau of Radiation Control  
Texas Department of Health  
1100 West 49th Street  
Austin, TX 78756-3189

Cornelius F. O'Keefe  
U. S. Nuclear Regulatory Commission  
P. O. Box 289, Mail Code: MN116  
Wadsworth, TX 77483

C. M. Canady  
City of Austin  
Electric Utility Department  
721 Barton Springs Road  
Austin, TX 78704

(electronic copy)

A. H. Gutterman, Esquire  
Morgan, Lewis & Bockius LLP

M. T. Hardt/W. C. Gunst  
City Public Service

Mohan C. Thadani  
U. S. Nuclear Regulatory Commission

R. L. Balcom  
Reliant Energy, Inc.

A. Ramirez  
City of Austin

C. A. Johnson  
AEP - Central Power and Light Company

Jon C. Wood  
Matthews & Branscomb

31526846

G0906



**SOUTH TEXAS PROJECT  
ELECTRIC GENERATING STATION  
UNIT 2 CYCLE 10  
CORE OPERATING LIMITS REPORT**

Revision 0

November 2002

## 1.0 CORE OPERATING LIMITS REPORT

This Core Operating Limits Report for STPEGS Unit 2 Cycle 10 has been prepared in accordance with the requirements of Technical Specification 6.9.1.6. The core operating limits have been developed using the NRC-approved methodologies specified in Technical Specification 6.9.1.6.

The Technical Specifications affected by this report are:

- |    |           |  |
|----|-----------|--|
| 1) | 2.1       | SAFETY LIMITS                            |
| 2) | 2.2       | LIMITING SAFETY SYSTEM SETTINGS          |
| 3) | 3/4.1.1.3 | MODERATOR TEMPERATURE COEFFICIENT LIMITS |
| 4) | 3/4.1.3.5 | SHUTDOWN ROD INSERTION LIMITS            |
| 5) | 3/4.1.3.6 | CONTROL ROD INSERTION LIMITS             |
| 6) | 3/4.2.1   | AFD LIMITS                               |
| 7) | 3/4.2.2   | HEAT FLUX HOT CHANNEL FACTOR             |
| 8) | 3/4.2.3   | NUCLEAR ENTHALPY RISE HOT CHANNEL FACTOR |
| 9) | 3/4.2.5   | DNB PARAMETERS                           |

## 2.0 OPERATING LIMITS

The cycle-specific parameter limits for the specifications listed in Section 1.0 are presented below.

### 2.1 SAFETY LIMITS (Specification 2.1):

- 2.1.1 The combination of THERMAL POWER, pressurizer pressure, and the highest operating loop coolant temperature ( $T_{avg}$ ) shall not exceed the limits shown in Figure 1.

### 2.2 LIMITING SAFETY SYSTEM SETTINGS (Specification 2.2):

- 2.2.1 The Loop design flow for Reactor Coolant Flow-Low is 98,000 gpm.
- 2.2.2 The Over-temperature  $\Delta T$  and Over-power  $\Delta T$  setpoint parameter values are listed below:

#### Over-temperature $\Delta T$ Setpoint Parameter Values

- |                 |   |
|-----------------|---|
| $\tau_1$        | measured reactor vessel $\Delta T$ lead/lag time constant, $\tau_1 = 8$ sec   |
| $\tau_2$        | measured reactor vessel $\Delta T$ lead/lag time constant, $\tau_2 = 3$ sec   |
| $\tau_3$        | measured reactor vessel $\Delta T$ lag time constant, $\tau_3 = 0$ sec  |
| $\tau_4$        | measured reactor vessel average temperature lead/lag time constant, $\tau_4 = 28$ sec   |
| $\tau_5$        | measured reactor vessel average temperature lead/lag time constant, $\tau_5 = 4$ sec  |
| $\tau_6$        | measured reactor vessel average temperature lag time constant, $\tau_6 = 0$ sec   |
| $K_1$           | Overtemperature $\Delta T$ reactor trip setpoint, $K_1 = 1.14$  |
| $K_2$           | Overtemperature $\Delta T$ reactor trip setpoint $T_{avg}$ coefficient, $K_2 = 0.028/^\circ F$  |
| $K_3$           | Overtemperature $\Delta T$ reactor trip setpoint pressure coefficient, $K_3 = 0.00143/\text{psig}$  |
| $T'$            | Nominal full power $T_{avg}$ , $T' \leq 592.0$ °F   |
| $P'$            | Nominal RCS pressure, $P' = 2235$ psig  |
| $f_1(\Delta I)$ | is a function of the indicated difference between top and bottom detectors of the power-range neutron ion chambers; with gains to be selected based on measured instrument response during plant startup tests such that; |

(Continued on next page)

- (1) For  $q_t - q_b$  between -70% and +8%,  $f_1(\Delta I) = 0$ , where  $q_t$  and  $q_b$  are percent RATED THERMAL POWER in the top and bottom halves of the core respectively, and  $q_t + q_b$  is total THERMAL POWER in percent of RATED THERMAL POWER;
- (2) For each percent that the magnitude of  $q_t - q_b$  exceeds -70%, the  $\Delta T$  Trip Setpoint shall be automatically reduced by 0.0% of its value at RATED THERMAL POWER; and
- (3) For each percent that the magnitude of  $q_t - q_b$  exceeds +8%, the  $\Delta T$  Trip Setpoint shall be automatically reduced by 2.65% of its value at RATED THERMAL POWER.

**Over-power  $\Delta T$  Setpoint Parameter Values**

- $\tau_1$  measured reactor vessel  $\Delta T$  lead/lag time constant,  $\tau_1 = 8$  sec
- $\tau_2$  measured reactor vessel  $\Delta T$  lead/lag time constant,  $\tau_2 = 3$  sec
- $\tau_3$  measured reactor vessel  $\Delta T$  lag time constant,  $\tau_3 = 0$  sec
- $\tau_6$  measured reactor vessel average temperature lag time constant,  $\tau_6 = 0$  sec
- $\tau_7$  Time constant utilized in the rate-lag compensator for  $T_{avg}$ ,  $\tau_7 = 10$  sec
- $K_4$  Overpower  $\Delta T$  reactor trip setpoint,  $K_4 = 1.08$
- $K_5$  Overpower  $\Delta T$  reactor trip setpoint  $T_{avg}$  rate/lag coefficient,  $K_5 = 0.02/^{\circ}F$  for increasing average temperature, and  $K_5 = 0$  for decreasing average temperature
- $K_6$  Overpower  $\Delta T$  reactor trip setpoint  $T_{avg}$  heatup coefficient  $K_6 = 0.002/^{\circ}F$  for  $T > T''$ , and  $K_6 = 0$  for  $T \leq T''$
- $T''$  Indicated full power  $T_{avg}$ ,  $T'' \leq 592.0$   $^{\circ}F$
- $f_2(\Delta I) = 0$  for all  $(\Delta I)$

**2.3 MODERATOR TEMPERATURE COEFFICIENT (Specification 3.1.1.3):**

- 2.3.1 The BOL, ARO, MTC shall be less positive than the limits shown in Figure 2.
- 2.3.2 The EOL, ARO, HFP, MTC shall be less negative than -61.2 pcm/ $^{\circ}F$ .
- 2.3.3 The 300 ppm, ARO, HFP, MTC shall be less negative than -53.6 pcm/ $^{\circ}F$  (300 ppm Surveillance Limit).

where: BOL stands for Beginning-of-Cycle Life  
 EOL stands for End-of-Cycle Life  
 ARO stands for All Rods Out  
 HFP stands for Hot Full Power (100% RATED THERMAL POWER)  
 HFP vessel average temperature is 592  $^{\circ}F$

**2.4 ROD INSERTION LIMITS (Specification 3.1.3.5 and 3.1.3.6):**

- 2.4.1 All banks shall have the same Full Out Position (FOP) of at least 250 steps withdrawn but not exceeding 259 steps withdrawn.
- 2.4.2 The Control Banks shall be limited in physical insertion as specified in Figure 3.
- 2.4.3 Individual Shutdown bank rods are fully withdrawn when the Bank Demand Indication is at the FOP and the Rod Group Height Limiting Condition for Operation is satisfied (T.S. 3.1.3.1).

**2.5 AXIAL FLUX DIFFERENCE (Specification 3.2.1):**

- 2.5.1 AFD limits as required by Technical Specification 3.2.1 are determined by CAOC Operations with an AFD target band of +5, -10%.
- 2.5.2 The AFD shall be maintained within the ACCEPTABLE OPERATION portion of Figure 4, as required by Technical Specifications.

**2.6 HEAT FLUX HOT CHANNEL FACTOR (Specification 3.2.2):**

- 2.6.1  $F_Q^{RTP} = 2.55$ .
- 2.6.2  $K(Z)$  is provided in Figure 5.
- 2.6.3 The  $F_{xy}$  limits for RATED THERMAL POWER ( $F_{xy}^{RTP}$ ) within specific core planes shall be:
  - 2.6.3.1 Less than or equal to 2.102 for all cycle burnups for all core planes containing Bank "D" control rods, and
  - 2.6.3.2 Less than or equal to the appropriate core height-dependent value from Table 1 for all unrodded core planes.
  - 2.6.3.3  $PF_{xy} = 0.2$ .

These  $F_{xy}$  limits were used to confirm that the heat flux hot channel factor  $F_Q(Z)$  will be limited by Technical Specification 3.2.2 assuming the most-limiting axial power distributions expected to result for the insertion and removal of Control Banks C and D during operation, including the accompanying variations in the axial xenon and power distributions, as described in WCAP-8385. Therefore, these  $F_{xy}$  limits provide assurance that the initial conditions assumed in the LOCA analysis are met, along with the ECCS acceptance criteria of 10 CFR 50.46.

**2.7 ENTHALPY RISE HOT CHANNEL FACTOR (Specification 3.2.3):**

- 2.7.1  $F_{AH}^{RTP} = 1.557^1$
- 2.7.2  $PF_{AH} = 0.3$

**2.8 DNB PARAMETERS (Specification 3.2.5):**

- 2.8.1 The following DNB-related parameters shall be maintained within the following limits:<sup>2</sup>
  - a. Reactor Coolant System  $T_{avg} \leq 595$  °F<sup>3</sup>,
  - b. Pressurizer Pressure,  $> 2200$  psig<sup>4</sup>,
  - c. Minimum Measured Reactor Coolant System Flow<sup>5</sup>  $> 403,000$  gpm.

**3.0 REFERENCES**

- 3.1 Letter from T. D. Croyle (Westinghouse) to D. F. Hoppes (STPNOC), "Unit 2 Cycle 10 Final Reload Evaluation," NF-TG-02-86 (ST-UB-NOC-02002294), October 1, 2002.
- 3.2 NUREG-1346, Technical Specifications, South Texas Project Unit Nos. 1 and 2.
- 3.3 STPNOC Calculation ZC-7035, Rev. 1, "Loop Uncertainty Calculation for RCS Tavg Instrumentation," October 19, 1998.
- 3.4 STPNOC Calculation ZC-7032, Rev. 3, "Loop Uncertainty Calculation for Narrow Range Pressurizer Pressure Monitoring Instrumentation," June 27, 2001.

<sup>1</sup> Applies to all fuel in the Unit 2 Cycle 10 Core

<sup>2</sup> A discussion of the processes to be used to take these readings is provided in the basis for Technical Specification 3.2.5

<sup>3</sup> Includes a 1.9 °F measurement uncertainty per Reference 3.3

<sup>4</sup> Limit not applicable during either a Thermal Power ramp in excess of 5% of RTP per minute or a Thermal Power step in excess of 10% RTP. Includes a 10.7 psi measurement uncertainty as read on QDPS display per Reference 3.4.

<sup>5</sup> Includes a 2.8% flow measurement uncertainty.

Figure 1

Reactor Core Safety Limits - Four Loops in Operation




Figure 2

MTC versus Power Level







Figure 3

### Control Rod Insertion Limits\* versus Power Level



\*Control Bank A is already withdrawn to Full Out Position. Fully withdrawn region shall be the condition where shutdown and control banks are at a position within the interval of 250 and ≤259 steps withdrawn, inclusive.

Figure 4

**AFD Limits versus Rated Thermal Power**





Figure 5

K(Z) - Normalized  $F_Q(Z)$  versus Core Height



**Table 1 (Part 1 of 2)**  
**Unrodded F<sub>xy</sub> for Each Core Height**  
**for Cycle Burnups Less Than 9000 MWD/MTU**

<u>Core Height (Ft.)</u>	<u>Axial Point</u>	<u>Unrodded F<sub>xy</sub></u>	<u>Core Height (Ft.)</u>	<u>Axial Point</u>	<u>Unrodded F<sub>xy</sub></u>
14.00	1	5.689	6.80	37	1.955
13.80	2	4.773	6.60	38	1.937
13.60	3	3.857	6.40	39	1.921
13.40	4	2.941	6.20	40	1.907
13.20	5	2.493	6.00	41	1.893
13.00	6	2.193	5.80	42	1.878
12.80	7	2.172	5.60	43	1.867
12.60	8	2.123	5.40	44	1.856
12.40	9	2.087	5.20	45	1.853
12.20	10	2.058	5.00	46	1.856
12.00	11	2.033	4.80	47	1.860
11.80	12	2.018	4.60	48	1.865
11.60	13	2.017	4.40	49	1.871
11.40	14	2.018	4.20	50	1.881
11.20	15	2.016	4.00	51	1.892
11.00	16	2.011	3.80	52	1.898
10.80	17	2.005	3.60	53	1.901
10.60	18	2.000	3.40	54	1.899
10.40	19	1.995	3.20	55	1.897
10.20	20	1.992	3.00	56	1.901
10.00	21	1.989	2.80	57	1.907
9.80	22	1.987	2.60	58	1.914
9.60	23	1.986	2.40	59	1.917
9.40	24	1.984	2.20	60	1.921
9.20	25	1.983	2.00	61	1.917
9.00	26	1.983	1.80	62	1.911
8.80	27	1.986	1.60	63	1.904
8.60	28	1.989	1.40	64	1.908
8.40	29	1.995	1.20	65	1.950
8.20	30	2.004	1.00	66	2.039
8.00	31	2.015	0.80	67	2.260
7.80	32	2.028	0.60	68	2.641
7.60	33	2.028	0.40	69	3.094
7.40	34	2.014	0.20	70	3.547
7.20	35	1.990	0.00	71	4.001
7.00	36	1.971			

**Table 1 (Part 2 of 2)**  
**Unrodded F<sub>xy</sub> for Each Core Height**  
**for Cycle Burnups Greater Than or Equal to 9000 MWD/MTU**

<u>Core Height</u> <u>(Ft.)</u>	<u>Axial</u> <u>Point</u>	<u>Unrodded F<sub>xy</sub></u>	<u>Core Height</u> <u>(Ft.)</u>	<u>Axial</u> <u>Point</u>	<u>Unrodded F<sub>xy</sub></u>
14.00	1	4.440	6.80	37	2.075
13.80	2	3.949	6.60	38	2.085
13.60	3	3.400	6.40	39	2.096
13.40	4	2.827	6.20	40	2.094
13.20	5	2.474	6.00	41	2.088
13.00	6	2.189	5.80	42	2.077
12.80	7	2.171	5.60	43	2.066
12.60	8	2.140	5.40	44	2.054
12.40	9	2.114	5.20	45	2.044
12.20	10	2.088	5.00	46	2.035
12.00	11	2.065	4.80	47	2.027
11.80	12	2.055	4.60	48	2.021
11.60	13	2.054	4.40	49	2.010
11.40	14	2.058	4.20	50	1.998
11.20	15	2.063	4.00	51	1.983
11.00	16	2.070	3.80	52	1.970
10.80	17	2.071	3.60	53	1.959
10.60	18	2.071	3.40	54	1.949
10.40	19	2.070	3.20	55	1.934
10.20	20	2.072	3.00	56	1.917
10.00	21	2.076	2.80	57	1.895
9.80	22	2.082	2.60	58	1.870
9.60	23	2.083	2.40	59	1.844
9.40	24	2.081	2.20	60	1.813
9.20	25	2.077	2.00	61	1.798
9.00	26	2.071	1.80	62	1.786
8.80	27	2.061	1.60	63	1.779
8.60	28	2.051	1.40	64	1.778
8.40	29	2.044	1.20	65	1.806
8.20	30	2.038	1.00	66	1.870
8.00	31	2.032	0.80	67	2.031
7.80	32	2.031	0.60	68	2.295
7.60	33	2.034	0.40	69	2.590
7.40	34	2.042	0.20	70	2.828
7.20	35	2.053	0.00	71	2.885
7.00	36	2.065			