

Containment Spray and Cooling Systems  
3.6.6

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE		FREQUENCY
SR 3.6.6.4	Verify each containment spray pump's developed head at the flow test point is greater than or equal to the required developed head.	In accordance with the Inservice Testing Program
SR 3.6.6.5	Verify each automatic containment spray valve in the flow path that is not locked, sealed, or otherwise secured in position, actuates to the correct position on an actual or simulated actuation signal.	18 months
SR 3.6.6.6	Verify each containment spray pump starts automatically on an actual or simulated actuation signal.	18 months
SR 3.6.6.7	Verify each containment cooling train starts automatically on an actual or simulated actuation signal.	18 months
SR 3.6.6.8	Verify each spray nozzle is unobstructed.	Following maintenance that could result in nozzle blockage  <u>OR</u> Following fluid flow through the nozzles