

**SURVEILLANCE REQUIREMENTS**

SURVEILLANCE		FREQUENCY
SR 3.6.6.7	Verify each containment spray pump starts automatically on an actual or simulated actuation signal.	18 months
SR 3.6.6.8	Verify each containment cooling fan starts automatically on an actual or simulated actuation signal.	18 months
SR 3.6.6.9	Verify each spray nozzle is unobstructed.	Following maintenance which could result in nozzle blockage