OFFSITE DOSE CALCULATION MANUAL (ODCM) (Continued)

c. Shall be submitted to the Commission in the form of a complete, legible copy of the entire ODCM as a part of or concurrent with the Annual Radioactive Effluent Release Report for the period of the report in which any change to the ODCM was made. Each change shall be identified by markings in the margin of the affected pages, clearly indicating the area of the page that was changed, and shall indicate the date (e.g., month/year) the change was implemented.

6.16 Moved to the PROCESS CONTROL PROGRAM.

6.17 Containment Leakage Rate Testing Program

A program shall be established to implement the leakage rate testing of the containment as required by 10 CFR 50.54(o) and 10 CFR 50, Appendix J, Option B, as modified by approved exemptions (1). This program shall be in accordance with the guidelines contained in Regulatory Guide 1.163, "Performance-Based Containment Leak-Test Program," dated September 1995, except that the next Type A test performed after the May 29, 1993 Type A test shall be performed no later than May 28, 2008.

The peak calculated containment internal pressure for the design basis loss of coolant accident, P_a , is 40.0 psig.

The maximum allowable containment leakage rate, L_a , at P_a , shall be 0.10% of containment air weight per day.

Leakage Rate acceptance criteria are:

containment leakage rate acceptance criterion is $\leq 1.0~L_a$ for the overall Type A leakage test and $< 0.60~L_a$ for the Type B and Type C tests on a minimum pathway leakage rate (MNPLR) basis. During the first unit startup following testing in accordance with this program, the leakage rate acceptance criteria are $< 0.60~L_a$ on a maximum pathway leakage rate (MXPLR) basis for Type B and Type C tests and $< 0.75~L_a$ for Type A tests.

⁽¹⁾ Exemptions to Appendix J of 10 CFR 50 dated November 19, 1984, December 5, 1984, and July 26, 1995.

⁽²⁾ For penetrations which are isolated by use of a closed valve(s), blind flange(s), or de-activated automatic valve(s), the MXPLR of the isolated penetration is assumed to be the measured leakage through the isolation device(s).

6.14 OFFSITE DOSE CALCULATION MANUAL (ODCM)

Changes to the ODCM:

- Shall be documented and records of reviews performed shall retained in accordance with the applicable record retention provision of the quality assurance program description included in the Updated Final Safety Analysis Report. This documentation shall contain:
 - Sufficient information to support the change together 1) with the appropriate analyses or evaluations justifying the change(s) and
 - A determination that the change will maintain the 2) level of radioactive effluent control required by 10 CFR 20.1302, 40 CFR Part 190, 10 CFR 50.36a, and Appendix I to 10 CFR Part 50 and not adversely impact the accuracy or reliability of effluent, dose, or setpoint calculations.
- Shall become effective after review and acceptance by the OSC and the approval of the plant manager, predesignated alternate or a predesignated manager to whom the plant manager has assigned in writing the responsibility for review and approval of specific subjects.
- Shall be submitted to the Commission in the form of a c. complete, legible copy of the entire ODCM as a part of or concurrent with the Annual Radioactive Effluent Release Report for the period of the report in which any change to the ODCM was made. Each change shall be identified by markings in the margin of the affected pages, clearly indicating the area of the page that was changed, and shall indicate the date (e.g., month/year) the change was implemented.

6.16 Moved to the PROCESS CONTROL PROGRAM.

6.17 CONTAINMENT LEAKAGE RATE TESTING PROGRAM

A program shall be established to implement the leakage rate testing of the containment as required by 10 CFR 50.54 (o) and 10 CFR 50, Appendix J, Option B, as modified by approved exemptions (1). This program shall be in accordance with the guidelines contained in Regulatory Guide 1.163, "Performance-Based Containment Leak-Test Program, dated September 1995, except that the next Type A test performed after the November 10, 1993 Type A test shall be performed no later than November 9, 2008.

Exemptions to Appendix J of 10 CFR 50, as stated in the (1) operating license.