ENCLOSURE 1

UNITED STATES NUCLEAR REGULATORY COMMISSION WASHINGTON, D.C. 20555

IE Bulletin No. 79-14 Date: July 2, 1979 Page 1 of 3

SEISMIC ANALYSES FOR AS-BUILT SAFETY-RELATED PIPING SYSTEMS

Description of Circumstances:

Recently two issues were identified which can cause seismic analysis of safety-related piping systems to yield nonconservative results. One issue involved algebraic summation of loads in some seismic analyses. This was addressed in show cause orders for Beaver Valley, Fitzpatrick, Maine Yankee and Surry. It was also addressed in IE Bulletin 79-07 which was sent to all power reactor licensees.

The other issue involves the accuracy of the information input for seismic analyses. In this regard, several potentially unconservative factors were discovered and subsequently addressed in IE Bulletin 79-02 (pipe supports) and 79-04 (valve weights). During resolution of these concerns, inspection by IE and by licensees of the as-built configuration of several piping systems revealed a number of nonconformances to design documents which could potentially affect the validity of seismic analyses. Nonconformances are identified in Appendix A to this bulletin. Because apparently significant nonconformances to design documents have occurred in a number of plants, this issue is generic.

The staff has determined, where design specifications and drawings are used to obtain input information for seismic analysis of safety-related piping systems, that it is essential for these documents to reflect as-built configurations. Where subsequent use, damage or modifications affect the condition or configuration of safety-related piping systems as described in documents from which seismic analysis input information was obtained, the licensee must consider the need to re-evaluate the seismic analyses to consider the as-built configuration.

Action to be taken by Licensees and Permit Holders:

All power reactor facility licensees and construction permit holders are requested to verify, unless verified to an equivalent degree within the last 12 months, that the seismic analysis applies to the actual configuration of safety-related piping systems. The safety related piping includes Seismic Category I systems as defined by Regulatory Guide 1.29, "Seismic

IE Bulletin No. 79-14 Date: July 2, 1979 Page 2 of 3

Design Classification" Revision 1, dated August 1, 1973 or as defined in the applicable FSAR. For older plants, where Seismic Category I requirements did not exist at the time of licensing, it must be shown that the actual configuration of these safety-related systems meets design requirements.

Specifically, each licensee is requested to:

- 1. Identify inspection elements to be used in verifying that the seismic analysis input information conforms to the actual configuration of safety-related systems. For each safety-related system, submit a list of design documents, including title, identification number, revision, and date, which were sources of input information for the seismic analyses. Also submit a description of the seismic analysis input information which is contained in each document. Identify systems or portions of systems which are planned to be inspected during each sequential inspection identified in Items 2 and 3. Submit all of this information within 30 days of the date of this bulletin.
- 2. For portions of systems which are normally accessible*, inspect one system in each set of redundant systems and all nonredundant systems for conformance to the seismic analysis input information set forth in design documents. Include in the inspection: pipe run geometry; support and restraint design, locations, function and clearance (including floor and wall penetration); embedments (excluding those covered in IE Bulletin 79-02); pipe attachments; and valve and valve operator locations and weights (excluding those covered in IE Bulletin 79-04). Within 60 days of the date of this bulletin, submit a description of the results of this inspection. Where nonconformances are found which affect operability of any system, the licensee will expedite completion of the inspection described in Item 3.

^{*}Normally accessible refers to those areas of the plant which can be entered during reactor operation.

IE Bulletin No. 79-14 Date: July 2, 1979 Page 3 of 3

3. In accordance with Item 2, inspect all other normally accessible safety-related systems and all normally inaccessible safety-related systems. Within 120 days of the date of this bulletin, submit a description of the results of this inspection.

4. If nonconformances are identified:

- A. Evaluate the effect of the nonconformance upon system operability under specified earthquake loadings and comply with applicable action statements in your technical specifications including prompt reporting.
- B. Submit an evaluation of identified nonconformances on the validity of piping and support analyses as described in the Final Safety Analysis Report (FSAR) or other NRC approved documents. Where you determine that reanalysis is necessary, submit your schedule for: (i) completing the reanalysis, (ii) comparisons of the results to FSAR or other NRC approved acceptance criteria and (iii) submitting descriptions of the results of reanalysis.
- C. In lieu of B, submit a schedule for correcting nonconforming systems so that they conform to the design documents. Also submit a description of the work required to establish conformance.
- D. Revise documents to reflect the as-built conditions in plant, and describe measures which are in effect which provide assurance that future modifications of piping systems, including their supports, will be reflected in a timely manner in design documents and the seismic analysis.

Facilities holding a construction permit shall inspect safety-related systems in accordance with Items 2 and 3 and report the results within 120 days.

Reports shall be submitted to the Regional Director with copies to the Director of the Office of Inspection and Enforcement and the Director of the Division of Operating Reactors, Office of Nuclear Reactor Regulation, Washington, D.C. 20555.

Approved by GAO (R0072); clearance expires 7/31/80. Approval was given under a blanket clearance specifically for generic problems.

APPENDIX A

PLANTS WITH SIGNIFICANT DIFFERENCES BETWEEN ORIGINAL DESIGN AND AS-BUILT CONDITION OF PIPING SYSTEMS

| 61 4 | Difference | Demonito |
|-------------------|---|--|
| Plant | Difference | Remarks |
| Surry 1 | Mislocated supports. Wrong Support Type. Different Pipe Run Geometry. | As built condition caused majority of pipe overstress problems, not algebraic summation. |
| Beaver Valley | Not specifically identified. Licensee reported "as-built conditions differ signifi- cantly from orginal design." | As built condition resulted in both pipe and support overstress. |
| Fitzpatrick | IE inspection identified differences similar to Surry. | Licensee is using as built configuration for reanalysis. |
| Pi1grim | Snubber sizing wrong. Snubber pipe attachment welds and snubber support assembly nonconformances. | Plant shutdown to restore original design condition. |
| Brunswick 1 and 2 | Pipe supports undersize. | Both units shutdown to restore original design condition. |
| Ginna | Pipe supports not built to original design. | Supports were repaired during refueling outage. |
| St. Lucie | Missing seismic supports. Supports on wrong piping. | Install corrected supports before start up from refueling. |

Page 2

APPENDIX A

| Plant | Difference | Remarks |
|-----------------|---|--|
| Nine Mile Point | Missing seismic supports. | Installed supports before startup from refueling. |
| Indian Point 3 | Support location and support construction deviations. | Licensee performing as built verification to be completed by July 1. |
| Davis-Besse . | Gussets missing from main Steam Line Supports. | Supports would be over- stressed. Repairs will be completed prior to start- up. |

IE Bulletin No. 79-14 Date: July 2, 1979 Page 1 of 4

ENCLOSURE 2

LISTING OF IE BULLETINS ISSUED IN LAST TWELVE MONTHS

| Bulletin No. | Subject | Date Issued | Issued To |
|-----------------|--|-------------|--|
| 78-11 | Examination of Mark I Containment Torus Welds | 7/24/78 | BWR Power Reactor Facilities with an OL for action: Peach Bottom 2 and 3, Quad Cities 1 and 2, Hatch 1, Monticello and Vermont Yankee. All other BWR Power Reactor Facilities with an OL for information |
| 78-12 | Atypical Weld Material in Reactor Pressure Vessel Welds | 9/29/78 | All Power Reactor Facilities with an OL or CP |
| 78-12A | Atypical Weld Material in Reactor Pressure Vessel Welds | 11/24/78 | All Power Reactor Facilities with an OL or CP |
| 78-12B | Atypical Weld Material in Reactor Pressure Vessel Welds | 3/19/79 | All Power Reactor Facilities with an OL or CP |
| 78-13 | Failures In Source Heads of Kay-Ray, Inc., Gauges Models 7050, 70508, 7051, 70518, 7060, 70608, 7061 and 70618 | 10/27/78 | All General and Specific Licensees with the subject Kay-Ray, Inc. Gauges |
| 78-14 | Deterioration of Buna-N Components In ASCO Solenoids | 12/19/78 | All GE BWR Faci- lities with an OL (for action), and all other Power Reactor Facilities with an OL or CP (for information) |

IE Bulletin No. 79-14 Date: July 2, 1979 Page 2 of 4

LISTING OF IE BULLETINS ISSUED IN LAST TWELVE MONTHS (CONTINUED)

| Bulletin No. | Subject | Date Issued | Issued To |
|------------------------------|--|-------------|--|
| 79-01 | Environmental Qualif- ication of Class IE Equipment | 2/8/79 | All Power Reactor Facilities with an OL, except the 11 Systematic Evaluation Program Plants (for action), and all other Power Reactor Facilities with an OL or CP (For Information) |
| 79-01A | Environmental Qualification of Class 1E Equipment (Deficiencies in the Environmental Qualification of ASCO Solenoid Valves) | 6/6/79 | All Power Reactor Facilities with an OL or CP |
| 79-02 | Pipe Support Base Plate Design Using Concrete Expansion Anchor Bolts | 3/8/79 | All Power Reactor Facilities with an OL or CP |
| 79-02 (Revision No. 1) | Same Title as 79-02 | 6/21/79 | Same as 79-02 |
| 79-03 | Longitudinal Weld Defects in ASME SA-312 Type 304 Stainless Steel Pipe Spools Manufactured by Youngstown Welding and Engineering Company | 3/12/79 | All Power Reactor Facilities with an OL or CP |
| 79-04 | Incorrect Weights for Swing Check Valves Manufactured by Velan Engineering Corporation | 3/30/79 | All Power Reactor Facilities with an OL or CP |
| 79-05 | Nuclear Incident at Three Mile Island | 4/1/79 | All Babcock and Wilcox Power Reactor Facilities with an OL, Except Three Mile Island 1 and 2 (For Action), and All Other Power Reactor Facilities With an OL or CP (For Information) |

IE Bulletin No. 79-14 Date: July 2, 1979 Page 3 of 4

LISTING OF IE BULLETINS ISSUED IN LAST TWELVE MONTHS (CONTINUED)

| | | | • |
|------------------------|--|-------------|---|
| Bulletin No. | Subject | Date Issued | Issued to |
| 79-05A | Nuclear Incident at Three Mile Island - Supplement | 4/5/79 | Same as 79-05 |
| 79-06 | Review of Operational Errors and System Mis- alignments Identified During the Three Mile Incident | 4/11/79 | All Pressurized Water Power Reactor Facil- ities with an OL Except B&W Facilities (For Action), All Other Power Reactor Facil- ities with an OL or CP (For Information) |
| 79-06A | Same Title as 79-06 | 4/14/79 | All Westinghouse Designed Pressurized Power Reactor Facil- ities with an OL (For Action), and All Other Power Reactor Facilities with an OL or CP (For Information) |
| 79-06A (Revision 1) | Same Title as 79-06 | 4/18/79 | All Westinghouse Designed Pressurized Power Reactor Facil- ities with an OL (For Action), and All Other Power Reactor Facilities with an OL or CP (For Information) |
| 79-06B | Same Title as 79-06 | 4/14/79 | All Combustion Engineering Designed Pressurized Power Reactor Facilities with an OL (For Action), and All Other Power Reactor Facilities with an OL or CP (For Information) |
| 79-07 | Seismic Stress Analysis of Safety-Related Piping | 4/14/79 | All Power Reactor Facilities with an OL or CP |

Enclosure 2

IE Bulletin No. 79-14 Date: July 2, 1979 Page 4 of 4

LISTING OF IE BULLETINS ISSUED IN LAST TWELVE MONTHS (CONTINUED)

| Bulletin No. | Subject | Date Issued | Issued to |
|-----------------|--|-------------|---|
| 79-0 8 | Events Relevant to Boiling Water Power Reactors Identified During Three Mile Island Incident | 4/14/79 | All BWR Power Reactor Facilities with an OL (For Action), All Other Power Reactor Facil- ities with an OL or CP (For Information) |
| 79-09 | Failures of GE Type AK-2 Type Circuit Breaker in Safety Related Systems | 4/17/79 | All Power Reactor Facilities with an OL or CP |
| 79-10 | Requalification Training Program Statistics | 5/11/79 | All Power Reactor Facilities with an OL |
| 79-11 | Faulty Overcurrent Trip Device in Circuit Breakers for Engineered Safety Systems | 5/22/79 | All Power Reactor Facilities with an OL or CP |
| 79-12 | Short Period Scrams at BWR Facilities | 5/31/79 | All GE BWR Facilities with an OL |
| 79-13 | Cracking in Feedwater System Piping | 6/25/79 | All PWRs with an OL (for Action), All Other Power Reactor Facilities with an OL or CP (For Information) |

LIS ORIGINAL

SSINS: 6820 Accession No: 7908080360

UNITED STATES
NUCLEAR REGULATORY COMMISSION
OFFICE OF INSPECTION AND ENFORCEMENT
WASHINGTON, D.C. 20555

August 15, 1979

Supplement IE Bulletin No. 79-14

SEISMIC ANALYSIS FOR AS-BUILT SAFETY-RELATED PIPING SYSTEMS

Description of Circumstances:

IE Bulletin No. 79-14 was issued on July 2, 1979 and revised on July 18, 1979 The bulletin requested licensees to take certain actions to verify that seism analyses are applicable to as-built plants. This supplement to the bulletin provides additional guidance and definition of Action Items 2, 3, and 4.

To comply with the requests in IE Bulletin 79-14, it will be necessary for li ensees to do the following:

2. Inspect Part of the Accessible Piping

For each system selected by the licensee in accordance with Item 2 of the Bulletin, the licensee is expected to verify by physical inspection, to the extent practicable, that the inspection elements meet the acceptance criteria. In performing these inspections, the licensee is expected to use measuring techniques of sufficient accuracy to demonstrate that acceptance criteria are met. Where inspection elements important to the seismic analysis cannot be viewed because of thermal insulation or location of the piping, the licensee is expected to remove thermal insulation or provide access. Where physical inspect: is not practicable, e.g., for valve weights and materials of construction the license is expected to verify conformance by inspection of quality assurance records. If a nonconformance is found, the licensee is expecin accordance with Item 4 of the Bulletin to perform an evaluation of the significance of the nonconformance as rapidly as possible to determine whether or not the operability of the system might be jeopardized durin: a safe shutdown earthquake as defined in the Regulations. This evaluat is expected to be done in two phases involving an initial engineering judgement (within 2 days), followed by an analytical engineering evalua (within 30 days). Where either phase of the evaluation shows that syst operability is in jeopardy, the licensee is expected to meet the application technical specification action statement and complete the inspections required by Item 2 and 3 of the Bulletin as soon as possible. The lice must report the results of these inspections in accordance with the rements for content and schedule as given in Item 2 and 3 of the Bulletin

3. Inspect Remaining Piping

The licensee is expected to inspect, as in Item 2 above, the remaining safety-related piping systems which were seismically analyzed and to report the results in accordance with the requirements for content and schedule as given in Item 3 of the Bulletin.

4A. Evaluate Nonconformances

With regard to Item 3A for the Bulletin, the licensee is expected to include in the initial engineering judgement his justification for continued reactor operation. For the analytical engineering evaluation the licensee is expected to perform the evaluation by using the same analytical technique used in the seismic analysis or by an alternate, less complex technique provided that the licensee can show that it is conservative.

If either part of the evaluation shows that the system may not perform its intended function during a design basis earthquake, the licensee must promptly comply with applicable action statements and reporting requirements in the Technical Specifications.

4B. Submit Nonconformance Evaluations

The licensee is expected to submit evaluations of all nonconformances and, where the licensee concludes that the seismic analysis may not be conservative, submit schedules for reanalysis in accordance with Item 4B of the Bulletin or correct the noncomformances.

4C. Correct Nonconformances

If the licensee elects to correct nonconformances, the licensee is expected to submit schedules and work descriptions in accordance with Item 4C of the Bulletin.

4D. Improve Quality Assurance

If noncomformances are identified, the licensee is expected to evaluat and improve quality assurance procedures to assure that future modific tions are handled efficiently. In accordance with Item 4D of the Bull the licensee is expected to revise design documents and seismic analys in a timely manner.

The schedule for the action and reporting requirements given in the Bullet as originally issued remains unchanged.

Approved by GAO, B180225 (R0072), clearance expires July 31, 1980. Approved was given under a blanket clearance specifically for identified generic presents.

Supplement IE Bulletin No. 79-14 August 15, 1979

LISTING OF IE BULLETINS ISSUED IN LAST SIX MONTHS

| Bulletin No. | Subject | Date Issued | Issued To |
|-------------------|---|-------------|--|
| 79-18 | Audibility Problems Encountered on Evaluation of Personnel From High Noise Areas | | All Power Reactor facilities with an OL |
| .79-17 | Pipe Cracks in Stagnant Borated Water Systems at PWR Plants | 7/26/79 | All PWR's with operating license |
| 79-16 | Vital Area Access Controls | 7/26/79 | All Holders of and applicants for Powe Reactor Operating 1 who anticipate load prior to 1981 |
| 79-15 | Deep Draft Pump Deficiencies | 7/11/79 | All Power Reactor Licensees with a Cand/or OL |
| 79-14 | Seismic Analyses for As-Built Safety-Related Piping System | 6/2/79 | All Power Reactor facilities with an OL or a CP |
| 79-13 | Cracking In Feedwater System Piping | 6/25/79 | All PWRs with an OL for action. All BWRs with a CP for information. |
| 79-02 (Rev. 1) | Pipe Support Base Plate Designs Using Concrete Expansion Anchor Bolts | 6/21/79 | All Power Reactor Facilities with ar OL or a CP |
| 79-12 | Short Period Scrams at BWR Facilities | 5/31/79 | All GE BWR Facilit with an OL |
| 79-11 | Faulty Overcurrent Trip Device in Circuit Breakers for Engineered Safety Systems | 5/22/79 | All Power Reactor Facilities with a OL or a CP |
| 79-10 | Requalification Training Program Statistics | 5/11/79 | All Power Reactor Facilities with a |

Supplement IE Bulletin No. 79-14 August 15, 1979

LISTING OF IE BULLETINS ISSUED IN LAST SIX MONTHS

| Bulletin No. | Subject | Date Issued | Issued To |
|-------------------|--|-------------|---|
| 79-09 | Failures of GE Type AK-2 Circuit Breaker in Safety Related Systems | 4/17/79 | All Power Reactor Facilities with a OL or CP |
| 79-08 | Events Relevant to BVR Reactors Identified During Three Mile Island Incident | 4/14/79 | All BWR Power Rea Facilities with a |
| 79-07 | Seismic Stress Analysis of Safety-Related Piping | 4/14/79 | All Power Reactor Facilities with a OL or CP |
| 79-05C&06C | Nuclear Incident at Three Mile Island - Supplement | 7/26/79 | To all PWR Power Reactor Facilities with an OL |
| 79 - 06B | Review of Operational Errors and System Mis- alignments Identified During the Three Mile Island Incident | 4/14/79 | All Combustion E ing Designed Pre Water Power Reac Facilities with Operating Licens |
| 79-06A (Rev 1) | Review of Operational Errors and System Micalignments Identified During the Three Mile Island Incident | 4/18/79 | All Pressurized Power Reactor Fa of Westinghouse with an OL |
| 79-06A | Review of Operational Errors and System Mis- alignments Identified During the Three Mile Island Incident | 4/14/79 | All Pressurized Power Reactor For Westinghouse with an OL |
| 79-06 | Review of Operational Errors and System Mis- alignments Identified During the Three Mile Island Incident | 4/11/79 | All Pressurized Power Reactors OL except B&W f |

Supplement IE Bulletin No. 79-14 August 15, 1979 Enclosure Page 3 of 3

LISTING OF IE BULLETINS ISSUED IN LAST SIX MONTHS

| Bulletin No. | Subject | .Date Issued | Issued To |
|--------------|---|--------------|--|
| 79-05B | Nuclear Incident at Three Mile Island | 5/21/79 | All B&W Power Reac Facilities with an |
| 79-05A | Nuclear Incident at Three Mile Island | 4/5/79 | All B&W Power Reac Facilities with an |
| 79-05 | Nuclear Incident at Three Mile Island | 4/2/79 | All Power Reactor Facilities with an OL and CP |
| 79-04 | Incorrect Weights for Swing Check Valves Manufactured by Velan Engineering Corporation | 3/30/79 | All Power Reactor Facilities with an OL or CP |
| 78-12B | Atypical Weld Material in Reactor Pressure Vessel Welds | 3/19/79 | All Power Reactor Facilities with an OL or CP |
| 79-03 | Longitudinal Welds Defects In ASME SA-312 Type 304 Stainless Steel Pipe Spools Manufactured by Youngstown Welding and Engineering Co. | | All Power Reactor Facilities with an OL or CP |
| 79-01A | Environmental Qualification of Class 1E Equipment (Deficiencies in the Environmental Qualification of ASCO Solenoid Valves) | 6/6/79 | All Power Reactor Facilities with a OL or CP |