RESULTS OF THE RADIOLOGICAL SURVEY AT KENNEDY PARK, MONEY AND SIDNEY STREETS, LODI, NEW JERSEY (LJ062)

063990

ORNL/RASA-88/55

R. D. Foley W. D. Cottrell L. M. Floyd

OPERATED BY MARTIN MARIETTA ENERGY SYSTEMS, INC. FOR THE UNITED STATES DEPARTMENT OF ENERGY

Ë

. s.

1.040

1.5

OAK RIDGE

NATIONAL LABORATORY

MARTIN MARIETTA

ORNL/RASA-88/55

063990

HEALTH AND SAFETY RESEARCH DIVISION

1. 1. 1. 1. S. 1.

Nuclear and Chemical Waste Programs (Activity No. AH 10 05 00 0; ONLWC01)

RESULTS OF THE RADIOLOGICAL SURVEY AT KENNEDY PARK, MONEY AND SIDNEY STREETS, LODI, NEW JERSEY (LJ062)

R. D. Foley, W. D. Cottrell, and L. M. Floyd

Date Published – July 1989

Investigation Team

R. E. Swaja – Measurement Applications and Development Manager W. D. Cottrell – FUSRAP Project Director R. D. Foley – Field Survey Supervisor

Survey Team Members

1. S. E.

- 2 × 11 ×

1.00

- 15 -

1.1

A. C. Butler* R. A. Mathis K. S. Dickerson C. A. Muhr C. A. Johnson E. M. Pilz A. K. Klitz W. Winton J. A. Rice (ORAU) W. H. Shinpaugh (Stone Associates)

*Former Employee of Martin Marietta Energy Systems, Inc.

Work performed by the MEASUREMENT APPLICATIONS AND DEVELOPMENT GROUP

> Prepared by the OAK RIDGE NATIONAL LABORATORY Oak Ridge, Tennessee 37831-6285 operated by MARTIN MARIETTA ENERGY SYSTEMS, INC. for the U.S. DEPARIMENT OF ENERGY under Contract No. DE-AC05-840R21400

CONTENTS

LIST OF FIGURES	¥	•
LIST OF TABLES		
 ACKNOWLEDGMENTS	ix	
 ABSTRACT	xi	
INTRODUCTION	1	
SURVEY METHODS	2	
SURVEY RESULTS	3	
Surface Gamma Radiation Levels	3	
SIGNIFICANCE OF FINDINGS	4	
REFERENCES	4	

LIST OF FIGURES

063990

1	Gamma radiation levels measured on the surface at Kennedy Park, Money and Sidney Streets, Lodi, New Jersey (LJ062)	5
2	Diagram showing locations of soil samples taken at Kennedy Park, Money and Sidney Streets, Lodi, New Jersey (LJ062)	6
3	Gamma profile for auger hole 1 at Kennedy Park, Money and Sidney Streets, Lodi, New Jersey	7
4	Gamma profile for auger hole 2 at Kennedy Park, Money and Sidney Streets, Lodi, New Jersey	8

....

1 - 1 - 1 - 1

LIST OF TABLES

063990

1	Applicable guidelines for protection against radiation	9
2	Background radiation levels for the northern New Jersey area	9
3	Concentrations of radionuclides in soil at Kennedy Park, Money and Sidney Streets, Lodi, New Jersey (LJ062)	10

٠

1

ACKNOWLEDGMENTS

996

Research for this project was sponsored by the Division of Facility and Site Decommissioning Projects, U.S. Department of Energy, under Contract No. DE-AC05-84OR21400 with Martin Marietta Energy Systems, Inc. The authors wish to acknowledge the support of J. E. Baublitz, Acting Director, Office of Remedial Action and Waste Technology; J. J. Fiore, Director, Division of Facility and Site Decommissioning Projects; and members of their staffs. The authors also appreciate the contributions of J. L. Rich, S. W. Hawthorne, B. C. Littleton, and L. J. Jeffers of the Publications Division; M. S. Uziel of the Environmental Information Systems Group; D. A. Roberts and T. R. Stewart of the Measurement Applications and Development Group; A. C. Butler and B. S. Ellis, former Employees of Martin Marietta Energy Systems, Inc.; and W. H. Shinpaugh of Don Stone Associates for participation in the collection, analyses, editing, and reporting of data for this survey.

1.12

-1-v-1.

 $(1,1)_{i\in I}$

ABSTRACT

063990

Maywood Chemical Works (MCW) of Maywood, New Jersey, generated process wastes and residues associated with the production and refining of thorium and thorium compounds from monazite ores from 1916 to 1956. MCW supplied rare earth metals and thorium compounds to the Atomic Energy Commission and various other government agencies from the late 1940s to the mid-1950s. Area residents used the sandlike waste from this thorium extraction process mixed with tea and cocoa leaves as mulch in their yards. Some of these contaminated wastes were also eroded from the site into Lodi Brook. At the request of the U.S. Department of Energy (DOE), a group from Oak Ridge National Laboratory conducts investigative radiological surveys of properties in the vicinity of MCW to determine whether a property is contaminated with radioactive residues, principally ²²⁰Th, derived from the MCW site. The survey typically includes direct measurement of gamma radiation levels and soil sampling for radionuclide analyses. The survey of this site, Kennedy Park, Money and Sidney Streets, Lodi, New Jersey (LJ062), was conducted during 1986 and 1987.

Results of the survey demonstrated radionuclide concentrations in excess of the DOE Formerly Utilized Sites Remedial Action Program criteria. The radionuclide distributions are typical of the type of material originating from the MCW site.

in the statistic states and the

RESULTS OF THE RADIOLOGICAL SURVEY AT KENNEDY PARK, MONEY AND SIDNEY STREETS, LODI, NEW JERSEY (LJ062)*

INTRODUCTION

From 1916 to 1956, process wastes and residues associated with the production and refining of thorium and thorium compounds from monazite ores were generated by the Maywood Chemical Works (MCW), Maywood, New Jersey. During the latter part of this period, MCW supplied rare earth metals and thorium compounds to various government agencies. In the 1940s and 1950s, MCW produced thorium and lithium, under contract, for the Atomic Energy Commission (AEC). These activities ceased in 1956, and, approximately three years later, the 30-acre real estate was purchased by the Stepan Company. The property is located at 100 Hunter Avenue in a highly developed area in Maywood and Rochelle Park, Bergen County, New Jersey.

During the early years of operation, MCW stored wastes and residues in low-lying areas west of the processing facilities. In the early 1930s, these areas were separated from the rest of the property by the construction of New Jersey State Highway 17. The Stepan property, the interim storage facility, and several vicinity properties have been designated for remedial action by the U.S. Department of Energy (DOE).

The waste produced by the thorium extraction process was a sandlike material containing residual amounts of thorium and its decay products, with smaller quantities of uranium and its decay products. During the years 1928 and 1944 to 1946, area residents used these process wastes mixed with tea and cocoa leaves as mulch in their lawns and gardens. In addition, some of the contaminated wastes were apparently eroded from the site into Lodi Brook and carried downstream.

Lodi Brook is a small stream flowing south from Maywood with its headwaters near the Stepan waste storage site. Approximately 150 ft after passing under State Route 17, the stream has been diverted underground through concrete or steel culverts until it merges with the Saddle River in Lodi, New Jersey. Only a small section near Interstate 80 remains uncovered. From the 1940s to the 1970s when the stream was being diverted underground, its course was altered several times. Some of these changes resulted in the movement of contaminated soil to the surface of a few properties, where it is still in evidence. In other instances, the contaminated soil was covered over or mixed with clean fill, leaving no immediate evidence on the surface. Therefore, properties in question may be

[•]The survey was performed by members of the Measurement Applications and Development Group of the Health and Safety Research Division at Oak Ridge National Laboratory under U.S. DOE contract DE-AC05-840R21400.

drilled in search of former stream bed material, even in the absence of surface contamination.

As a result of the Energy and Water Appropriations Act of Fiscal Year 1934, the property discussed in this report and properties in its vicinity contaminated with residues from the former MCW were included as a decontamination research and development project under the DOE Formerly Utilized Sites Remedial Action Program. As part of this project, DOE is conducting radiological surveys in the vicinity of the site to identify properties contaminated with residues derived from the MCW. The principal radionuclide of concern is thorium-232. The radiological surveys discussed in this report are part of that effort and were conducted, at the request of DOE, by members of the Measurement Applications and Development Group of the Oak Ridge National Laboratory.

A radiological survey of the public property at Kennedy Park, Money and Sidney Streets, Lodi, New Jersey, was conducted curing 1986 and 1987. The survey and sampling of the ground surface was carried out on November 14-20, 1986, and the follow-up subsurface investigation was performed on June 5, 1987.

SURVEY METHODS

The radiological survey of the property included: (1) a gamma scan of the entire property outdoors, (2) collection of surface and subsurface soil samples, and (3) gamma profiles of auger holes. No indoor survey measurements were performed.

Using a portable gamma scintillation meter, ranges of measurements were recorded for areas of the property surface. If the gamma exposure rates were elevated, a biased soil sample was taken at the point showing the highest gamma radiation level. Systematic soil samples were taken at various locations on the property, irrespective of gamma radiation levels. These survey methods followed the plan outlined in Reference 1.

To define the extent of possible subsurface soil contamination, the auger holes were drilled to depths of approximately 2.7 m. A plastic pipe was placed in each hole, and a NaI scintillation probe was lowered inside the pipe. The probe was encased in a lead shield with a horizontal row of collimating slits on the side. This collimation allows measurement of gamma radiation intensities resulting from contamination within small fractions of the hole depth. Measurements were usually made at 15- or 30-cm intervals. If the gamma readings in the hole were elevated, a soil sample was scraped from the wall of the auger hole at the point showing the highest gamma radiation level. The auger hole loggings were used to select locations where further soil sampling would be useful. A split-spoon sampler was used to collect subsurface samples at known depths. In some auger holes, a combination of split-spoon sampling and side-wall scraping was used to collect samples. A comprehensive description of the survey methods and instrumentation has been presented in another report.²

SURVEY RESULTS

Applicable federal guidelines are summarized in Table 1.³ The normal background radiation levels for the northern New Jersey area are presented in Table 2.⁴ These data are provided for comparison with survey results presented in this section. All direct measurement results presented in this report are gross readings; background radiation levels have not been subtracted. Similarly, background concentrations have not been subtracted from radionuclide concentrations measured in environmental samples.

Surface Gamma Radiation Levels

Gamma radiation levels measured during a gamma scan of the property surface are given in Fig. 1. Gamma exposure rates over the major portion of the property ranged from 8-15 μ R/h. The basketball court, in the eastern corner of the park, ranged from 10-14 μ R/h. The highest measurements found in this corner of the park were 11-24 μ R/h and were taken near the brick building adjacent to this ball court at the intersection of two brick walls. The other side of this court measured 8 and 11 μ R/h, as indicated in Fig. 1. The dugouts in the two baseball courts gave slightly higher readings than these, but the survey indicated that such readings were probably due to the block walls and brick floors. The highest gamma levels found in the park altogether were 11-36 μ R/h, from a strip of ground bordering Money Street on the western corner of the park. This area is indicated in Fig. 1 by crosshatching.

Systematic and Biased Soil Samples

Systematic and biased soil samples were taken from various locations on the property for radionuclide analyses. Locations of the systematic (S) and biased (B) samples are shown in Fig. 2, with results of laboratory analyses provided in Table 3. Concentrations of radium and thorium in the biased samples ranged from 0.71 to 7.8 pCi/g and 2.4 to 91 pCi/g, respectively. All thorium levels at biased sample location B1 were above DOE criteria (Table 1). Radium levels continued to rise with depth in both biased samples, and thorium levels increased at lower depths in sample B2.

Auger Soil Samples

Varying thicknesses of subsurface soil were sampled from depths of 45 to 275 cm in auger holes (A) which were drilled at 2 separate locations indicated in Fig. 2. Auger hole A1 was drilled and logged, in the manner described above, to determine if the location was in the old creek bed. The gamma log of this auger hole indicated an area of possible contamination. The drilling rig was therefore moved one foot west, and the hole redrilled. Samples were taken from the new hole using the split spoon method. Due to the close proximity of the two holes, the second hole was not logged, and both holes were assigned the same hole location and number. The results of analyses of these samples are given in Table 3. Concentrations of ²²⁶Ra and ²³²Th in soil samples from both auger holes ranged from 0.56 to 2.2 and 0.80 to 17 pCi/g, respectively. Radionuclide concentrations in sample A2D (17 pCi/g) were above DOE criteria (Table 1) for thorium; all other values were near or below criteria. Gamma logging was performed in each of the 2 auger holes to characterize and further define the extent of possible contamination. The logging technique used here is not radionuclide specific. However, logging data, in conjunction with soil analyses data, may be used to estimate regions of elevated radionuclide concentrations in auger holes when compared with background levels for the area. Following a comparison of these data, it appears that any shielded scintillator readings of 1000 counts per minute (cpm) or greater generally indicate the presence of elevated concentrations of ²²⁶Ra and/or ²³²Th. Data from the gamma profiles of the logged auger holes are graphically represented in Fig. 3 and Fig. 4. Readings at depths from 1.5 to 2.1 m were greater than 1000 cpm in auger hole A2, with a maximum reading of 3053 cpm at 1.8 m. Readings in auger hole A1 were above 1000 cpm from 1.5 m down, with a maximum reading of 6701 cpm at 2.4 m.

SIGNIFICANCE OF FINDINGS

Measurements taken at Kennedy Park indicate that the property contained radioactive contamination primarily from the 232 Th decay chain. These radionuclide distributions are typical of the type of material originating from the processing operations at the MCW site. The concentration and extent of 232 Th on this property was in excess of the applicable DOE criteria (Table 1). This material was found at sample locations B1, A1, and A2 shown in Fig. 2. Based on the results of this radiological assessment, it is recommended that this site be considered for inclusion in the DOE remedial action program.

REFERENCES

- 1. W. D. Cottrell, ORNL, to A. J. Whitman, DOE/HQ, correspondence, "Radiological Survey of Private Properties in Lodi, New Jersey" (August 15, 1984).
- T. E. Myrick, B. A. Berven, W. D. Cottrell, W. A. Goldsmith, and F. F. Haywood, *Procedures Manual for the ORNL Radiological Survey Activities (RASA) Program*, Oak Ridge National Laboratory, ORNL/TM-8600 (April 1987).
- 3. U.S. Department of Energy, Guidelines for Residual Radioactive Material at Formerly Utilized Sites, Remedial Action Program and Remote Surplus Facilities Management Program Sites (Rev. 2, March 1987).
- 4. T. E. Myrick, B. A. Berven, and F. F. Haywood, State Background Radiation Levels: Results of Measurements Taken During 1975-1979, Oak Ridge National Laboratory, ORNL/TM-7343 (November 1981).


063990


1.12

10.44

1.1


名為






.


in start





LJ062/

Fig. 3. Gamma profile for auger hole 1 at Kennedy Park, Money and Sidney Streets, Lodi, New Jersey.





412470

Stares.

Fig. 4. Gamma profile for auger hole 2 at Kennedy Park, Money and Sidney Streets, Lodi, New Jersey.

Table 1. Applicable guidelines for protection against radiation ^a						
Mode of exposure	Exposure conditions	Guideline value				
Radionuclide concentrations in soil	Maximum permissible concen- tration of the following radionuclides in soil above background levels averaged over 100 m ² area ²³² Th ²³⁰ Th ²²⁸ Ra ²²⁶ Ra	5 pCi/g averaged over the first 15 cm of soil below the surface; 15 pCi/g when averaged over 15-cm thick soil layers more than 15 cm below the surface				

^aReference 3.

•

. . . .

7

Table 2. Background radiation levels for the northern New Jersey area

Type of radiation measurement or sample	Radiation level or radionuclide concentration		
Concentration of radionuclides in soil (pCi/g) ²³² Th	0.9*		
2380	0.9*		
226Ra	0.9*		

^aReference 4.

10

Table 3. Concentrations of radionuclides in soil at Kennedy Park, Money and Sidney Streets, Lodi, New Jersey (LJ062)

		Radionuclide concentration (pCi/g)					
Sample [®]	Depth (cm)	226 R.a.b	235 LP.9				
	• •	Systematic Samples ^a					
S1	0-15	0.56 ± 0.02	1.2 ±0.2				
S2	0-15	0.58 ± 0.09	0.73±0.06				
S3	0-15	0.63 ± 0.07	0.73±0.1				
S4	0-15	0.61 ± 0.1	0.68 ± 0.04				
\$5	0-15	0.60±0.06	0.58 ± 0.08				
		Biased Samples ⁴	·				
B1A	0-15	1.8 ±0.3	15 ±2				
BIB	15-30	2.0 ± 0.2	17 ±0.6				
BIC	30-45	3.6 ± 0.3	36 ±2				
BID	45-60	4.3 ± 0.3	45 ±5				
BIE	60-75	6.8 ±0.6	91 ± 6				
BIF	75-90	7.8 ±0.2	46 ±3				
B2A	0-15	0.71 ± 0.03	2.4 ± 0.3				
B2B	15-30	0.83 ± 0.1	3.4 ± 0.4				
B2C	30-45	1.5 ±0.1	9.3 ±0.8				
		Auger Samples ^e					
AIA	90-105	0.58 ± 0.08	0.80 ± 0.2				
AIB	105-120	0.60 ± 0.04	0.92 ± 0.1				
AIC	135-150	0.72±0.05	1.4 ± 0.03				
AID	150-165	1.2 ± 0.1	5.5 ±0.3				
AIE	165-185	1.6 ±0.2	7.7 ±0.45				
AlF	185-195	1.1 ± 0.08	3.9 ± 0.08				
AIG	195-215	1.4 ± 0.8	12 ±0.5				
AlH	215-225	1.6 ±0.4	15 ±0.6				
AII	225-245	0.80 ± 0.1	1.9 ±0.2				
AIJ	245-255	0.78 ± 0.1	1.2 ± 0.2				
AIK	255-275	0.87 ± 0.1	1.1 ± 0.6				
A2A ·	45-60	0.85±0.9	3.7 ±0.05				
A2B	135-150	0.66 ± 0.06	1.3 ±0.07				
A2C	150-165	0.56 ± 0.1	0.99 ± 0.2				
A2D	165-185	2.2 ± 0.4	17 ± 1.2				
A2E	185-195	0.80 ± 0.03	1.5 ± 0.06				
A2F	195-215	0.77 ± 0.1	1.1 ± 0.1				
A2G	215-225	0.91 ± 0.05	1.3 ± 0.4				

*Locations of soil samples are shown on Fig. 2.

^bIndicated counting error is at the 95% confidence level $(\pm 2\sigma)$.

Systematic samples are taken at locations irrespective of gamma exposure rates.

^dBiased samples are taken from areas shown to have elevated gamma exposure rates.

⁴Auger samples are taken from holes drilled to further define the depth and extent of radioactive material. Holes are drilled where the surface may or may not be contaminated.

INTERNAL DISTRIBUTION

B. A. Berven
 R. F. Carrier
 W. D. Cottrell
 A. G. Croff
 J. W. Crutcher
 L. M. Floyd
 7-11. R. D. Foley
 S. V. Kaye

- P. Y. Lu
 P. T. Owen
 P. T. Owen
 15-17. R. E. Swaja
 I. K. Williams
 Central Research Library
 IR&A Publications Office
 - 21. Laboratory Records RC

063990

ORNL/RASA-82/55

22. Y-12 Technical Library

EXTERNAL DISTRIBUTION

- 23. J. D. Berger, Oak Ridge Associated Universities, P.O. Box 117, Oak Ridge, TN 37831
- 24. R. W. Doane, Eberline, Inc., 800 Oak Ridge Turnpike, P.O. Box 350, Oak Ridge, Tn 37831
- 25. J. J. Fiore, U.S. Department of Energy, 19901 Germantown Road, Germantown, MD 20874
- 26-28. G. K. Hovey, Bechtel National, Inc., 800 Oak Ridge Turnpike, P.O. Box
 350, Oak Ridge, TN 37831
 - 29. L. R. Levis, Roy F. Weston, Inc., 20030 Century Blvd., Germantown, MD 20874
 - 30. G. P. Turi, U.S. Department of Energy, 19901 Germantown Road, Germantown, MD 20874
 - 31. J. W. Wagoner, U.S. Department of Energy, 19901 Germantown Road, Germantown, MD 20874
- 32-34. Andrew Wallo III, U.S. Department of Energy, 19901 Germantown Road, Germantown, MD 20874
 - 35. Office of Assistant Manager, Energy Research and Development, Oak Ridge Operations Office, P.O. Box 2001, Oak Ridge, TN 37831-8600
- 36-37. Office of Scientific and Technical Information, DOE, P.O. Box 62, Oak Ridge, TN 37831

•					0	639	90
	IIIIIII			1111	IIII CCN		
DOE/OF	10 TECH	MMUNICATIONS DISTRIBU INICAL SERVICES DIVISIO NATIONAL, INC. — JOB 14	N (CE-	53)		10	<i>B</i> .
	Uts	of Radi Su	<u>vve</u>	4	at Kenedy Pl	zrk	
money	3 2	sidney St.		<u> </u>	· U		
OP IN		Dist			COMM DATE	9 %	29,89
FROM USUL		IVIVI		28	CD	- F	
	TCLOSES	• • •		10	__V		·
SUBJECT CODE	UAFF	ECTED DOCUMENT	Do L	7			
		RESPONSE TRACKING	NFORM	ATIO	N		7
PRIMARY:							
OWED TO:		OWED BY:)RG)	
(ORG)TARGET D	ate		COI	MPL. C	DATECLOSING RE	F	
SECONDARY:		I					
OWED TO:		I OWED BY:			(ORG)	
(ORG)TARGET D	ATE		CO	MPL.C	DATECLOSING RE	F	
					· · · · · · · · · · · · · · · · · · ·		
DISTRIBUTION	CODE WI	A W/O DISTRIBUTION	CODE	W/A W	DISTRIBUTION	CODE V	N/A W/O
DIRECTOR, TSD	DTS		1 1			1 1	1 1
	┢╾╼┝╼╼	┼╼╍┨┥╲╼╌╤╼╌╞╌╌╗╺╌╌╌╌	╇	_	PROGRAM MANAGER	BPM	
DEPUTY DIRECTOR, TSD	DTS	Beck MCName	20	1	PROGRAM MANAGER DEPUTY PROGRAM MANAGER	BPM BPM	
DEPUTY DIRECTOR, TSD	DTS DTS	BrekInchame	20		<u></u>	BPM BPM	
	DTS DTS		20		DEPUTY PROGRAM MANAGER	врм	
SITE MANAGER: R. Atkin A. Avel W. Sesy	DTS DTS DTS	Library	20		DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindia	BPM BPM	
SITE MANAGER: R. Atkin A. Avol	DTS DTS		20		DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson	BPM BPM BPM	
SITE MANAGER: R. Atkin A. Avel W. Seay PROJECT SUPPORT GRP: J. Hart	DTS DTS DTS DTS		20		DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Liede R. Robertson CONSTRUCTION	BPM BPM BPM BFC	
SITE MANAGER: R. Atkin A. Avel W. Sesy	DTS DTS DTS DTS				DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson	BPM BPM BPM	
SITE MANAGER: R. Atkin A. Avel W. Sesy PROJECT SUPPORT GRP: J. Hart S. Okthar	DTS				DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY	BPM BPM BPM BPM BFC BEH	
SITE MANAGER: R. Atkin A. Avel W. Seay PROJECT SUPPORT GRP: J. Hart S. Oktham PRGM ANALYST, B. Hughlett	DTS DTS DTS DTS DTS DTS DTE				DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY TWA/EDERLINE	BPM BPM BPM BFC BEH BEH	
SITE MANAGER: R. Atkin A. Avel W. Seay PROJECT SUPPORT GRP: J. Hart S. Oktham PRGM ANALYST, B. Hughlett	DTS DTS DTS DTS DTS DTS DTS DTS DTS		20		DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY TMA/EDERLINE FIELD OPERATIONS	BPM BPM BPM BFC BFC BEH BEH BOP	
SITE MANAGER: R. Atkin A. Avei W. Seay PROJECT SUPPORT GRP: J. Hart S. Oldharr PRGM ANALYST, B. Hughlett SECRETARIES: M. Seiber	DTS DTS DTS DTS DTS DTS DTS DTS DTS				DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lipdia R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY TRAVEBERLINE FIELD OPERATIONS PROCUREMENT	BPM BPM BPM BPM BFC BEH BEH BEH BCP BPO	
SITE MANAGER: R. Atkin A. Avel W. Seay PROJECT SUPPORT GRP: J. Hart S. Okthan PRGM ANALYST, B. Hughlett SECRETARIES: M. Seiber TSD CHRON FILE	DTS DTS DTS DTS DTS DTS DTS DTS DTS				DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY TMAVEDERLINE FIELD OPERATIONS PROCUREMENT PROJECT ADMINISTRATION	BPM BPM BPM BFC BEH BEH BEH BCP BPO BPO BPA	
SITE MANAGER: R. Atkin A. Avel W. Seay PROJECT SUPPORT GRP: J. Hart S. Okthar PRGM ANALYST, B. Hughlett SECRETARIES: M. Seiber TSD CHRON FILE TSD ACTION FILE	DTS	Kibrary Kidry			DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY TRAVEBERLINE FIELD OPERATIONS PROJECT ADMINISTRATION TECHNICAL REPORTS	BPM BPM BPM BFC BFC BEH BEH BEH BCP BPO BPA BPA	
SITE MANAGER: R. Atkin A. Avei W. Seay PROJECT SUPPORT GRP: J. Hart S. Okthan PRGM ANALYST. B. Hughlett SECRETARIES: M. Seiber TSD CHRON FILE TSD ACTION FILE DOE/CONTRACTS: DAVIS/SMITH	0TS	Kiblary Kiblary Stres:			DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY TMAEBERLINE FIELD OPERATIONS PROJECT ADMINISTRATION TECHNICAL REPORTS PROJECT CONTROLS PROJECT ENGINEERING PUBLIC AFFAIRS	BPM BPM BPM BFC BEH BEH BEH BEH BC BPO BPA BPO BPA BPC BPE BPA	
SITE MANAGER: R. Atkin A. Avei W. Seay PROJECT SUPPORT GRP: J. Hart S. Okthan PRGM ANALYST. B. Hughlett SECRETARIES: M. Seiber TSD CHRON FILE TSD ACTION FILE DOE/CONTRACTS: DAVIS/SMITH	0TS	SITES: 115/202 NFSS 116 SLDS 117/118 MIDOLESEX			DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindia R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY THAVEBERLINE FIELD OPERATIONS PROJECT ADMINISTRATION TECHNICAL REPORTS PROJECT CONTROLS PROJECT ENGINEERING PUBLIC AFFAIRS OUIALITY ASSURANCE	BPM BPM BPM BFC BEH BEH BEH BC BPO BPO BPO BPO BPC BPE	
SITE MANAGER: R. Atkin A. Avei W. Seay PROJECT SUPPORT GRP: J. Hart S. Okthan PRGM ANALYST, B. Hughlett SECRETARIES: M. Seiber TSD CHRON FILE TSD ACTION FILE DOE/CONTRACTS: DAVIS/SMITH DOE/CONTRACTS: DAVIS/SMITH DOE/ACDOL/ARTERS	DTS	SITES: 115/202 NFSS 115/202 NFSS 116 SLDS 117/118 MIDDLESEX 137/138 WAYNE/MAYWOOD			DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY TRAVEBERLINE FRELD OPERATIONS PROJECT ADMINISTRATION TECHNICAL REPORTS PROJECT CONTROLS PROJECT ENGINEERING PUBLIC AFFAIRS OUALITY ASSURANCE POCC READING FILE	BPM BPM BPM BFC BEH BEH BEH BEH BC BPO BPA BPO BPA BPC BPE BPA	
SITE MANAGER: R. Atkin A. Avei W. Seay PROJECT SUPPORT GRP: J. Hart S. Okthan PRGM ANALYST, B. Hughlett SECRETARIES: M. Seiber TSD CHRON FILE TSD ACTION FILE DOE/CONTRACTS: DAVIS/SMITH DOE/MEADQUARTERS	DTS DTS DTS DTS DTS DTS DTS DTS DTS DTS	SITES: 115/202 NFSS 116 SLDS 117/118 MIDDLESEX 137 /138 WAYNE/MAYWOOD 139 COLONIE (CISS)			DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY TRAVEDERLINE FIELD OPERATIONS PROJECT ADMINISTRATION TECHNICAL REPORTS PROJECT CONTROLS PROJECT ENGINEERING PUBLIC AFFAIRS OUALITY ASSURANCE POCC READING FILE TO DOE FROM DOE	BPM BPM BPM BFC BEH BEH BCP BPO BPO BPO BPO BPA BPA BPA BPA BPA BOA	
SITE MANAGER: R. Atkin A. Avei W. Seay PROJECT SUPPORT GRP: J. Hart S. Okthan PRGM ANALYST. B. Hughlett SECRETARIES: M. Seiber TSD CHRON FILE TSD ACTION FILE DOE/CONTRACTS: DAVIS/SMITH DOE/HEADQUARTERS AML: ORAU:	DTS	SITES: 115/202 NFSS 115/202 NFSS 116 SLDS 117/118 MIDDLESEX 137/138 WAYNE/MAYWOOD			DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY THAVEBERLINE FIELD OPERATIONS PROJECT ADMINISTRATION TECHNICAL REPORTS PROJECT CONTROLS PROJECT CONTROLS PROJECT ENGINEERING PUBLIC AFFAIRS OUALITY ASSURANCE POCC READING FILE TO DOE FROM DOE PDCC ADMIN RCD	BPM BPM BPM BFC BFC BEH BEH BEH BCP BPO BPA BTR BPC BPE BPR BOA	
SITE MANAGER: R. Atkin A. Avei W. Seay PROJECT SUPPORT GRP: J. Hart S. Okthan PRGM ANALYST, B. Hughlett SECRETARIES: M. Seiber TSD CHRON FILE TSD ACTION FILE DOE/CONTRACTS: DAVIS/SMITH DOE/CONTRACTS: DAVIS/SMITH DOE/ACDOL/ARTERS	DTS DTS DTS DTS DTS DTS DTS DTS DTS DTS	SITES: 115/202 NFSS 116 SLDS 117/118 MIDDLESEX 137 /138 WAYNE/MAYWOOD 139 COLONIE (CISS)			DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY THAVEBERLINE FIELD OPERATIONS PROJECT ADMINISTRATION TECHNICAL REPORTS PROJECT CONTROLS PROJECT CONTROLS PROJECT ENGINEERING PUBLIC AFFAIRS OUALITY ASSURANCE POCC READING FILE TO DOE FROM DOE	BPM BPM BPM BFC BFC BEH BEH BEH BCP BPO BPA BTR BPC BPE BPR BOA	
SITE MANAGER: R. Atkin A. Avei W. Seay PROJECT SUPPORT GRP: J. Hart S. Okthan PRGM ANALYST. B. Hughlett SECRETARIES: M. Seiber TSD CHRON FILE TSD ACTION FILE DOE/CONTRACTS: DAVIS/SMITH DOE/HEADQUARTERS AML: ORAU:	DTS	SITES: 115/202 NFSS 116 SLDS 117/118 MIDDLESEX 137 /138 WAYNE/MAYWOOD 139 COLONIE (CISS)			DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY THAVEBERLINE FIELD OPERATIONS PROJECT ADMINISTRATION TECHNICAL REPORTS PROJECT CONTROLS PROJECT CONTROLS PROJECT ENGINEERING PUBLIC AFFAIRS OUALITY ASSURANCE POCC READING FILE TO DOE FROM DOE PDCC ADMIN RCD	BPM BPM BPM BFC BFC BEH BEH BEH BCP BPO BPA BTR BPC BPE BPR BOA	
SITE MANAGER: R. Atkin A. Avei W. Seay PROJECT SUPPORT GRP: J. Hart S. Okthan PRGM ANALYST. B. Hughlett SECRETARIES: M. Seiber TSD CHRON FILE TSD ACTION FILE DOE/CONTRACTS: DAVIS/SMITH DOE/HEADQUARTERS ANL: ORAU:	DTS	SITES: 115/202 NFSS 116 SLDS 117/118 MIDDLESEX 137 /138 WAYNE/MAYWOOD 139 COLONIE (CISS)			DEPUTY PROGRAM MANAGER PROJECT MANAGER: S. Lindle R. Robertson CONSTRUCTION ENVIRON HEALTH & SAFETY THAVEBERLINE FIELD OPERATIONS PROJECT ADMINISTRATION TECHNICAL REPORTS PROJECT CONTROLS PROJECT CONTROLS PROJECT ENGINEERING PUBLIC AFFAIRS OUALITY ASSURANCE POCC READING FILE TO DOE FROM DOE PDCC ADMIN RCD	BPM BPM BPM BFC BFC BEH BEH BEH BCP BPO BPA BTR BPC BPE BPR BOA	

(SIGNED)