

**TRANSMITTAL OF MEETING HANDOUT MATERIALS FOR  
IMMEDIATE PLACEMENT IN THE PUBLIC DOMAIN**

*This form is to be filled out (typed or hand-printed) by the person who announced the meeting (i.e., the person who issued the meeting notice). The completed form, and the attached copy of meeting handout materials, will be sent to the Document Control Desk on the same day of the meeting; under no circumstances will this be done later than the working day after the meeting.*  
*Do not include proprietary materials.*

## DATE OF MEETING

08/05/2003

The attached document(s), which was/were handed out in this meeting, is/are to be placed in the public domain as soon as possible. The minutes of the meeting will be issued in the near future. Following are administrative details regarding this meeting:

Docket Number(s)	50-390
Plant/Facility Name	Watts Bar Nuclear Plant, Unit 1
TAC Number(s) (if available)	MC0106
Reference Meeting Notice	Dated July 24, 2003 ADAMS Accession ML032050102
Purpose of Meeting (copy from meeting notice)	To discuss TVA's potential amendment regarding a proposed modification to the ultimate heat sink temperature

## NAME OF PERSON WHO ISSUED MEETING NOTICE

Kahtan Jabbour

## TITLE

Senior Project Manager

## OFFICE

NRR

## DIVISION

DLPM

## BRANCH

PDII-2

Distribution of this form and attachments:

Docket File/Central File


PUBLIC





# Tennessee Valley Authority Watts Bar Nuclear Plant

## Increase in Ultimate Heat Sink Temperature



TVANRC Meeting  
NRR – Rockville, Maryland  
August 5, 2003.

# Agenda

---



- Introduction and Purpose
- Current UHS Technical Specification (TS) Requirements
- UHS Temperature History and Challenges
- UHS / Essential Raw Cooling Water (ERCW) Design Basis
- Analysis Methodology And Results
- Precedents
- Conclusions

# Introduction and Purpose

---



- Peak river water (ERCW) temperatures in recent summers have approached UHS Limits in Watts Bar Technical Specifications
- WBN plans to submit a TS Change which will increase UHS temperature limit from 85°F to 88°F
- TS submittal expected August 2003
- Approval to be requested before Summer 2004

# Current UHS TS Requirements

---




- LCO 3.7.9 – Ultimate Heat Sink
  - UHS is the TN River, also known as Chickamauga Lake
  - Requires UHS to be Operable in Modes 1-4
- Surveillance Requirement (SR) 3.7.9.1 (Perform every 24 hours):
  - “Verify average water temperature of the UHS is  $\leq 85^{\circ}\text{F}$ ”
  - Surveillance Instruction (SI) – 1-SI-0-2B
    - Temperature measured daily (with installed instrumentation) at each of four supply headers in the Auxiliary Building, indicated on the plant computer, averaged, and compared to the limit
    - Current limit is  $\leq 84^{\circ}\text{F}$  to account for instrument uncertainty (more accurate instrumentation is being installed)
    - Limit is close to  $85^{\circ}\text{F}$  if using precision M&TE

# UHS Temperature History & Challenges



- The region is generally experiencing hotter than normal summers
  - August 2, 2002 – UHS temperature approached T/S limit of 85°F
  - Maximum general river water temperatures for 1996 – 2002 approximately 83°F
- TVA River Systems Operations can manipulate river temperature by special operations of larger & cooler upstream reservoirs, but with limited success
  - Can involve significant operating expenses & coordination difficulties with unpredictable results – influenced by weather



# **UHS/ERCW Design Basis**

---



- UHS - Defined as the TN River, including the TVA controlled dams upstream of the intake structure, Chickamauga Dam (nearest downstream dam), and the plant intake channel (Reference WBN UFSAR Section 9.2.5)
- Provides a heat sink for removing heat from safety-related components during transients or accidents as well as normal operation
- The maximum UHS temperature of 85°F ensures adequate heat load removal capacity for a minimum of 30 days after reactor shutdown or following an accident, including worst case LOCA
- The system is designed in accordance with RG-1.27, Revision 1, March , 1974

# UHS/ERCW Design Basis



- Design basis of ERCW is for one train (2 ERCW pumps & associated piping, etc.) in conjunction with component cooling, containment spray, & RHR to remove core decay heat following a LOCA
  - Assumes simultaneous LOCA, with loss of downstream dam, loss of offsite power, with a worst case single failure
  - Design basis worst case lake level assumptions have not changed – Assumes Watts Bar Hydro water release of 2,000 CFS
- Maximum post-accident LOCA heat load occurs approximately 20 minutes after accident
- Worst-case heat load results during RHR cool-down following shutdown from 100 percent power
- UHS impacts post-LOCA containment pressure response
- UHS and ERCW design basis requirements continue to be satisfied with the subject change in TS temperature limit from 85°F to 88°F


# UHS/ERCW Design Basis



- WBN Design Bases will be revised to reflect UHS limit of 88°F for:
  - Containment Accident Analysis
    - Containment integrity analysis
    - Long-term cooling analysis
  - Residual Heat Removal Cooldown Analysis
- WBN Design Bases will continue to reflect UHS limit of 85° for:
  - UHS Design
  - ERCW Design
  - Future modifications will address impact of revised UHS limit of 88°F

# Simplified Diagram - Primary ERCW Users

IV



# Analysis Methodology and Results

---



- Containment Pressurization Re-analysis
  - Westinghouse performed based on 88°F ERCW
  - No changes in analysis assumptions or methods
  - ERCW is a minor contributor during ice melt phase
  - Pressure increased from 10.64 psig to 10.90 psig
  - Insignificant reduction in ice melt time (1 hour nominal)
- Containment Cooling Re-analysis
  - Westinghouse performed based on 88°F ERCW
  - No changes in analysis assumptions or methods
  - Results acceptable – No long-term impact on equipment environmental qualification



# Containment Pressure

## UFSAR Figure 6.2.1-1




Current UHS  $\leq 85^{\circ}\text{F}$

Proposed UHS  $\leq 88^{\circ}\text{F}$



# Upper and Lower Compartment Temperatures - UFSAR Figure 6.2.1-2

IV-A



# Analysis Methodology and Results

---



- Residual Heat Removal (RHR) - Shutdown And Cooldown
  - Westinghouse performed based on 88°F ERCW
  - No changes in analysis methods; Revised assumptions/procedural controls Required (See Below)
  - 2 Train cooldown within 23 hours of shutdown can be achieved
  - 1 Train cooldown within 36 hours of shutdown (as required by Tech Specs) can be achieved if:
    - Remaining RCP secured at 25 hours after shutdown
    - Securing RCP during cooldown is consistent with current operational practices during a Loss of Offsite Power event
    - SFP heat exchanger isolation limited to five hours (Previously 9 hours)

# Analysis Methodology and Results



- Evaluation of Other Major Components
  - Three critical areas were evaluated for impact:
    - Major safety related component heat transfer adequacy
    - Room / Area cooling capability
    - Impact on piping and piping support analyses
  - Margin was obtained using ERCW flows based on pre-operational test data, where necessary
  - The lowest preoperational test flow value was used (either from Appendix R or LOCA test configuration)
  - Sensitivity studies were performed on Aux Building temperature using TMG analysis
  - Piping / support analyses were evaluated at revised higher temperatures; significant margin existed in the few civil problems in which the analyzed temperature was exceeded.
  - Cooling capability analytically evaluated for Emergency Diesel Generators, Component Cooling System Hx, Containment Spray System Hx
  - Additional margin realized but not credited based on updated dam breach criteria. Resulted in revised WBH water release of 14,000 CFS, additional 7 feet of head above analysis basis.

# Analysis Methodology and Results



- Results - Evaluation of Other Major Components

## Emergency Diesel Generator Jacket Water Heat Exchanger (Hx) Cooling

- Analysis performed at 88°F ERCW – results were sensitive to fouling assumptions
- Analysis utilized ERCW flow margin, a relaxed maximum temperature limit, and revised maximum heat loads
- Marginal performance at design fouling at 85°F
- Analysis performed using actual fouling trends over a cleaning cycle period
- Annual spring cleaning of EDG Hx will result in acceptable summer operation at 88°F (procedure change planned)

## Room/Area Cooling - Safety Related Chillers

- SR Chillers are greatly oversized; therefore a loss of efficiency was not a concern
- MCR & EBR chillers (screw compressors) were determined to be acceptable up to 95°F
- Safety-Related Equipment Room & Area Coolers – Acceptable based on margins for ERCW flow and more accurate heat loads
- SDBR chiller compressors require re-gearing:
  - 88°F ERCW was determined by vendor to be unacceptable for SDBR chiller operation
  - Effort underway to re-gear and derate the SDBR chiller and revise design basis documentation
  - Both compressors to be rebuilt before 88°F TS is implemented

# Analysis Methodology and Results



## Environmental Qualification

- 100 days is still assumed for EQ; however, margin is realized due to hypothetical nature of ERCW temperature remaining elevated at 88°F for a 100 day duration
- TMG analysis of Auxiliary Building areas – Maximum EQ temperature not exceeded
- Maximum containment temperature not impacted based on Westinghouse analysis
- No impact on EQ Binders or program

## Other Major Areas Evaluated Acceptably

Acceptable evaluation results achieved for the following:

- ERCW Design Basis Events (LOOP, SBO, pipe breaks, etc.)
- Auxiliary Feedwater
- Appendix-R Safe Shutdown
- Spent Fuel Pool Cooling
- Flood Mode Operations
- Tritium Production

# Precedents



- TVA reviewed the submittals approved for Cooper, Palisades, and Braidwood
- WBN approach is similar
- TVA's submittal will addresses evaluation/analytical methods, assumptions, results
- TVA's submittal to provide detail list of components/calculations affected and basis for conclusions
- TVA reviewed TSTF-330 (Adoption of 24-hour temperature averaging) for UHS – Does not provide adequate relief for postulated, sustained high temperature conditions for UHS

# Conclusions



- WBN will submit a TS Change to increase UHS temperature from 85°F to 88°F
- Effects of proposed change have been examined in detail on equipment, components, systems, and safety-analyses. Included reviews of over 140 design documents and calculations
- Analysis methodologies and assumptions for major analyses (Containment and RHR cool-down) have not changed
- Component evaluations considered available margins and included sensitivity studies
- Modification of SDBR chiller compressors required prior to implementation
- Procedural controls to be revised as required (e.g., single-train RHR cool-down)
- Emergency Diesel Generators will require annual spring cleaning
- Proposed change is acceptable. No adverse affect on the safety of plant operations or the public