

3.5 EMERGENCY CORE COOLING SYSTEMS (ECCS)

3.5.2 ECCS – Operating

LCO 3.5.2 Two ECCS trains shall be OPERABLE.

-----NOTE-----
In MODE 3, both safety injection (SI) pump flow paths may be isolated by closing the isolation valves for up to 2 hours to perform pressure isolation valve testing per SR 3.4.14.1.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One ECCS train inoperable.	A.1 Restore train to OPERABLE status.	72 hours
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3.	6 hours
	<u>AND</u> B.2 Be in MODE 4.	12 hours

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
SR 3.5.2.1 Verify each ECCS manual, power operated, and automatic valve in the flow path, that is not locked, sealed, or otherwise secured in position, is in the correct position.	31 days
SR 3.5.2.2 Verify ECCS piping is full of water.	31 days

(continued)

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE		FREQUENCY
SR 3.5.2.3	Verify each ECCS pump's developed head at the test flow point is greater than or equal to the required developed head.	In accordance with the Inservice Testing Program
SR 3.5.2.4	Verify each ECCS automatic valve in the flow path that is not locked, sealed, or otherwise secured in position, actuates to the correct position on an actual or simulated actuation signal.	18 months
SR 3.5.2.5	Verify each ECCS pump starts automatically on an actual or simulated actuation signal.	18 months
SR 3.5.2.6	Verify, by visual inspection, each ECCS train containment sump suction inlet is not restricted by debris and the suction inlet debris screens show no evidence of structural distress or abnormal corrosion.	18 months

SURVEILLANCE REQUIREMENTS

SURVEILLANCE		FREQUENCY
SR 3.5.3.1	The following SRs are applicable for all equipment required to be OPERABLE: SR 3.5.2.1 SR 3.5.2.4 SR 3.5.2.2 SR 3.5.2.5 SR 3.5.2.3 SR 3.5.2.6	In accordance with applicable SRs