

NUREG-1433 Vol 1, Rev. 3.0

Standard Technical Specifications General Electric Plants, BWR/4

Specifications

Manuscript Completed: July 2003 Date Published: August 2003

Division of Regulatory Improvement Programs Office of Nuclear Reactor Regulation U.S. Nuclear Regulatory Commission Washington, DC 20555-0001



Availability of Reference Materials					
in NRC Put	in NRC Publications				
NRC Reference Material	Non-NRC Reference Material				
As of November 1999, you may electronically access NUREG-series publications and other NRC records at NRC's Public Electronic Reading Room at www.nrc.gov/NRC/ADAMS/index.htm. Publicly released documents include, to name a few, NUREG-series publications; <i>Federal Register</i> notices; applicant, licensee, and vendor documents and correspondence; NRC correspondence and internal memoranda; bulletins and information notices; inspection and investigation reports; licensee event reports; and Commission papers and their attachments.	Documents available from public and special technical libraries include all open literature items, such as books, journal articles, and transactions, <i>Federal Register</i> notices, Federal and State legislation, and congressional reports. Such documents as theses, dissertations, foreign reports and translations, and non-NRC conference proceedings may be purchased from their sponsoring organization. Copies of industry codes and standards used in a substantive manner in the NRC regulatory process are maintained at -				
 NRC publications in the NUREG series, NRC regulations, and <i>Title 10, Energy,</i> of the <i>Code of Federal Regulations</i>, may be purchased from one of these two sources: 1. The Superintendent of Documents U.S. Government Printing Office Mail Stop SSOP 	The NRC Library Two White Flint North 11545 Rockville Pike Rockville, MD 20852-2738 These standards are available in the library for reference use by the public. Codes and standards				
Washington, DC 20402-0001 Internet: bookstore.gpo.gov Telephone : 202-512-1800 Fax: 202-512-2250	are usually copyrighted and may be purchased from the originating organization or, if they are American National Standards, from—				
 The National Technical Information Service Springfield, VA 22161-0002 www.ntis.gov 1-800-553-6847 or locally 703-605-6000 	American National Standards Institute 11 West 42nd Street New York, NY 10036-8002 <http: www.ansi.org=""> 212-642-4900</http:>				
A single copy of each NRC draft report for comment is available free, to the extent of supply, upon written request as follows: Address: Office of the Chief Information Officer Reproduction and Distribution Services Section U.S. Nuclear Regulatory Commission Washington, DC 20555-0001	Legally binding regulatory requirements are stated only in laws; NRC regulations; licenses, including technical specifications; or orders, not in NUREG-series publications. The views expressed in contractor-prepared publications in this series are not necessarily those of the NRC.				
E-mail: DISTRIBUTION@nrc.gov Facsimile: 301-415-2289 Some publications in the NUREG series that are posted at the NRC's Web site address www.nrc.gov/NRC/NUREGS/indexnum.html are updated periodically and may differ from the last printed version. Although references to material found on a Web site bear the date the material was accessed, the material available on the date cited may subsequently be removed from the site.	The NUREG series comprises (1) technical and administrative books prepared by the staff (NUREG-XXXX) or agency contractors (NUREG/CR-XXXX), (2) proceedings of conferences (NUREG/CP-XXXX), (3) reports resulting from international agreements (NUREG/IA-XXXX), (4) brochures (NUREG/BR-XXXX), and (5) compilations of legal decisions and orders of the Commission and Atomic and Safety Licensing Boards and of Director's decisions under Section 2.206 of NRC's regulations (NUREG-0750).				

PREFACE

This NUREG contains the improved Standard Technical Specifications (STS) for General Electric (GE) BWR/4 plants. Revision 3 incorporates the cumulative changes to Revision 1 and 2, which was published in April 1995 and April 2001, respectively. The changes reflected in Revision 3 resulted from the experience gained from license amendment applications to convert to these improved STS or to adopt partial improvements to existing technical specifications. This publication is the result of extensive public technical meetings and discussions among the Nuclear Regulatory Commission (NRC) staff and various nuclear power plant licensees, Nuclear Steam Supply System (NSSS) Owners Groups, and the Nuclear Energy Institute (NEI). The improved STS were developed based on the criteria in the Final Commission Policy Statement on Technical Specifications Improvements for Nuclear Power Reactors, dated July 22, 1993 (58 FR 39132), which was subsequently codified by changes to Section 36 of Part 50 of Title 10 of the Code of Federal Regulations (10 CFR 50.36) (60 FR 36953). Licensees are encouraged to upgrade their technical specifications consistent with those criteria and conforming, to the practical extent, to Revision 2 to the improved STS. The Commission continues to place the highest priority on requests for complete conversions to the improved STS. Licensees adopting portions of the improved STS to existing technical specifications should adopt all related requirements, as applicable, to achieve a high degree of standardization and consistency.

The Table of Contents is now a Table of Contents / Revision Summary where the revision number and date are listed for each specification and bases, in lieu of traditional page numbers. Each limiting condition for operation (LCO) starts with page 1, with a specification, e.g., "2.0" or bases "B 2.0" number prefix. Subsequent approved revisions to sections will be noted in the Table of Contents, as well as on each affected page, using a decimal number to indicate the number of revisions to that section, along with the date, e.g., (Rev 3.3, 04/01/04) indicates the third approved change and date since Revision 3.0 was published. Additionally, the final page of each LCO section will be a historical listing of the changes affecting that section. This publication will be maintained in electronic format. Subsequent revisions will not be printed in hard copy. Users may access the subsequent revisions to the STS in the PDF format at (<u>http://www.nrc.gov/NRR/sts/sts.htm</u>). This Web site will be updated as needed and the contents may differ from the last printed version. Users may print or download copies from the NRC Web site.

PAPERWORK REDUCTION ACT STATEMENT

The information collections contained in this NUREG are covered by the requirements of 10 CFR Parts 20 and 50, which were approved by the Office of Management and Budget, approval numbers 31250-0006, 0011 and 0014.

PUBLIC PROTECTION NOTIFICATION

If a means used to impose an information collection does not display a currently valid OMB control number, the NRC may not conduct or sponsor, and a person is not required to respond to, the information collection.

1.0	USE AND APPLICATION		
1.1	Definitions	.3.0,	08/01/03
1.2	Logical Connectors	3.0,	08/01/03
1.3	Completion Times	3.0,	08/01/03
1.4	Frequency	3.0,	08/01/03
2.0	SAFETY LIMITS (SLs)	. 3.0.	08/01/03
2.1	Safety Limits		
2.2	SL Violations		
3.0	LIMITING CONDITION FOR OPERATION (LCO) APPLICABILITY	.3.0,	08/01/03
3.0	SURVEILLANCE REQUIREMENT (SR) APPLICABILITY	3.0,	08/01/03
3.1	REACTIVITY CONTROL SYSTEMS		
3.1.1	SHUTDOWN MARGIN (SDM)	3.0,	08/01/03
3.1.2	Reactivity Anomalies	3.0,	08/01/03
3.1.3	Control Rod OPERABILITY	3.0,	08/01/03
3.1.4	Control Rod Scram Times	.3.0,	08/01/03
3.1.5	Control Rod Scram Accumulators	.3.0,	08/01/03
3.1.6	Rod Pattern Control	.3.0,	08/01/03
3.1.7	Standby Liquid Control (SLC) System	3.U,	00/01/03
3.1.0	Scram Discharge volume (SDV) vent and Drain valves	3.0,	06/01/03
3.2	POWER DISTRIBUTION LIMITS		
3.2.1	AVERAGE PLANAR LINEAR HEAT GENERATION RATE		
	(APLHGR)	.3.0,	08/01/03
3.2.2	MINIMUM CRITICAL POWER RATIO (MCPR)	.3.0,	08/01/03
3.2.3	LINEAR HEAT GENERATION RATE (LHGR) (Optional)	3.0,	08/01/03
3.2.4	Average Power Range Monitor (APRM) Gain and Setpoints	30	00/01/02
		5.0,	00/01/03
3.3	INSTRUMENTATION	~ ~	00/04/00
3.3.1.1	Reactor Protection System (RPS) Instrumentation	.3.0,	08/01/03
3.3.1.2	Source Range Monitor (SRM) Instrumentation	3.0,	08/01/03
3.3.2.1	Control Rod Block Instrumentation	.3.0,	08/01/03
3331	Post Accident Monitoring (PAM) Instrumentation	3.0, 3.0	00/01/03
3332	Post Accident Monitoring (PAM) Institutientation	3.0,	08/01/03
3341	End of Cycle Recirculation Pump Trin (EOC-RPT) Instrumentation	3.0,	08/01/03
3342	Anticipated Transient Without Scram Recirculation Pump Trip	0.0,	00/01/00
0.0	(ATWS-RPT) Instrumentation	3.0.	08/01/03
3.3.5.1	Emergency Core Cooling System (ECCS) Instrumentation	3.0.	08/01/03
3.3.5.2	2 Reactor Core Isolation Cooling (RCIC) System Instrumentation	. 3.0,	08/01/03
3.3.6.1	Primary Containment Isolation Instrumentation	3.0,	08/01/03
3.3.6.2	2 Secondary Containment Isolation Instrumentation	3.0,	08/01/03
3.3.6.3	Low-Low Set (LLS) Instrumentation	3.0,	08/01/03

3.3 INSTRUMENTATION (continued)

3.3.7.1	[Main Control Room Environmental Control (MCREC)] System		
	Instrumentation	. 3.0,	08/01/03
3.3.8.1	Loss of Power (LOP) Instrumentation	. 3.0,	08/01/03
3.3.8.2	Reactor Protection System (RPS) Electric Power Monitoring	3.0,	08/01/03
34	REACTOR COOLANT SYSTEM (RCS)		
341	Recirculation Loops Operating	30	08/01/03
342	Jet Pumps	3.0	08/01/03
343	Safety/Relief Valves (S/RVs)	3.0	08/01/03
344	RCS Operational LEAKAGE	3.0	08/01/03
345	RCS Pressure Isolation Valve (PIV) Leakage	3.0	08/01/03
346	RCS Leakage Detection Instrumentation	3.0	08/01/03
347	RCS Specific Activity	3.0	08/01/03
348	Residual Heat Removal (RHR) Shutdown Cooling System - Hot	0.0,	00/01/00
0.110	Shutdown	30	08/01/03
3.4.9	Residual Heat Removal (RHR) Shutdown Cooling System - Cold	0.0,	00/01/00
	Shutdown	3.0.	08/01/03
3.4.10	RCS Pressure and Temperature (P/T) Limits	3.0	08/01/03
3.4.11	Reactor Steam Dome Pressure	.3.0.	08/01/03
		,	
3.5	EMERGENCY CORE COOLING SYSTEM (ECCS) AND REACTOR		
	CORE ISOLATION COOLING (RCIC) SYSTEM		
3.5.1	ECCS - Operating	. 3.0.	08/01/03
3.5.2	ECCS - Shutdown	. 3.0.	08/01/03
3.5.3	RCIC System	. 3.0,	08/01/03
		,	
3.6	CONTAINMENT SYSTEMS		
3.6.1.1	Primary Containment	. 3.0,	08/01/03
3.6.1.2	Primary Containment Air Lock	. 3.0,	08/01/03
3.6.1.3	Primary Containment Isolation Valves (PCIVs)	. 3.0,	08/01/03
3.6.1.4	Drywell Pressure	. 3.0,	08/01/03
3.6.1.5	Drywell Air Temperature	. 3.0,	08/01/03
3.6.1.6	Low-Low Set (LLS) Valves	. 3.0,	08/01/03
3.6.1.7	Reactor Building-to-Suppression Chamber Vacuum Breakers	.3.0,	08/01/03
3.6.1.8	Suppression Chamber-to-Drywell Vacuum Breakers	.3.0,	08/01/03
3.6.1.9	Main Steam Isolation Valve (MSIV) Leakage Control System (LCS)	.3.0,	08/01/03
3.6.2.1	Suppression Pool Average Temperature	. 3.0,	08/01/03
3.6.2.2	Suppression Pool Water Level	. 3.0,	08/01/03
3.6.2.3	Residual Heat Removal (RHR) Suppression Pool Cooling	. 3.0,	08/01/03
3.6.2.4	Residual Heat Removal (RHR) Suppression Pool Spray	. 3.0,	08/01/03
3.6.2.5	Drywell-to-Suppression Chamber Differential Pressure	. 3.0,	08/01/03
3.6.3.1	Primary Containment Hydrogen Recombiners (if permanently	,	
	installed)	. 3.0,	08/01/03
3.6.3.2	[Drywell Cooling System Fans]	. 3.0,	08/01/03

3.6 CONTAINMENT SYSTEMS (continued)

3.6.3.3 3.6.3.4 3.6.4.1 3.6.4.2	Primary Containment Oxygen Concentration Containment Atmosphere Dilution (CAD) System [Secondary] Containment Secondary Containment Isolation Valves (SCIVs)	3.0, 3.0, 3.0, 3.0, 3.0,	08/01/03 08/01/03 08/01/03 08/01/03
3.6.4.3	Standby Gas Treatment (SGT) System	. 3.0,	08/01/03
3.7 Pl 3.7.1 3.7.2	ANT SYSTEMS Residual Heat Removal Service Water (RHRSW) System [Plant Service Water (PSW)] System and [Ultimate Heat Sink	3.0,	08/01/03
3.7.3 3.7.4 3.7.5 3.7.6 3.7.7	Diesel Generator (DG) [1B] Standby Service Water (SSW) System [Main Control Room Environmental Control (MCREC)] System [Control Room Air Conditioning (AC)] System Main Condenser Offgas The Main Turbine Bypass System	3.0, 3.0, 3.0, .3.0, .3.0, .3.0,	08/01/03 08/01/03 08/01/03 08/01/03 08/01/03
3.7.8	Spent Fuel Storage Pool Water Level	.3.0,	08/01/03
3.8 El 3.8.1 3.8.2 3.8.3 3.8.4 3.8.5 3.8.6 3.8.6 3.8.7 3.8.8 3.8.9 3.8.10 3.8.10	LECTRICAL POWER SYSTEMS AC Sources - Operating AC Sources - Shutdown Diesel Fuel Oil, Lube Oil, and Starting Air DC Sources - Operating DC Sources - Shutdown Battery Parameters Inverters - Operating Inverters - Shutdown Distribution Systems - Operating Distribution Systems - Shutdown	3.0, 3.0, 3.0, 3.0, 3.0, 3.0, 3.0, 3.0,	08/01/03 08/01/03 08/01/03 08/01/03 08/01/03 08/01/03 08/01/03 08/01/03 08/01/03
3.9 RI 3.9.1 3.9.2 3.9.3 3.9.4 3.9.5 3.9.6 [3.9.7 3.9.8 3.9.9	EFUELING OPERATIONS Refueling Equipment Interlocks Refuel Position One-Rod-Out Interlock Control Rod Position Indication Control Rod OPERABILITY - Refueling [Reactor Pressure Vessel (RPV)] Water Level[- Irradiated Fuel] [Reactor Pressure Vessel (RPV)] Water Level - [New Fuel or Control Rods]	3.0, 3.0, 3.0, 3.0, 3.0, 3.0, 3.0, 3.0,	08/01/03 08/01/03 08/01/03 08/01/03 08/01/03 08/01/03] 08/01/03 08/01/03
3.10 SF 3.10.1 3.10.2 3.10.3	PECIAL OPERATIONS Inservice Leak and Hydrostatic Testing Operation Reactor Mode Switch Interlock Testing Single Control Rod Withdrawal - Hot Shutdown	. 3.0, . 3.0, . 3.0,	08/01/03 08/01/03 08/01/03

3.10 SPECIAL OPERATIONS (continued)

3.10.4	Single Control Rod Withdrawal - Cold Shutdown	
3.10.5	Single Control Rod Drive (CRD) Removal - Refueling	
3.10.6	Multiple Control Rod Withdrawal - Refueling	
3.10.7	Control Rod Testing - Operating	
3.10.8	SHUTDOWN MARGIN (SDM) Test - Refueling	
3.10.9	Recirculation Loops - Testing	
3.10.10) Training Startups	
4.0	DESIGN FEATURES	
4.1	Site Location	,
4.2	Reactor Core	
4.3	Fuel Storage	
5.0	ADMINISTRATIVE CONTROLS	
5.1	Responsibility	
5.2	Organization	
5.3	Unit Staff Qualifications	
5.4	Procedures	
5.5	Programs and Manuals	
5.6	Reporting Requirements	
[5.7	High Radiation Area	

1.0 USE AND APPLICATION

1.1 Definitions

-----NOTE------The defined terms of this section appear in capitalized type and are applicable throughout these Technical Specifications and Bases. Definition Term ACTIONS ACTIONS shall be that part of a Specification that prescribes Required Actions to be taken under designated Conditions within specified Completion Times. AVERAGE PLANAR LINEAR The APLHGR shall be applicable to a specific planar height and is equal to the sum of the [LHGRs] [heat generation rate HEAT GENERATION RATE (APLHGR) per unit length of fuel rod] for all the fuel rods in the specified bundle at the specified height divided by the number of fuel rods in the fuel bundle [at the height]. CHANNEL CALIBRATION A CHANNEL CALIBRATION shall be the adjustment, as necessary, of the channel output such that it responds within the necessary range and accuracy to known values of the parameter that the channel monitors. The CHANNEL CALIBRATION shall encompass all devices in the channel required for channel OPERABILITY and the CHANNEL FUNCTIONAL TEST. Calibration of instrument channels with resistance temperature detector (RTD) or thermocouple sensors may consist of an inplace gualitative assessment of sensor behavior and normal calibration of the remaining adjustable devices in the channel. The CHANNEL CALIBRATION may be performed by means of any series of sequential, overlapping, or total channel steps. CHANNEL CHECK A CHANNEL CHECK shall be the qualitative assessment, by observation, of channel behavior during operation. This determination shall include, where possible, comparison of the channel indication and status to other indications or status derived from independent instrument channels measuring the same parameter. CHANNEL FUNCTIONAL TEST A CHANNEL FUNCTIONAL TEST shall be the injection of a simulated or actual signal into the channel as close to the sensor as practicable to verify OPERABILITY of all devices in the channel required for channel OPERABILITY. The CHANNEL FUNCTIONAL TEST may be performed by means of any series of sequential, overlapping, or total channel steps.

CORE ALTERATION	CORE ALTERATION shall be the movement of any fuel, sources, or reactivity control components, within the reactive vessel with the vessel head removed and fuel in the vessel The following exceptions are not considered to be CORE ALTERATIONS:		
	a.	Movement of source range monitors, local power range monitors, intermediate range monitors, traversing incore probes, or special movable detectors (including undervessel replacement), and	
	b.	Control rod movement, provided there are no fuel assemblies in the associated core cell.	
	Susp com	pension of CORE ALTERATIONS shall not preclude pletion of movement of a component to a safe position.	
CORE OPERATING LIMITS REPORT (COLR)	The spec cycle in ac these	COLR is the unit specific document that provides cycle ific parameter limits for the current reload cycle. These e specific limits shall be determined for each reload cycle cordance with Specification 5.6.5. Plant operation within e limits is addressed in individual Specifications.	
DOSE EQUIVALENT I-31	DOS (mici dose I-134 facto [Tab Facto Table ICRF "Con Intak	E EQUIVALENT I-131 shall be that concentration of I-131 rocuries/gram) that alone would produce the same thyroid as the quantity and isotopic mixture of I-131, I-132, I-133, I, and I-135 actually present. The thyroid dose conversion rs used for this calculation shall be those listed in Ie III of TID-14844, AEC, 1962, "Calculation of Distance ors for Power and Test Reactor Sites" or those listed in e E-7 of Regulatory Guide 1.109, Rev. 1, NRC, 1977, or P 30, Supplement to Part 1, page 192-212, Table titled, nmitted Dose Equivalent in Target Organs or Tissues per te of Unit Activity"].	
EMERGENCY CORE COOLING SYSTEM (ECCS) RESPONSE TIME	The wher setpo capa to the their gene appli any s	ECCS RESPONSE TIME shall be that time interval from in the monitored parameter exceeds its ECCS initiation point at the channel sensor until the ECCS equipment is ble of performing its safety function (i.e., the valves travel eir required positions, pump discharge pressures reach required values, etc.). Times shall include diesel erator starting and sequence loading delays, where cable. The response time may be measured by means of series of sequential, overlapping, or total steps so that the	

ECCS RESPONSE TIME (continued)

	entir resp prov have	e resp onse ided t beer	conse time is measured. In lieu of measurement, time may be verified for selected components hat the components and methodology for verification n previously reviewed and approved by the NRC.
END OF CYCLE RECIRCULA- TION PUMP TRIP (EOC RPT) SYSTEM RESPONSE TIME	The inter stop hydr switc betw circu mea so th brea valid	EOC val fro valve aulic ch set reen t it bre ns of iat the ker an ated	RPT SYSTEM RESPONSE TIME shall be that time om initial signal generation by [the associated turbine e limit switch or from when the turbine control valve oil control oil pressure drops below the pressure point] to complete suppression of the electric arc he fully open contacts of the recirculation pump aker. The response time may be measured by any series of sequential, overlapping, or total steps e entire response time is measured, [except for the rc suppression time, which is not measured but is to conform to the manufacturer's design value].
ISOLATION SYSTEM RESPONSE TIME	The time isola inclu wher mea so th meas comp for ve by th	ISOL interv tion in tion v de die re app ns of nat the suren poner erifica ie NR	ATION SYSTEM RESPONSE TIME shall be that val from when the monitored parameter exceeds its initiation setpoint at the channel sensor until the valves travel to their required positions. Times shall esel generator starting and sequence loading delays, blicable. The response time may be measured by any series of sequential, overlapping, or total steps e entire response time is measured. In lieu of nent, response time may be verified for selected hts provided that the components and methodology ation have been previously reviewed and approved C.
LEAKAGE	LEA	KAGE	E shall be:
	a.	<u>Iden</u>	tified LEAKAGE
		1.	LEAKAGE into the drywell, such as that from pump seals or valve packing that is captured and conducted to a sump or collecting tank, or
		2.	LEAKAGE into the drywell atmosphere from sources that are both specifically located and known either not to interfere with the operation of leakage detection systems or not to be pressure

boundary LEAKAGE,

LEAKAGE (continued)		
	b.	Unidentified LEAKAGE
		All LEAKAGE into the drywell that is not identified LEAKAGE,
	C.	Total LEAKAGE
		Sum of the identified and unidentified LEAKAGE, and
	d.	Pressure Boundary LEAKAGE
		LEAKAGE through a nonisolable fault in a Reactor Coolant System (RCS) component body, pipe wall, or vessel wall.
[LINEAR HEAT GENERATION RATE (LHGR)	The I fuel r area	LHGR shall be the heat generation rate per unit length of rod. It is the integral of the heat flux over the heat transfer associated with the unit length.
LOGIC SYSTEM FUNCTIONAL TEST	A LC logic from inclui LOG mean steps	OGIC SYSTEM FUNCTIONAL TEST shall be a test of all components required for OPERABILITY of a logic circuit, as close to the sensor as practicable up to, but not ding, the actuated device, to verify OPERABILITY. The IC SYSTEM FUNCTIONAL TEST may be performed by ns of any series of sequential, overlapping, or total system as so that the entire logic system is tested.
[MAXIMUM FRACTION OF LIMITING POWER DENSITY (MFLPD)	The powe dens by th	MFLPD shall be the largest value of the fraction of limiting er density in the core. The fraction of limiting power ity shall be the LHGR existing at a given location divided e specified LHGR limit for that bundle type.]
MINIMUM CRITICAL POWER RATIO (MCPR)	The l exists powe appro to ex opera	MCPR shall be the smallest critical power ratio (CPR) that s in the core [for each class of fuel]. The CPR is that er in the assembly that is calculated by application of the opriate correlation(s) to cause some point in the assembly perience boiling transition, divided by the actual assembly ating power.
MODE	A MC mode and r Table	DDE shall correspond to any one inclusive combination of e switch position, average reactor coolant temperature, reactor vessel head closure bolt tensioning specified in e 1.1-1 with fuel in the reactor vessel.

OPERABLE – OPERABILITY	A system, subsystem, division, component, or device shall be OPERABLE or have OPERABILITY when it is capable of performing its specified safety function(s) and when all necessary attendant instrumentation, controls, normal or emergency electrical power, cooling and seal water, lubrication, and other auxiliary equipment that are required for the system, subsystem, division, component, or device to perform its specified safety function(s) are also capable of performing their related support function(s).		
PHYSIS TESTS	PHYSICS TESTS shall be those tests performed to measure the fundamental nuclear characteristics of the reactor core and related instrumentation.		
	These tests are:		
	a. Described in Chapter [14, Initial Test Program] of the FSAR,		
	b. Authorized under the provisions of 10 CFR 50.59, or		
	c. Otherwise approved by the Nuclear Regulatory Commission.		
PRESSURE AND TEMPERATURE LIMITS REPORT (PTLR)	The PTLR is the unit specific document that provides the reactor vessel pressure and temperature limits, including heatup and cooldown rates, for the current reactor vessel fluence period. These pressure and temperature limits shall be determined for each fluence period in accordance with Specification 5.6.6. Plant operation within these operating limits is addressed in LCO 3.4.10, "RCS Pressure and Temperature (P/T) Limits."		
RATED THERMAL POWER (RTP)	RTP shall be a total reactor core heat transfer rate to the reactor coolant of [2436] MWt.		
REACTOR PROTECTION SYSTEM (RPS) RESPONSE TIME	The RPS RESPONSE TIME shall be that time interval from when the monitored parameter exceeds its RPS trip setpoint at the channel sensor until de-energization of the scram pilot valve solenoids. The response time may be measured by means of any series of sequential, overlapping, or total steps so that the entire response time is measured. In lieu of measurement, response time may be verified for selected components provided that the components and methodology for verification have been previously reviewed and approved by the NRC.		

SHUTDOWN MARGIN (SDM)	SDM shall be the amount of reactivity by which the reactor is subcritical or would be subcritical assuming that:	
	a. The reactor is xenon free,	
	b. The moderator temperature is 68°F, and	
	c. All control rods are fully inserted except for the single control rod of highest reactivity worth, which is assumed to be fully withdrawn. With control rods not capable of being fully inserted, the reactivity worth of these control rods must be accounted for in the determination of SDM.	
STAGGERED TEST BASIS	A STAGGERED TEST BASIS shall consist of the testing of one of the systems, subsystems, channels, or other designated components during the interval specified by the Surveillance Frequency, so that all systems, subsystems, channels, or other designated components are tested during <i>n</i> Surveillance Frequency intervals, where <i>n</i> is the total number of systems, subsystems, channels, or other designated components in the associated function.	
THERMAL POWER	THERMAL POWER shall be the total reactor core heat transfer rate to the reactor coolant.	
[TURBINE BYPASS SYSTEM RESPONSE TIME	The TURBINE BYPASS SYSTEM RESPONSE TIME consists of two components:	
	a. The time from initial movement of the main turbine stop valve or control valve until 80% of the turbine bypass capacity is established and	
	b. The time from initial movement of the main turbine stop valve or control valve until initial movement of the turbine bypass valve.	
	The response time may be measured by means of any series of sequential, overlapping, or total steps so that the entire response time is measured.]	

Table 1.1-1 (page 1 of 1) MODES

MODE	TITLE	REACTOR MODE SWITCH POSITION	AVERAGE REACTOR COOLANT TEMPERATURE (°F)
1	Power Operation	Run	NA
2	Startup	Refuel ^(a) or Startup/Hot Standby	NA
3	Hot Shutdown ^(a)	Shutdown	> [200]
4	Cold Shutdown ^(a)	Shutdown	≤ [200]
5	Refueling ^(b)	Shutdown or Refuel	NA

(a) All reactor vessel head closure bolts fully tensioned.

(b) One or more reactor vessel head closure bolts less than fully tensioned.

1.0 USE AND APPLICATION

1.2 Logical Connectors

PURPOSE	The purpose of this section is to explain the meaning of logical connectors.				
	Logical connectors are used in Technical Specifications (TS) to discriminate between, and yet connect, discrete Conditions, Required Actions, Completion Times, Surveillances, and Frequencies. The only logical connectors that appear in TS are <u>AND</u> and <u>OR</u> . The physical arrangement of these connectors constitutes logical conventions with specific meanings.				
BACKGROUND	Several levels of logic may be used to state Required Actions. These levels are identified by the placement (or nesting) of the logical connectors and by the number assigned to each Required Action. The first level of logic is identified by the first digit of the number assigned to a Required Action and the placement of the logical connector in the first level of nesting (i.e., left justified with the number of the Required Action). The successive levels of logic are identified by additional digits of the Required Action number and by successive indentions of the logical connectors.				
	When logical connectors are used to state a Condition, Completion Time, Surveillance, or Frequency, only the first level of logic is used, and the logical connector is left justified with the statement of the Condition, Completion Time, Surveillance, or Frequency.				
EXAMPLES	The following examples illustrate the use of logical connectors.				

1.2 Logical Connectors

EXAMPLES (continued)

EXAMPLE 1.2-1

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. LCO not met.	A.1 Verify	
	AND	
	A.2 Restore	

In this example the logical connector <u>AND</u> is used to indicate that when in Condition A, both Required Actions A.1 and A.2 must be completed.

1.2 Logical Connectors

EXAMPLES (continued)

EXAMPLE 1.2-2

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. LCO not met.	A.1 Trip	
	OR	
	A.2.1 Verify	
	AND	
	A.2.2.1 Reduce	
	OR	
	A.2.2.2 Perform	
	OR	
	A.3 Align	

This example represents a more complicated use of logical connectors. Required Actions A.1, A.2, and A.3 are alternative choices, only one of which must be performed as indicated by the use of the logical connector <u>OR</u> and the left justified placement. Any one of these three Actions may be chosen. If A.2 is chosen, then both A.2.1 and A.2.2 must be performed as indicated by the logical connector <u>AND</u>. Required Action A.2.2 is met by performing A.2.2.1 or A.2.2.2. The indented position of the logical connector <u>OR</u> indicates that A.2.2.1 and A.2.2.2 are alternative choices, only one of which must be performed.

1.0 USE AND APPLICATION

1.3 Completion Times

PURPOSE	The purpose of this section is to establish the Completion Time convention and to provide guidance for its use.
BACKGROUND	Limiting Conditions for Operation (LCOs) specify minimum requirements for ensuring safe operation of the unit. The ACTIONS associated with an LCO state Conditions that typically describe the ways in which the requirements of the LCO can fail to be met. Specified with each stated Condition are Required Action(s) and Completion Time(s).
DESCRIPTION	The Completion Time is the amount of time allowed for completing a Required Action. It is referenced to the time of discovery of a situation (e.g., inoperable equipment or variable not within limits) that requires entering an ACTIONS Condition unless otherwise specified, providing the unit is in a MODE or specified condition stated in the Applicability of the LCO. Required Actions must be completed prior to the expiration of the specified Completion Time. An ACTIONS Condition remains in effect and the Required Actions apply until the Condition no longer exists or the unit is not within the LCO Applicability.
	If situations are discovered that require entry into more than one Condition at a time within a single LCO (multiple Conditions), the Required Actions for each Condition must be performed within the associated Completion Time. When in multiple Conditions, separate Completion Times are tracked for each Condition starting from the time of discovery of the situation that required entry into the Condition.
	Once a Condition has been entered, subsequent divisions, subsystems, components, or variables expressed in the Condition, discovered to be inoperable or not within limits, will <u>not</u> result in separate entry into the Condition, unless specifically stated. The Required Actions of the Condition continue to apply to each additional failure, with Completion Times based on initial entry into the Condition.
	However, when a <u>subsequent</u> division, subsystem, component, or variable expressed in the Condition is discovered to be inoperable or not within limits, the Completion Time(s) may be extended. To apply this Completion Time extension, two criteria must first be met. The subsequent inoperability:
	a. Must exist concurrent with the <u>first</u> inoperability and
	b. Must remain inoperable or not within limits after the first inoperability is resolved.

DESCRIPTION (continued)

The total Completion Time allowed for completing a Required Action to address the subsequent inoperability shall be limited to the more restrictive of either:

- a. The stated Completion Time, as measured from the initial entry into the Condition, plus an additional 24 hours or
- b. The stated Completion Time as measured from discovery of the subsequent inoperability.

The above Completion Time extensions do not apply to those Specifications that have exceptions that allow completely separate reentry into the Condition (for each division, subsystem, component, or variable expressed in the Condition) and separate tracking of Completion Times based on this re-entry. These exceptions are stated in individual Specifications.

The above Completion Time extension does not apply to a Completion Time with a modified "time zero." This modified "time zero" may be expressed as a repetitive time (i.e., "once per 8 hours," where the Completion Time is referenced from a previous completion of the Required Action versus the time of Condition entry) or as a time modified by the phrase "from discovery . . ." Example 1.3-3 illustrates one use of this type of Completion Time. The 10 day Completion Time specified for Conditions A and B in Example 1.3-3 may not be extended.

EXAMPLES The following examples illustrate the use of Completion Times with different types of Conditions and changing Conditions.

EXAMPLES (continued)

EXAMPLE 1.3-1

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
B. Required Action and associated	B.1 Be in MODE 3.	12 hours
Completion Time not met.	B.2 Be in MODE 4.	36 hours

Condition B has two Required Actions. Each Required Action has its own separate Completion Time. Each Completion Time is referenced to the time that Condition B is entered.

The Required Actions of Condition B are to be in MODE 3 within 12 hours <u>AND</u> in MODE 4 within 36 hours. A total of 12 hours is allowed for reaching MODE 3 and a total of 36 hours (not 48 hours) is allowed for reaching MODE 4 from the time that Condition B was entered. If MODE 3 is reached within 6 hours, the time allowed for reaching MODE 4 is the next 30 hours because the total time allowed for reaching MODE 4 is 36 hours.

If Condition B is entered while in MODE 3, the time allowed for reaching MODE 4 is the next 36 hours.

EXAMPLES (continued)

EXAMPLE 1.3-2

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One pump inoperable.	A.1 Restore pump to OPERABLE status.	7 days
B. Required Action and associated	B.1 Be in MODE 3. <u>AND</u>	12 hours
Completion Time not met.	B.2 Be in MODE 4.	36 hours

When a pump is declared inoperable, Condition A is entered. If the pump is not restored to OPERABLE status within 7 days, Condition B is also entered and the Completion Time clocks for Required Actions B.1 and B.2 start. If the inoperable pump is restored to OPERABLE status after Condition B is entered, Conditions A and B are exited, and therefore, the Required Actions of Condition B may be terminated.

When a second pump is declared inoperable while the first pump is still inoperable, Condition A is not re-entered for the second pump. LCO 3.0.3 is entered, since the ACTIONS do not include a Condition for more than one inoperable pump. The Completion Time clock for Condition A does not stop after LCO 3.0.3 is entered, but continues to be tracked from the time Condition A was initially entered.

While in LCO 3.0.3, if one of the inoperable pumps is restored to OPERABLE status and the Completion Time for Condition A has not expired, LCO 3.0.3 may be exited and operation continued in accordance with Condition A.

While in LCO 3.0.3, if one of the inoperable pumps is restored to OPERABLE status and the Completion Time for Condition A has expired, LCO 3.0.3 may be exited and operation continued in accordance with Condition B. The Completion Time for Condition B is tracked from the time the Condition A Completion Time expired.

EXAMPLES (continued)

On restoring one of the pumps to OPERABLE status, the Condition A Completion Time is not reset, but continues from the time the first pump was declared inoperable. This Completion Time may be extended if the pump restored to OPERABLE status was the first inoperable pump. A 24 hour extension to the stated 7 days is allowed, provided this does not result in the second pump being inoperable for > 7 days.

EXAMPLE 1.3-3

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One Function X subsystem inoperable.	A.1 Restore Function X subsystem to OPERABLE status.	7 days <u>AND</u> 10 days from discovery of failure to meet the LCO
B. One Function Y subsystem inoperable.	B.1 Restore Function Y subsystem to OPERABLE status.	72 hours <u>AND</u> 10 days from discovery of failure to meet the LCO
C. One Function X subsystem inoperable. <u>AND</u> One Function Y subsystem inoperable.	 C.1 Restore Function X subsystem to OPERABLE status. <u>OR</u> C.2 Restore Function Y subsystem to OPERABLE status. 	72 hours 72 hours

EXAMPLES (continued)

When one Function X subsystem and one Function Y subsystem are inoperable, Condition A and Condition B are concurrently applicable. The Completion Times for Condition A and Condition B are tracked separately for each subsystem starting from the time each subsystem was declared inoperable and the Condition was entered. A separate Completion Time is established for Condition C and tracked from the time the second subsystem was declared inoperable (i.e., the time the situation described in Condition C was discovered).

If Required Action C.2 is completed within the specified Completion Time, Conditions B and C are exited. If the Completion Time for Required Action A.1 has not expired, operation may continue in accordance with Condition A. The remaining Completion Time in Condition A is measured from the time the affected subsystem was declared inoperable (i.e., initial entry into Condition A).

The Completion Times of Conditions A and B are modified by a logical connector with a separate 10 day Completion Time measured from the time it was discovered the LCO was not met. In this example, without the separate Completion Time, it would be possible to alternate between Conditions A, B, and C in such a manner that operation could continue indefinitely without ever restoring systems to meet the LCO. The separate Completion Time modified by the phrase "from discovery of failure to meet the LCO" is designed to prevent indefinite continued operation while not meeting the LCO. This Completion Time allows for an exception to the normal "time zero" for beginning the Completion Time "clock." In this instance, the Completion Time "time zero" is specified as commencing at the time the LCO was initially not met, instead of at the time the associated Condition was entered.

EXAMPLES (continued)

EXAMPLE 1.3-4

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more valves inoperable.	A.1 Restore valve(s) to OPERABLE status.	4 hours
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3. <u>AND</u> B.2 Be in MODE 4.	12 hours 36 hours

A single Completion Time is used for any number of valves inoperable at the same time. The Completion Time associated with Condition A is based on the initial entry into Condition A and is not tracked on a per valve basis. Declaring subsequent valves inoperable, while Condition A is still in effect, does not trigger the tracking of separate Completion Times.

Once one of the valves has been restored to OPERABLE status, the Condition A Completion Time is not reset, but continues from the time the first valve was declared inoperable. The Completion Time may be extended if the valve restored to OPERABLE status was the first inoperable valve. The Condition A Completion Time may be extended for up to 4 hours provided this does not result in any subsequent valve being inoperable for > 4 hours.

If the Completion Time of 4 hours (plus the extension) expires while one or more valves are still inoperable, Condition B is entered.

EXAMPLES (continued)

EXAMPLE 1.3-5

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more valves inoperable.	A.1 Restore valve to OPERABLE status.	4 hours
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3. <u>AND</u> B.2 Be in MODE 4.	12 hours 36 hours

The Note above the ACTIONS Table is a method of modifying how the Completion Time is tracked. If this method of modifying how the Completion Time is tracked was applicable only to a specific Condition, the Note would appear in that Condition rather than at the top of the ACTIONS Table.

The Note allows Condition A to be entered separately for each inoperable valve, and Completion Times tracked on a per valve basis. When a valve is declared inoperable, Condition A is entered and its Completion Time starts. If subsequent valves are declared inoperable, Condition A is entered for each valve and separate Completion Times start and are tracked for each valve.

If the Completion Time associated with a valve in Condition A expires, Condition B is entered for that valve. If the Completion Times associated with subsequent valves in Condition A expire, Condition B is entered separately for each valve and separate Completion Times start and are tracked for each valve. If a valve that caused entry into Condition B is restored to OPERABLE status, Condition B is exited for that valve.

EXAMPLES (continued)

Since the Note in this example allows multiple Condition entry and tracking of separate Completion Times, Completion Time extensions do not apply.

EXAMPLE 1.3-6

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One channel inoperable.	A.1 Perform SR 3.x.x.x. OR	Once per 8 hours
	A.2 Reduce THERMAL POWER to ≤ 50% RTP.	8 hours
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3.	12 hours

Entry into Condition A offers a choice between Required Action A.1 or A.2. Required Action A.1 has a "once per" Completion Time, which qualifies for the 25% extension, per SR 3.0.2, to each performance after the initial performance. The initial 8 hour interval of Required Action A.1 begins when Condition A is entered and the initial performance of Required Action A.1 must be complete within the first 8 hour interval. If Required Action A.1 is followed and the Required Action is not met within the Completion Time (plus the extension allowed by SR 3.0.2), Condition B is entered. If Required Action A.2 is followed and the Completion Time of 8 hours is not met, Condition B is entered.

If after entry into Condition B, Required Action A.1 or A.2 is met, Condition B is exited and operation may then continue in Condition A.

EXAMPLES (continued)

EXAMPLE 1.3-7

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One subsystem inoperable.	A.1 Verify affected subsystem isolated.	1 hour <u>AND</u> Once per 8 hours thereafter
	AND A.2 Restore subsystem to OPERABLE status.	72 hours
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3. <u>AND</u> B.2 Be in MODE 4.	12 hours 36 hours

Required Action A.1 has two Completion Times. The 1 hour Completion Time begins at the time the Condition is entered and each "Once per 8 hours thereafter" interval begins upon performance of Required Action A.1.

If after Condition A is entered, Required Action A.1 is not met within either the initial 1 hour or any subsequent 8 hour interval from the previous performance (plus the extension allowed by SR 3.0.2), Condition B is entered. The Completion Time clock for Condition A does not stop after Condition B is entered, but continues from the time Condition A was initially entered. If Required Action A.1 is met after Condition B is entered, Condition B is exited and operation may continue in accordance with Condition A, provided the Completion Time for Required Action A.2 has not expired.

IMMEDIATEWhen "Immediately" is used as a Completion Time, the Required ActionCOMPLETION TIMEshould be pursued without delay and in a controlled manner.

1.0 USE AND APPLICATION

1.4 Frequency

PURPOSE	The purpose of this section is to define the proper use and application of Frequency requirements.
DESCRIPTION	Each Surveillance Requirement (SR) has a specified Frequency in which the Surveillance must be met in order to meet the associated LCO. An understanding of the correct application of the specified Frequency is necessary for compliance with the SR.
	The "specified Frequency" is referred to throughout this section and each of the Specifications of Section 3.0.2, Surveillance Requirement (SR) Applicability. The "specified Frequency" consists of the requirements of the Frequency column of each SR as well as certain Notes in the Surveillance column that modify performance requirements.
	Sometimes special situations dictate when the requirements of a Surveillance are to be met. They are "otherwise stated" conditions allowed by SR 3.0.1. They may be stated as clarifying Notes in the Surveillance, as part of the Surveillance, or both.
	Situations where a Surveillance could be required (i.e., its Frequency could expire), but where it is not possible or not desired that it be performed until sometime after the associated LCO is within its Applicability, represent potential SR 3.0.4 conflicts. To avoid these conflicts, the SR (i.e., the Surveillance or the Frequency) is stated such that it is only "required" when it can be and should be performed. With an SR satisfied, SR 3.0.4 imposes no restriction.
	The use of "met" or "performed" in these instances conveys specific meanings. A Surveillance is "met" only when the acceptance criteria are satisfied. Known failure of the requirements of a Surveillance, even without a Surveillance specifically being "performed," constitutes a Surveillance not "met." "Performance" refers only to the requirement to specifically determine the ability to meet the acceptance criteria.
	Some Surveillances contain notes that modify the Frequency of performance or the conditions during which the acceptance criteria must be satisfied. For these Surveillances, the MODE-entry restrictions of SR 3.0.4 may not apply. Such a Surveillance is not required to be performed prior to entering a MODE or other specified condition in the Applicability of the associated LCO if any of the following three conditions are satisfied:

DESCRIPTION (continued)

- a. The Surveillance is not required to be met in the MODE or other specified condition to be entered; or
- b. The Surveillance is required to be met in the MODE or other specified condition to be entered, but has been performed within the specified Frequency (i.e., it is current) and is known not to be failed; or
- c. The Surveillance is required to be met, but not performed, in the MODE or other specified condition to be entered, and is known not to be failed.

Examples 1.4-3, 1.4-4, 1.4-5, and 1.4-6 discuss these special situations.

EXAMPLES The following examples illustrate the various ways that Frequencies are specified. In these examples, the Applicability of the LCO (LCO not shown) is MODES 1, 2, and 3.

EXAMPLE 1.4-1

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
Perform CHANNEL CHECK.	12 hours

Example 1.4-1 contains the type of SR most often encountered in the Technical Specifications (TS). The Frequency specifies an interval (12 hours) during which the associated Surveillance must be performed at least one time. Performance of the Surveillance initiates the subsequent interval. Although the Frequency is stated as 12 hours, an extension of the time interval to 1.25 times the interval specified in the Frequency is allowed by SR 3.0.2 for operational flexibility. The measurement of this interval continues at all times, even when the SR is not required to be met per SR 3.0.1 (such as when the equipment is inoperable, a variable is outside specified limits, or the unit is outside the Applicability of the LCO). If the interval specified by SR 3.0.2 is exceeded while the unit is in a MODE or other specified condition in the Applicability of the LCO, and the performance of the Surveillance is not otherwise modified (refer to Examples 1.4-3 and 1.4-4), then SR 3.0.3 becomes applicable.

EXAMPLES (continued)

If the interval as specified by SR 3.0.2 is exceeded while the unit is not in a MODE or other specified condition in the Applicability of the LCO for which performance of the SR is required, the Surveillance must be performed within the Frequency requirements of SR 3.0.2 prior to entry into the MODE or other specified condition. Failure to do so would result in a violation of SR 3.0.4.

EXAMPLE 1.4-2

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
Verify flow is within limits.	Once within 12 hours after ≥ 25% RTP
	AND
	24 hours thereafter

Example 1.4-2 has two Frequencies. The first is a one time performance Frequency, and the second is of the type shown in Example 1.4-1. The logical connector "<u>AND</u>" indicates that both Frequency requirements must be met. Each time reactor power is increased from a power level < 25% RTP to \geq 25% RTP, the Surveillance must be performed within 12 hours.

The use of "once" indicates a single performance will satisfy the specified Frequency (assuming no other Frequencies are connected by "<u>AND</u>"). This type of Frequency does not qualify for the 25% extension allowed by SR 3.0.2. "Thereafter" indicates future performances must be established per SR 3.0.2, but only after a specified condition is first met (i.e., the "once" performance in this example). If reactor power decreases to < 25% RTP, the measurement of both intervals stops. New intervals start upon reactor power reaching 25% RTP.

EXAMPLES (continued)

EXAMPLE 1.4-3

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
Not required to be performed until 12 hours after ≥ 25% RTP.	
Perform channel adjustment.	7 days

The interval continues, whether or not the unit operation is < 25% RTP between performances.

As the Note modifies the required <u>performance</u> of the Surveillance, it is construed to be part of the "specified Frequency." Should the 7 day interval be exceeded while operation is < 25% RTP, this Note allows 12 hours after power reaches $\ge 25\%$ RTP to perform the Surveillance. The Surveillance is still considered to be within the "specified Frequency." Therefore, if the Surveillance were not performed within the 7 day interval (plus the extension allowed by SR 3.0.2), but operation was < 25% RTP, it would not constitute a failure of the SR or failure to meet the LCO. Also, no violation of SR 3.0.4 occurs when changing MODES, even with the 7 day Frequency not met, provided operation does not exceed 12 hours with power $\ge 25\%$ RTP.

Once the unit reaches 25% RTP, 12 hours would be allowed for completing the Surveillance. If the Surveillance were not performed within this 12 hour interval, there would then be a failure to perform a Surveillance within the specified Frequency, and the provisions of SR 3.0.3 would apply.

EXAMPLES (continued)

EXAMPLE 1.4-4

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
NOTENOTEOnly required to be met in MODE 1.	
Verify leakage rates are within limits.	24 hours

Example 1.4-4 specifies that the requirements of this Surveillance do not have to be met until the unit is in MODE 1. The interval measurement for the Frequency of this Surveillance continues at all times, as described in Example 1.4-1. However, the Note constitutes an "otherwise stated" exception to the Applicability of this Surveillance. Therefore, if the Surveillance were not performed within the 24 hour interval (plus the extension allowed by SR 3.0.2), but the unit was not in MODE 1, there would be no failure of the SR nor failure to meet the LCO. Therefore, no violation of SR 3.0.4 occurs when changing MODES, even with the 24 hour Frequency exceeded, provided the MODE change was not made into MODE 1. Prior to entering MODE 1 (assuming again that the 24 hour Frequency were not met), SR 3.0.4 would require satisfying the SR.

EXAMPLE 1.4-5

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
NOTENOTE Only required to be performed in MODE 1.	
Perform complete cycle of the valve.	7 days

The interval continues, whether or not the unit operation is in MODE 1, 2, or 3 (the assumed Applicability of the associated LCO) between performances.

EXAMPLES (continued)

As the Note modifies the required <u>performance</u> of the Surveillance, the Note is construed to be part of the "specified Frequency." Should the 7 day interval be exceeded while operation is not in MODE 1, this Note allows entry into and operation in MODES 2 and 3 to perform the Surveillance. The Surveillance is still considered to be performed within the "specified Frequency" if completed prior to entering MODE 1. Therefore, if the Surveillance were not performed within the 7 day (plus the extension allowed by SR 3.0.2) interval, but operation was not in MODE 1, it would not constitute a failure of the SR or failure to meet the LCO. Also, no violation of SR 3.0.4 occurs when changing MODES, even with the 7 day Frequency not met, provided operation does not result in entry into MODE 1.

Once the unit reaches MODE 1, the requirement for the Surveillance to be performed within its specified Frequency applies and would require that the Surveillance had been performed. If the Surveillance were not performed prior to entering MODE 1, there would then be a failure to perform a Surveillance within the specified Frequency, and the provisions of SR 3.0.3 would apply.

EXAMPLE 1.4-6

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
NOTENOTENOTENOTENOTENOTENOTE 3.	
Verify parameter is within limits.	24 hours

Example 1.4-[6] specifies that the requirements of this Surveillance do not have to be met while the unit is in MODE 3 (the assumed Applicability of the associated LCO is MODES 1, 2, and 3). The interval measurement for the Frequency of this Surveillance continues at all times, as described in Example 1.4-1. However, the Note constitutes an "otherwise stated" exception to the Applicability of this Surveillance. Therefore, if the Surveillance were not performed within the 24 hour interval (plus the extension allowed by SR 3.0.2), and the unit was in MODE 3, there would be no failure of the SR nor failure to meet the LCO. Therefore, no violation of SR 3.0.4 occurs when changing MODES to enter MODE 3,

EXAMPLES (continued)

even with the 24 hour Frequency exceeded, provided the MODE change does not result in entry into MODE 2. Prior to entering MODE 2 (assuming again that the 24 hour Frequency were not met), SR 3.0.4 would require satisfying the SR.

2.0 SAFETY LIMITS (SLs)

2.1 SLs

- 2.1.1 <u>Reactor Core SLs</u>
 - 2.1.1.1 With the reactor steam dome pressure < 785 psig or core flow < 10% rated core flow:

THERMAL POWER shall be $\leq 25\%$ RTP.

2.1.1.2 With the reactor steam dome pressure \geq 785 psig and core flow \geq 10% rated core flow:

MCPR shall be \geq [1.07] for two recirculation loop operation or \geq [1.08] for single recirculation loop operation.

- 2.1.1.3 Reactor vessel water level shall be greater than the top of active irradiated fuel.
- 2.1.2 Reactor Coolant System Pressure SL

Reactor steam dome pressure shall be \leq 1325 psig.

2.2 SL VIOLATIONS

With any SL violation, the following actions shall be completed within 2 hours:

- 2.2.1 Restore compliance with all SLs; and
- 2.2.2 Insert all insertable control rods.
3.0 LIMITING CONDITION FOR OPERATION (LCO) APPLICABILITY

LCO 3.0.1	LCOs shall be met during the MODES or other specified conditions in the Applicability, except as provided in LCO 3.0.2 and LCO 3.0.7.		
LCO 3.0.2	Upon discovery of a failure to meet an LCO, the Required Actions of the associated Conditions shall be met, except as provided in LCO 3.0.5 and LCO 3.0.6.		
	If the LCO is met or is no longer applicable prior to expiration of the specified Completion Time(s), completion of the Required Action(s) is n required, unless otherwise stated.		
LCO 3.0.3	When an LCO is not met and the associated ACTIONS are not met, an associated ACTION is not provided, or if directed by the associated ACTIONS, the unit shall be placed in a MODE or other specified condition in which the LCO is not applicable. Action shall be initiated within 1 hour to place the unit, as applicable, in:		
	a. MODE 2 within [7] hours,		
	b. MODE 3 within 13 hours, and		
	c. MODE 4 within 37 hours.		
	Exceptions to this Specification are stated in the individual Specifications.		
	Where corrective measures are completed that permit operation in accordance with the LCO or ACTIONS, completion of the actions required by LCO 3.0.3 is not required.		
	LCO 3.0.3 is only applicable in MODES 1, 2, and 3.		
	The brackets around the time provided to reach MODE 2 allow a plant to extend the time from 7 hours to a plant specific time. Before the time can be changed, plant specific data must be provided to support the extended time.		
LCO 3.0.4	When an LCO is not met, entry into a MODE or other specified condition in the Applicability shall not be made except when the associated ACTIONS to be entered permit continued operation in the MODE or other specified condition in the Applicability for an unlimited period of time. This Specification shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS or that are part of a shutdown of the unit.		

LCO Applicability

LCO 3.0.4 (continued)

	Exceptions to this Specification are stated in the individual Specifications.
	LCO 3.0.4 is only applicable for entry into a MODE or other specified condition in the Applicability in MODES 1, 2, and 3.
	REVIEWER'S NOTE
LCO 3.0.5	Equipment removed from service or declared inoperable to comply with ACTIONS may be returned to service under administrative control solely to perform testing required to demonstrate its OPERABILITY or the OPERABILITY of other equipment. This is an exception to LCO 3.0.2 for the system returned to service under administrative control to perform the testing required to demonstrate OPERABILITY.
LCO 3.0.6	When a supported system LCO is not met solely due to a support system LCO not being met, the Conditions and Required Actions associated with this supported system are not required to be entered. Only the support system LCO ACTIONS are required to be entered. This is an exception to LCO 3.0.2 for the supported system. In this event, an evaluation shall be performed in accordance with Specification 5.5.12, "Safety Function Determination Program (SFDP)." If a loss of safety function is determined to exist by this program, the appropriate Conditions and Required Actions of the LCO in which the loss of safety function exists are required to be entered.
	When a support system's Required Action directs a supported system to be declared inoperable or directs entry into Conditions and Required Actions for a supported system, the applicable Conditions and Required Actions shall be entered in accordance with LCO 3.0.2.

LCO Applicability	
LCO 3.0.7	Special Operations LCOs in Section 3.10 allow specified Technical Specifications (TS) requirements to be changed to permit performance of special tests and operations. Unless otherwise specified, all other TS requirements remain unchanged. Compliance with Special Operations LCOs is optional. When a Special Operations LCO is desired to be met but is not met, the ACTIONS of the Special Operations LCO shall be met. When a Special Operations LCO is not desired to be met, entry into a MODE or other specified condition in the Applicability shall only be made in accordance with the other applicable Specifications.

3.0 SURVEILLANCE REQUIREMENT (SR) APPLICABILITY

SR 3.0.1	SRs shall be met during the MODES or other specified conditions in the Applicability for individual LCOs, unless otherwise stated in the SR. Failure to meet a Surveillance, whether such failure is experienced during the performance of the Surveillance or between performances of the Surveillance, shall be failure to meet the LCO. Failure to perform a Surveillance within the specified Frequency shall be failure to meet the LCO except as provided in SR 3.0.3. Surveillances do not have to be performed on inoperable equipment or variables outside specified limits.
SR 3.0.2	The specified Frequency for each SR is met if the Surveillance is performed within 1.25 times the interval specified in the Frequency, as measured from the previous performance or as measured from the time a specified condition of the Frequency is met.
	For Frequencies specified as "once," the above interval extension does not apply.
	If a Completion Time requires periodic performance on a "once per" basis, the above Frequency extension applies to each performance after the initial performance.
	Exceptions to this Specification are stated in the individual Specifications.
SR 3.0.3	If it is discovered that a Surveillance was not performed within its specified Frequency, then compliance with the requirement to declare the LCO not met may be delayed, from the time of discovery, up to 24 hours or up to the limit of the specified Frequency, whichever is greater. This delay period is permitted to allow performance of the Surveillance. A risk evaluation shall be performed for any Surveillance delayed greater than 24 hours and the risk impact shall be managed.
	If the Surveillance is not performed within the delay period, the LCO must immediately be declared not met, and the applicable Condition(s) must be entered.
	When the Surveillance is performed within the delay period and the Surveillance is not met, the LCO must immediately be declared not met, and the applicable Condition(s) must be entered.
SR 3.0.4	Entry into a MODE or other specified condition in the Applicability of an LCO shall not be made unless the LCO's Surveillances have been met within their specified Frequency. This provision shall not prevent entry into MODES or other specified conditions in the Applicability that are required to comply with ACTIONS or that are part of a shutdown of the unit.

SR Applicability

SR 3.0.4 (continued)

SR 3.0.4 is only applicable for entry into a MODE or other specified condition in the Applicability in MODES 1, 2, and 3.

3.1.1 SHUTDOWN MARGIN (SDM)

LCO 3.1.1 SDM shall be:

- a. \geq [0.38] % Δ k/k, with the highest worth control rod analytically determined or
- b. \geq [0.28] % Δ k/k, with the highest worth control rod determined by test.

APPLICABILITY: MODES 1, 2, 3, 4, and 5.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. SDM not within limits in MODE 1 or 2.	A.1	Restore SDM to within limits.	6 hours
 B. Required Action and associated Completion Time of Condition A not met. 	B.1	Be in MODE 3.	12 hours
C. SDM not within limits in MODE 3.	C.1	Initiate action to fully insert all insertable control rods.	Immediately
D. SDM not within limits in MODE 4.	D.1	Initiate action to fully insert all insertable control rods.	Immediately
	<u>AND</u>		
	D.2	Initiate action to restore [secondary] containment to OPERABLE status.	1 hour
	<u>AND</u>		

ACTIONS	(continued)
---------	-------------

CONDITION		REQUIRED ACTION	COMPLETION TIME
	D.3	Initiate action to restore one standby gas treatment (SGT) subsystem to OPERABLE status.	1 hour
	<u>AND</u>		
	D.4	Initiate action to restore isolation capability in each required [secondary] containment penetration flow path not isolated.	1 hour
E. SDM not within limits in MODE 5.	E.1	Suspend CORE ALTERATIONS except for control rod insertion and fuel assembly removal.	Immediately
	<u>AND</u>		
	E.2	Initiate action to fully insert all insertable control rods in core cells containing one or more fuel assemblies.	Immediately
	<u>AND</u>		

ACTIONS	(continued)
---------	-------------

CONDITION		REQUIRED ACTION	COMPLETION TIME
	E.3	Initiate action to restore [secondary] containment to OPERABLE status.	1 hour
	<u>AND</u>		
	E.4	Initiate action to restore one SGT subsystem to OPERABLE status.	1 hour
	<u>AND</u>		
	E.5	Initiate action to restore isolation capability in each required [secondary] containment penetration flow path not isolated.	1 hour

	SURVEILLANCE	FREQUENCY
SR 3.1.1.1	Verify SDM to be within limits.	Prior to each in vessel fuel movement during fuel loading sequence <u>AND</u> Once within 4 hours after criticality following fuel movement within the reactor pressure vessel or control rod replacement

3.1.2 Reactivity Anomalies

LCO 3.1.2 The reactivity [difference] between the [monitored rod density and the predicted rod density] shall be within $\pm 1\% \Delta k/k$.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Core reactivity [difference] not within limit.	A.1 Restore core reactivity [difference] to within limit.	72 hours
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3.	12 hours

	SURVEILLANCE	FREQUENCY
SR 3.1.2.1	Verify core reactivity [difference] between the [monitored rod density and the predicted rod density] is within \pm 1% Δ k/k.	Once within 24 hours after reaching equilibrium conditions following startup after fuel movement within the reactor pressure vessel or control rod replacement <u>AND</u> 1000 MWD/T thereafter during operations in MODE 1

3.1.3 Control Rod OPERABILITY

LCO 3.1.3 Each control rod shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One withdrawn control rod stuck.	NOTE Rod worth minimizer (RWM) may be bypassed as allowed by LCO 3.3.2.1, "Control Rod Block Instrumentation," if required, to allow continued operation.	
	A.1 Verify stuck control rod separation criteria are met.	Immediately
	AND	
	A.2 Disarm the associated control rod drive (CRD).	2 hours
	AND	

ACTIONS	(continued)

CONDITION		REQUIRED ACTION	COMPLETION TIME
	A.3	Perform SR 3.1.3.2 and SR 3.1.3.3 for each withdrawn OPERABLE control rod.	24 hours from discovery of Condition A concurrent with THERMAL POWER greater than the low power setpoint (LPSP) of the RWM
	<u>AND</u>		
	A.4	Perform SR 3.1.1.1.	72 hours
B. Two or more withdrawn control rods stuck.	B.1	Be in MODE 3.	12 hours
C. One or more control rods inoperable for reasons other than Condition A or B.	C.1	NOTE RWM may be bypassed as allowed by LCO 3.3.2.1, if required, to allow insertion of inoperable control rod and continued operation. 	3 hours
		control rod.	
	C.2	Disarm the associated CRD.	4 hours

ACTIONS (continued)

	CONDITION	REQUIRED ACTION		COMPLETION TIME
D.	NOTE Not applicable when THERMAL POWER > [10]% RTP.	D.1 <u>OR</u>	Restore compliance with BPWS.	4 hours
	Two or more inoperable control rods not in compliance with banked position withdrawal sequence (BPWS) and not separated by two or more OPERABLE control rods.	D.2	Restore control rod to OPERABLE status.	4 hours
E.	NOTE [Not applicable when THERMAL POWER > [10]% RTP.	E.1	Restore control rod to OPERABLE status.	4 hours]
_	One or more groups with four or more inoperable control rods.			
F.	Required Action and associated Completion Time of Condition A, C, D, or E not met.	F.1	Be in MODE 3.	12 hours
	<u>OR</u>			
	Nine or more control rods inoperable.			

	SURVEILLANCE	FREQUENCY
SR 3.1.3.1	Determine the position of each control rod.	24 hours
SR 3.1.3.2	NOTENOTE Not required to be performed until 7 days after the control rod is withdrawn and THERMAL POWER is greater than the LPSP of RWM.	
	Insert each fully withdrawn control rod at least one notch.	7 days
SR 3.1.3.3	NOTENOTE Not required to be performed until 31 days after the control rod is withdrawn and THERMAL POWER is greater than the LPSP of the RWM.	
	Insert each partially withdrawn control rod at least one notch.	31 days
SR 3.1.3.4	Verify each control rod scram time from fully withdrawn to notch position [06] is \leq 7 seconds.	In accordance with SR 3.1.4.1, SR 3.1.4.2, SR 3.1.4.3, and SR 3.1.4.4
SR 3.1.3.5	Verify each control rod does not go to the withdrawn overtravel position.	Each time the control rod is withdrawn to "full out" position
		AND
		Prior to declaring control rod OPERABLE after work on control rod or CRD System that could affect coupling

3.1.4 Control Rod Scram Times

- LCO 3.1.4 a. No more than [10] OPERABLE control rods shall be "slow," in accordance with Table 3.1.4-1, and
 - b. No more than 2 OPERABLE control rods that are "slow" shall occupy adjacent locations.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Requirements of the LCO not met.	A.1 Be in MODE 3.	12 hours

SURVEILLANCE REQUIREMENTS

-----NOTE-----NOTE------NOTE of scram time Surveillances, the control rod drive (CRD) pumps shall be isolated from the associated scram accumulator.

	SURVEILLANCE	FREQUENCY
SR 3.1.4.1	Verify each control rod scram time is within the limits of Table 3.1.4-1 with reactor steam dome pressure \geq [800] psig.	Prior to exceeding 40% RTP after each reactor shutdown ≥ 120 days
SR 3.1.4.2	Verify, for a representative sample, each tested control rod scram time is within the limits of Table 3.1.4-1 with reactor steam dome pressure \geq [800] psig.	120 days cumulative operation in MODE 1

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.1.4.3	Verify each affected control rod scram time is within the limits of Table 3.1.4-1 with any reactor steam dome pressure.	Prior to declaring control rod OPERABLE after work on control rod or CRD System that could affect scram time
SR 3.1.4.4	Verify each affected control rod scram time is within the limits of Table 3.1.4-1 with reactor steam dome pressure ≥ [800] psig.	Prior to exceeding 40% RTP after fuel movement within the affected core cell <u>AND</u> Prior to exceeding 40% RTP after work on control rod or CRD System that could affect scram time

Table 3.1.4-1 (page 1 of 1) Control Rod Scram Times

-----NOTES-----

- 1. OPERABLE control rods with scram times not within the limits of this Table are considered "slow."
- Enter applicable Conditions and Required Actions of LCO 3.1.3, "Control Rod OPERABILITY," for control rods with scram times > 7 seconds to notch position [06]. These control rods are inoperable, in accordance with SR 3.1.3.4, and are not considered "slow."

NOTCH POSITION	SCRAM TIMES ^{(a)(b)} (seconds) WHEN REACTOR STEAM DOME PRESSURE ≥ [800] psig
[46]	[0.44]
[36]	[1.08]
[26]	[1.83]
[06]	[3.35]

- (a) Maximum scram time from fully withdrawn position, based on de-energization of scram pilot valve solenoids at time zero.
- (b) Scram times as a function of reactor steam dome pressure, when < 800 psig are within established limits.

3.1.5 Control Rod Scram Accumulators

LCO 3.1.5 Each control rod scram accumulator shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION		COMPLETION TIME
 A. One control rod scram accumulator inoperable with reactor steam dome pressure ≥ [900] psig. 	A.1	NOTE Only applicable if the associated control rod scram time was within the limits of Table 3.1.4-1 during the last scram time Surveillance.	
		Declare the associated control rod scram time "slow."	8 hours
	<u>OR</u>		
	A.2	Declare the associated control rod inoperable.	8 hours
 B. Two or more control rod scram accumulators inoperable with reactor steam dome pressure ≥ [900] psig. 	В.1 <u>AND</u>	Restore charging water header pressure to ≥ [940] psig.	20 minutes from discovery of Condition B concurrent with charging water header pressure < [940] psig

ACTIONS (continued)

CONDITION		REQUIRED ACTION	COMPLETION TIME
	B.2.1	Only applicable if the associated control rod scram time was within the limits of Table 3.1.4-1 during the last scram time Surveillance.	
		Declare the associated control rod scram time "slow."	1 hour
	<u>OR</u>		
	B.2.2	Declare the associated control rod inoperable.	1 hour
 C. One or more control rod scram accumulators inoperable with reactor steam dome pressure < [900] psig. 	C.1	Verify all control rods associated with inoperable accumulators are fully inserted.	Immediately upon discovery of charging water header pressure < [940] psig
	<u>AND</u>		
	C.2	Declare the associated control rod inoperable.	1 hour
D. Required Action and associated Completion Time of Required Action B.1 or C.1 not met.	D.1	NOTE Not applicable if all inoperable control rod scram accumulators are associated with fully inserted control rods.	
		Place the reactor mode switch in the shutdown position.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.1.5.1	Verify each control rod scram accumulator pressure is \geq [940] psig.	7 days

- 3.1.6 Rod Pattern Control
- LCO 3.1.6 OPERABLE control rods shall comply with the requirements of the [banked position withdrawal sequence (BPWS)].
- APPLICABILITY: MODES 1 and 2 with THERMAL POWER \leq [10]% RTP.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or more OPERABLE control rods not in compliance with [BPWS].	A.1	NOTE Rod worth minimizer (RWM) may be bypassed as allowed by LCO 3.3.2.1, "Control Rod Block Instrumentation."	9 houro
		rod(s) to correct position.	8 nours
	<u>OR</u>		
	A.2	Declare associated control rod(s) inoperable.	8 hours
 B. Nine or more OPERABLE control rods not in compliance with [BPWS]. 	B.1	NOTE Rod worth minimizer (RWM) may be bypassed as allowed by LCO 3.3.2.1.	
		Suspend withdrawal of control rods.	Immediately
	<u>AND</u>		

ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
	B.2 Place the reactor mode switch in the shutdown position.	1 hour

	SURVEILLANCE	FREQUENCY
SR 3.1.6.1	Verify all OPERABLE control rods comply with [BPWS].	24 hours

3.1.7 Standby Liquid Control (SLC) System

LCO 3.1.7 Two SLC subsystems shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
 A. [Concentration of boron in solution not within limits but > []. 	A.1	Restore concentration of boron in solution to within limits.	72 hours AND 10 days from discovery of failure to meet the LCO]
B. One SLC subsystem inoperable [for reasons other than Condition A].	B.1	Restore SLC subsystem to OPERABLE status.	7 days <u>AND</u> [10 days from discovery of failure to meet the LCO]
C. Two SLC subsystems inoperable [for reasons other than Condition A].	C.1	Restore one SLC subsystem to OPERABLE status.	8 hours
D. Required Action and associated Completion Time not met.	D.1	Be in MODE 3.	12 hours

	SURVEILLANCE	FREQUENCY
SR 3.1.7.1	Verify available volume of sodium pentaborate solution is [within the limits of Figure 3.1.7-1, or \geq [4530] gallons].	24 hours
SR 3.1.7.2	[Verify temperature of sodium pentaborate solution is within the limits of [Figure 3.1.7-2].	24 hours]
SR 3.1.7.3	[Verify temperature of pump suction piping is within the limits of [Figure 3.1.7-2].	24 hours]
SR 3.1.7.4	Verify continuity of explosive charge.	31 days
SR 3.1.7.5	Verify the concentration of boron in solution is [within the limits of Figure 3.1.7-1].	31 days <u>AND</u> Once within 24 hours after water or boron is added to solution <u>AND</u> Once within 24 hours after solution temperature is restored within the limits of [Figure 3.1.7-2]
SR 3.1.7.6	Verify each SLC subsystem manual, power operated, [and automatic valve] in the flow path that is not locked, sealed, or otherwise secured in position is in the correct position, or can be aligned to the correct position.	31 days

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.1.7.7	Verify each pump develops a flow rate \ge [41.2] gpm at a discharge pressure \ge [1190] psig.	[In accordance with the Inservice Testing Program or 92 days]
SR 3.1.7.8	Verify flow through one SLC subsystem from pump into reactor pressure vessel.	[18] months on a STAGGERED TEST BASIS
SR 3.1.7.9	[Verify all heat traced piping between storage tank and pump suction is unblocked.	[18] months <u>AND</u> Once within 24 hours after solution temperature is restored within the limits of [Figure 3.1.7-2]]
SR 3.1.7.10	[Verify sodium pentaborate enrichment is \geq [60.0] atom percent B-10.	Prior to addition to SLC tank]







Figure 3.1.7-2 (page 1 of 1) Sodium Pentaborate Solution Temperature Versus Concentration Requirements

3.1.8 Scram Discharge Volume (SDV) Vent and Drain Valves

LCO 3.1.8 Each SDV vent and drain valve shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more SDV vent or drain lines with one valve inoperable.	A.1 Restore valve to OPERABLE status.	7 days
B. One or more SDV vent or drain lines with both valves inoperable.	B.1NOTE An isolated line may be unisolated under administrative control to allow draining and venting of the SDV. 	8 hours
C. Required Action and associated Completion Time not met.	C.1 Be in MODE 3.	12 hours

	FREQUENCY	
SR 3.1.8.1	NOTENOTE-NOTE Not required to be met on vent and drain valves closed during performance of SR 3.1.8.2.	
	Verify each SDV vent and drain valve is open.	31 days
SR 3.1.8.2	Cycle each SDV vent and drain valve to the fully closed and fully open position.	92 days
SR 3.1.8.3	 Verify each SDV vent and drain valve: a. Closes in ≤ [60] seconds after receipt of an actual or simulated scram signal and b. Opens when the actual or simulated scram signal is reset. 	[18] months

3.2 POWER DISTRIBUTION LIMITS

3.2.1 AVERAGE PLANAR LINEAR HEAT GENERATION RATE (APLHGR)

LCO 3.2.1 All APLHGRs shall be less than or equal to the limits specified in the COLR.

APPLICABILITY: THERMAL POWER \geq 25% RTP.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Any APLHGR not within limits.	A.1 Restore APLHGR(s) to within limits.	2 hours
B. Required Action and associated Completion Time not met.	B.1 Reduce THERMAL POWER to < 25% RTP.	4 hours

	SURVEILLANCE	FREQUENCY
SR 3.2.1.1	Verify all APLHGRs are less than or equal to the limits specified in the COLR.	Once within 12 hours after ≥ 25% RTP <u>AND</u> 24 hours thereafter

3.2 POWER DISTRIBUTION LIMITS

3.2.2 MINIMUM CRITICAL POWER RATIO (MCPR)

LCO 3.2.2 All MCPRs shall be greater than or equal to the MCPR operating limits specified in the COLR.

APPLICABILITY: THERMAL POWER \geq 25% RTP.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. Any MCPR not within limits.	A.1	Restore MCPR(s) to within limits.	2 hours
B. Required Action and associated Completion Time not met.	B.1	Reduce THERMAL POWER to < 25% RTP.	4 hours

	SURVEILLANCE	FREQUENCY
SR 3.2.2.1	Verify all MCPRs are greater than or equal to the limits specified in the COLR.	Once within 12 hours after ≥ 25% RTP <u>AND</u> 24 hours
		thereafter

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.2.2.2	Determine the MCPR limits.	Once within 72 hours after each completion of SR 3.1.4.1
		AND
		Once within 72 hours after each completion of SR 3.1.4.2
		AND
		Once within 72 hours after each completion of SR 3.1.4.4

3.2 POWER DISTRIBUTION LIMITS

3.2.3 LINEAR HEAT GENERATION RATE (LHGR) (Optional)

LCO 3.2.3 All LHGRs shall be less than or equal to the limits specified in the COLR.

APPLICABILITY: THERMAL POWER $\geq 25\%$ RTP.

ACTIONS

CONDITION	REQUIRED ACTION		COMPLETION TIME
A. Any LHGR not within limits.	A.1	Restore LHGR(s) to within limits.	2 hours
B. Required Action and associated Completion Time not met.	B.1	Reduce THERMAL POWER to < 25% RTP.	4 hours

SURVEILLANCE	FREQUENCY
SR 3.2.3.1 Verify all LHGRs are less than or equal to the limits specified in the COLR.	Once within 12 hours after ≥ 25% RTP <u>AND</u> 24 hours thereafter

3.2 POWER DISTRIBUTION LIMITS

- 3.2.4 Average Power Range Monitor (APRM) Gain and Setpoints (Optional)
- LCO 3.2.4 a. MFLPD shall be less than or equal to Fraction of RTP, or
 - b. Each required APRM setpoint specified in the COLR shall be made applicable, or
 - c. Each required APRM gain shall be adjusted such that the APRM readings are \geq 100% times MFLPD.
- APPLICABILITY: THERMAL POWER $\geq 25\%$ RTP.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Requirements of the LCO not met.	A.1 Satisfy the requirements of the LCO.	6 hours
B. Required Action and associated Completion Time not met.	B.1 Reduce THERMAL POWER to < 25% RTP.	4 hours

SURVEILLANCE		FREQUENCY
SR 3.2.4.1	NOTENOTE Not required to be met if SR 3.2.4.2 is satisfied for LCO 3.2.4 Item b or c requirements.	
	Verify MFLPD is within limits.	Once within 12 hours after ≥ 25% RTP
		AND
		24 hours thereafter
SR 3.2.4.2	NOTENOTENOTENOTENOTENOTENOTENOTENOTE	
	Verify APRM setpoints or gains are adjusted for the calculated MFLPD.	12 hours
- 3.3.1.1 Reactor Protection System (RPS) Instrumentation
- LCO 3.3.1.1 The RPS instrumentation for each Function in Table 3.3.1.1-1 shall be OPERABLE.

APPLICABILITY: According to Table 3.3.1.1-1.

ACTIONS

CONDITION		REQUIRED ACTION		COMPLETION TIME
A. One or mo	ore required inoperable.	A.1	Place channel in trip.	12 hours
		<u>OR</u>		
		A.2	Place associated trip system in trip.	12 hours
B. One or mo with one o	ore Functions or more channels	B.1	Place channel in one trip system in trip.	6 hours
inoperable in both trip		<u>OR</u>		
systems.		B.2	Place one trip system in trip.	6 hours
C. One or mo with RPS not mainta	ore Functions trip capability ained.	C.1	Restore RPS trip capability.	1 hour
D. Required associated Time of Co or C not m	Action and d Completion ondition A, B, net.	D.1	Enter the Condition referenced in Table 3.3.1.1-1 for the channel.	Immediately

ACTIONS (continued)

CONDITION		REQUIRED ACTION	COMPLETION TIME
E. As required by Required Action D.1 and referenced in Table 3.3.1.1-1.	E.1	Reduce THERMAL POWER to < [30]% RTP.	4 hours
F. As required by Required Action D.1 and referenced in Table 3.3.1.1-1.	F.1	Be in MODE 2.	6 hours
G. As required by Required Action D.1 and referenced in Table 3.3.1.1-1.	G.1	Be in MODE 3.	12 hours
H. As required by Required Action D.1 and referenced in Table 3.3.1.1-1.	H.1	Initiate action to fully insert all insertable control rods in core cells containing one or more fuel assemblies.	Immediately

SURVEILLANCE REQUIREMENTS

- Refer to Table 3.3.1.1-1 to determine which SRs apply for each RPS Function.
- When a channel is placed in an inoperable status solely for performance of required Surveillances, entry into associated Conditions and Required Actions may be delayed for up to 6 hours provided the associated Function maintains RPS trip capability.

	SURVEILLANCE	FREQUENCY
SR 3.3.1.1.1	Perform CHANNEL CHECK.	12 hours

	SURVEILLANCE	FREQUENCY
SR 3.3.1.1.2	NOTENOTENOTENOTENOTENOTE	
	Verify the absolute difference between the average power range monitor (APRM) channels and the calculated power is $\leq 2\%$ RTP [plus any gain adjustment required by LCO 3.2.4, "Average Power Range Monitor (APRM) Setpoints"] while operating at $\geq 25\%$ RTP.	7 days
SR 3.3.1.1.3	Adjust the channel to conform to a calibrated flow signal.	7 days
SR 3.3.1.1.4	NOTENOTE Not required to be performed when entering MODE 2 from MODE 1 until 12 hours after entering MODE 2.	
	Perform CHANNEL FUNCTIONAL TEST.	7 days
SR 3.3.1.1.5	Perform CHANNEL FUNCTIONAL TEST.	7 days
SR 3.3.1.1.6	Calibrate the local power range monitors.	1000 MWD/T average core exposure
SR 3.3.1.1.7	Perform CHANNEL FUNCTIONAL TEST.	[92] days
SR 3.3.1.1.8	[Calibrate the trip units.	[92] days]

	FREQUENCY	
SR 3.3.1.1.9	 Neutron detectors are excluded. For Function 2.a, not required to be performed when entering MODE 2 from MODE 1 until 12 hours after entering MODE 2. 	
	Perform CHANNEL CALIBRATION.	184 days
SR 3.3.1.1.10	Perform CHANNEL FUNCTIONAL TEST.	[18] months
SR 3.3.1.1.11	 Neutron detectors are excluded. For Function 1, not required to be performed when entering MODE 2 from MODE 1 until 12 hours after entering MODE 2. Perform CHANNEL CALIBRATION. 	[18] months
SR 3.3.1.1.12	Verify the APRM Flow Biased Simulated Thermal Power - High time constant is \leq [7] seconds.	[18] months
SR 3.3.1.1.13	Perform LOGIC SYSTEM FUNCTIONAL TEST.	[18] months
SR 3.3.1.1.14	Verify Turbine Stop Valve - Closure and Turbine Control Valve Fast Closure, Trip Oil Pressure - Low Functions are not bypassed when THERMAL POWER is \geq [30]% RTP.	[18] months

	SURVEILLANCE	FREQUENCY
SR 3.3.1.1.15	 NOTES	[18] months on a STAGGERED TEST BASIS

Table 3.3.1.1-1 (page 1 of 4) Reactor Protection System Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION D.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
1.	Inte Mo	ermediate Range nitors					
	a.	Neutron Flux - High	2	[3]	G	SR 3.3.1.1.1 SR 3.3.1.1.4 SR 3.3.1.1.11 SR 3.3.1.1.13	≤ [120/125] divisions of full scale
			5 ^(a)	[3]	Н	SR 3.3.1.1.1 SR 3.3.1.1.5 SR 3.3.1.1.11 SR 3.3.1.1.13	≤ [120/125] divisions of full scale
	b.	Inop	2	[3]	G	SR 3.3.1.1.4 SR 3.3.1.1.13	NA
			5 ^(a)	[3]	Н	SR 3.3.1.1.5 SR 3.3.1.1.13	NA
2.	Ave Mo	erage Power Range nitors					
	a.	Neutron Flux - High, Setdown	2	[2]	G	SR 3.3.1.1.1 SR 3.3.1.1.4 SR 3.3.1.1.6 SR 3.3.1.1.9 SR 3.3.1.1.13	≤ [20]% RTP
	b.	Flow Biased Simulated Thermal Power - High	1	[2]	F	SR 3.3.1.1.1 SR 3.3.1.1.2 SR 3.3.1.1.3 SR 3.3.1.1.6 SR 3.3.1.1.6 SR 3.3.1.1.7 SR 3.3.1.1.9 SR 3.3.1.1.12 SR 3.3.1.1.13 SR 3.3.1.1.15	\leq [0.58 W + 62]% RTP and \leq [115.5]% RTP ^(b)

(a) With any control rod withdrawn from a core cell containing one or more fuel assemblies.

(b) [0.58 W + 62% - 0.58 △W]RTP when reset for single loop operation per LCO 3.4.1, "Recirculation Loops Operating."

Table 3.3.1.1-1 (page 2 of 4) Reactor Protection System Instrumentation

	FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION D.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
2.	Average Power Range Monitors					
	c. Fixed Neutron Flux - High	1	[2]	F	SR 3.3.1.1.1 SR 3.3.1.1.2 SR 3.3.1.1.6 SR 3.3.1.1.7 SR 3.3.1.1.9 SR 3.3.1.1.13 SR 3.3.1.1.15	≤ [120]% RTP
	[d. Downscale	1	[2]	F	SR 3.3.1.1.6 SR 3.3.1.1.7 SR 3.3.1.1.13	≥[3]% RTP]
	e. Inop	1,2	[2]	G	SR 3.3.1.1.6 SR 3.3.1.1.7 SR 3.3.1.1.13	NA
3.	Reactor Vessel Steam Dome Pressure - High	1,2	[2]	G	SR 3.3.1.1.1 SR 3.3.1.1.7 [SR 3.3.1.1.8] SR 3.3.1.1.11 SR 3.3.1.1.13 SR 3.3.1.1.15	≤ [1054] psig
4.	Reactor Vessel Water Level - Low, Level 3	1,2	[2]	G	SR 3.3.1.1.1 SR 3.3.1.1.7 [SR 3.3.1.1.8] SR 3.3.1.1.11 SR 3.3.1.1.13 SR 3.3.1.1.15	≥ [10] inches
5.	Main Steam Isolation Valve - Closure	1	[8]	F	SR 3.3.1.1.7 SR 3.3.1.1.11 SR 3.3.1.1.13 SR 3.3.1.1.15	\leq [10]% closed
6.	Drywell Pressure - High	1,2	[2]	G	SR 3.3.1.1.1 SR 3.3.1.1.7 [SR 3.3.1.1.8] SR 3.3.1.1.11 SR 3.3.1.1.13	≤ [1.92] psig

Table 3.3.1.1-1 (page 3 of 4) Reactor Protection System Instrumentation

	FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION D.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
7.	Scram Discharge Volume Water Level - High					
	a. Resistance Temperature Detector	1,2	[2]	G	SR 3.3.1.1.1 SR 3.3.1.1.7 [SR 3.3.1.1.8] SR 3.3.1.1.11 SR 3.3.1.1.13	≤ [57.15] gallons
		5 ^(a)	[2]	н	SR 3.3.1.1.1 SR 3.3.1.1.7 [SR 3.3.1.1.8] SR 3.3.1.1.11 SR 3.3.1.1.13	≤ [57.15] gallons
	b. Float Switch	1,2	[2]	G	SR 3.3.1.1.7 SR 3.3.1.1.11 SR 3.3.1.1.13	≤ [57.15] gallons
		5 ^(a)	[2]	Н	SR 3.3.1.1.7 SR 3.3.1.1.11 SR 3.3.1.1.13	≤ [57.15] gallons
8.	Turbine Stop Valve - Closure	≥ [30]% RTP	[4]	E	SR 3.3.1.1.7 [SR 3.3.1.1.8] SR 3.3.1.1.11 SR 3.3.1.1.13 SR 3.3.1.1.14 SR 3.3.1.1.15	≤ [10]% closed
9.	Turbine Control Valve Fast Closure, Trip Oil Pressure - Low	≥ [30]% RTP	[2]	E	SR 3.3.1.1.7 [SR 3.3.1.1.8] SR 3.3.1.1.11 SR 3.3.1.1.13 SR 3.3.1.1.14 SR 3.3.1.1.15	≥ [600] psig
10.	Reactor Mode Switch - Shutdown Position	1,2	[2]	G	SR 3.3.1.1.10 SR 3.3.1.1.13	NA
		5 ^(a)	[2]	Н	SR 3.3.1.1.10 SR 3.3.1.1.13	NA

(a) With any control rod withdrawn from a core cell containing one or more fuel assemblies.

Table 3.3.1.1-1 (page 4 of 4) Reactor Protection System Instrumentation

FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION D.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
11. Manual Scram	1,2	[2]	G	SR 3.3.1.1.5 SR 3.3.1.1.13	NA
	5 ^(a)	[2]	Н	SR 3.3.1.1.5 SR 3.3.1.1.13	NA

(a) With any control rod withdrawn from a core cell containing one or more fuel assemblies.

3.3.1.2 Source Range Monitor (SRM) Instrumentation

100 3312	The SRM instrumentation in	Table 3 3 1 2-1 shall be OPERARI E
LCO 3.3.1.Z		TADIE J.J. I.Z-I SHAII DE OFERADLE.

APPLICABILITY: According to Table 3.3.1.2-1.

ACTIONS

CONDITION	REQUIRED ACTION		COMPLETION TIME
A. One or more required SRMs inoperable in MODE 2 with intermediate range monitors (IRMs) on Range 2 or below.	A.1	Restore required SRMs to OPERABLE status.	4 hours
 B. [Three] required SRMs inoperable in MODE 2 with IRMs on Range 2 or below. 	B.1	Suspend control rod withdrawal.	Immediately
C. Required Action and associated Completion Time of Condition A or B not met.	C.1	Be in MODE 3.	12 hours
D. One or more required SRMs inoperable in MODE 3 or 4.	D.1 <u>AND</u>	Fully insert all insertable control rods.	1 hour
	D.2	Place reactor mode switch in the shutdown position.	1 hour

CONDITION	REQUIRED ACTION		COMPLETION TIME
E. One or more required SRMs inoperable in MODE 5.	RMs inoperable in IODE 5.		Immediately
	<u>AND</u>		
	E.2	Initiate action to fully insert all insertable control rods in core cells containing one or more fuel assemblies.	Immediately

SURVEILLANCE REQUIREMENTS

Refer to Table 3.3.1.2-1 to determine which SRs apply for each applicable MODE or other specified conditions.

	SURVEILLANCE	FREQUENCY
SR 3.3.1.2.1	Perform CHANNEL CHECK.	12 hours

	SURVEILLANCE	FREQUENCY
SR 3.3.1.2.2	 Only required to be met during CORE ALTERATIONS. One SRM may be used to satisfy more than one of the following. 	
	Verify an OPERABLE SRM detector is located in: a. The fueled region,	12 hours
	 b. The core quadrant where CORE ALTERATIONS are being performed, when the associated SRM is included in the fueled region, and 	
	c. A core quadrant adjacent to where CORE ALTERATIONS are being performed, when the associated SRM is included in the fueled region.	
SR 3.3.1.2.3	Perform CHANNEL CHECK.	24 hours
SR 3.3.1.2.4	Not required to be met with less than or equal to four fuel assemblies adjacent to the SRM and no other fuel assemblies in the associated core quadrant. Verify count rate is:	12 hours during
	a. \geq [3.0] cps with a signal to noise ratio \geq [2:1] or b. \geq [0.7] cps with a signal to noise ratio \geq [20:1]	ALTERATIONS
		24 hours
SR 3.3.1.2.5	Perform CHANNEL FUNCTIONAL TEST [and determination of signal to noise ratio].	7 days

	FREQUENCY	
SR 3.3.1.2.6NOTENOTENOTENOTENOTENOTE		
	Perform CHANNEL FUNCTIONAL TEST [and determination of signal to noise ratio].	31 days
SR 3.3.1.2.7 NOTES 1. Neutron detectors are excluded. 2. Not required to be performed until 12 hours after IRMs on Range 2 or below. Perform CHANNEL CALIBRATION.		[18] months

Table 3.3.1.2-1 (page 1 of 1)
Source Range Monitor Instrumentation

FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS	SURVEILLANCE REQUIREMENTS
1. Source Range Monitor	2 ^(a)	[3]	SR 3.3.1.2.1 SR 3.3.1.2.4 SR 3.3.1.2.6 SR 3.3.1.2.7
	3, 4	2	SR 3.3.1.2.3 SR 3.3.1.2.4 SR 3.3.1.2.6 SR 3.3.1.2.7
	5	2(b), (c)	SR 3.3.1.2.1 SR 3.3.1.2.2 SR 3.3.1.2.4 SR 3.3.1.2.5 SR 3.3.1.2.7

(a) With IRMs on Range 2 or below.

(b) Only one SRM channel is required to be OPERABLE during spiral offload or reload when the fueled region includes only that SRM detector.

(c) Special movable detectors may be used in place of SRMs if connected to normal SRM circuits.

- 3.3.2.1 Control Rod Block Instrumentation
- LCO 3.3.2.1 The control rod block instrumentation for each Function in Table 3.3.2.1-1 shall be OPERABLE.
- APPLICABILITY: According to Table 3.3.2.1-1.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One rod block monitor (RBM) channel inoperable.	A.1 Restore RBM channel to OPERABLE status.	24 hours
 B. Required Action and associated Completion Time of Condition A not met. <u>OR</u> Two RBM channels inoperable. 	B.1 Place one RBM channel in trip.	1 hour
C. Rod worth minimizer (RWM) inoperable during reactor startup.	 C.1 Suspend control rod movement except by scram. <u>OR</u> C.2.1.1 Verify ≥ 12 rods withdrawn. <u>OR</u> 	Immediately Immediately

CONDITION	REQUIRED ACTION		COMPLETION TIME
	C.2.1.2	2 Verify by administrative methods that startup with RWM inoperable has not been performed in the last calendar year.	Immediately
	C.2.2	Verify movement of control rods is in compliance with banked position withdrawal sequence (BPWS) by a second licensed operator or other qualified member of the technical staff.	During control rod movement
D. RWM inoperable during reactor shutdown.	D.1	Verify movement of control rods is in compliance with BPWS by a second licensed operator or other qualified member of the technical staff.	During control rod movement
E. One or more Reactor Mode Switch - Shutdown Position channels inoperable.	E.1 <u>AND</u>	Suspend control rod withdrawal.	Immediately
	E.2	Initiate action to fully insert all insertable control rods in core cells containing one or more fuel assemblies.	Immediately

SURVEILLANCE REQUIREMENTS

- Refer to Table 3.3.2.1-1 to determine which SRs apply for each Control Rod Block Function.
- 2. When an RBM channel is placed in an inoperable status solely for performance of required Surveillances, entry into associated Conditions and Required Actions may be delayed for up to 6 hours provided the associated Function maintains control rod block capability.

	SURVEILLANCE	FREQUENCY
SR 3.3.2.1.1	Perform CHANNEL FUNCTIONAL TEST.	[92] days
SR 3.3.2.1.2	Not required to be performed until 1 hour after any control rod is withdrawn at \leq [10]% RTP in MODE 2.	
	Perform CHANNEL FUNCTIONAL TEST.	[92] days
SR 3.3.2.1.3	NOTENOTENOTENOTENOTENOTENOTE	
	Perform CHANNEL FUNCTIONAL TEST.	[92] days

	FREQUENCY	
SR 3.3.2.1.4	NOTE [Neutron detectors are excluded.]	
	Verify the RBM:	[18] months
	 Low Power Range - Upscale Function is not bypassed when THERMAL POWER is ≥ 29% and ≤ 64% RTP. 	
	 b. Intermediate Power Range - Upscale Function is not bypassed when THERMAL POWER is > 64% and ≤ 84% RTP. 	
	 c. High Power Range - Upscale Function is not bypassed when THERMAL POWER is > 84% RTP. 	
SR 3.3.2.1.5	Verify the RWM is not bypassed when THERMAL POWER is \leq [10]% RTP.	[18] months
SR 3.3.2.1.6	NOTENOTENOTE Not required to be performed until 1 hour after reactor mode switch is in the shutdown position.	
	Perform CHANNEL FUNCTIONAL TEST.	[18] months
SR 3.3.2.1.7	NOTENOTENOTENOTENOTENOTE	
	Perform CHANNEL CALIBRATION.	[18] months
SR 3.3.2.1.8	Verify control rod sequences input to the RWM are in conformance with BPWS.	Prior to declaring RWM OPERABLE following loading of sequence into RWM

Table 3.3.2.1-1 (page 1 of 1)
Control Rod Block Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
1.	Ro	d Block Monitor				
	a.	Low Power Range - Upscale	(a)	[2]	SR 3.3.2.1.1 SR 3.3.2.1.4 SR 3.3.2.1.7	\leq [115.5/125] divisions of full scale
	b.	Intermediate Power Range - Upscale	(b)	[2]	SR 3.3.2.1.1 SR 3.3.2.1.4 SR 3.3.2.1.7	\leq [109.7/125] divisions of full scale
	C.	High Power Range - Upscale	(c),(d)	[2]	SR 3.3.2.1.1 SR 3.3.2.1.4 SR 3.3.2.1.7	\leq [105.9/125] divisions of full scale
	d.	Inop	(d),(e)	[2]	SR 3.3.2.1.1	NA
	e.	Downscale	(d),(e)	[2]	SR 3.3.2.1.1 SR 3.3.2.1.7	≥ [93/125] divisions of full scale
	f.	Bypass Time Delay	(d),(e)	[2]	SR 3.3.2.1.1 SR 3.3.2.1.7	\leq [2.0] seconds
2.	Ro	d Worth Minimizer	1 ^(f) , 2 ^(f)	[1]	SR 3.3.2.1.2 SR 3.3.2.1.3 SR 3.3.2.1.5 SR 3.3.2.1.8	NA
3.	Re Po	actor Mode Switch - Shutdown sition	(g)	[2]	SR 3.3.2.1.6	NA

(a) THERMAL POWER \geq [29]% and \leq [64]% RTP and MCPR < 1.70.

(b) THERMAL POWER > [64]% and \leq [84]% RTP and MCPR < 1.70.

(c) THERMAL POWER > [84]% and < 90% RTP and MCPR < 1.70.

- (d) THERMAL POWER \geq 90% RTP and MCPR < 1.40.
- (e) THERMAL POWER \geq [64]% and < 90% RTP and MCPR < 1.70.

(f) With THERMAL POWER \leq [10]% RTP.

(g) Reactor mode switch in the shutdown position.

3322	Feedwater and Main	Turbine High Water	Level Trip	Instrumentation
0.0.2.2		rubine riigir water		monutation

LCO 3.3.2.2 [Three] channels of feedwater and main turbine high water level trip instrumentation shall be OPERABLE.

APPLICABILITY: THERMAL POWER \geq [25]% RTP.

ACTIONS

CONDITION	CONDITION REQUIRED ACTION	
A. One feedwater and main turbine high water level trip channel inoperable.	A.1 Place channel in trip.	7 days
B. Two or more feedwater and main turbine high water level trip channels inoperable.	B.1 Restore feedwater and main turbine high water level trip capability.	2 hours
C. Required Action and associated Completion Time not met.	 NOTE Only applicable if inoperable channel is the result of inoperable feedwater pump [valve] or main turbine stop valve. C.1 Remove affected feedwater pump(s) and main turbine valve(s) from service. 	4 hours
	OR	

ACTIONS (continued)					
CONDITION	REQUIRED ACTION	COMPLETION TIME			
	C.2 Reduce THERMAL POWER to < [25]% RTP.	4 hours			

SURVEILLANCE REQUIREMENTS

	SURVEILLANCE	FREQUENCY
SR 3.3.2.2.1	Perform CHANNEL CHECK.	24 hours]
SR 3.3.2.2.2	Perform CHANNEL FUNCTIONAL TEST.	[92] days
SR 3.3.2.2.3	Perform CHANNEL CALIBRATION. The Allowable Value shall be \leq [58.0] inches.	[18] months
SR 3.3.2.2.4	Perform LOGIC SYSTEM FUNCTIONAL TEST including [valve] actuation.	[18] months

3.3 INSTRUMENTATION

3.3.3.1 Post Accident Monitoring (PAM) Instrumentation

LCO 3.3.3.1 The PAM instrumentation for each Function in Table 3.3.3.1-1 shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

-----NOTES------

- 1. LCO 3.0.4 is not applicable.
- 2. Separate Condition entry is allowed for each Function.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more Functions with one required channel inoperable.	A.1 Restore required channel to OPERABLE status.	30 days
B. Required Action and associated Completion Time of Condition A not met.	B.1 Initiate action in accordance with Specification 5.6.7.	Immediately
CNOTE Not applicable to [hydrogen monitor] channels. One or more Functions with two required channels inoperable.	C.1 Restore one required channel to OPERABLE status.	7 days
D. Two [required hydrogen monitor] channels inoperable.	D.1 Restore one [required hydrogen monitor] channel to OPERABLE status.	72 hours

CONDITION	REQUIRED ACTION		COMPLETION TIME
E. Required Action and associated Completion Time of Condition C or D not met.	E.1	Enter the Condition referenced in Table 3.3.3.1-1 for the channel.	Immediately
F. As required by Required Action E.1 and referenced in Table 3.3.3.1-1.	F.1	Be in MODE 3.	12 hours
G. [As required by Required Action E.1 and referenced in Table 3.3.3.1-1.	G.1	Initiate action in accordance with Specification 5.6.7.	Immediately]

SURVEILLANCE REQUIREMENTS

	SURVEILLANCE	FREQUENCY
SR 3.3.3.1.1	Perform CHANNEL CHECK.	31 days
SR 3.3.3.1.2	Perform CHANNEL CALIBRATION.	[18] months

Table 3.3.3.1-1 (page 1 of 1) Post Accident Monitoring Instrumentation

	FUNCTION	REQUIRED CHANNELS	CONDITIONS REFERENCED FROM REQUIRED ACTION E.1
1.	Reactor Steam Dome Pressure	2	F
2.	Reactor Vessel Water Level	2	F
3.	Suppression Pool Water Level	2	F
4.	Drywell Pressure	2	F
5.	Primary Containment Area Radiation	2	[G]
[6.	Drywell Sump Level	2	F]
[7.	Drywell Drain Sump Level	2	F]
8.	Penetration Flow Path PCIV Position	2 per penetration flow path ^{(a) (b)}	F
9.	Wide Range Neutron Flux	2	F
10.	Drywell H ₂ & O ₂ Analyzer	2	F
11.	Containment H ₂ & O ₂ Analyzer	2	F
12.	Primary Containment Pressure	2	F
13.	[Relief Valve Discharge Location] Suppression Pool Water Temperature	2 ^(c)	F

(a) Not required for isolation valves whose associated penetration flow path is isolated by at least one closed and deactivated automatic valve, closed manual valve, blind flange, or check valve with flow through the valve secured.

(b) Only one position indication channel is required for penetration flow paths with only one installed control room indication channel.

(c) Monitoring each [relief valve discharge location].

Table 3.3.3.1-1 shall be amended for each plant as necessary to list:

1.

All Regulatory Guide 1.97, Type A instruments and All Regulatory Guide 1.97, Category 1, non-Type A instruments specified in the plant's Regulatory Guide 1.97, 2. Safety Evaluation Report.

3.3.3.2 Remote Shutdown System

LCO 3.3.3.2 The Remote Shutdown System Functions shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

-----NOTES-----

1. LCO 3.0.4 is not applicable.

2. Separate Condition entry is allowed for each Function.

CONDITION	REQUIRED ACTION		COMPLETION TIME
A. One or more required Functions inoperable.	A.1 F	Restore required Function of OPERABLE status.	30 days
B. Required Action and associated Completion Time not met.	B.1 E	3e in MODE 3.	12 hours

SURVEILLANCE REQUIREMENTS

	SURVEILLANCE	FREQUENCY
SR 3.3.3.2.1	[Perform CHANNEL CHECK for each required instrumentation channel that is normally energized.	31 days]
SR 3.3.3.2.2	Verify each required control circuit and transfer switch is capable of performing the intended function.	[18] months
SR 3.3.3.2.3	Perform CHANNEL CALIBRATION for each required instrumentation channel.	[18] months

3.3.4.1 End of Cycle Recirculation Pump Trip (EOC-RPT) Instrumentation

LCO 3.3.4.1 a. Two channels per trip system for each EOC-RPT instrumentation Function listed below shall be OPERABLE:

- 1. Turbine Stop Valve (TSV) Closure and
- 2. Turbine Control Valve (TCV) Fast Closure, Trip Oil Pressure Low.
- [<u>OR</u>
- LCO 3.2.2, "MINIMUM CRITICAL POWER RATIO (MCPR)," limits for inoperable EOC-RPT as specified in the COLR are made applicable.]

APPLICABILITY: THERMAL POWER > [30]% RTP.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or more required channels inoperable.	A.1	Restore channel to OPERABLE status.	72 hours
	<u>OR</u>		
	A.2	NOTENOTE Not applicable if inoperable channel is the result of an inoperable breaker.	
		Place channel in trip.	72 hours

ACTIONS (continued)

CONDITION		REQUIRED ACTION		COMPLETION TIME
В.	One or more Functions with EOC-RPT trip capability not maintained.	B.1 OR	Restore EOC-RPT trip capability.	2 hours
	AND [MCPR limit for inoperable EOC-RPT not made applicable.]	[B.2	Apply the MCPR limit for inoperable EOC-RPT as specified in the COLR.	2 hours]
C.	Required Action and associated Completion Time not met.	C.1	Only applicable if inoperable channel is the result of an inoperable RPT breaker. Remove the affected recirculation pump from service.	4 hours
		<u>OR</u>		
		C.2	Reduce THERMAL POWER to < [30]% RTP.	4 hours

SURVEILLANCE REQUIREMENTS

	SURVEILLANCE	FREQUENCY
SR 3.3.4.1.1	Perform CHANNEL FUNCTIONAL TEST.	[92] days

	SURVEILLANCE	FREQUENCY
SR 3.3.4.1.2	Calibrate the trip units.	[92] days]
SR 3.3.4.1.3	 Perform CHANNEL CALIBRATION. The Allowable Values shall be: a. TSV - Closure: ≤ [10]% closed and b. TCV Fast Closure, Trip Oil Pressure - Low: ≥ [600] psig. 	[18] months
SR 3.3.4.1.4	Perform LOGIC SYSTEM FUNCTIONAL TEST including breaker actuation.	[18] months
SR 3.3.4.1.5	Verify TSV - Closure and TCV Fast Closure, Trip Oil Pressure - Low Functions are not bypassed when THERMAL POWER is \geq [30]% RTP.	[18] months
SR 3.3.4.1.6	NOTE Breaker [interruption] time may be assumed from the most recent performance of SR 3.3.4.1.7. Verify the EOC-RPT SYSTEM RESPONSE TIME is within limits.	[18] months on a STAGGERED TEST BASIS
SR 3.3.4.1.7	Determine RPT breaker [interruption] time.	60 months

- 3.3.4.2 Anticipated Transient Without Scram Recirculation Pump Trip (ATWS-RPT) Instrumentation
- LCO 3.3.4.2 Two channels per trip system for each ATWS-RPT instrumentation Function listed below shall be OPERABLE:
 - a. Reactor Vessel Water Level Low Low, Level 2 and
 - b. Reactor Steam Dome Pressure High.

APPLICABILITY: MODE 1.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or more channels inoperable.	A.1	Restore channel to OPERABLE status.	14 days
	A.2	NOTENOTE Not applicable if inoperable channel is the result of an inoperable breaker.	
		Place channel in trip.	14 days'
B. One Function with ATWS-RPT trip capability not maintained.	B.1	Restore ATWS-RPT trip capability.	72 hours

CONDITION		REQUIRED ACTION	COMPLETION TIME
C. Both Functions with ATWS-RPT trip capability not maintained.	C.1	Restore ATWS-RPT trip capability for one Function.	1 hour
D. Required Action and associated Completion Time not met.	D.1	Only applicable if inoperable channel is the result of an inoperable RPT breaker. Remove the affected recirculation pump from service.	6 hours
	<u>OR</u>		
	D.2	Be in MODE 2.	6 hours

SURVEILLANCE REQUIREMENTS

When a channel is placed in an inoperable status solely for performance of required Surveillances, entry into associated Conditions and Required Actions may be delayed for up to 6 hours provided the associated Function maintains ATWS-RPT trip capability.

	SURVEILLANCE	FREQUENCY
SR 3.3.4.2.1	Perform CHANNEL CHECK.	12 hours]
SR 3.3.4.2.2	Perform CHANNEL FUNCTIONAL TEST.	[92] days
SR 3.3.4.2.3	Calibrate the trip units.	[92] days]

	FREQUENCY	
SR 3.3.4.2.4	 Perform CHANNEL CALIBRATION. The Allowable Values shall be: a. Reactor Vessel Water Level - Low Low, Level 2: ≥ [-47] inches and b. Reactor Steam Dome Pressure - High: 	[18] months
	≤ [1095] psig.	
SR 3.3.4.2.5	Perform LOGIC SYSTEM FUNCTIONAL TEST including breaker actuation.	[18] months

- 3.3.5.1 Emergency Core Cooling System (ECCS) Instrumentation
- LCO 3.3.5.1 The ECCS instrumentation for each Function in Table 3.3.5.1-1 shall be OPERABLE.

APPLICABILITY: According to Table 3.3.5.1-1.

ACTIONS

-----NOTE-----

Separate Condition entry is allowed for each channel.

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or more channels inoperable.	A.1	Enter the Condition referenced in Table 3.3.5.1-1 for the channel.	Immediately
B. As required by Required Action A.1 and referenced in Table 3.3.5.1-1.	В.1 <u>AND</u>	 NOTES 1. Only applicable in MODES 1, 2, and 3. 2. Only applicable for Functions 1.a, 1.b, 2.a, and 2.b. Declare supported feature(s) inoperable when its redundant feature ECCS initiation capability is inoperable. 	1 hour from discovery of loss of initiation capability for feature(s) in both divisions

CONDITION		REQUIRED ACTION	COMPLETION TIME
	B.2	NOTE Only applicable for Functions 3.a and 3.b.	
		Declare High Pressure Coolant Injection (HPCI) System inoperable.	1 hour from discovery of loss of HPCI initiation capability
	<u>AND</u>		
	B.3	Place channel in trip.	24 hours
C. As required by Required Action A.1 and referenced in Table 3.3.5.1-1.	C.1	 NOTES 1. Only applicable in MODES 1, 2, and 3. 2. Only applicable for Functions 1.c, 2.c, 2.d, and 2.f. Declare supported feature(s) inoperable when its redundant feature ECCS initiation capability is inoperable. 	1 hour from discovery of loss of initiation capability for feature(s) in both divisions
	AND		
	C.2	Restore channel to OPERABLE status.	24 hours

ACTIONS (continued)

CONDITION		REQUIRED ACTION	COMPLETION TIME
D. As required by Required Action A.1 and referenced in Table 3.3.5.1-1.	D.1	NOTE Only applicable if HPCI pump suction is not aligned to the suppression pool.	
		Declare HPCI System inoperable.	1 hour from discovery of loss of HPCI initiation capability
	<u>AND</u>		
	D.2.1	Place channel in trip.	24 hours
	OF	<u>R</u>	
	D.2.2	Align the HPCI pump suction to the suppression pool.	24 hours
E. As required by Required Action A.1 and referenced in Table 3.3.5.1-1.	E.1	 NOTES 1. Only applicable in MODES 1, 2, and 3. 2. Only applicable for Functions 1.d and 2.g. Declare supported feature(s) inoperable when its redundant feature ECCS initiation capability is inoperable. 	1 hour from discovery of loss of initiation capability for subsystems in both divisions
	<u>AND</u>		
	E.2	Restore channel to OPERABLE status.	7 days

CONDITION		REQUIRED ACTION	COMPLETION TIME
F. As required by Required Action A.1 and referenced in Table 3.3.5.1-1.	F.1	Declare Automatic Depressurization System (ADS) valves inoperable.	1 hour from discovery of loss of ADS initiation capability in both trip systems
	<u>AND</u>		
	F.2	Place channel in trip.	96 hours from discovery of inoperable channel concurrent with HPCI or reactor core isolation cooling (RCIC) inoperable
			AND
			8 days
G. As required by Required Action A.1 and referenced in Table 3.3.5.1-1.	G.1	NOTE Only applicable for Functions 4.c, 4.e, 4.f, 4.g, 5.c, 5.e, 5.f, and 5.g.	
		Declare ADS valves inoperable.	1 hour from discovery of loss of ADS initiation capability in both trip systems
	<u>AND</u>		
	G.2	Restore channel to OPERABLE status.	96 hours from discovery of inoperable channel concurrent with HPCI or RCIC inoperable
			AND
			8 days

CONDITION	REQUIRED ACTION	COMPLETION TIME
 H. Required Action and associated Completion Time of Condition B, C, D, E, F, or G not met. 	H.1 Declare associated supported feature(s) inoperable.	Immediately

SURVEILLANCE REQUIREMENTS

- 2. When a channel is placed in an inoperable status solely for performance of required Surveillances, entry into associated Conditions and Required Actions may be delayed as follows: (a) for up to 6 hours for Functions 3.c, 3.f, and 3.g; and (b) for up to 6 hours for Functions other than 3.c, 3.f, and 3.g provided the associated Function or the redundant Function maintains ECCS initiation capability.

	SURVEILLANCE	FREQUENCY
SR 3.3.5.1.1	Perform CHANNEL CHECK.	12 hours
SR 3.3.5.1.2	Perform CHANNEL FUNCTIONAL TEST.	[92] days
SR 3.3.5.1.3	Calibrate the trip unit.	[92] days]
SR 3.3.5.1.4	[Perform CHANNEL CALIBRATION.	92 days]
SR 3.3.5.1.5	Perform CHANNEL CALIBRATION.	[18] months
SR 3.3.5.1.6	Perform LOGIC SYSTEM FUNCTIONAL TEST.	[18] months
SR 3.3.5.1.7	Verify the ECCS RESPONSE TIME is within limits.	[18] months on a STAGGERED TEST BASIS
Table 3.3.5.1-1 (page 1 of 6) Emergency Core Cooling System Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER FUNCTION	CONDITIONS REFERENCED FROM REQUIRED ACTION A.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
1.	Cor	e Spray System					
	a.	Reactor Vessel Water Level - Low Low Low, Level 1	1, 2, 3, 4 ^(a) , 5 ^(a)	[4] ^(b)	В	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6 SR 3.3.5.1.7	≥ [-113] inches
	b.	Drywell Pressure - High	1, 2, 3	[4] ^(b)	В	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6 SR 3.3.5.1.7	≤ [1.92] psig
	C.	Reactor Steam Dome Pressure - Low (Injection Permissive)	1, 2, 3	[4]	С	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6 SR 3.3.5.1.7	≥ [390] psig and ≤ [500] psig
			4 ^(a) , 5 ^(a)	[4]	В	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6 SR 3.3.5.1.7	≥ [390] psig and ≤ [500] psig
	[d.	Core Spray Pump Discharge Flow - Low (Bypass)	1, 2, 3, 4 ^(a) , 5 ^(a)	[2] - [1 per pump]	E	SR 3.3.5.1.1 SR 3.3.5.1.2 SR 3.3.5.1.5 SR 3.3.5.1.6	≥ [] gpm and ≤ [] gpm]
	[e.	Manual Initiation	1, 2, 3, 4 ^(a) , 5 ^(a)	[2] - [1 per subsystem]	С	SR 3.3.5.1.6	NA]

(a) When associated ECCS subsystem(s) are required to be OPERABLE per LCO 3.5.2, "ECCS - Shutdown."

(b) Also required to initiate the associated [diesel generator (DG) and isolate the associated plant service water (PSW) turbine building (T/B) isolation valves].

Table 3.3.5.1-1 (page 2 of 6) Emergency Core Cooling System Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER FUNCTION	CONDITIONS REFERENCED FROM REQUIRED ACTION A.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
2.	Lov Inje	v Pressure Coolant ection (LPCI) System					
	a.	Reactor Vessel Water Level - Low Low Low, Level 1	1, 2, 3, 4 ^(a) , 5 ^(a)	[4] ^(b)	В	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6 SR 3.3.5.1.7	≥ [-113] inches
	b.	Drywell Pressure - High	1, 2, 3	[4] ^(b)	В	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6 SR 3.3.5.1.7	≤ [1.92] psig
	C.	Reactor Steam Dome Pressure - Low (Injection Permissive)	1, 2, 3	[4]	С	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6 SR 3.3.5.1.7	≥ [390] psig and ≤ [500] psig
			4 ^(a) , 5 ^(a)	[4]	В	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6 SR 3.3.5.1.7	≥ [390] psig and ≤ [500] psig
	d.	Reactor Steam Dome Pressure - Low (Recirculation Discharge Valve Permissive)	1 ^(c) ,2 ^(c) ,3 ^(c)	[4]	С	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6	≥ [335] psig
	e.	Reactor Vessel Shroud Level - Level 0	1, 2, 3	[2]	В	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6	≥ [-202] inches

(a) When associated ECCS subsystem(s) are required to be OPERABLE per LCO 3.5.2, "ECCS - Shutdown."

(b) Also required to initiate the associated [DG and isolate the associated PSW T/B isolation valves].

(c) With associated recirculation pump discharge valve open.

Table 3.3.5.1-1 (page 3 of 6) Emergency Core Cooling System Instrumentation

	FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER FUNCTION	CONDITIONS REFERENCED FROM REQUIRED ACTION A.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
LPO	CI System					
[f.	Low Pressure Coolant Injection Pump Start - Time Delay Relay	1, 2, 3, 4 ^(a) , 5 ^(a)	[4] - [1 per pump]	С	SR 3.3.5.1.5 SR 3.3.5.1.6	
	Pumps A,B,D					≥ 9 seconds and ≤ 11 seconds
	Pump C					\leq 1 second]
[g.	Low Pressure Coolant Injection Pump Discharge Flow - Low Bypass)	1, 2, 3, 4 ^(a) , 5 ^(a)	[4] - [1 per pump]	E	SR 3.3.5.1.1 SR 3.3.5.1.2 SR 3.3.5.1.5 SR 3.3.5.1.6	≥ [] gpm and ≤ [] gpm]
[h.	Manual Initiation	1, 2, 3, 4 ^(a) , 5 ^(a)	[2] - [1 per subsystem]	С	SR 3.3.5.1.6	NA]
Hig Inje	h Pressure Coolant ction (HPCI) System					
a.	Reactor Vessel Water Level - Low Low, Level 2	1, 2 ^(d) , 3 ^(d)	[4]	В	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6 SR 3.3.5.1.7	≥ [-47] inches
b.	Drywell Pressure – High	1, 2 ^(d) , 3 ^(d)	[4]	В	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6 SR 3.3.5.1.7	≤ [1.92] psig
C.	Reactor Vessel Water Level - High, Level 8	1, 2 ^(d) , 3 ^(d)	[2]	С	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6 SR 3.3.5.1.7	≤ [56.5] inches
	LPC [f. [g. [h. Higg Inje a. b.	FUNCTIONLPCI System[f.Low Pressure Coolant Injection Pump Start - Time Delay Relay Pumps A,B,DPump C[g.Low Pressure Coolant Injection Pump Discharge Flow - Low Bypass)[h.Manual InitiationHigh Pressure Coolant Injection (HPCI) Systema.Reactor Vessel Water Level - Low Low, Level 2b.Drywell Pressure - Highc.Reactor Vessel Water Level - High, Level 8	FUNCTIONAPPLICABLE MODES OR OTHER SPECIFIED CONDITIONSLPCI System1, 2, 3, 4(a), 5(a)[f. Low Pressure Coolant Injection Pump Start - Time Delay Relay Pumps A,B,D1, 2, 3, 4(a), 5(a)Pump C[g. Low Pressure Coolant Injection Pump Discharge Flow - Low Bypass)1, 2, 3, 4(a), 5(a)[h. Manual Initiation Injection (HPCI) System1, 2, 3, 4(a), 5(a)a. Reactor Vessel Water Level - Low Low, Level 21, 2(d), 3(d)b. Drywell Pressure - High1, 2(d), 3(d)c. Reactor Vessel Water Level - High, Level 81, 2(d), 3(d)	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONSREQUIRED CHANNELS PER FUNCTIONLPCI System1, 2, 3 (4) - [1 per Coolant Injection Pump Start - Time Delay Relay Pumps A,B,D1, 2, 3 (4) - 5(*)[4] - [1 per pump]Pump C1, 2, 3, (4) - 5(*)[4] - [1 per pump][9. Low Pressure Coolant Injection Pump Discharge Flow - Low Bypass)1, 2, 3, (4) - [1 per pump][4] - [1 per pump][h. Manual Initiation1, 2, 3, (4) , 5(*)[2] - [1 per subsystem]High Pressure Coolant Injection (HPCI) System Low, Level 21, 2(*), 3(*)[4]b. Drywell Pressure - High1, 2(*), 3(*)[4]c. Reactor Vessel Water Level - High, Level 81, 2(*), 3(*)[2]	APPLICABLE MODES OR OTHER CONDITIONSREQUIRED REQUIRED REQUIRED PER FUNCTIONCONDITIONS REFERENCED FROM PER FUNCTIONLPCI System1, 2, 3, 4 ^(a) , 5 ^(a) [4] - [1 per pump]C[f. Low Pressure Coolant Injection Pump Start - Time Delay Relay Pump A,B,D1, 2, 3, 4 ^(a) , 5 ^(a) [4] - [1 per pump]C[g. Low Pressure Coolant Injection Pump Discharge Flow - Low Bypass)1, 2, 3, 4 ^(a) , 5 ^(a) [4] - [1 per pump]E[h. Manual Initiation Injection (HPCI) System Low, Level 21, 2 ^(a) , 3 ^(d) [2] - [1 per subsystem]Ca. Reactor Vessel Water Level - Low Low, Level 21, 2 ^(d) , 3 ^(d) [4]Bb. Drywell Pressure - High1, 2 ^(d) , 3 ^(d) [4]Bc. Reactor Vessel Water Level - High, Level 81, 2 ^(d) , 3 ^(d) [2]C	APPLICABLE OTHER SPECIFIED CONDITIONSREQUIRED REQUIRED PER PER FUNCTIONCONDITIONS REFERENCED FROM REQUIRED ACTION A.1SURVEILLANCE REQUIRED ACTION A.1LPCI System1.2.3 4 ⁽⁰⁾ , 5 ⁽⁰⁾ [4]-[1 per pump]CSR 3.3.5.1.5 SR 3.3.5.1.6LPCI System1.2.3 4 ⁽⁰⁾ , 5 ⁽⁰⁾ [4]-[1 per pump]CSR 3.3.5.1.6 SR 3.3.5.1.6Pump C1.2.3 4 ⁽⁰⁾ , 5 ⁽⁰⁾ [4]-[1 per pump]ESR 3.3.5.1.6 SR 3.3.5.1.6[g. Low Pressure Coolant Injection Pump Discharge Flow - Low Bypass)1.2.3 4 ⁽⁰⁾ , 5 ⁽⁰⁾ [2]-[1 per subsystem]CSR 3.3.5.1.6[h. Manual Initiation Injection (HPCI) System1.2 ⁽⁰⁾ , 3 ^(d) [2]-[1 per subsystem]CSR 3.3.5.1.6High Pressure Coolant Injection (HPCI) System1.2 ^(d) , 3 ^(d) [4]BSR 3.3.5.1.1 SR 3.3.5.1.6b. Drywell Pressure - High1.2 ^(d) , 3 ^(d) [4]BSR 3.3.5.1.1 SR 3.3.5.1.6b. Drywell Pressure - High1.2 ^(d) , 3 ^(d) [4]BSR 3.3.5.1.1 SR 3.3.5.1.6 SR

(a) When associated ECCS subsystem(s) are required to be OPERABLE per LCO 3.5.2, "ECCS - Shutdown."

Table 3.3.5.1-1 (page 4 of 6) Emergency Core Cooling System Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER FUNCTION	CONDITIONS REFERENCED FROM REQUIRED ACTION A.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
3.	HP	CI System					
	d.	Condensate Storage Tank Level - Low	1, 2 ^(d) , 3 ^(d)	[2]	D	[SR 3.3.5.1.1] SR 3.3.5.1.2 [SR 3.3.5.1.4] SR 3.3.5.1.6	\geq [0] inches
	e.	Suppression Pool Water Level - High	1, 2 ^(d) , 3 ^(d)	[2]	D	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6	\leq [154] inches
	[f.	High Pressure Coolant Injection Pump Discharge Flow - Low (Bypass)	1, 2 ^(d) , 3 ^(d)	[1]	E	SR 3.3.5.1.1 SR 3.3.5.1.2 SR 3.3.5.1.5 SR 3.3.5.1.6	≥ [] gpm and ≤ [] gpm]
	[g.	Manual Initiation	1, 2 ^(d) , 3 ^(d)	[1]	С	SR 3.3.5.1.6	NA]
4.	Aut De (AE	tomatic pressurization System DS) Trip System A					
	a.	Reactor Vessel Water Level - Low Low Low, Level 1	1, 2 ^(d) , 3 ^(d)	[2]	F	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6	\geq [-113] inches
	b.	Drywell Pressure - High	1, 2 ^(d) , 3 ^(d)	[2]	F	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6	≤ [1.92] psig
	C.	Automatic Depressurization System Initiation Timer	1, 2 ^(d) , 3 ^(d)	[1]	G	[SR 3.3.5.1.5] SR 3.3.5.1.6	\leq [120] seconds

Table 3.3.5.1-1 (page 5 of 6) Emergency Core Cooling System Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER FUNCTION	CONDITIONS REFERENCED FROM REQUIRED ACTION A.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
4.	AD	S Trip System A					
	d.	Reactor Vessel Water Level - Low, Level 3 (Confirmatory)	1, 2 ^(d) , 3 ^(d)	[1]	F	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6	≥ [10] inches
	e.	Core Spray Pump Discharge Pressure - High	1, 2 ^(d) , 3 ^(d)	[2]	G	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6	≥ [137] psig and ≤ [] psig
	f.	Low Pressure Coolant Injection Pump Discharge Pressure - High	1, 2 ^(d) , 3 ^(d)	[4]	G	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6	≥ [112] psig and ≤ [] psig
	g.	Automatic Depressurization System Low Water Level Actuation Timer	1, 2 ^(d) , 3 ^(d)	[2]	G	[SR 3.3.5.1.5] SR 3.3.5.1.6	≤ [13] minutes
	[h.	Manual Initiation	1, 2 ^(d) , 3 ^(d)	[2]	G	SR 3.3.5.1.6	N/A]
5.	AD	S Trip System B					
	a.	Reactor Vessel Water Level - Low Low Low, Level 1	1, 2 ^(d) , 3 ^(d)	[2]	F	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6	\geq [-113] inches
	b.	Drywell Pressure - High	1, 2 ^(d) , 3 ^(d)	[2]	F	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6	≤ [1.92] psig
	C.	Automatic Depressurization System Initiation Timer	1, 2 ^(d) , 3 ^(d)	[1]	G	[SR 3.3.5.1.5] SR 3.3.5.1.6	\leq [120] seconds

Table 3.3.5.1-1 (page 6 of 6) Emergency Core Cooling System Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER FUNCTION	CONDITIONS REFERENCED FROM REQUIRED ACTION A.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
5.	AD	S Trip System B					
	d.	Reactor Vessel Water Level - Low, Level 3 (Confirmatory)	1, 2 ^(d) , 3 ^(d)	[1]	F	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6	≥ [10] inches
	e.	Core Spray Pump Discharge Pressure - High	1, 2 ^(d) , 3 ^(d)	[2]	G	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6	≥ [137] psig and ≤ [] psig
	f.	Low Pressure Coolant Injection Pump Discharge Pressure - High	1, 2 ^(d) , 3 ^(d)	[4]	G	SR 3.3.5.1.1 SR 3.3.5.1.2 [SR 3.3.5.1.3] SR 3.3.5.1.5 SR 3.3.5.1.6	≥ [112] psig and ≤ [] psig
	g.	Automatic Depressurization System Low Water Level Actuation Timer	1, 2 ^(d) , 3 ^(d)	[2]	G	[SR 3.3.5.1.5] SR 3.3.5.1.6	≥ [13] minutes
	[h.	Manual Initiation	1, 2 ^(d) , 3 ^(d)	[2]	G	SR 3.3.5.1.6	NA]

3.3 INSTRUMENTATION

3.3.5.2	Reactor Core Isolation Cooling (RCIC) System	n Instrumentation
---------	--	-------------------

LCO 3.3.5.2 The RCIC System instrumentation for each Function in Table 3.3.5.2-1 shall be OPERABLE.

APPLICABILITY: MODE 1, MODES 2 and 3 with reactor steam dome pressure > [150] psig.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME	
A. One or more channels inoperable.	A.1	Enter the Condition referenced in Table 3.3.5.2-1 for the channel.	Immediately	
B. As required by Required Action A.1 and referenced in Table 3.3.5.2-1.	equired by Required B.1 Declare RCIC System in A.1 and inoperable. enced in e 3.3.5.2-1. <u>AND</u>		1 hour from discovery of loss of RCIC initiation capability	
	B.2	Place channel in trip.	24 hours	
C. As required by Required Action A.1 and referenced in Table 3.3.5.2-1.	C.1	Restore channel to OPERABLE status.	24 hours	

ACTIONS (continued)

CONDITION		REQUIRED ACTION	COMPLETION TIME
D. As required by Required Action A.1 and referenced in Table 3.3.5.2-1.	D.1NOTE Only applicable if RCIC pump suction is not aligned to the suppression pool.		
		Declare RCIC System inoperable.	1 hour from discovery of loss of RCIC initiation capability
	AND		
	D.2.1	Place channel in trip.	24 hours
	OF	<u>R</u>	
	D.2.2	Align RCIC pump suction to the suppression pool.	24 hours
E. Required Action and associated Completion Time of Condition B, C, or D not met.	E.1	Declare RCIC System inoperable.	Immediately

SURVEILLANCE REQUIREMENTS

- -----NOTES-----
- 1. Refer to Table 3.3.5.2-1 to determine which SRs apply for each RCIC Function.
- When a channel is placed in an inoperable status solely for performance of required Surveillances, entry into associated Conditions and Required Actions may be delayed as follows: (a) for up to 6 hours for Functions 2 and 5; and (b) for up to 6 hours for Functions 1, 3, and 4 provided the associated Function maintains RCIC initiation capability.

	SURVEILLANCE	FREQUENCY
SR 3.3.5.2.1	Perform CHANNEL CHECK.	12 hours

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.3.5.2.2	Perform CHANNEL FUNCTIONAL TEST.	[92] days
SR 3.3.5.2.3	Calibrate the trip units.	[92] days]
SR 3.3.5.2.4	[Perform CHANNEL CALIBRATION.	92 days]
SR 3.3.5.2.5	Perform CHANNEL CALIBRATION.	[18] months
SR 3.3.5.2.6	Perform LOGIC SYSTEM FUNCTIONAL TEST.	[18] months

	FUNCTION	REQUIRED CHANNELS PER FUNCTION	CONDITIONS REFERENCED FROM REQUIRED ACTION A.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
1.	Reactor Vessel Water Level - Low Low, Level 2	[4]	В	SR 3.3.5.2.1 SR 3.3.5.2.2 [SR 3.3.5.2.3] SR 3.3.5.2.5 SR 3.3.5.2.6	≥ [-47] inches
2.	Reactor Vessel Water Level - High, Level 8	[2]	С	SR 3.3.5.2.1 SR 3.3.5.2.2 [SR 3.3.5.2.3] SR 3.3.5.2.5 SR 3.3.5.2.6	\leq [56.5] inches
3.	Condensate Storage Tank Level - Low	[2]	D	[SR 3.3.5.2.1] SR 3.3.5.2.2 [SR 3.3.5.2.3] [SR 3.3.5.2.4] SR 3.3.5.2.6	≥ [0] inches
[4.	Suppression Pool Water Level - High	[2]	D	[SR 3.3.5.2.1] SR 3.3.5.2.2 [SR 3.3.5.2.3] SR 3.3.5.2.5 SR 3.3.5.2.6	≤ [151] inches]
[5.	Manual Initiation	[1]	С	SR 3.3.5.2.6	NA]

Table 3.3.5.2-1 (page 1 of 1) Reactor Core Isolation Cooling System Instrumentation

3.3 INSTRUMENTATION

3.3.6.1	Primary	Containment	Isolation	Instrumentation
---------	---------	-------------	-----------	-----------------

LCO 3.3.6.1 The primary containment isolation instrumentation for each Function in Table 3.3.6.1-1 shall be OPERABLE.

APPLICABILITY: According to Table 3.3.6.1-1.

ACTIONS

-----NOTES-----

1. Penetration flow paths may be unisolated intermittently under administrative controls.

2. Separate Condition entry is allowed for each channel.

CONDITION		REQUIRED ACTION	COMPLETION TIME	
A. One or more required channels inoperable.	. One or more required A.1 Place channel in trip. channels inoperable.		12 hours for Functions 2.a, 2.b, 6.b, 7.a, and 7.b	
			AND	
			24 hours for Functions other than Functions 2.a, 2.b, 6.b, 7.a, and 7.b	
B. One or more automatic Functions with isolation capability not maintained.	B.1	Restore isolation capability.	1 hour	
C. Required Action and associated Completion Time of Condition A or B not met.	C.1	Enter the Condition referenced in Table 3.3.6.1-1 for the channel.	Immediately	

ACTIONS (continued)

CONDITION		REQUIRED ACTION	COMPLETION TIME
D. As required by Required Action C.1 and referenced in	D.1	Isolate associated main steam line (MSL).	12 hours
Table 3.3.6.1-1.	<u>OR</u>		
	D.2.1	Be in MODE 3.	12 hours
	<u>AN</u>	<u>ID</u>	
	D.2.2	Be in MODE 4.	36 hours
E. As required by Required Action C.1 and referenced in Table 3.3.6.1-1.	E.1	Be in MODE 2.	6 hours
F. As required by Required Action C.1 and referenced in Table 3.3.6.1-1.	F.1	Isolate the affected penetration flow path(s).	1 hour
G. As required by Required Action C.1 and referenced in Table 3.3.6.1-1.	G.1	Isolate the affected penetration flow path(s).	24 hours
H. As required by Required Action C.1 and referenced in Table 3.3.6.1-1.	H.1 <u>AND</u>	Be in MODE 3.	12 hours
<u>OR</u>	H.2	Be in MODE 4.	36 hours
Required Action and associated Completion Time for Condition F or G not met.			

ACTIONS	(continued)
---------	-------------

	CONDITION		REQUIRED ACTION	COMPLETION TIME
Ι.	As required by Required Action C.1 and referenced in Table 3.3.6.1-1.	I.1 <u>OR</u>	Declare associated standby liquid control subsystem (SLC) inoperable.	1 hour
		1.2	Isolate the Reactor Water Cleanup System.	1 hour
J.	As required by Required Action C.1 and referenced in Table 3.3.6.1-1.	J.1 <u>OR</u>	Initiate action to restore channel to OPERABLE status.	Immediately
		J.2	Initiate action to isolate the Residual Heat Removal (RHR) Shutdown Cooling System.	Immediately

SURVEILLANCE REQUIREMENTS

	NOTES
	NOTEO
1.	Refer to Table 3.3.6.1-1 to determine which SRs apply for each Primary Containment Isolation Function.

2. When a channel is placed in an inoperable status solely for performance of required Surveillances, entry into associated Conditions and Required Actions may be delayed for up to 6 hours provided the associated Function maintains isolation capability.

	SURVEILLANCE	FREQUENCY
SR 3.3.6.1.1	Perform CHANNEL CHECK.	12 hours
SR 3.3.6.1.2	Perform CHANNEL FUNCTIONAL TEST.	[92] days

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.3.6.1.3	Calibrate the trip unit.	[92] days]
SR 3.3.6.1.4	Perform CHANNEL CALIBRATION.	92 days
SR 3.3.6.1.5	Perform CHANNEL FUNCTIONAL TEST.	[184] days]
SR 3.3.6.1.6	Perform CHANNEL CALIBRATION.	[18] months
SR 3.3.6.1.7	Perform LOGIC SYSTEM FUNCTIONAL TEST.	[18] months
This SR is applied response times n	d only to Functions of Table 3.3.6.1-1 with required of corresponding to DG start time.	
SR 3.3.6.1.8	NOTENOTENOTE[Radiation detectors may be excluded.]	
	Verify the ISOLATION SYSTEM RESPONSE TIME is within limits.	[18] months on a STAGGERED TEST BASIS

Table 3.3.6.1-1 (page 1 of 7) Primary Containment Isolation Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION C.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
1.	Mai Isol	n Steam Line ation					
	a.	Reactor Vessel Water Level - Low Low Low, Level 1	1, 2, 3	[2]	D	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7 SR 3.3.6.1.8	≥ [-113] inches
	b.	Main Steam Line Pressure - Low	1	[2]	E	[SR 3.3.6.1.1] [SR 3.3.6.1.2] SR 3.3.6.1.4 SR 3.3.6.1.7 SR 3.3.6.1.8	≥ [825] psig
	C.	Main Steam Line Flow - High	1, 2, 3	[2] per MSL	D	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7 SR 3.3.6.1.8	≤ [138]% rated steam flow
	d.	Condenser Vacuum - Low	1, 2 ^(a) , 3 ^(a)	[2]	D	SR 3.3.6.1.1 SR 3.3.6.1.2 SR 3.3.6.1.4 SR 3.3.6.1.7	≥ [7] inches Hg vacuum
	e.	Main Steam Tunnel Temperature - High	1, 2, 3	[8]	D	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7 SR 3.3.6.1.8	≤ [194] °F
	[f.	Main Steam Tunnel Differential Temperature - High	1,2,3	[2]	D	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≤[]°F]
	g.	Turbine Building Area Temperature - High	1, 2, 3	[32]	D	[SR 3.3.6.1.1] SR 3.3.6.1.2 SR 3.3.6.1.6 SR 3.3.6.1.7	≤ [200] °F
	[h.	Manual Initiation	1, 2, 3	[1]	G	SR 3.3.6.1.7	NA]

(a) With any turbine [stop valve] not closed.

Table 3.3.6.1-1 (page 2 of 7) Primary Containment Isolation Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION C.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
2.	Prir Isol	nary Containment ation					
	a.	Reactor Vessel Water Level - Low, Level 3	1, 2, 3	[2]	н	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7 SR 3.3.6.1.8	≥ [10] inches
	b.	Drywell Pressure - High	1, 2, 3	[2]	н	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7 SR 3.3.6.1.8	≥ [1.92] psig
	C.	Drywell Radiation - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 SR 3.3.6.1.6 SR 3.3.6.1.7	≤ [138] R/hr
	[d.	Reactor Building Exhaust Radiation - High	1, 2, 3	[2]	Н	SR 3.3.6.1.1 SR 3.3.6.1.2 SR 3.3.6.1.6 SR 3.3.6.1.7 SR 3.3.6.1.8	≤ [60] mR/hr]
	[e.	Refueling Floor Exhaust Radiation - High	1, 2, 3	[2]	Н	SR 3.3.6.1.1 SR 3.3.6.1.2 SR 3.3.6.1.6 SR 3.3.6.1.7 SR 3.3.6.1.8	≤ [20] mR/hr]
	[f.	Manual Initiation	1, 2, 3	[1 per group]	G	SR 3.3.6.1.7	NA]
3.	Hig Inje Isol	h Pressure Coolant ection (HPCI) System ation					
	a.	HPCI Steam Line Flow - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7 SR 3.3.6.1.8	≤ [303]% rated steam flow

Table 3.3.6.1-1 (page 3 of 7) Primary Containment Isolation Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION C.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
3.	HP	CI System Isolation					
	b.	HPCI Steam Supply Line Pressure - Low	1, 2, 3	[2]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7 SR 3.3.6.1.8	≥ [100] psig
	C.	HPCI Turbine Exhaust Diaphragm Pressure - High	1, 2, 3	[2]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≤ [20] psig
	d.	Drywell Pressure - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7 [SR 3.3.6.1.8]	≤ [1.92] psig
	e.	HPCI Pipe Penetration Room Temperature - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≤ [169] °F
	f.	Suppression Pool Area Ambient Temperature - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≤ [169]°F
	g.	Suppression Pool Area Temperature - Time Delay Relays	1, 2, 3	[1]	F	SR 3.3.6.1.5 SR 3.3.6.1.6 SR 3.3.6.1.7	≥ [NA] [minutes]
	h.	Suppression Pool Area Differential Temperature - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≤ [42]°F

Table 3.3.6.1-1 (page 4 of 7) Primary Containment Isolation Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION C.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
3.	HP	CI System Isolation					
	i.	Emergency Area Cooler Temperature - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≤ [169]°F
	[j.	Manual Initiation	1, 2, 3	[1 per group]	G	SR 3.3.6.1.7	NA]
4.	Re Co Iso	actor Core Isolation oling (RCIC) System lation					
	a.	RCIC Steam Line Flow - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7 SR 3.3.6.1.8	≤ [307]% rated steam flow
	b.	RCIC Steam Supply Line Pressure - Low	1, 2, 3	[2]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≤ [60] psig
	C.	RCIC Turbine Exhaust Diaphragm Pressure - High	1, 2, 3	[2]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≤ [20] psig
	d.	Drywell Pressure - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7 [SR 3.3.6.1.8]	≤ [1.92] psig
	e.	RCIC Suppression Pool Ambient Area Temperature - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≤[169]°F

Table 3.3.6.1-1 (page 5 of 7) Primary Containment Isolation Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION C.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
4.	RC	IC System Isolation					
	f.	Suppression Pool Area Temperature - Time Delay Relays	1, 2, 3	[1]	F	SR 3.3.6.1.5 SR 3.3.6.1.6 SR 3.3.6.1.7	≥ [NA] [minutes]
	g.	RCIC Suppression Pool Area Differential Temperature - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≤ [42]°F
	h.	Emergency Area Cooler Temperature - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≤ [169]°F
	[i.	RCIC Equipment Room Temperature - High	1, 2, 3	[1]	F	[SR 3.3.6.1.1] SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.4 SR 3.3.6.1.7	≤[]°F]
	[j.	RCIC Equipment Room Differential Temperature - High	1, 2, 3	[1]	F	[SR 3.3.6.1.1] SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.4 SR 3.3.6.1.7	≤[]°F]
	[k.	Manual Initiation	1, 2, 3	[1 per group]	G	SR 3.3.6.1.7	NA]
5.	Rea (RV Isol	actor Water Cleanup VCU) System ation					
	a.	Differential Flow - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 SR 3.3.6.1.6 SR 3.3.6.1.7 SR 3.3.6.1.8	≤ [79] gpm

Table 3.3.6.1-1 (page 6 of 7) Primary Containment Isolation Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION C.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
5.	RW	/CU System Isolation					
	b.	Area Temperature - High	1, 2, 3	[3] [1 per room]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7 [SR 3.3.6.1.8]	≤ [150]°F
	C.	Area Ventilation Differential Temperature - High	1, 2, 3	[3] [1 per room]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7 [SR 3.3.6.1.8]	≤ [67]°F
	d.	SLC System Initiation	1, 2	[2] ^(b)	I	SR 3.3.6.1.7	NA
	e.	Reactor Vessel Water Level - Low Low, Level 2	1, 2, 3	[2]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7 SR 3.3.6.1.8	≥ [-47] inches
	[f.	Manual Initiation	1, 2, 3	[1 per group]	G	SR 3.3.6.1.7	NA]
6.	Shi Sys	utdown Cooling stem Isolation					
	a.	Reactor Steam Dome Pressure - High	1, 2, 3	[1]	F	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≤ [145] psig
	b.	Reactor Vessel Water Level - Low, Level 3	3, 4, 5	[2] ^(c)	J	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≥ [10] inches

(b) SLC System Initiation only inputs into one of the two trip systems.

(c) Only one trip system required in MODES 4 and 5 with RHR Shutdown Cooling integrity maintained.

Table 3.3.6.1-1 (page 7 of 7) Primary Containment Isolation Instrumentation

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION C.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
7.	Tra Iso	iversing Incore Probe lation					
	a.	Reactor Vessel Water Level - Low, Level 3	1, 2, 3	[2]	G	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≥ [10] inches
	b.	Drywell Pressure - High	1, 2, 3	[2]	G	SR 3.3.6.1.1 SR 3.3.6.1.2 [SR 3.3.6.1.3] SR 3.3.6.1.6 SR 3.3.6.1.7	≤ [1.92] psig

3.3 INSTRUMENTATION

3.3.6.2	Secondary	Containment	Isolation	Instrumentation

LCO 3.3.6.2 The secondary containment isolation instrumentation for each Function in Table 3.3.6.2-1 shall be OPERABLE.

APPLICABILITY: According to Table 3.3.6.2-1.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or more channels inoperable.	A.1	Place channel in trip.	12 hours for Function 2
			AND
			24 hours for Functions other than Function 2
B. One or more automatic Functions with secondary containment isolation capability not maintained.	B.1	Restore secondary containment isolation capability.	1 hour
C. Required Action and associated Completion Time of Condition A or B not met.	C.1.1 <u>OF</u>	Isolate the associated [zone(s)].	1 hour
	C.1.2	Declare associated secondary containment isolation valves inoperable.	1 hour
	<u>AND</u>		

CONDITION	REQUIRED ACTION	COMPLETION TIME
	C.2.1 Place the associated standby gas treatment (SGT) subsystem(s) in operation.	1 hour
	OR	
	C.2.2 Declare associated SGT subsystem(s) inoperable.	1 hour

ACTIONS (continued)

SURVEILLANCE REQUIREMENTS

------NOTES------NOTES------

- 1. Refer to Table 3.3.6.2-1 to determine which SRs apply for each Secondary Containment Isolation Function.
- 2. When a channel is placed in an inoperable status solely for performance of required Surveillances, entry into associated Conditions and Required Actions may be delayed for up to 6 hours provided the associated Function maintains secondary containment isolation capability.

	SURVEILLANCE	FREQUENCY
SR 3.3.6.2.1	Perform CHANNEL CHECK.	12 hours
SR 3.3.6.2.2	Perform CHANNEL FUNCTIONAL TEST.	[92] days
SR 3.3.6.2.3	Calibrate the trip unit.	[92] days]
SR 3.3.6.2.4	Perform CHANNEL CALIBRATION.	92 days]
SR 3.3.6.2.5	Perform CHANNEL CALIBRATION.	[18] months
SR 3.3.6.2.6	Perform LOGIC SYSTEM FUNCTIONAL TEST.	[18] months

SURVEILLANCE REQUIREMENTS (continued)

	FREQUENCY	
This SR is applie response times r		
SR 3.3.6.2.7	NOTENOTENOTENOTE	
	Verify the ISOLATION SYSTEM RESPONSE TIME is within limits.	[18] months on a STAGGERED TEST BASIS

		FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
	1.	Reactor Vessel Water Level - Low Low, Level 2	1, 2, 3, [(a)]	[2]	SR 3.3.6.2.1 SR 3.3.6.2.2 [SR 3.3.6.2.3] SR 3.3.6.2.5 SR 3.3.6.2.6 SR 3.3.6.2.7	\geq [-47] inches
	2.	Drywell Pressure - High	1, 2, 3	[2]	SR 3.3.6.2.1 SR 3.3.6.2.2 [SR 3.3.6.2.3] SR 3.3.6.2.5 SR 3.3.6.2.6 SR 3.3.6.2.7	≤ [1.92] psig
	3.	Reactor Building Exhaust Radiation - High	1, 2, 3, [(a), (b)]	[2]	SR 3.3.6.2.1 SR 3.3.6.2.2 SR 3.3.6.2.5 SR 3.3.6.2.6 SR 3.3.6.2.7	≤ [60] mR/hr
[4.	Refueling Floor Exhaust Radiation - High	1, 2, 3, [(a), (b)]	[2]	SR 3.3.6.2.1 SR 3.3.6.2.2 [SR 3.3.6.2.4] SR 3.3.6.2.6 SR 3.3.6.2.7	≤ [20] mR/hr]
[5.	Manual Initiation	1, 2, 3, [(a), (b)]	[1 per group]	SR 3.3.6.2.6	NA]

Table 3.3.6.2-1 (page 1 of 1) Secondary Containment Isolation Instrumentation

(a) During operations with a potential for draining the reactor vessel.

(b) During movement of [recently] irradiated fuel assemblies in [secondary] containment.

3.3 INSTRUMENTATION

- 3.3.6.3 Low-Low Set (LLS) Instrumentation
- LCO 3.3.6.3 The LLS valve instrumentation for each Function in Table 3.3.6.3-1 shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One LLS valve inoperable due to inoperable channel(s).	A.1	Restore channel(s) to OPERABLE status.	24 hours
 B. One or more safety/relief valves (S/RVs) with one Function 3 channel inoperable. 	B.1	NOTE LCO 3.0.4 is not applicable. Restore tailpipe pressure switches to OPERABLE status.	Prior to entering MODE 2 or 3 from MODE 4
CNOTE Separate Condition entry is allowed for each S/RV. One or more S/RVs with two Function 3 channels inoperable.	C.1	Restore one tailpipe pressure switch to OPERABLE status.	[14] days

ACTIONS (continued)

CONDITION		REQUIRED ACTION	COMPLETION TIME
D. Required Action and associated Completion Time of Condition A, B, or C not met.	D.1	Declare the associated LLS valve(s) inoperable.	Immediately
<u>OR</u>			
Two or more LLS valves inoperable due to inoperable channels.			

SURVEILLANCE REQUIREMENTS

1.	Refer to Table 3.3.6.3-1 to determine which SRs apply for each Function.
----	--

 When a channel is placed in an inoperable status solely for performance of required Surveillances, entry into associated Conditions and Required Actions may be delayed for up to 6 hours provided the associated Function maintains LLS initiation capability.

	SURVEILLANCE	FREQUENCY
SR 3.3.6.3.1	Perform CHANNEL CHECK.	12 hours
SR 3.3.6.3.2	Perform CHANNEL FUNCTIONAL TEST for portion of the channel outside primary containment.	[92] days
SR 3.3.6.3.3	NOTE Only required to be performed prior to entering MODE 2 during each scheduled outage > 72 hours when entry is made into primary containment. 	[92] days

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.3.6.3.4	Perform CHANNEL FUNCTIONAL TEST.	[92] days
SR 3.3.6.3.5	Calibrate the trip unit.	[92] days]
SR 3.3.6.3.6	Perform CHANNEL CALIBRATION.	[18] months
SR 3.3.6.3.7	Perform LOGIC SYSTEM FUNCTIONAL TEST.	[18] months

Table 3.3.6.3-1 (page 1 of 1) Low-Low Set Instrumentation

FUNCTION	REQUIRED CHANNELS PER FUNCTION	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
 Reactor Steam Dome Pressure - High 	[1 per LLS valve]	[SR 3.3.6.3.1] SR 3.3.6.3.4 [SR 3.3.6.3.5] SR 3.3.6.3.6 SR 3.3.6.3.7	≤ [1054] psig
2. Low-Low Set Pressure Setpoints	[2 per LLS valve]	[SR 3.3.6.3.1] SR 3.3.6.3.4 [SR 3.3.6.3.5] SR 3.3.6.3.6 SR 3.3.6.3.7	Low: Open \leq [1010] psig Close \leq [860] psig Medium-Low: Open \leq [1025] psig Close \leq [875] psig Medium-High: Open \leq [1040] psig Close \leq [890] psig High: Open \leq [1050] psig Close \leq [900] psig
3. Tailpipe Pressure Switch	[22] [2 per S/RV]	[SR 3.3.6.3.1] SR 3.3.6.3.2 [SR 3.3.6.3.3] SR 3.3.6.3.6 [SR 3.3.6.3.7]	≥ [80] psig and ≤ [100] psig

3.3 INSTRUMENTATION

3.3.7.1	[Main Control Room E	Environmental Control	(MCREC)] System	Instrumentation
---------	----------------------	------------------------------	-----------------	-----------------

LCO 3.3.7.1 The [MCREC] System instrumentation for each Function in Table 3.3.7.1-1 shall be OPERABLE.

APPLICABILITY: According to Table 3.3.7.1-1.

ACTIONS

-----NOTE-----NOTE------

Separate Condition entry is allowed for each channel.

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or more required channels inoperable.	A.1	Enter the Condition referenced in Table 3.3.7.1-1 for the channel.	Immediately
 B. [As required by Required Action A.1 and referenced in Table 3.3.7.1-1. 	B.1	Declare associated [MCREC] subsystem inoperable.	1 hour from discovery of loss of [MCREC] initiation capability in both trip systems
	<u>AND</u>		
	B.2	Place channel in trip.	24 hours]
C. As required by Required Action A.1 and referenced in Table 3.3.7.1-1.	C.1 <u>AND</u>	Declare associated [MCREC] subsystem inoperable.	1 hour from discovery of loss of [MCREC] initiation capability in both trip systems
	C.2	Place channel in trip.	6 hours

ACTIONS (continued)

CONDITION	REQUIRED ACTION		COMPLETION TIME
D. Required Action and associated Completion Time of Condition B or C not met.	D.1	[Place in toxic gas protection mode if automatic transfer to toxic gas protection mode is inoperable.] Place the associated [MCREC] subsystem(s) in the [pressurization] mode of operation.	1 hour
	<u> 0R</u>		
	D.2	NOTE Only applicable to Function 3 channels.	
		Isolate associated main steam line (MSL).	1 hour
	<u>OR</u>		
	D.3	Declare associated [MCREC] subsystem inoperable.	1 hour

SURVEILLANCE REQUIREMENTS

- 2. When a channel is placed in an inoperable status solely for performance of required Surveillances, entry into associated Conditions and Required Actions may be delayed for up to 6 hours provided the associated Function maintains [MCREC] initiation capability.

	SURVEILLANCE	FREQUENCY
SR 3.3.7.1.1	Perform CHANNEL CHECK.	12 hours
SR 3.3.7.1.2	Perform CHANNEL FUNCTIONAL TEST.	[92] days
SR 3.3.7.1.3	[Calibrate the trip units.	[92] days]
SR 3.3.7.1.4	Perform CHANNEL CALIBRATION.	[18] months
SR 3.3.7.1.5	Perform LOGIC SYSTEM FUNCTIONAL TEST.	[18] months

-						
	FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION A.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
[1.	Reactor Vessel Water Level - Low Low Low, Level 1	1, 2, 3, [a]	[2]	В	SR 3.3.7.1.1 SR 3.3.7.1.2 [SR 3.3.7.1.3] SR 3.3.7.1.4 SR 3.3.7.1.5	≥ [-113] inches]
[2.	Drywell Pressure - High	1, 2, 3	[2]	В	SR 3.3.7.1.1 SR 3.3.7.1.2 [SR 3.3.7.1.3] SR 3.3.7.1.4 SR 3.3.7.1.5	≤ [1.92] psig]
[3.	Main Steam Line Flow - High	1, 2, 3	[2 per MSL]	В	SR 3.3.7.1.1 SR 3.3.7.1.2 [SR 3.3.7.1.3] SR 3.3.7.1.4 SR 3.3.7.1.5	[138]% rated steam flow]
[4.	Refueling Floor Area Radiation - High	1, 2, 3, [(a), (b)]	[1]	С	SR 3.3.7.1.1 SR 3.3.7.1.2 SR 3.3.7.1.4 SR 3.3.7.1.5	≤ [20] mR/hr]
5.	Control Room Air Inlet Radiation - High	1, 2, 3, (a), (b)	[1]	С	SR 3.3.7.1.1 SR 3.3.7.1.2 SR 3.3.7.1.4 SR 3.3.7.1.5	≤ [1] mR/hr

Table 3.3.7.1-1 (page 1 of 1) [Main Control Room Environmental Control] System Instrumentation

(a) During operations with a potential for draining the reactor vessel.

(b) During movement of [recently] irradiated fuel assemblies in the [secondary] containment.

3.3 INSTRUMENTATION

- 3.3.8.1 Loss of Power (LOP) Instrumentation
- LCO 3.3.8.1 The LOP instrumentation for each Function in Table 3.3.8.1-1 shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3, When the associated diesel generator is required to be OPERABLE by LCO 3.8.2, "AC Sources - Shutdown."

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or more channels inoperable.	A.1	Place channel in trip.	1 hour
 B. Required Action and associated Completion Time not met. 	B.1	Declare associated diesel generator (DG) inoperable.	Immediately

SURVEILLANCE REQUIREMENTS

- Refer to Table 3.3.8.1-1 to determine which SRs apply for each LOP Function.
- 2. When a channel is placed in an inoperable status solely for performance of required Surveillances, entry into associated Conditions and Required Actions may be delayed for up to 2 hours provided the associated Function maintains DG initiation capability.

 SURVEILLANCE
 FREQUENCY

 SR 3.3.8.1.1
 [Perform CHANNEL CHECK.
 12 hours]

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.3.8.1.2	Perform CHANNEL FUNCTIONAL TEST.	31 days
SR 3.3.8.1.3	Perform CHANNEL CALIBRATION.	[18] months
SR 3.3.8.1.4	Perform LOGIC SYSTEM FUNCTIONAL TEST.	[18] months

Table 3.3.8.1-1 (page 1 of 1) Loss of Power Instrumentation

	FUNCTION	REQUIRED CHANNELS PER BUS	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
1.	4.16 kV Emergency Bus Undervoltage (Loss of Voltage)			
	a. Bus Undervoltage	[2]	[SR 3.3.8.1.1] SR 3.3.8.1.2 SR 3.3.8.1.3 SR 3.3.8.1.4	\geq [2800] V and \leq [$$] V
	b. Time Delay	[2]	[SR 3.3.8.1.2] SR 3.3.8.1.3 SR 3.3.8.1.4	\geq [] seconds and \leq [6.5] seconds
2.	4.16 kV Emergency Bus Undervoltage (Degraded Voltage)			
	a. Bus Undervoltage	[2]	[SR 3.3.8.1.1] SR 3.3.8.1.2 SR 3.3.8.1.3 SR 3.3.8.1.4	\geq [3280] V and \leq [$$] V
	b. Time Delay	[2]	[SR 3.3.8.1.2] SR 3.3.8.1.3 SR 3.3.8.1.4	≥ [] seconds and ≤ [21.5] seconds
3.3 INSTRUMENTATION

- 3.3.8.2 Reactor Protection System (RPS) Electric Power Monitoring
- LCO 3.3.8.2 Two RPS electric power monitoring assemblies shall be OPERABLE for each inservice RPS motor generator set or alternate power supply.
- APPLICABILITY: MODES 1, 2, and 3, MODES 4 and 5 [with any control rod withdrawn from a core cell containing one or more fuel assemblies].

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or both inservice power supplies with one electric power monitoring assembly inoperable.	A.1 Remove associated inservice power supply(s) from service.	72 hours
B. One or both inservice power supplies with both electric power monitoring assemblies inoperable.	B.1 Remove associated inservice power supply(s) from service.	1 hour
C. Required Action and associated Completion Time of Condition A or B not met in MODE 1, 2, or 3.	C.1 Be in MODE 3. AND C.2 Be in MODE 4.	12 hours 36 hours
D. Required Action and associated Completion Time of Condition A or B not met in MODE 4 or 5 [with any control rod withdrawn from a core cell containing one or more fuel assemblies].	 D.1 Initiate action to fully insert all insertable control rods in core cells containing one or more fuel assemblies. <u>AND</u> 	Immediately

ACTIONS (continued)

CONDITION	REQUIRED ACTION		COMPLETION TIME
	D.2.1	[Initiate action to restore one electric power monitoring assembly to OPERABLE status for inservice power supply(s) supplying required instrumentation.	Immediately]
	OF	2	
	D.2.2	[Initiate action to isolate the Residual Heat Removal Shutdown Cooling System.	Immediately]

	FREQUENCY	
SR 3.3.8.2.1	NOTE Only required to be performed prior to entering MODE 2 or 3 from MODE 4, when in MODE 4 for \geq 24 hours.	
	Perform CHANNEL FUNCTIONAL TEST.	184 days
SR 3.3.8.2.2	Perform CHANNEL CALIBRATION. The Allowable Values shall be:	[18] months
	a. Overvoltage \leq [132] V.	
	 b. Undervoltage ≥ [108] V, with time delay set to [zero]. 	
	 C. Underfrequency ≥ [57] Hz, with time delay set to [zero]. 	
SR 3.3.8.2.3	Perform a system functional test.	[18] months

3.4.1 Recirculation Loops Operating

LCO 3.4.1 Two recirculation loops with matched flows shall be in operation,

[One recirculation loop may be in operation provided the following limits are applied when the associated LCO is applicable:

- a. LCO 3.2.1, "AVERAGE PLANAR LINEAR HEAT GENERATION RATE (APLHGR)," single loop operation limits [specified in the COLR],
- b. LCO 3.2.2, "MINIMUM CRITICAL POWER RATIO (MCPR)," single loop operation limits [specified in the COLR], and
- LCO 3.3.1.1, "Reactor Protection System (RPS) Instrumentation," Function 2.b (Average Power Range Monitors Flow Biased Simulated Thermal Power - High), Allowable Value of Table 3.3.1.1-1 is reset for single loop operation.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. Requirements of the LCO not met.*	A.1	Satisfy the requirements of the LCO.	24 hours
 B. Required Action and associated Completion Time of Condition A not met. 	B.1	Be in MODE 3.	12 hours
OR			
No recirculation loops in operation.			

*Pending resolution of the stability issue.

	FREQUENCY	
SR 3.4.1.1	NOTENOTE Not required to be performed until 24 hours after both recirculation loops are in operation.	
	Verify recirculation loop jet pump flow mismatch with both recirculation loops in operation is:	24 hours
	a. \leq [10]% of rated core flow when operating at < [70]% of rated core flow and	
	 b. ≤ [5]% of rated core flow when operating at ≥ [70]% of rated core flow. 	

3.4.2 Jet Pumps

LCO 3.4.2 All jet pumps shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more jet pumps inoperable.	A.1 Be in MODE 3.	12 hours

	SURVEILLANCE	FREQUENCY		
SR 3.4.2.1	 Not required to be performed until 4 hours after associated recirculation loop is in operation. Not required to be performed until 24 hours after > 25% RTP. 			
	Verify at least one of the following criteria (a, b, or c) is satisfied for each operating recirculation loop:			
	a. Recirculation pump flow to speed ratio differs by $\leq 5\%$ from established patterns, and jet pump loop flow to recirculation pump speed ratio differs by $\leq 5\%$ from established patterns.			
	 Each jet pump diffuser to lower plenum differential pressure differs by ≤ 20% from established patterns. 			
	 Each jet pump flow differs by ≤ 10% from established patterns. 			

-----REVIEWER'S NOTE------An acceptable option to these criteria for jet pump OPERABILITY can be found in the BWR/6 STS, NUREG-1434.

- 3.4.3 Safety/Relief Valves (S/RVs)
- LCO 3.4.3 The safety function of [11] S/RVs shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. [One [or two] [required] S/RV[s] inoperable.	A.1	Restore the [required] S/RV[s] to OPERABLE status.	14 days]
B. [Required Action and associated Completion Time of Condition A not met.]	B.1 <u>AND</u>	Be in MODE 3.	12 hours
<u>OR</u>	B.2	Be in MODE 4.	36 hours
[Three] or more [required] S/RVs inoperable.			

	FREQUENCY	
SR 3.4.3.1	NOTENOTE ≤ [2] [required] S/RVs may be changed to a lower setpoint group.	
	Verify the safety function lift setpoints of the [required] S/RVs are as follows: Number of Setpoint	[In accordance with the Inservice Testing Program or [18] months]
	$\begin{array}{c c} \underline{S/RVS} & \underline{(psig)} \\ \hline [4] & [1090 \pm 32.7] \\ \hline [4] & [1100 \pm 33.0] \\ \hline [3] & [1110 \pm 33.3] \end{array}$	
	Following testing, lift settings shall be within \pm 1%.	
SR 3.4.3.2	NOTENOTE Not required to be performed until 12 hours after reactor steam pressure and flow are adequate to perform the test.	
	Verify each [required] S/RV opens when manually actuated.	[18] months [on a STAGGERED TEST BASIS for each valve solenoid]

3.4.4 RCS Operational LEAKAGE

- LCO 3.4.4 RCS operational LEAKAGE shall be limited to:
 - a. No pressure boundary LEAKAGE,
 - b. \leq 5 gpm unidentified LEAKAGE, [and]
 - c. \leq [30] gpm total LEAKAGE averaged over the previous 24 hour period, [and
 - [d. \leq 2 gpm increase in unidentified LEAKAGE within the previous [4] hour period in MODE 1.]

APPLICABILITY: MODES 1, 2, and 3.

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. Unidentified LEAKAGE not within limit.	A.1	Reduce LEAKAGE to within limits.	4 hours
OR			
Total LEAKAGE not within limit.			
B. Unidentified LEAKAGE increase not within limit.	B.1	Reduce LEAKAGE to within limits.	4 hours
	<u>OR</u>		
	B.2	Verify source of unidentified LEAKAGE increase is not service sensitive type 304 or type 316 austenitic stainless steel.	4 hours

ACTIONS (continued)

CONDITION		REQUIRED ACTION	COMPLETION TIME
C. Required Action and associated Completion Time of Condition A or B not met. OR	C.1 <u>AND</u> C.2	Be in MODE 3. Be in MODE 4.	12 hours 36 hours
Pressure boundary LEAKAGE exists.			

	SURVEILLANCE	FREQUENCY
SR 3.4.4.1	Verify RCS unidentified and total LEAKAGE and unidentified LEAKAGE increase are within limits.	8 hours

- 3.4.5 RCS Pressure Isolation Valve (PIV) Leakage
- LCO 3.4.5 The leakage from each RCS PIV shall be within limit.

APPLICABILITY: MODES 1 and 2, MODE 3, except valves in the residual heat removal (RHR) shutdown cooling flow path when in, or during the transition to or from, the shutdown cooling mode of operation.

ACTIONS

2. Enter applicable Conditions and Required Actions for systems made inoperable by PIVs.

	•	2		

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more flow paths with leakage from one or more RCS PIVs not within limit.	 NOTE Each valve used to satisfy Required Action A.1 and Required Action A.2 must have been verified to meet SR 3.4.5.1 and be in the reactor coolant pressure boundary [or the high pressure portion of the system]. A.1 Isolate the high pressure portion of the affected system from the low pressure portion by use of one closed manual, de- activated automatic, or check valve. 	4 hours

ACTIONS (continued)

CONDITION	REQUIRED ACTION		COMPLETION TIME
	A.2	Isolate the high pressure portion of the affected system from the low pressure portion by use of a second closed manual, de- activated automatic, or check valve.	72 hours
 B. Required Action and associated Completion Time not met. 	B.1 <u>AND</u>	Be in MODE 3.	12 hours
	B.2	Be in MODE 4.	36 hours

	SURVEILLANCE	FREQUENCY
SR 3.4.5.1	Not required to be performed in MODE 3. Verify equivalent leakage of each RCS PIV is ≤ 0.5 gpm per nominal inch of valve size up to a maximum of 5 gpm, at an RCS pressure \geq [] and \leq [] psig.	[In accordance with the Inservice Testing Program or [18] months]

3.4.6 RCS Leakage Detection Instrumentation

LCO 3.4.6 The following RCS leakage detection instrumentation shall be OPERABLE:

- a. Drywell floor drain sump monitoring system, [and]
- b. One channel of either primary containment atmospheric particulate or atmospheric gaseous monitoring system, and
- [c. Primary containment air cooler condensate flow rate monitoring system.]

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION	REQUIRED ACTION		COMPLETION TIME
A. Drywell floor drain sump monitoring system inoperable.	A.1 Restore sump m OPERA	drywell floor drain onitoring system to BLE status.	30 days
 B. Required primary containment atmospheric monitoring system inoperable. 	B.1 Analyze primary atmospl	e grab samples of containment here.	Once per 12 hours
	B.2 [Restor contain monitor OPERA	re required primary ment atmospheric ing system to BLE status.	30 days]

ACTIONS (continued)

CONDITION		REQUIRED ACTION	COMPLETION TIME
C. [Primary containment air cooler condensate flow rate monitoring system inoperable.	C.1	NOTE Not applicable when required primary containment atmospheric monitoring system is inoperable.	
		Perform SR 3.4.6.1.	Once per 8 hours]
 D. [Required primary containment atmospheric monitoring system inoperable. 	D.1	Restore required primary containment atmospheric monitoring system to OPERABLE status.	30 days
AND	<u>OR</u>		
Primary containment air cooler condensate flow rate monitoring system inoperable.	D.2	Restore primary containment air cooler condensate flow rate monitoring system to OPERABLE status.	30 days]
E. Required Action and associated Completion Time of Condition A, B,	E.1 <u>AND</u>	Be in MODE 3.	12 hours
[C, or D] not met.	E.2	Be in MODE 4.	36 hours
F. All required leakage detection systems inoperable.	F.1	Enter LCO 3.0.3.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.4.6.1	Perform a CHANNEL CHECK of required primary containment atmospheric monitoring system.	12 hours
SR 3.4.6.2	Perform a CHANNEL FUNCTIONAL TEST of required leakage detection instrumentation.	31 days
SR 3.4.6.3	Perform a CHANNEL CALIBRATION of required leakage detection instrumentation.	[18] months

3.4.7 RCS Specific Activity

- LCO 3.4.7 The specific activity of the reactor coolant shall be limited to DOSE EQUIVALENT I-131 specific activity \leq [0.2] μ Ci/gm.
- APPLICABILITY: MODE 1, MODES 2 and 3 with any main steam line not isolated.

CONDITION	REQUIRED ACTION	COMPLETION TIME
 A. Reactor coolant specific activity > [0.2] μCi/gm and ≤ 4.0 μCi/gm DOSE EQUIVALENT I-131. 	AND	Once per 4 hours
	A.2 Restore DOSE EQUIVALENT I-131 to within limits.	48 hours
 B. Required Action and associated Completion Time of Condition A not met. 	B.1 Determine DOSE EQUIVALENT I-131.	Once per 4 hours
<u>OR</u>	B.2.1 Isolate all main steam lines.	12 hours
Reactor Coolant specific activity > [4.0] μCi/gm DOSE EQUIVALENT I-131.	<u>OR</u> B.2.2.1 Be in MODE 3. <u>AND</u>	12 hours
	B.2.2.2 Be in MODE 4.	36 hours

	SURVEILLANCE	FREQUENCY
SR 3.4.7.1	Only required to be performed in MODE 1.	
	Verify reactor coolant DOSE EQUIVALENT I-131 specific activity is \leq [0.2] μ Ci/gm.	7 days

3.4.8	Residual Heat Removal ((RHR)	Shutdown	Cooling S	system - Ho	ot Shutdown
		. ,			1	

ACTIONS

-----NOTES-----

1. LCO 3.0.4 is not applicable.

2. Separate Condition entry is allowed for each RHR shutdown cooling subsystem.

CONDITION	REQUIRED ACTION		COMPLETION TIME
A. One or two RHR shutdown cooling subsystems inoperable.	A.1	Initiate action to restore RHR shutdown cooling subsystem(s) to OPERABLE status.	Immediately
	<u>AND</u>		
	A.2	Verify an alternate method of decay heat removal is available for each inoperable RHR shutdown cooling subsystem.	1 hour
	<u>AND</u>		

CONDITION		REQUIRED ACTION		COMPLETION TIME
		A.3	Be in MODE 4.	24 hours
В.	No RHR shutdown cooling subsystem in operation. <u>AND</u> No recirculation pump in	B.1	Initiate action to restore one RHR shutdown cooling subsystem or one recirculation pump to operation.	Immediately
	operation.	B.2	Verify reactor coolant circulation by an alternate method.	1 hour from discovery of no reactor coolant circulation <u>AND</u> Once per 12 hours
		<u>AND</u> B.3	Monitor reactor coolant temperature and pressure.	thereafter Once per hour

ACTIONS (continued)

	SURVEILLANCE	FREQUENCY	
SR 3.4.8.1	NOTENOTE Not required to be met until 2 hours after reactor steam dome pressure is < [the RHR cut in permissive pressure].		
	Verify one RHR shutdown cooling subsystem or recirculation pump is operating.	12 hours	

3.4.9 Residual Heat Removal (RHR) Shutdown Cooling System - Cold Shutdown

LCO 3.4.9 Two RHR shutdown cooling subsystems shall be OPERABLE, and, with no recirculation pump in operation, at least one RHR shutdown cooling subsystem shall be in operation.

Both RHR shutdown cooling subsystems and recirculation pumps may be not in operation for up to 2 hours per 8 hour period.

 One RHR shutdown cooling subsystem may be inoperable for up to 2 hours for the performance of Surveillances.

APPLICABILITY: MODE 4.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or two RHR	A.1	Verify an alternate method	1 hour
subsystems inoperable.		available for each	AND
	inoperable RHR shutdown cooling subsystem.	cooling subsystem.	Once per 24 hours thereafer
 B. No RHR shutdown cooling subsystem in operation. 	B.1	Verify reactor coolant circulating by an alternate method.	1 hour from discovery of no reactor coolant circulation
AND			AND
No recirculation pump in operation.			Once per 12 hours thereafter
	AND		

ACTIONS ((continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME	
	B.2 Monitor reactor coolant temperature.	Once per hour	

	SURVEILLANCE	FREQUENCY
SR 3.4.9.1	Verify one RHR shutdown cooling subsystem or recirculation pump is operating.	12 hours

- 3.4.10 RCS Pressure and Temperature (P/T) Limits
- LCO 3.4.10 RCS pressure, RCS temperature, RCS heatup and cooldown rates, and the recirculation pump starting temperature requirements shall be maintained within the limits specified in the PTLR.

APPLICABILITY: At all times.

CONDITION		REQUIRED ACTION		COMPLETION TIME
A.	NOTE Required Action A.2 shall be completed if this Condition is entered.	A.1 <u>AND</u> A.2	Restore parameter(s) to within limits.	30 minutes 72 hours
	Requirements of the LCO not met in MODES 1, 2, and 3.		acceptable for continued operation.	
В.	Required Action and associated Completion Time of Condition A not met	B.1 <u>AND</u>	Be in MODE 3.	12 hours
	inct.	B.2	Be in MODE 4.	36 hours
C.	NOTE Required Action C.2 shall be completed if this Condition is entered.	C.1 <u>AND</u>	Initiate action to restore parameter(s) to within limits.	Immediately
	Requirements of the LCO not met in other than MODES 1, 2, and 3.	C.2	Determine RCS is acceptable for operation.	Prior to entering MODE 2 or 3

	FREQUENCY	
SR 3.4.10.1	20 minutos	
	heatup and cooldown rates are within the limits specified in the PTLR.	50 minutes
SR 3.4.10.2	Verify RCS pressure and RCS temperature are within the criticality limits specified in the PTLR.	Once within 15 minutes prior to control rod withdrawal for the purpose of achieving criticality
SR 3.4.10.3	NOTENOTE Only required to be met in MODES 1, 2, 3, and 4 during recirculation pump startup [with reactor steam dome pressure \geq 25 psig].	
	Verify the difference between the bottom head coolant temperature and the reactor pressure vessel (RPV) coolant temperature is within the limits specified in the PTLR.	Once within 15 minutes prior to each startup of a recirculation pump

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.4.10.4		
	Verify the difference between the reactor coolant temperature in the recirculation loop to be started and the RPV coolant temperature is within the limits specified in the PTLR.	Once within 15 minutes prior to each startup of a recirculation pump
SR 3.4.10.5	[Only required to be met during a THERMAL POWER increase or recirculation flow increase in MODES 1 and 2 with one idle recirculation loop when [THERMAL POWER is \leq 30% RTP or when operating loop flow is \leq 50% rated loop flow].	
	Verify the difference between the bottom head coolant temperature and the RPV coolant temperature is [\leq 145°F].	Once within 15 minutes prior to a THERMAL POWER increase or recirculation flow increase]
SR 3.4.10.6	[Only required to be met during a THERMAL POWER increase or recirculation flow increase in MODES 1 and 2 with one non-isolated idle recirculation loop when [THERMAL POWER is \leq 30% RTP or when operating loop flow is \leq 50% rated loop flow].	
	Verify the difference between the reactor coolant temperature in the idle recirculation loop and the RPV coolant temperature is [\leq 50°F].	Once within 15 minutes prior to a THERMAL POWER increase or recirculation flow increase]

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.4.10.7	NOTENOTE Only required to be performed when tensioning the reactor vessel head bolting studs.	
	Verify reactor vessel flange and head flange temperatures are within the limits specified in the PTLR.	30 minutes
SR 3.4.10.8	NOTE Not required to be performed until 30 minutes after RCS temperature ≤ 80°F in MODE 4. Verify reactor vessel flange and head flange temperatures are within the limits specified in the PTLR.	30 minutes
SR 3.4.10.9	NOTE Not required to be performed until 12 hours after RCS temperature ≤ 100°F in MODE 4. 	12 hours

- 3.4.11 Reactor Steam Dome Pressure
- LCO 3.4.11 The reactor steam dome pressure shall be \leq [1020] psig.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Reactor steam dome pressure not within limit.	A.1 Restore reactor steam dome pressure to within limit.	15 minutes
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3.	12 hours

	SURVEILLANCE	FREQUENCY
SR 3.4.11.1	Verify reactor steam dome pressure is \leq [1020] psig.	12 hours

- 3.5 EMERGENCY CORE COOLING SYSTEM (ECCS) AND REACTOR CORE ISOLATION COOLING SYSTEM (RCIC)
- 3.5.1 ECCS Operating
- LCO 3.5.1 Each ECCS injection/spray subsystem and the Automatic Depressurization System (ADS) function of [seven] safety/relief valves shall be OPERABLE.

APPLICABILITY: MODE 1, MODES 2 and 3, except high pressure coolant injection (HPCI) and ADS valves are not required to be OPERABLE with reactor steam dome pressure ≤ [150] psig.

CONDITION		REQUIRED ACTION		COMPLETION TIME
A.	One low pressure ECCS injection/spray subsystem inoperable. <u>OR</u> One LPCI pump in both LPCI subsystems inoperable.	A.1	Restore low pressure ECCS injection/spray subsystem(s) to OPERABLE status.	7 days
В.	Required Action and associated Completion Time of Condition A not met.	B.1 <u>AND</u> B.2	Be in MODE 3. Be in MODE 4.	12 hours 36 hours
C.	HPCI System inoperable.	C.1	Verify by administrative means RCIC System is OPERABLE.	Immediately
		$\frac{AND}{C}$	Restore HPCI System to	14 days
		0.2	OPERABLE status.	in days

ACTIONS (continued)

CONDITION		REQUIRED ACTION		COMPLETION TIME
D. HPCI System inoperable.		D.1	Restore HPCI System to OPERABLE status.	72 hours
	AND	<u>OR</u>		
	Condition A entered.	D.2	Restore low pressure ECCS injection/spray subsystem to OPERABLE status.	72 hours
E.	One ADS valve inoperable.	E.1	Restore ADS valve to OPERABLE status.	14 days
F.	One ADS valve inoperable.	F.1	Restore ADS valve to OPERABLE status.	72 hours
	AND	<u>OR</u>		
	Condition A entered.	F.2	Restore low pressure ECCS injection/spray subsystem to OPERABLE status.	72 hours
G.	Two or more ADS valves inoperable.	G.1 <u>AND</u>	Be in MODE 3.	12 hours
	Required Action and associated Completion Time of Condition C, D, E, or F not met.	G.2	Reduce reactor steam dome pressure to ≤ [150] psig.	36 hours

ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
H. Two or more low pressure ECCS injection/spray subsystems inoperable for reasons other than Condition A.	H.1 Enter LCO 3.0.3.	Immediately
<u>OR</u>		
HPCI System and one or more ADS valves inoperable.		

	SURVEILLANCE	FREQUENCY
SR 3.5.1.1	Verify, for each ECCS injection/spray subsystem, the piping is filled with water from the pump discharge valve to the injection valve.	31 days
SR 3.5.1.2	SR 3.5.1.2NOTE	
SR 3.5.1.3	Verify ADS [air supply header] pressure is \geq [90] psig.	31 days

SURVEILLANCE REQUIREMENTS (continued)

	FREQUENCY	
SR 3.5.1.4	[Verify the [RHR] System cross tie valve[s] [is] closed and power is removed from the valve operator[s].	31 days]
SR 3.5.1.5	[Verify each LPCI inverter output voltage is \geq [570] V and \leq [630] V while supplying the respective bus.	31 days]
SR 3.5.1.6	NOTENOTENOTENOTENOTENOTENOTE	Once each startur
	bypass valve] cycles through one complete cycle of full travel [or is de-energized in the closed position].	prior to exceeding 25% RTP
SR 3.5.1.7	Verify the following ECCS pumps develop the specified flow rate [against a system head corresponding to the specified reactor pressure]. [System Head No. Corresponding	[In accordance with the Inservice Testing Program or 92 days]
	System Flow Rate Pumps Pressure of	
	CoreSpray \geq [4250] gpm[1] \geq [113] psigLPCI \geq [17,000] gpm[2] \geq [20] psig	
SR 3.5.1.8	NOTENOTE Not required to be performed until 12 hours after reactor steam pressure and flow are adequate to perform the test.	
	Verify, with [reactor pressure] \leq [1020] and \geq [920] psig, the HPCI pump can develop a flow rate \geq [4250] gpm [against a system head corresponding to reactor pressure].	92 days

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY		
SR 3.5.1.9	3.5.1.9NOTENOTENOTENOTE			
	Verify, with [reactor pressure] \leq [165] psig, the HPCI pump can develop a flow rate \geq [4250] gpm [against a system head corresponding to reactor pressure].	[18] months		
SR 3.5.1.10	NOTE			
	Vessel injection/spray may be excluded.			
	Verify each ECCS injection/spray subsystem actuates on an actual or simulated automatic initiation signal.	[18] months		
SR 3.5.1.11	NOTENOTEValve actuation may be excluded.			
	Verify the ADS actuates on an actual or simulated automatic initiation signal.	[18] months		
SR 3.5.1.12	NOTENOTE Not required to be performed until 12 hours after reactor steam pressure and flow are adequate to perform the test.			
	Verify each ADS valve opens when manually actuated.	[18] months [on a STAGGERED TEST BASIS for each valve solenoid]		

- 3.5 EMERGENCY CORE COOLING SYSTEM (ECCS) AND REACTOR CORE ISOLATION COOLING SYSTEM (RCIC)
- 3.5.2 ECCS Shutdown
- LCO 3.5.2 Two low pressure ECCS injection/spray subsystems shall be OPERABLE.
- APPLICABILITY: MODE 4, MODE 5, except with the spent fuel storage pool gates removed and water level ≥ [23 ft] over the top of the reactor pressure vessel flange.

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One required ECCS injection/spray subsystem inoperable.	A.1	Restore required ECCS injection/spray subsystem to OPERABLE status.	4 hours
 B. Required Action and associated Completion Time of Condition A not met. 	B.1	Initiate action to suspend operations with a potential for draining the reactor vessel (OPDRVs).	Immediately
C. Two required ECCS injection/spray	C.1	Initiate action to suspend OPDRVs.	Immediately
	<u>AND</u>		
	C.2	Restore one ECCS injection/spray subsystem to OPERABLE status.	4 hours
D. Required Action C.2 and associated Completion Time not met.	D.1	Initiate action to restore [secondary] containment to OPERABLE status.	Immediately
	<u>AND</u>		

CONDITION	REQUIRED ACTION		COMPLETION TIME
	D.2	[Initiate action to restore one standby gas treatment subsystem to OPERABLE status.	Immediately]
	<u>AND</u>		
	D.3	Initiate action to restore isolation capability in each required [secondary] containment penetration flow path not isolated.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.5.2.1	Verify, for each required low pressure coolant injection (LPCI) subsystem, the suppression pool water level is \geq [12 ft 2 inches].	12 hours
SR 3.5.2.2	 Verify, for each required core spray (CS) subsystem, the: a. Suppression pool water level is ≥ [12 ft 2 inches] or b. Condensate storage tank water level is ≥ [12 ft]. NOTEOnly one required CS subsystem may take credit for this option during OPDRVs. 	12 hours
SR 3.5.2.3	Verify, for each required ECCS injection/spray subsystem, the piping is filled with water from the pump discharge valve to the injection valve.	31 days

SURVEILLANCE REQUIREMENTS (continued)

	FREQUENCY				
SR 3.5.2.4	One LPC OPERAE decay he realigned				
	Verify each required ECCS injection/spray subsystem manual, power operated, and automatic valve in the flow path, that is not locked, sealed, or otherwise secured in position, is in the correct position.				31 days
SR 3.5.2.5	Verify each required ECCS pump develops the specified flow rate [against a system head corresponding to the specified reactor pressure].				[In accordance with the Inservice Testing Program
	<u>System</u> CS	or 92 daysj			
	LPCI	≥ [7700] gpm	[1]	≥ [20] psig	
SR 3.5.2.6	NOTENOTEVessel injection/spray may be excluded.				
	Verify each required ECCS injection/spray subsystem actuates on an actual or simulated automatic initiation signal.				[18] months

- 3.5 EMERGENCY CORE COOLING SYSTEM (ECCS) AND REACTOR CORE ISOLATION COOLING SYSTEM (RCIC)
- 3.5.3 RCIC System
- LCO 3.5.3 The RCIC System shall be OPERABLE.
- APPLICABILITY: MODE 1, MODES 2 and 3 with reactor steam dome pressure > [150] psig.

ACTIONS

CONDITION	REQUIRED ACTION		COMPLETION TIME
A. RCIC System inoperable.	A.1 Verify by administrative means High Pressure Coolant Injection System is OPERABLE.		Immediately
	AND		
	A.2	Restore RCIC System to OPERABLE status.	14 days
B. Required Action and	B.1	Be in MODE 3.	12 hours
associated Completion Time not met.	<u>AND</u>		
	B.2	Reduce reactor steam dome pressure to ≤ [150] psig.	36 hours

	SURVEILLANCE	FREQUENCY
SR 3.5.3.1	Verify the RCIC System piping is filled with water from the pump discharge valve to the injection valve.	31 days

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.5.3.2	Verify each RCIC System manual, power operated, and automatic valve in the flow path, that is not locked, sealed, or otherwise secured in position, is in the correct position.	31 days
SR 3.5.3.3	NOTENOTE Not required to be performed until 12 hours after reactor steam pressure and flow are adequate to perform the test.	
	Verify, with [reactor pressure] \leq [1020] psig and \geq [920] psig, the RCIC pump can develop a flow rate \geq [400] gpm [against a system head corresponding to reactor pressure].	92 days
SR 3.5.3.4	Not required to be performed until 12 hours after reactor steam pressure and flow are adequate to perform the test.	[40]
	Verify, with [reactor pressure] \leq [165] psig, the RCIC pump can develop a flow rate \geq [400] gpm [against a system head corresponding to reactor pressure].	[18] months
SR 3.5.3.5	NOTENOTENOTENOTE	
	Verify the RCIC System actuates on an actual or simulated automatic initiation signal.	[18] months
3.6.1.1 Primary Containment

LCO 3.6.1.1 Primary containment shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. Primary containment inoperable.	A.1	Restore primary containment to OPERABLE status.	1 hour
 B. Required Action and associated Completion Time not met. 	В.1 <u>AND</u>	Be in MODE 3.	12 hours
	B.2	Be in MODE 4.	36 hours

	SURVEILLANCE	FREQUENCY
SR 3.6.1.1.1	Perform required visual examinations and leakage rate testing except for primary containment air lock testing, in accordance with the Primary Containment Leakage Rate Testing Program.	In accordance with the Primary Containment Leakage Rate Testing Program

	SURVEILLANCE	FREQUENCY
SR 3.6.1.1.2	Verify drywell to suppression chamber differential pressure does not decrease at a rate > [0.25] inch water gauge per minute tested over a [10] minute period at an initial differential pressure of [1] psid.	[18] months <u>AND</u> NOTE Only required after two consecutive tests fail and continues until two consecutive tests pass [9] months

3.6.1.2 Primary Containment Air Lock

LCO 3.6.1.2 The primary containment air lock shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

Entry and exit is permissible to perform repairs of the air lock components.

2. Enter applicable Conditions and Required Actions of LCO 3.6.1.1, "Primary Containment," when air lock leakage results in exceeding overall containment leakage rate acceptance criteria.

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One primary containment air lock door inoperable.	 Rec and doo inop ente Enti 7 da con 	yuired Actions A.1, A.2, A.3 are not applicable if both rs in the air lock are berable and Condition C is ered. Ty and exit is permissible for ays under administrative trols.	
	A.1	Verify the OPERABLE door is closed.	1 hour
	AND		
	A.2	Lock the OPERABLE door closed.	24 hours
	<u>AND</u>		

ACTIONS	(continued)
---------	-------------

CONDITION	REQUIRED ACTION	COMPLETION TIME
	A.3NOTE Air lock doors in high radiation areas or areas with limited access due to inerting may be verified locked closed by administrative means.	
	Verify the OPERABLE door is locked closed.	Once per 31 days
B. Primary containment air lock interlock mechanism inoperable.	 NOTES Required Actions B.1, B.2, and B.3 are not applicable if both doors in the air lock are inoperable and Condition C is entered. 2. Entry into and exit from containment is permissible under the control of a dedicated individual. 	
	B.1 Verify an OPERABLE door is closed.	1 hour
	AND	
	B.2 Lock an OPERABLE door closed.	24 hours
	AND	

CONDITION		REQUIRED ACTION	COMPLETION TIME
	B.3	NOTE Air lock doors in high radiation areas or areas with limited access due to inerting may be verified locked closed by administrative means.	
		Verify an OPERABLE door is locked closed.	Once per 31 days
C. Primary containment air lock inoperable for reasons other than Condition A or B.	C.1	Initiate action to evaluate primary containment overall leakage rate per LCO 3.6.1.1, using current air lock test results.	Immediately
	<u>AND</u>		
	C.2	Verify a door is closed.	1 hour
	<u>AND</u>		
	C.3	Restore air lock to OPERABLE status.	24 hours
D. Required Action and	D.1	Be in MODE 3.	12 hours
associated Completion Time not met.	AND		
	D.2	Be in MODE 4.	36 hours

	FREQUENCY	
SR 3.6.1.2.1	 NOTES	In accordance with the Primary Containment Leakage Rate Testing Program
SR 3.6.1.2.2	Verify only one door in the primary containment air lock can be opened at a time.	24 months

3.6.1.3 Primary Containment Isolation Valves (PCIVs)

LCO 3.6.1.3 Each PCIV, except reactor building-to-suppression chamber vacuum breakers, shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3, When associated instrumentation is required to be OPERABLE per LCO 3.3.6.1, "Primary Containment Isolation Instrumentation."

ACTIONS

-----NOTES------

- 1. Penetration flow paths [except for purge valve penetration flow paths] may be unisolated intermittently under administrative controls.
- 2. Separate Condition entry is allowed for each penetration flow path.
- 3. Enter applicable Conditions and Required Actions for systems made inoperable by PCIVs.
- 4. Enter applicable Conditions and Required Actions of LCO 3.6.1.1, "Primary Containment," when PCIV leakage results in exceeding overall containment leakage rate acceptance criteria in MODES 1, 2, and 3.

CONDITION	REQUIRED ACTION	COMPLETION TIME
ANOTE Only applicable to penetration flow paths with two [or more] PCIVs. One or more penetration flow paths with one PCIV inoperable [for reasons other than Condition[s] D [and E]].	 A.1 Isolate the affected penetration flow path by use of at least one closed and de-activated automatic valve, closed manual valve, blind flange, or check valve with flow through the valve secured. 	4 hours except for main steam line <u>AND</u> 8 hours for main steam line

CONDITION	REQUIRED ACTION	COMPLETION TIME
	 A.2NOTES	Once per 31 days for isolation devices outside primary containment <u>AND</u> Prior to entering MODE 2 or 3 from MODE 4, if primary containment was de- inerted while in MODE 4, if not performed within the previous 92 days, for isolation devices inside primary containment

CONDITION	REQUIRED ACTION	COMPLETION TIME
 BNOTE Only applicable to penetration flow paths with two [or more] PCIVs. One or more penetration flow paths with two [or more] PCIVs inoperable [for reasons other than Condition[s] D [and E]]. 	B.1 Isolate the affected penetration flow path by use of at least one closed and de-activated automatic valve, closed manual valve, or blind flange.	1 hour
CNOTE Only applicable to penetration flow paths with only one PCIV. One or more penetration flow paths with one PCIV inoperable [for reasons other than Condition[s] D [and E]].	C.1 Isolate the affected penetration flow path by use of at least one closed and de-activated automatic valve, closed manual valve, or blind flange.	 [4] hours except for excess flow check valves (EFCVs) and penetrations with a closed system <u>AND</u> 72 hours for EFCVs and penetrations with a closed system

ACTIONS ((continued)
-----------	-------------

CONDITION		REQUIRED ACTION	COMPLETION TIME
	C.2	 Isolation devices in high radiation areas may be verified by use of administrative means. Isolation devices that are locked, sealed, or otherwise secured may be verified by use of administrative means. 	
		Verify the affected penetration flow path is isolated.	Once per 31 days

CONDITION		REQUIRED ACTION	COMPLETION TIME
D. [One or more [secondary containment bypass leakage rate,] [MSIV leakage rate,] [purge valve leakage rate,] [hydrostatically tested line leakage rate,] [or] [EFCV leakage rate] not within limit.	D.1	Restore leakage rate to within limit.	[4 hours for hydrostatically tested line leakage [not on a closed system]] AND [4 hours for secondary containment bypass leakage] AND [8 hours for MSIV leakage] AND [24 hours for purge valve leakage] AND [72 hours for hydrostatically tested line leakage [on a closed system] [and EFCV leakage]]
E. [One or more penetration flow paths with one or more containment purge valves not within purge valve leakage limits.	E.1	Isolate the affected penetration flow path by use of at least one [closed and de-activated automatic valve, closed manual valve, or blind flange].	24 hours

CONDITION	REQUIRED ACTION		COMPLETION TIME	
	E.2	 NOTES 1. Isolation devices in high radiation areas may be verified by use of administrative means. 2. Isolation devices that are locked, sealed, or otherwise secured may be verified by use of administrative means. 		
		Verify the affected penetration flow path is isolated.	Once per 31 days for isolation devices outside containment	
			AND	
			Prior to entering MODE 2 or 3 from MODE 4 if not performed within the previous 92 days for isolation devices inside containment	
	<u>AND</u>			
	E.3	Perform SR 3.6.1.3.7 for the resilient seal purge valves closed to comply with Required Action E.1.	Once per [92] days]	
F. Required Action and associated Completion	F.1	Be in MODE 3.	12 hours	
C, D, or E not met in				
MODE 1, 2, or 3.	F.2	Be in MODE 4.	36 hours	

CONDITION	REQUIRED ACTION	COMPLETION TIME
G. [Required Action and associated Completion Time of Condition A, B, C, D, or E not met for PCIV(s) required to be OPERABLE during movement of [recently] irradiated fuel assemblies in [secondary] containment.	G.1NOTE LCO 3.0.3 is not applicable. Suspend movement of [recently] irradiated fuel assemblies in [secondary] containment.	Immediately]
H. [Required Action and associated Completion Time of Condition A, B, C, D, or E not met for PCIV(s) required to be OPERABLE during MODE 4 or 5 or during operations with a potential for draining the reactor vessel (OPDRVs).	 H.1 Initiate action to suspend OPDRVs. OR H.2 Initiate action to restore valve(s) to OPERABLE status. 	Immediately Immediately]

	FREQUENCY	
SR 3.6.1.3.1	[[Only required to be met in MODES 1, 2, and 3.]	
	Verify each [18] inch primary containment purge valve is sealed closed except for one purge valve in a penetration flow path while in Condition E of this LCO.	31 days]
SR 3.6.1.3.2	 NOTES	
	Verify each [18] inch primary containment purge valve is closed.	31 days]
SR 3.6.1.3.3	 Valves and blind flanges in high radiation areas may be verified by use of administrative means. Not required to be met for PCIVs that are open under administrative controls. 	
	Verify each primary containment isolation manual valve and blind flange that is located outside primary containment and not locked, sealed, or otherwise secured and is required to be closed during accident conditions is closed.	31 days

	SURVEILLANCE	FREQUENCY
SR 3.6.1.3.4	 NOTESNOTESNOTESNOTES	
	Verify each primary containment manual isolation valve and blind flange that is located inside primary containment and not locked, sealed, or otherwise secured and is required to be closed during accident conditions is closed.	Prior to entering MODE 2 or 3 from MODE 4 if primary containment was de-inerted while in MODE 4, if not performed within the previous 92 days
SR 3.6.1.3.5	Verify continuity of the traversing incore probe (TIP) shear isolation valve explosive charge.	31 days
SR 3.6.1.3.6	Verify the isolation time of each power operated automatic PCIV, [except for MSIVs], is within limits.	[In accordance with the Inservice Testing Program or 92 days]
SR 3.6.1.3.7	[[Only required to be met in MODES 1, 2 and 3.] Perform leakage rate testing for each primary containment purge valve with resilient seals.	184 days <u>AND</u> Once within 92 days after opening the valve]

	SURVEILLANCE	FREQUENCY
SR 3.6.1.3.8	Verify the isolation time of each MSIV is \geq [2] seconds and \leq [8] seconds.	[In accordance with the Inservice Testing Program or 18 months]
SR 3.6.1.3.9	Verify each automatic PCIV actuates to the isolation position on an actual or simulated isolation signal.	[18] months
The bracketed po discussed in NEI	ortions of the SR apply to the representative sample as 00-32977-A.	
SR 3.6.1.3.10	Verify each [a representative sample of] reactor instrumentation line EFCV actuates [on a simulated instrument line break to restrict flow to \leq 1 gph].	[18] months
SR 3.6.1.3.11	Remove and test the explosive squib from each shear isolation valve of the TIP System.	[18] months on a STAGGERED TEST BASIS
SR 3.6.1.3.12	[[Only required to be met in MODES 1, 2, and 3.]	
	Verify the combined leakage rate for all secondary containment bypass leakage paths is \leq [] L _a when pressurized to \geq [] psig.	In accordance with the Primary Containment Leakage Rate Testing Program]
SR 3.6.1.3.13	NOTENOTENOTE [Only required to be met in MODES 1, 2, and 3.]	[In accordance with the Primary Containment
	Verify leakage rate through each MSIV is \leq [11.5] scfh when tested at \geq [28.8] psig.	Leakage Rate Testing Program]

	SURVEILLANCE	FREQUENCY
SR 3.6.1.3.14	NOTENOTENOTE	
	Verify combined leakage rate through hydrostatically tested lines that penetrate the primary containment is within limits.	In accordance with the Primary Containment Leakage Rate Testing Program
SR 3.6.1.3.15	<pre>NOTE [[Only required to be met in MODES 1, 2, and 3.] </pre>	[18] months]

3.6.1.4 Drywell Pressure

LCO 3.6.1.4 Drywell pressure shall be [≤ 0.75 psig].

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. Drywell pressure not within limit.	A.1	Restore drywell pressure to within limit.	1 hour
B. Required Action and associated Completion Time not met.	B.1 <u>AND</u>	Be in MODE 3.	12 hours
	B.2	Be in MODE 4.	36 hours

	SURVEILLANCE	FREQUENCY
SR 3.6.1.4.1	Verify drywell pressure is within limit.	12 hours

- 3.6.1.5 Drywell Air Temperature
- LCO 3.6.1.5 Drywell average air temperature shall be \leq [135]°F.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
 A. Drywell average air temperature not within limit. 	A.1	Restore drywell average air temperature to within limit.	8 hours
 B. Required Action and associated Completion Time not met. 	В.1 <u>AND</u>	Be in MODE 3.	12 hours
	B.2	Be in MODE 4.	36 hours

	SURVEILLANCE	FREQUENCY
SR 3.6.1.5.1	Verify drywell average air temperature is within limit.	24 hours

- 3.6.1.6 Low-Low Set (LLS) Valves
- LCO 3.6.1.6 The LLS function of [four] safety/relief valves shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One LLS valve inoperable.	A.1	Restore LLS valve to OPERABLE status.	14 days
B. Required Action an associated Comple Time of Condition A met.	etion A not <u>AND</u>	Be in MODE 3.	12 hours
<u>OR</u>	B.2	Be in MODE 4.	36 hours
Two or more LLS v inoperable.	alves		

	FREQUENCY	
SR 3.6.1.6.1	NOTENOTE Not required to be performed until 12 hours after reactor steam pressure and flow are adequate to perform the test.	
	Verify each LLS valve opens when manually actuated.	[18] months [on a STAGGERED TEST BASIS for each valve solenoid]
SR 3.6.1.6.2	NOTENOTENOTENOTENOTE	
	Verify the LLS System actuates on an actual or simulated automatic initiation signal.	18 months

3.6.1.7 Reactor Building-to-Suppression Chamber Vacuum Breakers

LCO 3.6.1.7 Each reactor building-to-suppression chamber vacuum breaker shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION	REQUIRED ACTION		COMPLETION TIME
A. One or more lines with one reactor building-to- suppression chamber vacuum breaker not closed.	A.1 Clo brea	se the open vacuum aker.	72 hours
B. One or more lines with two reactor building-to- suppression chamber vacuum breakers not closed.	B.1 Clo brea	se one open vacuum aker.	1 hour
C. One line with one or more reactor building-to- suppression chamber vacuum breakers inoperable for opening.	C.1 Res brea stat	store the vacuum aker(s) to OPERABLE rus.	72 hours
D. Two [or more] lines with one or more reactor building-to-suppression chamber vacuum breakers inoperable for opening.	D.1 Res brea OP	store all vacuum akers in [one] line to ERABLE status.	1 hour

CONDITION		REQUIRED ACTION	COMPLETION TIME
E. Required Action and Associated Completion Time not met.	E.1 <u>AND</u>	Be in MODE 3.	12 hours
	E.2	Be in MODE 4.	36 hours

	FREQUENCY	
SR 3.6.1.7.1	 Not required to be met for vacuum breakers that are open during Surveillances. Not required to be met for vacuum breakers open when performing their intended function. 	
	Verify each vacuum breaker is closed.	14 days
SR 3.6.1.7.2	Perform a functional test of each vacuum breaker.	[92] days
SR 3.6.1.7.3	Verify the opening setpoint of each vacuum breaker is \leq [0.5] psid.	[18] months

- 3.6.1.8 Suppression Chamber-to-Drywell Vacuum Breakers
- LCO 3.6.1.8 [Nine] suppression chamber-to-drywell vacuum breakers shall be OPERABLE for opening.

<u>AND</u>

[Twelve] suppression chamber-to-drywell vacuum breakers shall be closed, except when performing their intended function.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

	REQUIRED ACTION	COMPLETION TIME
A.1	Restore one vacuum breaker to OPERABLE status.	72 hours
B.1	Close the open vacuum breaker.	2 hours
C.1 <u>AND</u> C.2	Be in MODE 3. Be in MODE 4.	12 hours 36 hours
	A.1 B.1 C.1 <u>AND</u> C.2	REQUIRED ACTIONA.1Restore one vacuum breaker to OPERABLE status.B.1Close the open vacuum breaker.C.1Be in MODE 3.AND C.2Be in MODE 4.

	SURVEILLANCE	FREQUENCY
SR 3.6.1.8.1	NOTENOTE Not required to be met for vacuum breakers that are open during Surveillances.	
	Verify each vacuum breaker is closed.	14 days <u>AND</u> Within 2 hours after any discharge of steam to the suppression chamber from the safety/relief valves (S/RVs) or any operation that causes the drywell-to- suppression chamber differential pressure to be reduced by ≥ [0.5] psid

SURVEILLANCE REQUIREMENTS	(continued)
---------------------------	-------------

	SURVEILLANCE	FREQUENCY
SR 3.6.1.8.2	Perform a functional test of each required vacuum breaker.	31 days <u>AND</u> Within 12 hours after any discharge of steam to the suppression chamber from the S/RVs <u>AND</u> Within 12 hours following an operation that causes any of the vacuum breakers to open
SR 3.6.1.8.3	Verify the opening setpoint of each required vacuum breaker is \leq [0.5] psid.	[18] months

3.6.1.9 Main Steam Isolation Valve (MSIV) Leakage Control System (LCS)

LCO 3.6.1.9 Two MSIV LCS subsystems shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One MSIV LCS subsystem inoperable.	A.1	Restore MSIV LCS subsystem to OPERABLE status.	30 days
B. Two MSIV LCS subsystems inoperable.	B.1	Restore one MSIV LCS subsystem to OPERABLE status.	7 days
C. Required Action and associated Completion Time not met.	C.1 <u>AND</u> C.2	Be in MODE 3. Be in MODE 4.	12 hours 36 hours

	SURVEILLANCE	FREQUENCY
SR 3.6.1.9.1	Operate each MSIV LCS blower \geq [15] minutes.	31 days
SR 3.6.1.9.2	Verify electrical continuity of each inboard MSIV LCS subsystem heater element circuitry.	31 days

	SURVEILLANCE	FREQUENCY
SR 3.6.1.9.3	Perform a system functional test of each MSIV LCS subsystem.	[18] months

3.6.2.1 Suppression Pool Average Temperature

LCO 3.6.2.1 Suppression pool average temperature shall be:

- a. ≤ [95]° F [when any OPERABLE intermediate range monitor (IRM) channel is > [25/40] divisions of full scale on Range 7] [with THERMAL POWER > 1% RTP] and no testing that adds heat to the suppression pool is being performed,
- b. ≤ [105]° F [when any OPERABLE IRM channel is > [25/40] divisions of full scale on Range 7] [with THERMAL POWER > 1% RTP] and testing that adds heat to the suppression pool is being performed, and
- c. \leq [110]°F [when all OPERABLE IRM channels are \leq [25/40] divisions of full scale on Range 7] [with THERMAL POWER \leq 1% RTP].

APPLICABILITY: MODES 1, 2, and 3.

CONDITION	REQUIRED ACTION		COMPLETION TIME
 A. Suppression pool average temperature > [95]°F but ≤ [110]°F. 	A.1	Verify suppression pool average temperature ≤ [110]°F.	Once per hour
AND	<u>AND</u>		
[Any OPERABLE IRM channel > [25/40] divisions of full scale on Range 7] [THERMAL POWER > 1% RTP].	A.2	Restore suppression pool average temperature to ≤ [95]°F.	24 hours
AND			
Not performing testing that adds heat to the suppression pool.			

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
B. Required Action and associated Completion Time of Condition A not met.	B.1	Reduce THERMAL POWER [until all OPERABLE IRM channels \leq [25/40] divisions of full scale on Range 7] [to \leq 1% RTP.]	12 hours
 C. Suppression pool average temperature > [105]°F. <u>AND</u> 	C.1	Suspend all testing that adds heat to the suppression pool.	Immediately
[Any OPERABLE IRM channel > [25/40] divisions of full scale on Range 7] [THERMAL POWER > 1% RTP].			
AND			
Performing testing that adds heat to the suppression pool.			
 D. Suppression pool average temperature > [110]°F but ≤ [120]°F. 	D.1	Place the reactor mode switch in the shutdown position.	Immediately
	<u>AND</u>		
	D.2	Verify suppression pool average temperature ≤ [120]°F.	Once per 30 minutes
	AND		
	D.3	Be in MODE 4.	36 hours

CONDITION		REQUIRED ACTION	COMPLETION TIME
 E. Suppression pool average temperature > [120]°F. 	E.1 <u>AND</u>	Depressurize the reactor vessel to < [200] psig.	12 hours
	E.2	Be in MODE 4.	[36 hours]

	SURVEILLANCE	FREQUENCY
SR 3.6.2.1.1	Verify suppression pool average temperature is within the applicable limits.	24 hours <u>AND</u> 5 minutes when performing testing that adds heat to the suppression pool

- 3.6.2.2 Suppression Pool Water Level
- LCO 3.6.2.2 Suppression pool water level shall be \geq [12 ft 2 inches] and \leq [12 ft 6 inches].

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. Suppression pool water level not within limits.	A.1	Restore suppression pool water level to within limits.	2 hours
 B. Required Action and associated Completion Time not met. 	В.1 <u>AND</u>	Be in MODE 3.	12 hours
	B.2	Be in MODE 4.	36 hours

	SURVEILLANCE	FREQUENCY
SR 3.6.2.2.1	Verify suppression pool water level is within limits.	24 hours

- 3.6.2.3 Residual Heat Removal (RHR) Suppression Pool Cooling
- LCO 3.6.2.3 Two RHR suppression pool cooling subsystems shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One RHR suppression pool cooling subsystem inoperable.	A.1	Restore RHR suppression pool cooling subsystem to OPERABLE status.	7 days
B. Two RHR suppression pool cooling subsystems inoperable.	B.1	Restore one RHR suppression pool cooling subsystem to OPERABLE status.	8 hours
C. Required Action and associated Completion Time not met.	C.1 <u>AND</u> C.2	Be in MODE 3. Be in MODE 4.	12 hours 36 hours

	SURVEILLANCE	FREQUENCY
SR 3.6.2.3.1	Verify each RHR suppression pool cooling subsystem manual, power operated, and automatic valve in the flow path that is not locked, sealed, or otherwise secured in position is in the correct position or can be aligned to the correct position.	31 days

	SURVEILLANCE	FREQUENCY
SR 3.6.2.3.2	Verify each RHR pump develops a flow rate > [7700] gpm through the associated heat exchanger while operating in the suppression pool cooling mode.	[In accordance with the Inservice Testing Program or 92 days]

3.6.2.4 Residual Heat Removal (RHR) Suppression Pool Spray

LCO 3.6.2.4 Two RHR suppression pool spray subsystems shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One RHR suppression pool spray subsystem inoperable.	A.1	Restore RHR suppression pool spray subsystem to OPERABLE status.	7 days
B. Two RHR suppression pool spray subsystems inoperable.	B.1	Restore one RHR suppression pool spray subsystem to OPERABLE status.	8 hours
C. Required Action and associated Completion Time not met.	C.1 <u>AND</u> C.2	Be in MODE 3. Be in MODE 4.	12 hours 36 hours

	SURVEILLANCE	FREQUENCY
SR 3.6.2.4.1	Verify each RHR suppression pool spray subsystem manual, power operated, and automatic valve in the flow path that is not locked, sealed, or otherwise secured in position is in the correct position or can be aligned to the correct position.	31 days

	SURVEILLANCE	FREQUENCY
SR 3.6.2.4.2	[Verify each RHR pump develops a flow rate \geq [400] gpm through the heat exchanger while operating in the suppression pool spray mode.	In accordance with the Inservice Testing Program or 92 days]
- 3.6.2.5 Drywell-to-Suppression Chamber Differential Pressure
- LCO 3.6.2.5 The drywell pressure shall be maintained \geq [1.5] psid above the pressure of the suppression chamber.
- APPLICABILITY: MODE 1 during the time period:
 - a. From [24] hours after THERMAL POWER is > [15]% RTP following startup, to
 - b. [24] hours prior to reducing THERMAL POWER to < [15]% RTP prior to the next scheduled reactor shutdown.

ACTIONS

	CONDITION		REQUIRED ACTION	COMPLETION TIME
A.	Drywell-to-suppression chamber differential pressure not within limit.	A.1	Restore differential pressure to within limit.	8 hours
В.	Required Action and associated Completion Time not met.	B.1	Reduce THERMAL POWER to ≤ [15]% RTP.	12 hours

	SURVEILLANCE	FREQUENCY
SR 3.6.2.5.1	Verify drywell-to-suppression chamber differential pressure is within limit.	12 hours

3.6.3.1 Primary Containment Hydrogen Recombiners (if permanently installed)

LCO 3.6.3.1 Two primary containment hydrogen recombiners shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

	CONDITION		REQUIRED ACTION	COMPLETION TIME
A.	One primary containment hydrogen recombiner inoperable.	A.1	NOTE LCO 3.0.4 is not applicable.	
			Restore primary containment hydrogen recombiner to OPERABLE status.	30 days
В.	[Two primary	B.1	Verify by administrative	1 hour
	recombiners inoperable.		means that the hydrogen control function is	AND
			maintaineu.	Once per 12 hours thereafter
		<u>AND</u>		
		B.2	Restore one primary containment hydrogen recombiner to OPERABLE status.	7 days]
C.	Required Action and associated Completion Time not met.	C.1	Be in MODE 3.	12 hours

	SURVEILLANCE	FREQUENCY
SR 3.6.3.1.1	Perform a system functional test for each primary containment hydrogen recombiner.	[18] months
SR 3.6.3.1.2	Visually examine each primary containment hydrogen recombiner enclosure and verify there is no evidence of abnormal conditions.	[18] months
SR 3.6.3.1.3	Perform a resistance to ground test for each heater phase.	[18] months

3.6.3.2 [Drywell Cooling System Fans]

LCO 3.6.3.2 Two [drywell cooling system fans] shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

CONDITION	REQUIRED ACTION		COMPLETION TIME
A. One [required] [drywell cooling system fan] inoperable.	A.1	NOTE LCO 3.0.4 is not applicable. Restore [required] [drywell cooling system fan] to OPERABLE status.	30 days
B. Two [required] [drywell cooling system fans] inoperable.	B.1 <u>AND</u>	Verify by administrative means that the hydrogen control function is maintained.	1 hour <u>AND</u> Once per 12 hours thereafter
	B.2	Restore one [required] [drywell cooling system fan] to OPERABLE status.	7 days
C. Required Action and associated Completion Time not met.	C.1	Be in MODE 3.	12 hours

	SURVEILLANCE	FREQUENCY
SR 3.6.3.2.1	Operate each [required] [drywell cooling system fan] for \geq [15] minutes.	92 days
SR 3.6.3.2.2	[Verify each [required] [drywell cooling system fan] flow rate is \ge [500] scfm.	[18] months]

- 3.6.3.3 Primary Containment Oxygen Concentration
- LCO 3.6.3.3 The primary containment oxygen concentration shall be < 4.0 volume percent.
- APPLICABILITY: MODE 1 during the time period:
 - a. From [24] hours after THERMAL POWER is > [15]% RTP following startup, to
 - b. [24] hours prior to reducing THERMAL POWER to < [15]% RTP prior to the next scheduled reactor shutdown.

ACTIONS

	CONDITION		REQUIRED ACTION	COMPLETION TIME
A.	Primary containment oxygen concentration not within limit.	A.1	Restore oxygen concentration to within limit.	24 hours
B.	Required Action and associated Completion Time not met.	B.1	Reduce THERMAL POWER to ≤ [15]% RTP.	8 hours

	SURVEILLANCE	FREQUENCY
SR 3.6.3.3.1	Verify primary containment oxygen concentration is within limits.	7 days

3.6.3.4 Containment Atmosphere Dilution (CAD) System

LCO 3.6.3.4 Two CAD subsystems shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One CAD subsystem inoperable.	A.1	NOTE LCO 3.0.4 is not applicable.	
		Restore CAD subsystem to OPERABLE status.	30 days
B. [Two CAD subsystems	B.1	Verify by administrative	1 hour
		means that the hydrogen control function is	AND
		maintaineu.	Once per 12 hours thereafter
	AND		
	B.2	Restore one CAD subsystem to OPERABLE status.	7 days]
C. Required Action and associated Completion Time not met.	C.1	Be in MODE 3.	12 hours

	SURVEILLANCE	FREQUENCY
SR 3.6.3.4.1	Verify \geq [4350] gal of liquid nitrogen are contained in the CAD System.	31 days
SR 3.6.3.4.2	Verify each CAD subsystem manual, power operated, and automatic valve in the flow path that is not locked, sealed, or otherwise secured in position is in the correct position or can be aligned to the correct position.	31 days

3.6.4.1 [Secondary] Containment

LCO 3.6.4.1 The [secondary] containment shall be OPERABLE.

 APPLICABILITY: MODES 1, 2, and 3, During movement of [recently] irradiated fuel assemblies in the [secondary] containment, During operations with a potential for draining the reactor vessel (OPDRVs).

CONDITION		REQUIRED ACTION	COMPLETION TIME
 A. [Secondary] containment inoperable in MODE 1, 2, or 3. 	A.1	Restore [secondary] containment to OPERABLE status.	4 hours
 B. Required Action and associated Completion Time of Condition A not met. 	B.1 <u>AND</u> B.2	Be in MODE 3. Be in MODE 4.	12 hours 36 hours
C. [Secondary] containment inoperable during movement of [recently] irradiated fuel assemblies in the [secondary] containment or during OPDRVs.	C.1	NOTE LCO 3.0.3 is not applicable. Suspend movement of [recently] irradiated fuel assemblies in the [secondary] containment.	Immediately
	<u>AND</u> C.2	Initiate action to suspend OPDRVs.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.6.4.1.1	[Verify [secondary] containment vacuum is \geq [0.25] inch of vacuum water gauge.	24 hours]
SR 3.6.4.1.2	Verify all [secondary] containment equipment hatches are closed and sealed.	31 days
SR 3.6.4.1.3	Verify one [secondary] containment access door in each access opening is closed.	31 days
SR 3.6.4.1.4	[Verify [secondary] containment can be drawn down to \geq [0.25] inch of vacuum water gauge in \leq [120] seconds using one standby gas treatment (SGT) subsystem.	[18] months on a STAGGERED TEST BASIS for each subsystem]
SR 3.6.4.1.5	Verify the [secondary] containment can be maintained \ge [0.25] inch of vacuum water gauge for 1 hour using one SGT subsystem at a flow rate \le [4000] cfm.	[18] months on a STAGGERED TEST BASIS for each SGT subsystem

3.6.4.2 Secondary Containment Isolation Valves (SCIVs)

LCO 3.6.4.2 Each SCIV shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3, During movement of [recently] irradiated fuel assemblies in the [secondary] containment, During operations with a potential for draining the reactor vessel (OPDRVs).

ACTIONS

-----NOTES------

- 1. Penetration flow paths may be unisolated intermittently under administrative controls.
- 2. Separate Condition entry is allowed for each penetration flow path.

3. Enter applicable Conditions and Required Actions for systems made inoperable by SCIVs.

CONDITION	REQUIRED ACTION	COMPLETION TIME
 A. One or more penetration flow paths with one SCIV inoperable. 	A.1 Isolate the affected penetration flow path by use of at least one closed and de-activated automatic valve, closed manual valve, or blind flange.	8 hours
	AND	

CONDITION		REQUIRED ACTION	COMPLETION TIME
	A.2	 NOTES 1. Isolation devices in high radiation areas may be verified by use of administrative means. 2. Isolation devices that are locked, sealed, or otherwise secured may be verified by use of administrative means. 	Once per 31 days
 BNOTE Only applicable to penetration flow paths with two isolation valves. One or more penetration flow paths with two SCIVs inoperable. 	B.1	Isolate the affected penetration flow path by use of at least one closed and de-activated automatic valve, closed manual valve, or blind flange.	4 hours
C. Required Action and associated Completion Time of Condition A or B not met in MODE 1, 2, or 3.	C.1 <u>AND</u> C.2	Be in MODE 3. Be in MODE 4.	12 hours 36 hours

CONDITION		REQUIRED ACTION	COMPLETION TIME
D. Required Action and associated Completion Time of Condition A or B not met during movement of [recently] irradiated fuel assemblies in the [secondary] containment or during OPDRVs.	D.1 <u>AND</u>	NOTE LCO 3.0.3 is not applicable. Suspend movement of [recently] irradiated fuel assemblies in the [secondary] containment.	Immediately
	D.2	Initiate action to suspend OPDRVs.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.6.4.2.1	 NOTESNOTES 1. Valves and blind flanges in high radiation areas may be verified by use of administrative means. 2. Not required to be met for SCIVs that are open under administrative controls. 	
	Verify each secondary containment isolation manual valve and blind flange that is not locked, sealed, or otherwise secured and is required to be closed during accident conditions is closed.	31 days
SR 3.6.4.2.2	Verify the isolation time of each power operated, automatic SCIV is within limits.	[In accordance with the Inservice Testing Program or 92 days]
SR 3.6.4.2.3	Verify each automatic SCIV actuates to the isolation position on an actual or simulated actuation signal.	[18] months

- 3.6.4.3 Standby Gas Treatment (SGT) System
- LCO 3.6.4.3 [Two] SGT subsystems shall be OPERABLE.

 APPLICABILITY: MODES 1, 2, and 3, During movement of [recently] irradiated fuel assemblies in the [secondary] containment, During operations with a potential for draining the reactor vessel (OPDRVs).

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One SGT subsystem inoperable.	A.1 Restore SGT subsystem to OPERABLE status.	7 days
 B. Required Action and associated Completion Time of Condition A not met in MODE 1, 2, or 3. 	B.1Be in MODE 3.ANDB.2Be in MODE 4.	12 hours 36 hours
C. Required Action and associated Completion Time of Condition A not	NOTE LCO 3.0.3 is not applicable.	
met during movement of [recently] irradiated fuel assemblies in the [secondary] containment or during OPDRVs.	C.1 Place OPERABLE SGT subsystem in operation.	Immediately
	C.2.1 Suspend movement of [recently] irradiated fuel assemblies in [secondary] containment.	Immediately
	AND	

CONDITION		REQUIRED ACTION	COMPLETION TIME
	C.2.2	Initiate action to suspend OPDRVs.	Immediately
 D. Two SGT subsystems inoperable in MODE 1, 2, or 3. 	D.1	Enter LCO 3.0.3.	Immediately
E. Two SGT subsystems inoperable during movement of [recently] irradiated fuel assemblies in the [secondary] containment or during OPDRVs.	E.1	NOTE LCO 3.0.3 is not applicable. Suspend movement of [recently] irradiated fuel assemblies in [secondary] containment.	Immediately
	<u>AND</u> E.2	Initiate action to suspend OPDRVs.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.6.4.3.1	Operate each SGT subsystem for \geq [10] continuous hours [with heaters operating].	31 days
SR 3.6.4.3.2	Perform required SGT filter testing in accordance with the Ventilation Filter Testing Program (VFTP).	In accordance with the VFTP
SR 3.6.4.3.3	Verify each SGT subsystem actuates on an actual or simulated initiation signal.	[18] months

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.6.4.3.4	[Verify each SGT filter cooler bypass damper can be opened and the fan started.	[18] months]

3.7.1 Residual Heat Removal Service Water (RHRSW) System

LCO 3.7.1 Two RHRSW subsystems shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One RHRSW pump inoperable.	A.1	Restore RHRSW pump to OPERABLE status.	30 days
B. One RHRSW pump in each subsystem inoperable.	B.1	Restore one RHRSW pump to OPERABLE status.	7 days
C. One RHRSW subsystem inoperable for reasons other than Condition A.	C.1	NOTE Enter applicable Conditions and Required Actions of LCO 3.4.8, "Residual Heat Removal (RHR) Shutdown Cooling System - Hot Shutdown," for [RHR shutdown cooling] made inoperable by RHRSW System. Restore RHRSW subsystem to OPERABLE status.	7 days

CONDITION		REQUIRED ACTION	COMPLETION TIME
D. Both RHRSW subsystems inoperable for reasons other than Condition B.	D.1	NOTE Enter applicable Conditions and Required Actions of LCO 3.4.8 for [RHR shutdown cooling] made inoperable by RHRSW System. Restore one RHRSW subsystem to OPERABLE	[8] hours
		status.	
E. Required Action and associated Completion Time not met.	E.1 <u>AND</u>	Be in MODE 3.	12 hours
	E.2	Be in MODE 4.	36 hours

	SURVEILLANCE	FREQUENCY
SR 3.7.1.1	Verify each RHRSW manual, power operated, and automatic valve in the flow path, that is not locked, sealed, or otherwise secured in position, is in the correct position or can be aligned to the correct position.	31 days

3.7.2 [Plant Service Water (PSW)] System and [Ultimate Heat Sink (UHS)]

LCO 3.7.2 Two [PSW] subsystems and [UHS] shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One [PSW] pump inoperable.	A.1 Restore [PSW] pump to OPERABLE status.	30 days
B. One [PSW] pump in each subsystem inoperable.	B.1 Restore one [PSW] pump to OPERABLE status.	7 days
C. [One or more cooling towers with one cooling tower fan inoperable.	C.1 Restore cooling tower fan(s) to OPERABLE status.	7 days]
 REVIEWER'S NOTE The []°F is the maximum allowed UHS temperature value and is based on temperature limitations of the equipment that is relied upon for accident mitigation and safe shutdown of the unit. D. [Water temperature of the UHS > [90]°F and ≤ []°F. 	D.1 Verify water temperature of the UHS is ≤ [90]°F averaged over the previous 24 hour period.	Once per hour]

CONDITION	REQUIRED ACTION	COMPLETION TIME
E. One [PSW] subsystem inoperable for reasons other than Condition[s] A [and C].	E.1NOTES 1. Enter applicable Conditions and Required Actions of LCO 3.8.1, "AC Sources - Operating," for diesel generator made inoperable by [PSW].	
	2. Enter applicable Conditions and Required Actions of LCO 3.4.8, "Residual Heat Removal (RHR) Shutdown Cooling System - Hot Shutdown," for [RHR shutdown cooling] made inoperable by [PSW].	
	Restore the [PSW] subsystem to OPERABLE status.	72 hours

	CONDITION		REQUIRED ACTION	COMPLETION TIME
F.	Required Action and associated Completion Time of Condition A, B	F.1 <u>AND</u>	Be in MODE 3.	12 hours
	[or D] not met.	F.2	Be in MODE 4.	36 hours
	Both [PSW] subsystems inoperable for reasons other than Condition[s] B [and C].			
	[<u>OR</u>			
_	[UHS] inoperable for reasons other than Condition C [or D].]			

	SURVEILLANCE	FREQUENCY
SR 3.7.2.1	[Verify the water level of each [PSW] cooling tower basin is \geq [] ft.	24 hours]
SR 3.7.2.2	[Verify the water level [in each PSW pump well of the intake structure] is \geq [60.1] ft [mean sea level].	24 hours]
SR 3.7.2.3	[Verify the average water temperature of [UHS] is $\leq [$]°F.	24 hours]
SR 3.7.2.4	[Operate each [PSW] cooling tower fan for \geq [15] minutes.	31 days]

SURVEILLANCE REQUIREMENTS (continued)

	FREQUENCY	
SR 3.7.2.5	NOTENOTENOTENOTE	
	Verify each [PSW] subsystem manual, power operated, and automatic valve in the flow paths servicing safety related systems or components, that is not locked, sealed, or otherwise secured in position, is in the correct position.	31 days
SR 3.7.2.6	Verify each [PSW] subsystem actuates on an actual or simulated initiation signal.	[18] months

3.7.3 Diesel Generator (DG) [1B] Standby Service Water (SSW) System

LCO 3.7.3 The DG [1B] SSW System shall be OPERABLE.

APPLICABILITY: When DG [1B] is required to be OPERABLE.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. DG [1B] SSW System inoperable.	NOTE LCO 3.0.4 is not applicable.	
	A.1 Align cooling water to DG [1B] from a Unit [1] plant service water (PSW) subsystem.	8 hours
	AND	
	A.2 Verify cooling water is aligned to DG [1B] from a Unit [1] PSW subsystem.	Once per 31 days
	AND	
	A.3 Restore DG [1B] SSW System to OPERABLE status.	60 days
B. Required Action and associated Completion Time not met.	B.1 Declare DG [1B] inoperable.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.7.3.1	Verify each DG [1B] SSW System manual, power operated, and automatic valve in the flow path, that is not locked, sealed, or otherwise secured in position, is in the correct position.	31 days
SR 3.7.3.2	Verify the DG [1B] SSW System pump starts automatically when DG [1B] starts and energizes the respective bus.	[18] months

3.7.4	[Main Control Room Environmental Control (MCREC)] System
-------	--

LCO 3.7.4 Two [MCREC] subsystems shall be OPERABLE.

-----NOTE-----NOTE opened intermittently under administrative control.

APPLICABILITY: MODES 1, 2, and 3, During movement of [recently] irradiated fuel assemblies in the [secondary] containment, During operations with a potential for draining the reactor vessel (OPDRVs).

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One [MCREC] subsystem inoperable.	A.1	Restore [MCREC] subsystem to OPERABLE status.	7 days
B. Two [MCREC] subsystems inoperable due to inoperable control room boundary in MODE 1, 2, or 3.	B.1	Restore control room boundary to OPERABLE status.	24 hours
C. Required Action and associated Completion Time of Condition A or B not met in MODE 1, 2, or 3.	C.1 <u>AND</u> C.2	Be in MODE 3. Be in MODE 4.	12 hours 36 hours

	1		
CONDITION		REQUIRED ACTION	COMPLETION TIME
D. Required Action and associated Completion Time of Condition A not	NOTE LCO 3.0.3 is not applicable.		
met during movement of [recently] irradiated fuel assemblies in the [secondary] containment or during OPDRVs.	D.1	NOTE [Place in toxic gas protection mode if automatic transfer to toxic gas protection mode is inoperable.]	
		Place OPERABLE [MCREC] subsystem in [pressurization] mode.	Immediately
	<u>OR</u>		
	D.2.1	Suspend movement of [recently] irradiated fuel assemblies in the [secondary] containment.	Immediately
	AN	ID	
	D.2.2	Initiate action to suspend OPDRVs.	Immediately
E. Two [MCREC] subsystems inoperable in MODE 1, 2, or 3 for reasons other than Condition B.	E.1	Enter LCO 3.0.3.	Immediately

	CONDITION	REQUIRED ACTION		COMPLETION TIME
F. Two [MCREC] subsystems inoperable during movement of	NOTE LCO 3.0.3 is not applicable.			
	[recently] irradiated fuel assemblies in the [secondary] containment or during OPDRVs.	F.1	Suspend movement of [recently] irradiated fuel assemblies in the [secondary] containment.	Immediately
		<u>AND</u>		
		F.2	Initiate action to suspend OPDRVs.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.7.4.1	Operate each [MCREC] subsystem for [\geq 10 continuous hours with the heaters operating or (for systems without heaters) \geq 15 minutes].	31 days
SR 3.7.4.2	Perform required [MCREC] filter testing in accordance with the [Ventilation Filter Testing Program (VFTP)].	In accordance with the [VFTP]
SR 3.7.4.3	Verify each [MCREC] subsystem actuates on an actual or simulated initiation signal.	[18] months
SR 3.7.4.4	[Verify each [MCREC] subsystem can maintain a positive pressure of \geq [0.1] inches water gauge relative to the [turbine building] during the [pressurization] mode of operation at a flow rate of \leq [400] cfm.	[18] months on a STAGGERED TEST BASIS]

- 3.7.5 [Control Room Air Conditioning (AC)] System
- LCO 3.7.5 Two [control room AC] subsystems shall be OPERABLE.

 APPLICABILITY: MODES 1, 2, and 3, During movement of [recently] irradiated fuel assemblies in the [secondary] containment, During operations with a potential for draining the reactor vessel (OPDRVs).

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One [control room AC] subsystem inoperable.	A.1 Restore [control room AC] subsystem to OPERABLE status.	30 days
B. Required Action and associated Completion Time of Condition A not met in MODE 1, 2, or 3.	B.1 Be in MODE 3.ANDB.2 Be in MODE 4.	12 hours 36 hours
C. Required Action and associated Completion Time of Condition A not met during movement of [recently] irradiated fuel assemblies in the [secondary] containment or during OPDRVs.	NOTE LCO 3.0.3 is not applicable. C.1 Place OPERABLE [control room AC] subsystem in operation. <u>OR</u>	Immediately

CONDITION	REQUIRED ACTION		COMPLETION TIME
	C.2.1	Suspend movement of [recently] irradiated fuel assemblies in the [secondary] containment.	Immediately
	<u>AN</u>	ID	
	C.2.2	Initiate action to suspend OPDRVs.	Immediately
D. Two [control room AC] subsystems inoperable in MODE 1, 2, or 3.	D.1	Enter LCO 3.0.3.	Immediately
E. Two [control room AC] subsystems inoperable during movement of [recently] irradiated fuel assemblies in the [secondary] containment or during OPDRVs.	NOTENOTE-LCO 3.0.3 is not applicable.		
	E.1	Suspend movement of [recently] irradiated fuel assemblies in the [secondary] containment.	Immediately
	AND		
	E.2	Initiate actions to suspend OPDRVs.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.7.5.1	Verify each [control room AC] subsystem has the capability to remove the assumed heat load.	[18] months

3.7.6 Main Condenser Offgas

LCO 3.7.6 The gross gamma activity rate of the noble gases measured at [the main condenser evacuation system pretreatment monitor station] shall be \leq [240] mCi/second [after decay of 30 minutes].

APPLICABILITY: MODE 1, MODES 2 and 3 with any [main steam line not isolated and] steam jet air ejector (SJAE) in operation.

	REQUIRED ACTION	COMPLETION TIME
A.1	Restore gross gamma activity rate of the noble gases to within limit.	72 hours
B.1	[Isolate all main steam lines.	12 hours]
B.2	Isolate SJAE.	12 hours
OR		
B.3.1	Be in MODE 3.	12 hours
AN	ID	
B.3.2	Be in MODE 4.	36 hours
	A.1 B.1 <u>OR</u> B.2 <u>OR</u> B.3.1 <u>AN</u> B.3.2	REQUIRED ACTIONA.1Restore gross gamma activity rate of the noble gases to within limit.B.1[Isolate all main steam lines.ORIsolate SJAE.ORIsolate SJAE.ORB.3.1Be in MODE 3. ANDB.3.2Be in MODE 4.

	FREQUENCY	
SR 3.7.6.1	NOTE Not required to be performed until 31 days after any [main steam line not isolated and] SJAE in operation. Verify the gross gamma activity rate of the noble gases is ≤ [240] mCi/second [after decay of 30 minutes].	31 days <u>AND</u> Once within 4 hours after a \geq 50% increase in the nominal steady state fission gas release after factoring out
		increases due to changes in THERMAL POWER level

3.7.7 The Main Turbine Bypass System

LCO 3.7.7 The Main Turbine Bypass System shall be OPERABLE.

The following limits are made applicable:

- [a. LCO 3.2.1, "AVERAGE PLANAR LINEAR HEAT GENERATION RATE (APLHGR)," limits for an inoperable Main Turbine Bypass System, as specified in the [COLR]; and]
- [b. LCO 3.2.2, "MINIMUM CRITICAL POWER RATIO (MCPR)," limits for an inoperable Main Turbine Bypass System, as specified in the [COLR].]

APPLICABILITY: THERMAL POWER \geq 25% RTP.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
 A. [Requirements of the LCO not met or Main Turbine Bypass System inoperable]. 	A.1 [Satisfy the requirements of the LCO or restore Main Turbine Bypass System to OPERABLE status].	2 hours
B. Required Action and associated Completion Time not met.	B.1 Reduce THERMAL POWER to < 25% RTP.	4 hours

	SURVEILLANCE	FREQUENCY
SR 3.7.7.1	Verify one complete cycle of each main turbine bypass valve.	31 days

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.7.7.2	Perform a system functional test.	[18] months
SR 3.7.7.3	Verify the TURBINE BYPASS SYSTEM RESPONSE TIME is within limits.	[18] months

- 3.7.8 Spent Fuel Storage Pool Water Level
- LCO 3.7.8 The spent fuel storage pool water level shall be \geq [23] ft over the top of irradiated fuel assemblies seated in the spent fuel storage pool racks.
- APPLICABILITY: During movement of irradiated fuel assemblies in the spent fuel storage pool.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Spent fuel storage pool water level not within limit.	A.1NOTE LCO 3.0.3 is not applicable. 	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.7.8.1	Verify the spent fuel storage pool water level is \geq [23] ft over the top of irradiated fuel assemblies seated in the spent fuel storage pool racks.	7 days

3.8 ELECTRICAL POWER SYSTEMS

3.8.1 AC Sources - Operating

- LCO 3.8.1 The following AC electrical power sources shall be OPERABLE:
 - a. Two qualified circuits between the offsite transmission network and the onsite Class 1E AC Electrical Power Distribution System,
 - b. [Three] diesel generators (DGs), and
 - [c. Three automatic sequencers.]

APPLICABILITY: MODES 1, 2, and 3.

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One [required] offsite circuit inoperable.	A.1	Perform SR 3.8.1.1 for OPERABLE [required] offsite circuit.	1 hour <u>AND</u> Once per 8 hours thereafter
	<u>AND</u> A.2 <u>AND</u>	Declare required feature(s) with no offsite power available inoperable when the redundant required feature(s) are inoperable.	24 hours from discovery of no offsite power to one division concurrent with inoperability of redundant required feature(s)

· · · · · · · · · · · · · · · · · · ·			
CONDITION		REQUIRED ACTION	COMPLETION TIME
	A.3 Restore [required] offsite	Restore [required] offsite	72 hours
		status.	AND
			6 days from discovery of failure to meet LCO
B. One [required] DG	B.1	Perform SR 3.8.1.1 for	1 hour
inoperable.		OPERABLE [required] offsite circuit(s).	AND
			Once per 8 hours thereafter
	<u>AND</u>		
	B.2	Declare required feature(s), supported by the inoperable DG, inoperable when the redundant required feature(s) are inoperable.	4 hours from discovery of Condition B concurrent with inoperability of redundant required feature(s)
	<u>AND</u>		
	B.3.1	Determine OPERABLE DG(s) are not inoperable due to common cause failure.	[24] hours
	OF	<u>R</u>	
	B.3.2	Perform SR 3.8.1.2 for OPERABLE DG(s).	[24] hours
	<u>AND</u>		
CONDITION	REQUIRED ACTION	COMPLETION TIME	
--	---	---	
	B.4 Restore [required] DG to OPERABLE status.	72 hours AND 6 days from discovery of failure to meet LCO	
C. Two [required] offsite circuits inoperable.	C.1 Declare required feature(s) inoperable when the redundant required feature(s) are inoperable.	12 hours from discovery of Condition C concurrent with inoperability of redundant required feature(s)	
	C.2 Restore one [required] offsite circuit to OPERABLE status.	24 hours	
 D. One [required] offsite circuit inoperable. <u>AND</u> One [required] DG inoperable. 	 NOTE Enter applicable Conditions and Required Actions of LCO 3.8.9, "Distribution Systems - Operating," when Condition D is entered with no AC power source to any division. D.1 Restore [required] offsite circuit to OPERABLE status. <u>OR</u> D.2 Restore [required] DG to OPERABLE status. 	12 hours 12 hours	
E. Two [or three] [required] DGs inoperable.	E.1 Restore one [required] DG to OPERABLE status.	2 hours	

CONDITION	REQUIRED ACTION	COMPLETION TIME
F. [One [required] [automatic load sequencer] inoperable.	REVIEWER'S NOTE This Condition may be deleted if the unit design is such that any sequencer failure mode will only affect the ability of the associated DG to power its respective safety loads following a loss of offsite power independent of, or coincident with, a Design Basis Event.	
	F.1 Restore [required] [automatic load sequencer] to OPERABLE status.	[12] hours]
G. Required Action and Associated Completion Time of Condition A, B, C, D, E, or [F] not met.	G.1 Be in MODE 3.ANDG.2 Be in MODE 4.	12 hours 36 hours
H. Three or more [required] AC sources inoperable [for reasons other than Condition E].	H.1 Enter LCO 3.0.3.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.8.1.1	Verify correct breaker alignment and indicated power availability for each [required] offsite circuit.	7 days

	FREQUENCY	
SR 3.8.1.2	 NOTESNOTES	
	Verify each DG starts from standby conditions and achieves steady state voltage \geq [3740] V and \leq [4580] V and frequency \geq [58.8] Hz and \leq [61.2] Hz.	31 days
SR 3.8.1.3	 NOTES	31 days
SR 3.8.1.4	Verify each day tank [and engine mounted tank] contain[s] \ge [900] gal of fuel oil.	31 days

	SURVEILLANCE	FREQUENCY
SR 3.8.1.5	Check for and remove accumulated water from each day tank [and engine mounted tank].	[31] days
SR 3.8.1.6	Verify the fuel oil transfer system operates to [automatically] transfer fuel oil from storage tank[s] to the day tank [and engine mounted tank].	[92] days
SR 3.8.1.7	NOTENOTE All DG starts may be preceded by an engine prelube period.	
	Verify each DG starts from standby condition and achieves:	184 days
	 In ≤ [12] seconds, voltage ≥ [3740] V and frequency ≥ [58.8] Hz and 	
	b. Steady state voltage \geq [3740] V and \leq [4580] V and frequency \geq [58.8] Hz and \leq [61.2] Hz.	
SR 3.8.1.8	[This Surveillance shall not normally be performed in MODE 1 or 2. However, this Surveillance may be performed to reestablish OPERABILITY provided an assessment determines the safety of the plant is maintained or enhanced. Credit may be taken for unplanned events that satisfy this SR.]	
	[Verify [automatic [and] manual] transfer of [unit power supply] from the [normal offsite circuit to the alternate] offsite circuit.	[18] months]

	SURVEILLANCE			
SR 3.8.1.9	 I. This Surveillance shall not normally be performed in MODE 1 or 2. However, this Surveillance may be performed to reestablish OPERABILITY provided an assessment determines the safety of the plant is maintained or enhanced. Credit may be taken for unplanned events that satisfy this SR. If performed with DC synchronized with effected 			
	 In performed with DG synchronized with onsite power, it shall be performed at a power factor ≤ [0.9]. However, if grid conditions do not permit, the power factor limit is not required to be met. Under this condition the power factor shall be maintained as close to the limit as practicable.] 			
	Verify each DG rejects a load greater than or equal to its associated single largest post-accident load, and:	[18] months		
	 a. Following load rejection, the frequency is ≤ [65.5] Hz, 			
	b. Within [3] seconds following load rejection, the voltage is \geq [3740] V and \leq [4580] V, and			
	[c. Within [6] seconds following load rejection, the frequency is \geq [58.8] Hz and \leq [61.2] Hz.]			

	FREQUENCY	
SR 3.8.1.10	 This Surveillance shall not normally be performed in MODE 1 or 2. However, this Surveillance may be performed to reestablish OPERABILITY provided an assessment determines the safety of the plant is maintained or enhanced. Credit may be taken for unplanned events that satisfy this SR. 	
	 If performed with DG synchronized with offsite power, it shall be performed at a power factor ≤ [0.9]. However, if grid conditions do not permit, the power factor limit is not required to be met. Under this condition the power factor shall be maintained as close to the limit as practicable.] 	
	Verify each DG does not trip and voltage is maintained \leq [4800] V during and following a load rejection of \geq [1710] kW and \leq [2000] kW.	[18] months

SURVEILLANCE				FREQUENCY
SR 3.8.1.11	 1. 2.	All D prelu This perfo porti to re asse is ma take	Surveillance shall not normally be borned in MODE 1, 2, or 3. However, ons of the Surveillance may be performed establish OPERABILITY provided an essment determines the safety of the plant aintained or enhanced. Credit may be n for unplanned events that satisfy this SR.	
	Ve sig	rify on Inal:	an actual or simulated loss of offsite power	[18] months
	a.	De-e	energization of emergency buses,	
	b.	b. Load shedding from emergency buses, and		
	C.	DG a	auto-starts from standby condition and:	
		1.	Energizes permanently connected loads in \leq [12] seconds,	
		2.	Energizes auto-connected shutdown loads through [automatic load sequencer],	
		3.	Maintains steady state voltage \geq [3740] V and \leq [4580] V,	
		4.	Maintains steady state frequency \geq [58.8] Hz and \leq [61.2] Hz, and	
		5.	Supplies permanently connected and auto-connected shutdown loads for \geq [5] minutes.	

		SURVEILLANCE	FREQUENCY
SR 3.8.1.12	 1. 2. Ve Cc au a. b. c. d. e.	NOTES- [All DG starts may be preceded by an engine prelube period. This Surveillance shall not normally be performed in MODE 1 or 2. However, portions of the Surveillance may be performed to reestablish OPERABILITY provided an assessment determines the safety of the plant is maintained or enhanced. Credit may be taken for unplanned events that satisfy this SR. Trify on an actual or simulated Emergency Core poling System (ECCS) initiation signal each DG to-starts from standby condition and: In \leq [12] seconds after auto-start and during tests, achieves voltage \geq [3740] V and frequency \geq [58.8] Hz, Achieves steady state voltage \geq [3740] V and \leq [4580] V and frequency \geq [58.8] Hz, Operates for \geq [5] minutes, Permanently connected loads remain energized from the offsite power system, and Emergency loads are energized [or auto-connected through the automatic load	[18] months]

Т

	FREQUENCY	
SR 3.8.1.13	[This Surveillance shall not normally be performed in MODE 1, 2, or 3. However, this Surveillance may be performed to reestablish OPERABILITY provided an assessment determines the safety of the plant is maintained or enhanced. Credit may be taken for unplanned events that satisfy this SR.]	
	Verify each DG's automatic trips are bypassed on [actual or simulated loss of voltage signal on the emergency bus concurrent with an actual or simulated ECCS initiation signal] except:	[18] months
	a. Engine overspeed,	
	b. Generator differential current,	
	[c. Low lube oil pressure,	
	d. High crankcase pressure, and	
	e. Start failure relay.]	

	FREQUENCY		
SR 3.8.1.14	 1.	NOTESNOTES Momentary transients outside the load and	
		power factor ranges do not invalidate this test.	
	2.	This Surveillance shall not normally be performed in MODE 1 or 2. However, this Surveillance may be performed to reestablish OPERABILITY provided an assessment determines the safety of the plant is maintained or enhanced. Credit may be taken for unplanned events that satisfy this SR.	
	3.	If performed with DG synchronized with offsite power, it shall be performed at a power factor \leq [0.9]. However, if grid conditions do not permit, the power factor limit is not required to be met. Under this condition the power factor shall be maintained as close to the limit as practicable.	
	Ve	rify each DG operates for \ge 24 hours:	[18] months
	a.	For \ge [2] hours loaded \ge [3100] kW and \le [3400] kW and	
	b.	For the remaining hours of the test loaded \ge [2850] kW and \le [3150] kW.	

	SURVEILLANCE	FREQUENCY
SR 3.8.1.15	 This Surveillance shall be performed within 5 minutes of shutting down the DG after the DG has operated ≥ [2] hours loaded ≥ [1710] kW and ≤ [2000] kW. Momentary transients outside of load range do not invalidate this test. 	
	 All DG starts may be preceded by an engine prelube period. 	
	Verify each DG starts and achieves:	[18] months
	a. In \leq [12] seconds, voltage \geq [3740] V and frequency \geq [58.8] Hz and	
	b. Steady state voltage \ge [3740] V and \le [4580] V and frequency \ge [58.8] Hz and \le [61.2] Hz.	
SR 3.8.1.16	This Surveillance shall not normally be performed in MODE 1, 2, or 3. However, this Surveillance may be performed to reestablish OPERABILITY provided an assessment determines the safety of the plant is maintained or enhanced. Credit may be taken for unplanned events that satisfy this SR.	
	Verify each DG:	[18] months
	 Synchronizes with offsite power source while loaded with emergency loads upon a simulated restoration of offsite power, 	
	b. Transfers loads to offsite power source, and	
	c. Returns to ready-to-load operation.	

	SURVEILLANCE	FREQUENCY
SR 3.8.1.17	 NOTE	[18] months]
SR 3.8.1.18	NOTE [This Surveillance shall not normally be performed in MODE 1, 2, or 3. However, this Surveillance may be performed to reestablish OPERABILITY provided an assessment determines the safety of the plant is maintained or enhanced. Credit may be taken for unplanned events that satisfy this SR.] [Verify interval between each sequenced load block is within ± [10% of design interval] [for each load sequencer timer].	[18] months]

	FREQUENCY			
SR 3.8.1.19	 1. 2.	All D prelu This perfo porti to re asse is ma take	OG starts may be preceded by an engine ube period. Surveillance shall not normally be prmed in MODE 1, 2, or 3. However, ons of the Surveillance may be performed establish OPERABILITY provided an essment determines the safety of the plant aintained or enhanced. Credit may be n for unplanned events that satisfy this SR.	
	Ve po sin	erify, oi wer sig nulate	n an actual or simulated loss of offsite gnal in conjunction with an actual or d ECCS initiation signal:	[18] months
	a.	De-e	energization of emergency buses,	
	b.	Load	shedding from emergency buses, and	
	C.	DG a	auto-starts from standby condition and:	
		1.	Energizes permanently connected loads in \leq [12] seconds,	
		2.	Energizes auto-connected emergency loads through [load sequencer],	
		3.	Achieves steady state voltage \ge [3740] V and \le [4580] V,	
		4.	Achieves steady state frequency \geq [58.8] Hz and \leq [61.2] Hz, and	
		5.	Supplies permanently connected and auto-connected emergency loads for \geq [5] minutes.	

	FREQUENCY	
SR 3.8.1.20	3.8.1.20NOTENOTE All DG starts may be preceded by an engine prelube period.	
	Verify, when started simultaneously from standby condition, [each] [2A and 2C] DG achieves:	10 years
	 a. In ≤ [12] seconds, voltage ≥ [3740] V and frequency ≥ [58.8] Hz and 	
	b. Steady state voltage \ge [3740] V and \le [4580] V and frequency \ge [58.8] Hz and \le [61.2] Hz.	

3.8.2 AC Sources - Shutdown

LCO 3.8.2 The following AC electrical power sources shall be OPERABLE:

- a. One qualified circuit between the offsite transmission network and the onsite Class 1E AC electrical power distribution subsystem(s) required by LCO 3.8.10, "Distribution Systems Shutdown" and
- One diesel generator (DG) capable of supplying one division of the onsite Class 1E AC electrical power distribution subsystem(s) required by LCO 3.8.10.

APPLICABILITY: MODES 4 and 5, During movement of [recently] irradiated fuel assemblies in the [secondary] containment.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One required offsite circuit inoperable.	 NOTE Enter applicable Condition and Required Actions of LCO 3.8.10, with one required division de- energized as a result of Condition A. A.1 Declare affected required feature(s), with no offsite power available, inoperable. 	Immediately

CONDITION		REQUIRED ACTION	COMPLETION TIME
	A.2.1	Suspend CORE ALTERATIONS.	Immediately
	<u>AN</u>	ID	
	A.2.2	Suspend movement of [recently] irradiated fuel assemblies in the [secondary] containment.	Immediately
	<u>AN</u>	<u>ID</u>	
	A.2.3	Initiate action to suspend operations with a potential for draining the reactor vessel (OPDRVs).	Immediately
	AN	ID	
	A.2.4	Initiate action to restore required offsite power circuit to OPERABLE status.	Immediately
B. One required DG inoperable.	B.1	Suspend CORE ALTERATIONS.	Immediately
	<u>AND</u>		
	B.2	Suspend movement of [recently] irradiated fuel assemblies in [secondary] containment.	Immediately
	<u>AND</u>		
	В.3	Initiate action to suspend OPDRVs.	Immediately
	<u>AND</u>		

CONDITION		REQUIRED ACTION	COMPLETION TIME
	B.4	Initiate action to restore required DG to OPERABLE status.	Immediately

	FREQUENCY	
SR 3.8.2.1	 NOTESNOTES	
	For AC sources required to be OPERABLE the SRs of Specification 3.8.1, except SR 3.8.1.8, SR 3.8.1.17, and SR 3.8.1.20, are applicable.	In accordance with applicable SRs

3.8.3 Diesel Fuel Oil, Lube Oil, and Starting Air

LCO 3.8.3 The stored diesel fuel oil, lube oil, and starting air subsystem shall be within limits for each required diesel generator (DG).

APPLICABILITY: When associated DG is required to be OPERABLE.

ACTIONS

CONDITION	REQUIRED ACTION		COMPLETION TIME	
 A. One or more DGs with fuel oil level < [33,000] gal and > [28,285] gal in storage tank. 	A.1	Restore fuel oil level to within limits.	48 hours	
 B. One or more DGs with lube oil inventory < [500] gal and > [425] gal. 	B.1	Restore lube oil inventory to within limits.	48 hours	
C. One or more DGs with stored fuel oil total particulates not within limit.	C.1	Restore fuel oil total particulates to within limit.	7 days	
D. One or more DGs with new fuel oil properties not within limits.	D.1	Restore stored fuel oil properties to within limits.	30 days	

ACTIONS	(continued)
---------	-------------

CONDITION		REQUIRED ACTION		COMPLETION TIME
E.	One or more DGs with starting air receiver pressure < [225] psig and \geq [125] psig.	E.1	Restore starting air receiver pressure to \geq [225] psig.	48 hours
F.	Required Action and associated Completion Time not met.	F.1	Declare associated DG inoperable.	Immediately
	<u>OR</u>			
	One or more DGs with diesel fuel oil, lube oil, or starting air subsystem not within limits for reasons other than Condition A, B, C, D, or E.			

	SURVEILLANCE	FREQUENCY
SR 3.8.3.1	Verify each fuel oil storage tank contains \geq [33,000] gal of fuel.	31 days
SR 3.8.3.2	Verify lube oil inventory is \geq [500] gal.	31 days
SR 3.8.3.3	Verify fuel oil properties of new and stored fuel oil are tested in accordance with, and maintained within the limits of, the Diesel Fuel Oil Testing Program.	In accordance with the Diesel Fuel Oil Testing Program
SR 3.8.3.4	Verify each DG air start receiver pressure is \geq [225] psig.	31 days

	SURVEILLANCE	FREQUENCY
SR 3.8.3.5	Check for and remove accumulated water from each fuel oil storage tank.	[31] days

3.8.4 DC Sources - Operating

LCO 3.8.4 The [Division 1 and Division 2 station service, and DG 1B, 2A, and 2C] DC electrical power subsystems shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One [or two] battery charger[s on one division] inoperable.	A.1	Restore battery terminal voltage to greater than or equal to the minimum established float voltage.	2 hours
	<u>AND</u>		
	A.2	Verify battery float current ≤ [2] amps.	Once per [12] hours
	<u>AND</u>		
	A.3	Restore battery charger[s] to OPERABLE status.	7 days
[B. One [or two] batter[y][ies on one division] inoperable.	B.1	Restore batter[y][ies] to OPERABLE status.	[2] hours]
C. One DC electrical power subsystem inoperable for reasons other than Condition A [or B].	C.1	Restore DC electrical power subsystem to OPERABLE status.	[2] hours

CONDITION		REQUIRED ACTION	COMPLETION TIME
 Required Action and Associated Completion Time of Condition A[, B, or C] not met for station service DC subsystem. 	D.1 <u>AND</u> D.2	Be in MODE 3. Be in MODE 4.	12 hours 36 hours
E. [Required Action and associated Completion Time of Condition A[, B, or C] not met for DG DC subsystem.	E.1	Declare associated DG inoperable.	Immediately]

	SURVEILLANCE	FREQUENCY
SR 3.8.4.1	Verify battery terminal voltage is greater than or equal to the minimum established float voltage.	7 days
SR 3.8.4.2	Verify each required battery charger supplies \geq [400 amps for station service subsystems, and \geq 100 amps for DG subsystems] at greater than or equal to the minimum established float voltage for \geq [4] hours.	[18 months]
	OR	
	Verify each battery charger can recharge the battery to the fully charged state within [24] hours while supplying the largest combined demands of the various continuous steady state loads, after a battery discharge to the bounding design basis event discharge state.	

	FREQUENCY	
SR 3.8.4.3	 The modified performance discharge test in SR 3.8.6.6 may be performed in lieu of SR 3.8.4.3. This Surveillance shall not normally be performed in MODE 1, 2, or 3. However, portions of the Surveillance may be performed to reestablish OPERABILITY provided an assessment determines the safety of the plant is maintained or enhanced. Credit may be taken for unplanned events that satisfy this SR. 	
	Verify battery capacity is adequate to supply, and maintain in OPERABLE status, the required emergency loads for the design duty cycle when subjected to a battery service test.	[18] months

3.8.5 DC Sources - Shutdown

LCO 3.8.5 [DC electrical power subsystems shall be OPERABLE to support the DC electrical power distribution subsystem(s) required by LCO 3.8.10, "Distribution Systems - Shutdown."]

[One DC electrical power subsystem shall be OPERABLE.]

-----NOTE-----

APPLICABILITY: MODES 4 and 5, During movement of [recently] irradiated fuel assemblies in the [secondary] containment.

ACTIONS

LCO 3.0.3 is not applicable.

CONDITION	REQUIRED ACTION	COMPLETION TIME
 [A. One [or two] battery charger[s on one division] inoperable. <u>AND</u> The redundant division battery and charger[s] OPERABLE. 	 A.1 Restore battery terminal voltage to greater than or equal to the minimum established float voltage. <u>AND</u> 	2 hours

	CONDITION		REQUIRED ACTION	COMPLETION TIME
		A.2	Verify battery float current ≤ [2] amps.	Once per [12] hours
		<u>AND</u>		
		A.3	Restore battery charger[s] to OPERABLE status.	7 days]
В.	One [or more] required DC electrical power subsystem[s] inoperable	B.1	Declare affected required feature(s) inoperable.	Immediately
	[for reasons other than Condition A	<u>OR</u>		
	<u>OR</u>	B.2.1	Suspend CORE ALTERATIONS.	Immediately
	Required Action and associated Completion Time of Condition A not met.]	AND		
		B.2.2	Suspend movement of [recently] irradiated fuel assemblies in the [secondary] containment.	Immediately
		AND		
		B.2.3	Initiate action to suspend operations with a potential for draining the reactor vessel.	Immediately
		AN	D	
		B.2.4	Initiate action to restore required DC electrical power subsystems to OPERABLE status.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.8.5.1	NOTE The following SRs are not required to be performed: SR 3.8.4.2 and SR 3.8.4.3. For DC sources required to be OPERABLE, the following SRs are applicable: SR 3.8.4.1 SR 3.8.4.2 SR 3.8.4.2 SR 3.8.4.3	In accordance with applicable SRs

3.8.6 Battery Parameters

LCO 3.8.6 Battery parameters for the [station service and DG] batteries shall be within limits.

APPLICABILITY: When associated DC electrical power subsystems are required to be OPERABLE.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
 A. One [or two] batter[y][ies on one division] with one or more battery cells 	A.1 <u>AND</u>	Perform SR 3.8.4.1.	2 hours
float voltage < [2.07] V.	A.2	Perform SR 3.8.6.1.	2 hours
	<u>AND</u>		
	A.3	Restore affected cell voltage \geq [2.07] V.	24 hours
B. One [or two] batter[y][ies	B.1	Perform SR 3.8.4.1.	2 hours
on one division] with float current > [2] amps.	AND		
	B.2	Restore battery float current to \leq [2] amps.	[12] hours

ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
NOTE Required Action C.2 shall be completed if electrolyte level was below the top of plates.	NOTE Required Actions C.1 and C.2 are only applicable if electrolyte level was below the top of plates.	
C. One [or two] batter[y][ies on one division] with one or more cells electrolyte level less than minimum	C.1 Restore electrolyte level to above top of plates.	8 hours
established design limits.	C.2 Verify no evidence of leakage.	12 hours
	AND	
	C.3 Restore electrolyte level to greater than or equal to minimum established design limits.	31 days
D. One [or two] batter[y][ies on one division] with pilot cell electrolyte temperature less than minimum established design limits.	D.1 Restore battery pilot cell temperature to greater than or equal to minimum established design limits.	12 hours
E. One or more batteries in redundant divisions with battery parameters not within limits.	E.1 Restore battery parameters for batteries in one division to within limits.	2 hours

ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
 F. Required Action and associated Completion Time of Condition A, B, C, D, or E not met. OR 	F.1 Declare associated battery inoperable.	Immediately
One [or two] batter[y][ies on one division] with one or more battery cells float voltage < [2.07] V and float current > [2] amps.		

	SURVEILLANCE	FREQUENCY
SR 3.8.6.1	NOTENOTENOTENOTENOTENOTENOTENOTENOTENOTENOTE Not required to be met when battery terminal voltage is less than the minimum established float voltage of SR 3.8.4.1.	
	Verify each battery float current is \leq [2] amps.	7 days
SR 3.8.6.2	Verify each battery pilot cell voltage is \geq [2.07] V.	31 days
SR 3.8.6.3	Verify each battery connected cell electrolyte level is greater than or equal to minimum established design limits.	31 days
SR 3.8.6.4	Verify each battery pilot cell temperature is greater than or equal to minimum established design limits.	31 days

	SURVEILLANCE	FREQUENCY
SR 3.8.6.5	Verify each battery connected cell voltage is \geq [2.07] V.	92 days
SR 3.8.6.6	NOTE This Surveillance shall not normally be performed in MODE 1, 2, or 3. However, portion of the Surveillance may be performed to reestablish OPERABILITY provided an assessment determines the safety of the plant is maintained or enhanced. Credit may be taken for unplanned events that satisfy this SR. 	60 months <u>AND</u> 12 months when battery shows degradation, or has reached [85]% of the expected life with capacity < 100% of manufacturer's rating <u>AND</u> 24 months when battery has reached [85]% of the expected life with capacity ≥ 100% of manufacturer's rating

3.8.7 Inverters - Operating

LCO 3.8.7 The [Division 1] and [Division 2] inverters shall be OPERABLE.

- The associated AC vital bus[es] [is/are] energized from [its/their] [Class 1E constant voltage transformers] [inverter using internal AC source] and
- All other AC vital buses are energized from their associated OPERABLE inverters.]

APPLICABILITY: MODES 1, 2, and 3.

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One [required] inverter inoperable.	A.1	NOTE Enter applicable Conditions and Required Actions of LCO 3.8.9, "Distribution Systems - Operating" with any AC vital bus de- energized. Restore inverter to OPERABLE status.	24 hours
B. Required Action and associated Completion Time not met.	B.1 <u>AND</u> B.2	Be in MODE 3. Be in MODE 4.	12 hours 36 hours

	SURVEILLANCE	FREQUENCY
SR 3.8.7.1	Verify correct inverter voltage, [frequency,] and alignment to required AC vital buses.	7 days

3.8.8 Inverters - Shutdown

LCO 3.8.8 [Inverter(s) shall be OPERABLE to support the onsite Class 1E AC vital bus electrical power distribution subsystem(s) required by LCO 3.8.10, "Distribution Systems - Shutdown."]

[One] inverter[s] shall be OPERABLE.]

-

APPLICABILITY: MODES 4 and 5, During movement of [recently] irradiated fuel assemblies in the [secondary] containment.

ACTIONS

LCO 3.0.3 is not applicable.

	CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One inve	[or more] [required] rter[s] inoperable.	A.1	Declare affected required feature(s) inoperable.	Immediately
		<u>OR</u>		
		A.2.1	Suspend CORE ALTERATIONS.	Immediately
		<u>AN</u>	D	

ACTIONS (continued)			
CONDITION	REQUIRED ACTION		COMPLETION TIME
	A.2.2	Suspend handling of [recently] irradiated fuel assemblies in the [secondary] containment.	Immediately
	AND		
	A.2.3	Initiate action to suspend operations with a potential for draining the reactor vessel.	Immediately
	AND		
	A.2.4	Initiate action to restore [required] inverters to OPERABLE status.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.8.8.1	Verify correct inverter voltage, [frequency,] and alignments to [required] AC vital buses.	7 days

- 3.8.9 Distribution Systems Operating
- LCO 3.8.9 [Division 1] and [Division 2] AC, DC, [and AC vital bus] electrical power distribution subsystems shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more AC electrical power distribution subsystems inoperable.	NOTE Enter applicable Conditions and Required Actions of LCO 3.8.4, "DC Sources - Operating," for DC divisions made inoperable by inoperable power distribution subsystems.	
	A.1 Restore AC electrical power distribution subsystem(s) to OPERABLE status.	8 hours <u>AND</u> 16 hours from discovery of failure to meet LCO
B. [One or more AC vital buses inoperable.	B.1 Restore AC vital bus distribution subsystem(s) to OPERABLE status.	2 hours <u>AND</u> 16 hours from discovery of failure to meet LCO]

CONDITION	REQUIRED ACTION	COMPLETION TIME
C. One or more [station service] DC electrical power distribution subsystems inoperable.	C.1 Restore DC electrical power distribution subsystem(s) to OPERABLE status.	2 hours <u>AND</u> 16 hours from discovery of failure to meet LCO
 Required Action and associated Completion Time of Condition A, B, or C not met. 	D.1 Be in MODE 3. AND D.2 Be in MODE 4.	12 hours 36 hours
E. [One or more DG DC electrical power distribution subsystems inoperable.	E.1 Declare associated DG(s) inoperable.	Immediately]
F. Two or more electrical power distribution subsystems inoperable that result in a loss of function.	F.1 Enter LCO 3.0.3.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.8.9.1	Verify correct breaker alignments and voltage to [required] AC, DC, [and AC vital bus] electrical power distribution subsystems.	7 days
3.8 ELECTRICAL POWER SYSTEMS

3.8.10 Distribution Systems - Shutdown

LCO 3.8.10 The necessary portions of the AC, DC, [and AC vital bus] electrical power distribution subsystems shall be OPERABLE to support equipment required to be OPERABLE.

APPLICABILITY: MODES 4 and 5, During movement of [recently] irradiated fuel assemblies in the [secondary] containment.

ACTIONS

CONDITION	REQUIRED ACTION		COMPLETION TIME
A. One or more required AC, DC, [or AC vital bus] electrical power distribution subsystems inoperable.	A.1 <u>OR</u>	Declare associated supported required feature(s) inoperable.	Immediately
	A.2.1	Suspend CORE ALTERATIONS.	Immediately
	AN	D	
	A.2.2	Suspend handling of [recently] irradiated fuel assemblies in the [secondary] containment.	Immediately
	AN		

ACTIONS (contin	nned)

CONDITION		REQUIRED ACTION	COMPLETION TIME
	A.2.3	Initiate action to suspend operations with a potential for draining the reactor vessel.	Immediately
	AN	D	
	A.2.4	Initiate actions to restore required AC, DC, [and AC vital bus] electrical power distribution subsystems to OPERABLE status.	Immediately
	AN	D	
	A.2.5	Declare associated required shutdown cooling subsystem(s) inoperable and not in operation.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.8.10.1	Verify correct breaker alignments and voltage to required AC, DC, [and AC vital bus] electrical power distribution subsystems.	7 days

3.9.1 Refueling Equipment Interlocks

LOO 0.0.1	

APPLICABILITY: During in-vessel fuel movement with equipment associated with the interlocks.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or more required refueling equipment interlocks inoperable.	A.1	Suspend in-vessel fuel movement with equipment associated with the inoperable interlock(s).	Immediately
	<u>OR</u>		
	A.2.1	Insert a control rod withdrawal block.	Immediately
		AND	
	A.2.2	Verify all control rods are fully inserted.	Immediately

	FREQUENCY	
SR 3.9.1.1	Perform CHANNEL FUNCTIONAL TEST on each of the following required refueling equipment interlock inputs:	7 days
	a. All-rods-in,	
	b. Refuel platform position,	
	c. Refuel platform [fuel grapple], fuel loaded,	
	[d. Refuel platform fuel grapple fully retracted position,]	
	[e. Refuel platform frame mounted hoist, fuel loaded,]	
	[f. Refuel platform monorail mounted hoist, fuel loaded,] and	
	[g. Service platform hoist, fuel loaded.]	

- 3.9.2 Refuel Position One-Rod-Out Interlock
- LCO 3.9.2 The refuel position one-rod-out interlock shall be OPERABLE.
- APPLICABILITY: MODE 5 with the reactor mode switch in the refuel position and any control rod withdrawn.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. Refuel position one-rod- out interlock inoperable.	A.1	Suspend control rod withdrawal.	Immediately
	<u>AND</u>		
	A.2	Initiate action to fully insert all insertable control rods in core cells containing one or more fuel assemblies.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.9.2.1	Verify reactor mode switch locked in Refuel position.	12 hours
SR 3.9.2.2	NOTENOTE Not required to be performed until 1 hour after any control rod is withdrawn.	
	Perform CHANNEL FUNCTIONAL TEST.	7 days

3.9.3 Control Rod Position

LCO 3.9.3 All control rods shall be fully inserted.

APPLICABILITY: When loading fuel assemblies into the core.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more control rods not fully inserted.	A.1 Suspend loading fuel assemblies into the core.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.9.3.1	Verify all control rods are fully inserted.	12 hours

- 3.9.4 Control Rod Position Indication
- LCO 3.9.4 The control rod "full-in" position indication channel for each control rod shall be OPERABLE.

APPLICABILITY: MODE 5.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or more required control rod position indication channels	A.1.1	Suspend in vessel fuel movement.	Immediately
inoperable.	<u>AN</u>	<u>ID</u>	
	A.1.2	Suspend control rod withdrawal.	Immediately
	<u>AN</u>	<u>ID</u>	
	A.1.3	Initiate action to fully insert all insertable control rods in core cells containing one or more fuel assemblies.	Immediately
	<u>OR</u>		
	A.2.1	Initiate action to fully insert the control rod associated with the inoperable position indicator.	Immediately
	<u>AN</u>	ID	

ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
	A.2.2 Initiate action to disarm the control rod drive associated with the fully inserted control rod.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.9.4.1	Verify the required channel has no "full-in" indication on each control rod that is not "full-in."	Each time the control rod is withdrawn from the "full-in" position

3.9.5 Control Rod OPERABILITY - Refueling

LCO 3.9.5 Each withdrawn control rod shall be OPERABLE.

APPLICABILITY: MODE 5.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or more withdrawn control rods inoperable.	A.1	Initiate action to fully insert inoperable withdrawn control rods.	Immediately

	FREQUENCY	
SR 3.9.5.1	NOTENOTENOTENOTENOTENOTENOTENOTENOTENOTENOTE- Not required to be performed until 7 days after the control rod is withdrawn.	
	Insert each withdrawn control rod at least one notch.	7 days
SR 3.9.5.2	Verify each withdrawn control rod scram accumulator pressure is \geq [940] psig.	7 days

- 3.9.6 [Reactor Pressure Vessel (RPV)] Water Level [Irradiated Fuel]
- LCO 3.9.6 [RPV] water level shall be \geq [23] ft above the top of the [RPV flange].

APPLICABILITY: During movement of irradiated fuel assemblies within the [RPV], [During movement of new fuel assemblies or handling of control rods within the [RPV], when irradiated fuel assemblies are seated within the [RPV].]

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. [RPV] water level not within limit.	A.1 Suspend movement of fuel assemblies [and handling of control rods] within the [RPV].	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.9.6.1	Verify [RPV] water level is \geq [23] ft above the top of the [RPV flange].	24 hours

3.9.7	[Reactor	Pressure Vessel (RPV)] Water Level - [New Fuel or Control Rods]
LCO 3.9.	7	[RPV] water level shall be \geq [23] ft above the top of irradiated fuel assemblies seated within the [RPV].
APPLICA	BILITY:	During movement of new fuel assemblies or handling of control rods within the [RPV], when irradiated fuel assemblies are seated within the [RPV].

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. [RPV] water level not within limit.	A.1 Suspend movement of fuel assemblies and handling of control rods within the [RPV].	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.9.7.1	Verify [RPV] water level is \geq [23] ft above the top of irradiated fuel assemblies seated within the [RPV].	24 hours

3.9.8	Residual Heat Removal (RHR) - High Water Level
-------	--

APPLICABILITY:	MODE 5 with irradiated fuel in the reactor pressure vessel (RPV) and the
	water level \geq [23] ft above the top of the [RPV flange].

ACTIONS

	CONDITION		REQUIRED ACTION	COMPLETION TIME
A.	Required RHR shutdown cooling subsystem inoperable.	A.1	Verify an alternate method of decay heat removal is available.	1 hour <u>AND</u> Once per 24 hours thereafter
B.	Required Action and associated Completion Time of Condition A not met.	B.1 <u>AND</u>	Suspend loading irradiated fuel assemblies into the RPV.	Immediately
		B.2	Initiate action to restore [secondary] containment to OPERABLE status.	Immediately
		<u>AND</u>		

COMPLETION TIME

Immediately

ACTIONS (continued)		
CONDITION		REQUIRED ACTION
	B.3	Initiate action to restore one standby gas treatment subsystem to OPERABLE status.

	<u>AND</u>	subsystem to OPERABLE status.	
	B.4	Initiate action to restore isolation capability in each required [secondary] containment penetration flow path not isolated.	Immediately
C. No RHR shutdown cooling subsystem in operation.	C.1	Verify reactor coolant circulation by an alternate method.	1 hour from discovery of no reactor coolant circulation <u>AND</u> Once per 12 hours thereafter
	<u>AND</u>		
	C.2	Monitor reactor coolant temperature.	Once per hour

	SURVEILLANCE	FREQUENCY
SR 3.9.8.1	Verify one RHR shutdown cooling subsystem is operating.	12 hours

3.9.9 Residual Heat Removal (RHR) - Low Water Level

LCO 3.9.9 Two RHR shutdown cooling subsystems shall be OPERABLE, and one RHR shutdown cooling subsystem shall be in operation.

The required operating shutdown cooling subsystem may not be in operation for up to 2 hours per 8 hour period.

APPLICABILITY:	MODE 5 with irradiated fuel in the reactor pressure vessel (RPV) and the
	water level < [23] ft above the top of the [RPV flange].

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
 A. One or two required RHR shutdown cooling subsystems inoperable. 	A.1	Verify an alternate method of decay heat removal is available for each inoperable required RHR shutdown cooling subsystem.	1 hour <u>AND</u> Once per 24 hours thereafter
 B. Required Action and associated Completion Time of Condition A not met. 	B.1 <u>AND</u>	Initiate action to restore [secondary] containment to OPERABLE status.	Immediately
	B.2	Initiate action to restore one standby gas treatment subsystem to OPERABLE status.	Immediately
	<u>AND</u>		

ACTIONS (continued)

CONDITION		REQUIRED ACTION	COMPLETION TIME
	B.3	Initiate action to restore isolation capability in each required [secondary] containment penetration flow path not isolated.	Immediately
C. No RHR shutdown cooling subsystem in operation.	C.1	Verify reactor coolant circulation by an alternate method.	 1 hour from discovery of no reactor coolant circulation <u>AND</u> Once per 12 hours thereafter
	<u>AND</u> C.2	Monitor reactor coolant temperature.	Once per hour

	SURVEILLANCE	FREQUENCY
SR 3.9.9.1	Verify one RHR shutdown cooling subsystem is operating.	12 hours

- 3.10.1 Inservice Leak and Hydrostatic Testing Operation
- LCO 3.10.1 The average reactor coolant temperature specified in Table 1.1-1 for MODE 4 may be changed to "NA," and operation considered not to be in MODE 3; and the requirements of LCO 3.4.9, "Residual Heat Removal (RHR) Shutdown Cooling System - Cold Shutdown," may be suspended, to allow performance of an inservice leak or hydrostatic test provided the following MODE 3 LCOs are met:
 - a. LCO 3.3.6.2, "Secondary Containment Isolation Instrumentation," Functions [1, 3, 4 and 5] of Table 3.3.6.2-1,
 - b. LCO 3.6.4.1, "Secondary Containment,"
 - c. LCO 3.6.4.2, "Secondary Containment Isolation Valves (SCIVs)," and
 - d. LCO 3.6.4.3, "Standby Gas Treatment (SGT) System."
- APPLICABILITY: MODE 4 with average reactor coolant temperature > [200]°F.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
 A. One or more of the above requirements not met. 	A.1	NOTE Required Actions to be in MODE 4 include reducing average reactor coolant temperature to \leq [200]°F.	
		Enter the applicable Condition of the affected LCO.	Immediately
	<u>OR</u>		
	A.2.1	Suspend activities that could increase the average reactor coolant temperature or pressure.	Immediately
	AN	<u>ID</u>	
	A.2.2	Reduce average reactor coolant temperature to \leq [200]°F.	24 hours

	SURVEILLANCE	FREQUENCY
SR 3.10.1.1	Perform the applicable SRs for the required MODE 3 LCOs.	According to the applicable SRs

3.10.2 Reactor Mode Switch Interlock Testing

- LCO 3.10.2 The reactor mode switch position specified in Table 1.1-1 for MODES 3, 4, and 5 may be changed to include the run, startup/hot standby, and refuel position, and operation considered not to be in MODE 1 or 2, to allow testing of instrumentation associated with the reactor mode switch interlock functions, provided:
 - a. All control rods remain fully inserted in core cells containing one or more fuel assemblies and
 - b. No CORE ALTERATIONS are in progress.

APPLICABILITY: MODES 3 and 4 with the reactor mode switch in the run, startup/hot standby, or refuel position, MODE 5 with the reactor mode switch in the run or startup/hot standby position.

ACTIONS

CONDITION	REQUIRED ACTION		COMPLETION TIME
A. One or more of the above requirements not met.	A.1	Suspend CORE ALTERATIONS except for control rod insertion.	Immediately
	<u>AND</u>		
	A.2	Fully insert all insertable control rods in core cells containing one or more fuel assemblies.	1 hour
	<u>AND</u>		
	A.3.1	Place the reactor mode switch in the shutdown position.	1 hour
	<u>OF</u>		

ACTIONS (continued)			
CONDITION	REQUIRED ACTION		COMPLETION TIME
	A.3.2	NOTE Only applicable in MODE 5.	
		Place the reactor mode switch in the refuel position.	1 hour

SURVEILLANCE REQUIREMENTS					
	SURVEILLANCE	FREQUENCY			
SR 3.10.2.1	Verify all control rods are fully inserted in core cells containing one or more fuel assemblies.	12 hours			
SR 3.10.2.2	Verify no CORE ALTERATIONS are in progress.	24 hours			

BWR/4 STS

3.10.3 Single Control Rod Withdrawal - Hot Shutdown

LCO 3.10.3 The reactor mode switch position specified in Table 1.1-1 for MODE 3 may be changed to include the refuel position, and operation considered not to be in MODE 2, to allow withdrawal of a single control rod, provided the following requirements are met:

- a. LCO 3.9.2, "Refuel Position One-Rod-Out Interlock,"
- b. LCO 3.9.4, "Control Rod Position Indication,"
- c. All other control rods are fully inserted, and
- d.1. LCO 3.3.1.1, "Reactor Protection System (RPS) Instrumentation," MODE 5 requirements for Functions [1.a, 1.b, 7.a, 7.b, 10, and 11] of Table 3.3.1.1-1 and LCO 3.9.5, "Control Rod OPERABILITY -Refueling,"

 All other control rods in a five by five array centered on the control rod being withdrawn are disarmed; at which time LCO 3.1.1, "SHUTDOWN MARGIN (SDM)," MODE 3 requirements may be changed to allow the single control rod withdrawn to be assumed to be the highest worth control rod.

APPLICABILITY: MODE 3 with the reactor mode switch in the refuel position.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or more of the above requirements not met.	A.1	 NOTES Required Actions to fully insert all insertable control rods include placing the reactor mode switch in the shutdown position. Only applicable if the requirement not met is a required LCO. 	
		Enter the applicable Condition of the affected LCO.	Immediately
	<u>OR</u>		
	A.2.1	Initiate action to fully insert all insertable control rods.	Immediately
	AN	D	
	A.2.2	Place the reactor mode switch in the shutdown position.	1 hour

	SURVEILLANCE	FREQUENCY
SR 3.10.3.1	Perform the applicable SRs for the required LCOs.	According to the applicable SRs

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE		FREQUENCY
SR 3.10.3.2	NOTE	
	Verify all control rods, other than the control rod being withdrawn, in a five by five array centered on the control rod being withdrawn, are disarmed.	24 hours
SR 3.10.3.3	Verify all control rods, other than the control rod being withdrawn, are fully inserted.	24 hours

- 3.10.4 Single Control Rod Withdrawal Cold Shutdown
- LCO 3.10.4 The reactor mode switch position specified in Table 1.1-1 for MODE 4 may be changed to include the refuel position, and operation considered not to be in MODE 2, to allow withdrawal of a single control rod, and subsequent removal of the associated control rod drive (CRD) if desired, provided the following requirements are met:
 - a. All other control rods are fully inserted,
 - b.1. LCO 3.9.2, "Refuel Position One-Rod-Out Interlock," and LCO 3.9.4, "Control Rod Position Indication,"

- 2. A control rod withdrawal block is inserted,
- c.1. LCO 3.3.1.1, "Reactor Protection System (RPS) Instrumentation," MODE 5 requirements for Functions [1.a, 1.b, 7.a, 7.b, 10, and 11] of Table 3.3.1.1-1 and LCO 3.9.5, "Control Rod OPERABILITY -Refueling,"

- All other control rods in a five by five array centered on the control rod being withdrawn are disarmed; at which time LCO 3.1.1, "SHUTDOWN MARGIN (SDM)," MODE 4 requirements may be changed to allow the single control rod withdrawn to be assumed to be the highest worth control rod.
- APPLICABILITY: MODE 4 with the reactor mode switch in the refuel position.

ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or more of the above requirements not met with the affected control rod insertable.	A.1	 NOTES Required Actions to fully insert all insertable control rods include placing the reactor mode switch in the shutdown position. Only applicable if the requirement not met is a required LCO. 	
		Enter the applicable Condition of the affected LCO.	Immediately
	<u>OR</u>		
	A.2.1	Initiate action to fully insert all insertable control rods.	Immediately
	<u>AN</u>	ID	
	A.2.2	Place the reactor mode switch in the shutdown position.	1 hour
 B. One or more of the above requirements not met with the affected 	B.1	Suspend withdrawal of the control rod and removal of associated CRD.	Immediately
insertable.	<u>AND</u>		
	B.2.1	Initiate action to fully insert all control rods.	Immediately
	OF	2	

ACTIONS	(continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
	B.2.2 Initiate action to satisfy the requirements of this LCO.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.10.4.1	Perform the applicable SRs for the required LCOs.	According to the applicable SRs
SR 3.10.4.2	NOTENOTENOTENOTENOTENOTENOTENOTENOTE	
	Verify all control rods, other than the control rod being withdrawn, in a five by five array centered on the control rod being withdrawn, are disarmed.	24 hours
SR 3.10.4.3	Verify all control rods, other than the control rod being withdrawn, are fully inserted.	24 hours
SR 3.10.4.4	NOTENOTENOTENOTENOTENOTENOTENOTENOTENOTE	
	Verify a control rod withdrawal block is inserted.	24 hours

- 3.10.5 Single Control Rod Drive (CRD) Removal Refueling
- LCO 3.10.5 The requirements of:

LCO 3.3.1.1, "Reactor Protection System (RPS) Instrumentation,"

LCO 3.3.8.2, "Reactor Protection System (RPS) Electric Power Monitoring,"

LCO 3.9.1, "Refueling Equipment Interlocks,"

LCO 3.9.2, "Refuel Position One Rod Out Interlock,"

LCO 3.9.4, "Control Rod Position Indication," and

LCO 3.9.5, "Control Rod OPERABILITY - Refueling,"

may be suspended in MODE 5 to allow the removal of a single CRD associated with a control rod withdrawn from a core cell containing one or more fuel assemblies, provided the following requirements are met:

- a. All other control rods are fully inserted,
- b. All other control rods in a five by five array centered on the withdrawn control rod are disarmed,
- A control rod withdrawal block is inserted and LCO 3.1.1, "SHUTDOWN MARGIN (SDM)," MODE 5 requirements may be changed to allow the single control rod withdrawn to be assumed to be the highest worth control rod, and
- d. No other CORE ALTERATIONS are in progress.

APPLICABILITY: MODE 5 with LCO 3.9.5 not met.

	CONDITION		REQUIRED ACTION	COMPLETION TIME
A.	One or more of the above requirements not	A.1	Suspend removal of the CRD mechanism.	Immediately
	met.	<u>AND</u>		
		A.2.1	Initiate action to fully insert all control rods.	Immediately
		OF	<u>R</u>	
		A.2.2	Initiate action to satisfy the requirements of this LCO.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.10.5.1	Verify all control rods, other than the control rod withdrawn for the removal of the associated CRD, are fully inserted.	24 hours
SR 3.10.5.2	Verify all control rods, other than the control rod withdrawn for the removal of the associated CRD, in a five by five array centered on the control rod withdrawn for the removal of the associated CRD, are disarmed.	24 hours
SR 3.10.5.3	Verify a control rod withdrawal block is inserted.	24 hours
SR 3.10.5.4	Perform SR 3.1.1.1.	According to SR 3.1.1.1
SR 3.10.5.5	Verify no CORE ALTERATIONS are in progress.	24 hours

- 3.10.6 Multiple Control Rod Withdrawal Refueling
- LCO 3.10.6 The requirements of:

LCO 3.9.3, "Control Rod Position,"

LCO 3.9.4, "Control Rod Position Indication," and

LCO 3.9.5, "Control Rod OPERABILITY - Refueling,"

may be suspended, and the "full in" position indicators may be bypassed for any number of control rods in MODE 5, to allow withdrawal of these control rods, removal of associated control rod drives (CRDs), or both, provided the following requirements are met:

- a. The four fuel assemblies are removed from the core cells associated with each control rod or CRD to be removed,
- b. All other control rods in core cells containing one or more fuel assemblies are fully inserted, and
- c. Fuel assemblies shall only be loaded in compliance with an approved [spiral] reload sequence.
- APPLICABILITY: MODE 5 with LCO 3.9.3, LCO 3.9.4, or LCO 3.9.5 not met.

CONDITION		REQUIRED ACTION	COMPLETION TIME
A. One or more of the above requirements not met.	A.1	Suspend withdrawal of control rods and removal of associated CRDs.	Immediately
	<u>AND</u>		
	A.2	Suspend loading fuel assemblies.	Immediately
	<u>AND</u>		

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
	A.3.1 Initiate action to fully ins all control rods in core of containing one or more assemblies.	sert Immediately cells fuel
	<u>OR</u>	
	A.3.2 Initiate action to satisfy requirements of this LC	the Immediately O.

ACTIONS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.10.6.1	Verify the four fuel assemblies are removed from core cells associated with each control rod or CRD removed.	24 hours
SR 3.10.6.2	Verify all other control rods in core cells containing one or more fuel assemblies are fully inserted.	24 hours
SR 3.10.6.3	NOTE Only required to be met during fuel loading. Verify fuel assemblies being loaded are in compliance with an approved [spiral] reload sequence.	24 hours

3.10.7 Control Rod Testing - Operating

- LCO 3.10.7 The requirements of LCO 3.1.6, "Rod Pattern Control," may be suspended to allow performance of SDM demonstrations, control rod scram time testing, control rod friction testing, and the Startup Test Program, provided:
 - a. The banked position withdrawal sequence requirements of SR 3.3.2.1.8 are changed to require the control rod sequence to conform to the specified test sequence,

b. The RWM is bypassed; the requirements of LCO 3.3.2.1, "Control Rod Block Instrumentation," Function 2 are suspended; and conformance to the approved control rod sequence for the specified test is verified by a second licensed operator or other qualified member of the technical staff.

APPLICABILITY:	MODES 1 and 2 with LCO 3.1.6 not met.
----------------	---------------------------------------

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Requirements of the LCO not met.	A.1 Suspend performance of the test and exception to LCO 3.1.6.	Immediately

SURVEILLANCE		FREQUENCY
SR 3.10.7.1	NOTENOTENOTENOTENOTENOTENOTE	
	Verify movement of control rods is in compliance with the approved control rod sequence for the specified test by a second licensed operator or other qualified member of the technical staff.	During control rod movement
SR 3.10.7.2	NOTENOTE-NOTE-NOTENOTENOTENOTENOTENOTE	
	Verify control rod sequence input to the RWM is in conformance with the approved control rod sequence for the specified test.	Prior to control rod movement

3.10.8 SHUTDOWN MARGIN (SDM) Test - Refueling

- LCO 3.10.8 The reactor mode switch position specified in Table 1.1-1 for MODE 5 may be changed to include the startup/hot standby position, and operation considered not to be in MODE 2, to allow SDM testing, provided the following requirements are met:
 - a. LCO 3.3.1.1, "Reactor Protection System Instrumentation," MODE 2 requirements for Functions 2.a and 2.e of Table 3.3.1.1-1,
 - b.1. LCO 3.3.2.1, "Control Rod Block Instrumentation," MODE 2 requirements for Function 2 of Table 3.3.2.1-1, with the banked position withdrawal sequence requirements of SR 3.3.2.1.8 changed to require the control rod sequence to conform to the SDM test sequence,

- 2. Conformance to the approved control rod sequence for the SDM test is verified by a second licensed operator or other qualified member of the technical staff,
- c. Each withdrawn control rod shall be coupled to the associated CRD,
- d. All control rod withdrawals [during out of sequence control rod moves] shall be made in notch out mode,
- e. No other CORE ALTERATIONS are in progress, and
- f. CRD charging water header pressure \geq [940] psig.
- APPLICABILITY: MODE 5 with the reactor mode switch in startup/hot standby position.

ACTIONS

CONDITION	REQU	JIRED ACTION	COMPLETION TIME
ANOTE Separate Condition entry is allowed for each control rod. One or more control rods not coupled to its associated CRD.	Rod worth mi bypassed as LCO 3.3.2.1, Instrumentati allow insertio rod and conti 	NOTE nimizer may be allowed by "Control Rod Block on," if required, to n of inoperable control nued operation. 	3 hours 4 hours
B. One or more of the above requirements not met for reasons other than Condition A.	B.1 Place switc refue	e the reactor mode h in the shutdown or I position.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.10.8.1	Perform the MODE 2 applicable SRs for LCO 3.3.1.1, Functions 2.a and 2.d of Table 3.3.1.1-1.	According to the applicable SRs
SR 3.10.8.2	NOTENOTE-NOTE-NOTE	
	Perform the MODE 2 applicable SRs for LCO 3.3.2.1, Function 2 of Table 3.3.2.1-1.	According to the applicable SRs

SURVEILLANCE REQUIREMENTS (continued)

	SURVEILLANCE	FREQUENCY
SR 3.10.8.3	Not required to be met if SR 3.10.8.2 satisfied. Verify movement of control rods is in compliance with the approved control rod sequence for the SDM test by a second licensed operator or other qualified member of the technical staff.	During control rod movement
SR 3.10.8.4	Verify no other CORE ALTERATIONS are in progress.	12 hours
SR 3.10.8.5	Verify each withdrawn control rod does not go to the withdrawn overtravel position.	Each time the control rod is withdrawn to "full out" position <u>AND</u> Prior to satisfying LCO 3.10.8.c requirement after work on control rod or CRD System that could affect coupling
SR 3.10.8.6	Verify CRD charging water header pressure \geq [940] psig.	7 days

3.10.9 Recirculation Loops - Testing

- LCO 3.10.9 The requirements of LCO 3.4.1, "Recirculation Loops Operating," may be suspended for \leq 24 hours to allow:
 - a. PHYSICS TESTS, provided THERMAL POWER is \leq [5]% RTP and
 - b. Performance of the Startup Test Program.

APPLICABILITY: MODES 1 and 2 with less than two recirculation loops in operation.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
 A. Requirements of LCO 3.4.1 not met for > 24 hours. 	A.1 Insert all insertable control rods.	[1] hour
B. Requirements of the LCO not met for reasons other than Condition A.	B.1 Place the reactor mode switch in the shutdown position.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.10.9.1	Verify LCO 3.4.1 requirements suspended for \leq 24 hours.	1 hour
SR 3.10.9.2	Verify THERMAL POWER is \leq [5]% RTP during PHYSICS TESTS.	1 hour

3.10.10 Training Startups

- LCO 3.10.10 The low pressure coolant injection (LPCI) OPERABILITY requirements specified in LCO 3.5.1, "Emergency Core Cooling Systems (ECCS) Operating," may be changed to allow one residual heat removal subsystem to be aligned in the shutdown cooling mode for training startups, provided the following requirements are met:
 - a. All OPERABLE intermediate range monitor (IRM) channels are \leq [25/40] divisions of full scale on Range 7 and
 - b. Average reactor coolant temperature is < 200°F.
- APPLICABILITY: MODE 2 with one LPCI subsystem suction valve closed.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more of the above requirements not met.	A.1 Place the reactor mode switch in the shutdown position.	Immediately

	SURVEILLANCE	FREQUENCY
SR 3.10.10.1	Verify all OPERABLE IRM channels are \leq [25/40] divisions of full scale on Range 7.	1 hour
SR 3.10.10.2	Verify average reactor coolant temperature is < 200°F.	1 hour
4.0 DESIGN FEATURES

4.1 Site Location

[Text description of site location.]

4.2 Reactor Core

4.2.1 <u>Fuel Assemblies</u>

The reactor shall contain [560] fuel assemblies. Each assembly shall consist of a matrix of [Zircalloy or ZIRLO] fuel rods with an initial composition of natural or slightly enriched uranium dioxide (UO_2) as fuel material and [water rods]. Limited substitutions of zirconium alloy or stainless steel filler rods for fuel rods, in accordance with approved applications of fuel rod configurations, may be used. Fuel assemblies shall be limited to those fuel designs that have been analyzed with NRC staff approved codes and methods and have been shown by tests or analyses to comply with all safety design bases. A limited number of lead test assemblies that have not completed representative testing may be placed in nonlimiting core regions.

4.2.2 <u>Control Rod Assemblies</u>

The reactor core shall contain [137] cruciform shaped control rod assemblies. The control material shall be [boron carbide, hafnium metal] as approved by the NRC.

4.3 Fuel Storage

- 4.3.1 <u>Criticality</u>
 - 4.3.1.1 The spent fuel storage racks are designed and shall be maintained with:
 - a. Fuel assemblies having a maximum [k-infinity of [1.31] in the normal reactor core configuration at cold conditions] [average U-235 enrichment of [4.5] weight percent],
 - b. $k_{eff} \le 0.95$ if fully flooded with unborated water, which includes an allowance for uncertainties as described in [Section 9.1 of the FSAR], and
 - c. A nominal [6.5] inch center to center distance between fuel assemblies placed in the storage racks.
 - 4.3.1.2 The new fuel storage racks are designed and shall be maintained with:

4.0 DESIGN FEATURES

4.3 Fuel Storage (continued)

- a. Fuel assemblies having a maximum [k-infinity of [1.31] in the normal reactor core configuration at cold conditions] [average U-235 enrichment of [4.5] weight percent],
- b. $k_{eff} \le 0.95$ if fully flooded with unborated water, which includes an allowance for uncertainties as described in [Section 9.1 of the FSAR],
- c. $k_{eff} \le 0.98$ if moderated by aqueous foam, which includes an allowance for uncertainties as described in [Section 9.1 of the FSAR], and
- d. A nominal [6.50] inch center to center distance between fuel assemblies placed in storage racks.

4.3.2 Drainage

The spent fuel storage pool is designed and shall be maintained to prevent inadvertent draining of the pool below elevation [185 ft].

4.3.3 Capacity

The spent fuel storage pool is designed and shall be maintained with a storage capacity limited to no more than [2845] fuel assemblies.

5.1 Responsibility

-----REVIEWER'S NOTES------

- 1. Titles for members of the unit staff shall be specified by use of an overall statement referencing an ANSI Standard acceptable to the NRC staff from which the titles were obtained, or an alternative title may be designated for this position. Generally, the first method is preferable; however, the second method is adaptable to those unit staffs requiring special titles because of unique organizational structures.
- 2. The ANSI Standard shall be the same ANSI Standard referenced in Section 5.3, Unit Staff Qualifications. If alternative titles are used, all requirements of these Technical Specifications apply to the position with the alternative title as apply with the specified title. Unit staff titles shall be specified in the Final Safety Analysis Report or Quality Assurance Plan. Unit staff titles shall be maintained and revised using those procedures approved for modifying/revising the Final Safety Analysis Report or Quality Assurance Plan.
- 5.1.1 The plant manager shall be responsible for overall unit operation and shall delegate in writing the succession to this responsibility during his absence.

The plant manager or his designee shall approve, prior to implementation, each proposed test, experiment or modification to systems or equipment that affect nuclear safety.

5.1.2 The [Shift Supervisor (SS)] shall be responsible for the control room command function. During any absence of the [SS] from the control room while the unit is in MODE 1, 2, or 3, an individual with an active Senior Reactor Operator (SRO) license shall be designated to assume the control room command function. During any absence of the [SS] from the control room while the unit is in MODE 4 or 5, an individual with an active SRO license or Reactor Operator license shall be designated to assume the control room command function.

5.2 Organization

5.2.1 Onsite and Offsite Organizations

Onsite and offsite organizations shall be established for unit operation and corporate management, respectively. The onsite and offsite organizations shall include the positions for activities affecting safety of the nuclear power plant.

- a. Lines of authority, responsibility, and communication shall be defined and established throughout highest management levels, intermediate levels, and all operating organization positions. These relationships shall be documented and updated, as appropriate, in organization charts, functional descriptions of departmental responsibilities and relationships, and job descriptions for key personnel positions, or in equivalent forms of documentation. These requirements including the plant-specific titles of those personnel fulfilling the responsibilities of the positions delineated in these Technical Specifications shall be documented in the [FSAR/QA Plan].
- b. The plant manager shall be responsible for overall safe operation of the plant and shall have control over those onsite activities necessary for safe operation and maintenance of the plant.
- c. A specified corporate officer shall have corporate responsibility for overall plant nuclear safety and shall take any measures needed to ensure acceptable performance of the staff in operating, maintaining, and providing technical support to the plant to ensure nuclear safety.
- d. The individuals who train the operating staff, carry out health physics, or perform quality assurance functions may report to the appropriate onsite manager; however, these individuals shall have sufficient organizational freedom to ensure their independence from operating pressures.

5.2.2 Unit Staff

The unit staff organization shall include the following:

a. A non-licensed operator shall be assigned to each reactor containing fuel and an additional non-licensed operator shall be assigned for each control room from which a reactor is operating in MODES 1, 2, or 3.

5.2 Organization

5.2.2 Unit Staff (continued)

- b. Shift crew composition may be less than the minimum requirement of 10 CFR 50.54(m)(2)(i) and 5.2.2.a and 5.2.2.f for a period of time not to exceed 2 hours in order to accommodate unexpected absence of on-duty shift crew members provided immediate action is taken to restore the shift crew composition to within the minimum requirements.
- c. A radiation protection technician shall be on site when fuel is in the reactor. The position may be vacant for not more than 2 hours, in order to provide for unexpected absence, provided immediate action is taken to fill the required position.
- d. Administrative procedures shall be developed and implemented to limit the working hours of personnel who perform safety related functions (e.g., [licensed Senior Reactor Operators (SROs), licensed Reactor Operators (ROs), health physicists, auxiliary operators, and key maintenance personnel]).

The controls shall include guidelines on working hours that ensure adequate shift coverage shall be maintained without routine heavy use of overtime.

Any deviation from the above guidelines shall be authorized in advance by the plant manager or the plant manager's designee, in accordance with approved administrative procedures, and with documentation of the basis for granting the deviation. Routine deviation from the working hour guidelines shall not be authorized.

Controls shall be included in the procedures to require a periodic independent review be conducted to ensure that excessive hours have not been assigned.

- e. The operations manager or assistant operations manager shall hold an SRO license.
- f. An individual shall provide advisory technical support to the unit operations shift crew in the areas of thermal hydraulics, reactor engineering, and plant analysis with regard to the safe operation of the unit. This individual shall meet the qualifications specified by the Commission Policy Statement on Engineering Expertise on Shift.

5.3 Unit Staff Qualifications

------REVIEWER'S NOTE-------Minimum qualifications for members of the unit staff shall be specified by use of an overall qualification statement referencing an ANSI Standard acceptable to the NRC staff or by specifying individual position qualifications. Generally, the first method is preferable; however, the second method is adaptable to those unit staffs requiring special qualification statements because of unique organizational structures.

- 5.3.1 Each member of the unit staff shall meet or exceed the minimum qualifications of [Regulatory Guide 1.8, Revision 2, 1987, or more recent revisions, or ANSI Standard acceptable to the NRC staff]. [The staff not covered by Regulatory Guide 1.8 shall meet or exceed the minimum qualifications of Regulations, Regulatory Guides, or ANSI Standards acceptable to NRC staff].
- 5.3.2 For the purpose of 10 CFR 55.4, a licensed Senior Reactor Operator (SRO) and a licensed Reactor Operator (RO) are those individuals who, in addition to meeting the requirements of Specification 5.3.1, perform the functions described in 10 CFR 50.54(m).

5.4 Procedures

- 5.4.1 Written procedures shall be established, implemented, and maintained covering the following activities:
 - a. The applicable procedures recommended in Regulatory Guide 1.33, Revision 2, Appendix A, February 1978,
 - b. The emergency operating procedures required to implement the requirements of NUREG-0737 and to NUREG-0737, Supplement 1, as stated in [Generic Letter 82-33],
 - c. Quality assurance for effluent and environmental monitoring,
 - d. Fire Protection Program implementation, and
 - e. All programs specified in Specification 5.5.

5.5 Programs and Manuals

The following programs shall be established, implemented, and maintained.

5.5.1 Offsite Dose Calculation Manual (ODCM)

- a. The ODCM shall contain the methodology and parameters used in the calculation of offsite doses resulting from radioactive gaseous and liquid effluents, in the calculation of gaseous and liquid effluent monitoring alarm and trip setpoints, and in the conduct of the radiological environmental monitoring program, and
- b. The ODCM shall also contain the radioactive effluent controls and radiological environmental monitoring activities, and descriptions of the information that should be included in the Annual Radiological Environmental Operating, and Radioactive Effluent Release Reports required by Specification [5.6.2] and Specification [5.6.3].

Licensee initiated changes to the ODCM:

- a. Shall be documented and records of reviews performed shall be retained. This documentation shall contain:
 - 1. Sufficient information to support the change(s) together with the appropriate analyses or evaluations justifying the change(s) and
 - A determination that the change(s) maintain the levels of radioactive effluent control required by 10 CFR 20.1302, 40 CFR 190, 10 CFR 50.36a, and 10 CFR 50, Appendix I, and not adversely impact the accuracy or reliability of effluent, dose, or setpoint calculations,
- b. Shall become effective after the approval of the plant manager, and
- c. Shall be submitted to the NRC in the form of a complete, legible copy of the entire ODCM as a part of or concurrent with the Radioactive Effluent Release Report for the period of the report in which any change in the ODCM was made. Each change shall be identified by markings in the margin of the affected pages, clearly indicating the area of the page that was changed, and shall indicate the date (i.e., month and year) the change was implemented.

5.5.2 Primary Coolant Sources Outside Containment

This program provides controls to minimize leakage from those portions of systems outside containment that could contain highly radioactive fluids during a serious transient or accident to levels as low as practicable. The systems include [the Low Pressure Core Spray, High Pressure Coolant Injection, Residual Heat Removal, Reactor Core Isolation Cooling, hydrogen recombiner, process sampling, and Standby Gas Treatment]. The program shall include the following:

- a. Preventive maintenance and periodic visual inspection requirements and
- b. Integrated leak test requirements for each system at least once per [18] months.

The provisions of SR 3.0.2 are applicable.

5.5.3 Post Accident Sampling

This program provides controls that ensure the capability to obtain and analyze reactor coolant, radioactive gases, and particulates in plant gaseous effluents and containment atmosphere samples under accident conditions. The program shall include the following:

- a. Training of personnel,
- b. Procedures for sampling and analysis, and
- c. Provisions for maintenance of sampling and analysis equipment.

5.5.4 Radioactive Effluent Controls Program

This program conforms to 10 CFR 50.36a for the control of radioactive effluents and for maintaining the doses to members of the public from radioactive effluents as low as reasonably achievable. The program shall be contained in the ODCM, shall be implemented by procedures, and shall include remedial actions to be taken whenever the program limits are exceeded. The program shall include the following elements:

a. Limitations on the functional capability of radioactive liquid and gaseous monitoring instrumentation including surveillance tests and setpoint determination in accordance with the methodology in the ODCM,

5.5.4 <u>Radioactive Effluent Controls Program</u> (continued)

- b. Limitations on the concentrations of radioactive material released in liquid effluents to unrestricted areas, conforming to ten times the concentration values in Appendix B, Table 2, Column 2 to 10 CFR 20.1001-20.2402,
- c. Monitoring, sampling, and analysis of radioactive liquid and gaseous effluents in accordance with 10 CFR 20.1302 and with the methodology and parameters in the ODCM,
- d. Limitations on the annual and quarterly doses or dose commitment to a member of the public from radioactive materials in liquid effluents released from each unit to unrestricted areas, conforming to 10 CFR 50, Appendix I,
- e. Determination of cumulative dose contributions from radioactive effluents for the current calendar quarter and current calendar year in accordance with the methodology and parameters in the ODCM at least every 31 days. Determination of projected dose contributions from radioactive effluents in accordance with the methodology in the ODCM at least every 31 days,
- f. Limitations on the functional capability and use of the liquid and gaseous effluent treatment systems to ensure that appropriate portions of these systems are used to reduce releases of radioactivity when the projected doses in a period of 31 days would exceed 2% of the guidelines for the annual dose or dose commitment, conforming to 10 CFR 50, Appendix I,
- g. Limitations on the dose rate resulting from radioactive material released in gaseous effluents from the site to areas at or beyond the site boundary shall be in accordance with the following:
 - 1. For noble gases: a dose rate \leq 500 mrem/yr to the whole body and a dose rate \leq 3000 mrem/yr to the skin and
 - 2. For iodine-131, iodine-133, tritium, and all radionuclides in particulate form with half-lives greater than 8 days: a dose rate \leq 1500 mrem/yr to any organ,
- h. Limitations on the annual and quarterly air doses resulting from noble gases released in gaseous effluents from each unit to areas beyond the site boundary, conforming to 10 CFR 50, Appendix I,
- i. Limitations on the annual and quarterly doses to a member of the public from iodine-131, iodine-133, tritium, and all radionuclides in particulate form with half lives > 8 days in gaseous effluents released from each unit to areas beyond the site boundary, conforming to 10 CFR 50, Appendix I,

5.5.4 <u>Radioactive Effluent Controls Program</u> (continued)

- j. Limitations on the annual dose or dose commitment to any member of the public, beyond the site boundary, due to releases of radioactivity and to radiation from uranium fuel cycle sources, conforming to 40 CFR 190, and
- k. Limitations on venting and purging of the Mark II containment through the Standby Gas Treatment System to maintain releases as low as reasonably achievable (in BWR/4s with Mark II containments).

The provisions of SR 3.0.2 and SR 3.0.3 are applicable to the Radioactive Effluent Controls Program surveillance frequency.

5.5.5 <u>Component Cyclic or Transient Limit</u>

This program provides controls to track the FSAR Section [], cyclic and transient occurrences to ensure that components are maintained within the design limits.

5.5.6 [Pre-Stressed Concrete Containment Tendon Surveillance Program

This program provides controls for monitoring any tendon degradation in prestressed concrete containments, including effectiveness of its corrosion protection medium, to ensure containment structural integrity. The program shall include baseline measurements prior to initial operations. The Tendon Surveillance Program, inspection frequencies, and acceptance criteria shall be in accordance with [Regulatory Guide 1.35, Revision 3, 1989].

The provisions of SR 3.0.2 and SR 3.0.3 are applicable to the Tendon Surveillance Program inspection frequencies.]

5.5.7 Inservice Testing Program

This program provides controls for inservice testing of ASME Code Class 1, 2, and 3 components. The program shall include the following:

5.5.7 <u>Inservice Testing Program</u> (continued)

a. Testing frequencies specified in Section XI of the ASME Boiler and Pressure Vessel Code and applicable Addenda as follows:

ASME Boiler and Pressure Vessel Code and applicable Addenda terminology for inservice testing activities	Required Frequencies for performing inservice testing activities	
Weekly	At least once per 7 days	
Monthly	At least once per 31 days	
Quarterly or every 3 months	At least once per 92 days	
Semiannually or every 6 months	At least once per 184 days	
Every 9 months	At least once per 276 days	
Yearly or annually	At least once per 366 days	
Biennially or every 2 years	At least once per 731 days	

- b. The provisions of SR 3.0.2 are applicable to the above required Frequencies for performing inservice testing activities,
- c. The provisions of SR 3.0.3 are applicable to inservice testing activities, and
- d. Nothing in the ASME Boiler and Pressure Vessel Code shall be construed to supersede the requirements of any TS.

5.5.8 Ventilation Filter Testing Program (VFTP)

A program shall be established to implement the following required testing of Engineered Safety Feature (ESF) filter ventilation systems at the frequencies specified in [Regulatory Guide], and in accordance with [Regulatory Guide 1.52, Revision 2, ASME N510-1989, and AG-1].

Demonstrate for each of the ESF systems that an inplace test of the high efficiency particulate air (HEPA) filters shows a penetration and system bypass < [0.05]% when tested in accordance with [Regulatory Guide 1.52, Revision 2, and ASME N510-1989] at the system flowrate specified below [± 10%].

ESF Ventilation System	Flowrate

[] []

5.5.8 <u>Ventilation Filter Testing Program</u> (continued)

Demonstrate for each of the ESF systems that an inplace test of the charcoal adsorber shows a penetration and system bypass < [0.05]% when tested in accordance with [Regulatory Guide 1.52, Revision 2, and ASME N510-1989] at the system flowrate specified below [± 10%].

ESF Ventilation System Flowrate

- [] []
- c. Demonstrate for each of the ESF systems that a laboratory test of a sample of the charcoal adsorber, when obtained as described in [Regulatory Guide 1.52, Revision 2], shows the methyl iodide penetration less than the value specified below when tested in accordance with ASTM D3803-1989 at a temperature of 30°C (86°F) and the relative humidity specified below.

ESF Ventilation System	Penetration	RH	Face Velocity (fps)
[]	[See Reviewer's Note]	[See Reviewer's Note]	[See Reviewer's Note]

ASTM D 3803-1989 is a more stringent testing standard because it does not differentiate between used and new charcoal, it has a longer equilibration period performed at a temperature of 30°C (86°F) and a relative humidity (RH) of 95% (or 70% RH with humidity control), and it has more stringent tolerances that improve repeatability of the test.

Allowable Penetration = [(100% - Methyl Iodide Efficiently * for Charcoal Credited in Licensee's Accident Analysis) / Safety Factor]

When ASTM D3803-1989 is used with 30°C (86°F) and 95% RH (or 70% RH with humidity control) is used, the staff will accept the following:

Safety factor \geq 2 for systems with or without humidity control.

5.5.8 <u>Ventilation Filter Testing Program</u> (continued)

Humidity control can be provided by heaters or an NRC-approved analysis that demonstrates that the air entering the charcoal will be maintained less than or equal to 70 percent RH under worst-case design-basis conditions.

If the system has a face velocity greater than 110 percent of 0.203 m/s (40 ft/min), the face velocity should be specified.

*This value should be the efficiency that was incorporated in the licensee's accident analysis which was reviewed and approved by the staff in a safety evaluation.

d. Demonstrate for each of the ESF systems that the pressure drop across

the combined HEPA filters, the prefilters, and the charcoal adsorbers is less than the value specified below when tested in accordance with [Regulatory Guide 1.52, Revision 2, and ASME N510-1989] at the system flowrate specified below [± 10%].

ESF Ventilation System	Delta P	Flowrate
[]	[]	[]

[e. Demonstrate that the heaters for each of the ESF systems dissipate the value specified below [± 10%] when tested in accordance with [ASME N510-1989].

ESF Ventilation System	Wattage]
[]	[]

The provisions of SR 3.0.2 and SR 3.0.3 are applicable to the VFTP test frequencies.

5.5.9 Explosive Gas and Storage Tank Radioactivity Monitoring Program

This program provides controls for potentially explosive gas mixtures contained in the [Waste Gas Holdup System], [the quantity of radioactivity contained in gas storage tanks or fed into the offgas treatment system, and the quantity of radioactivity contained in unprotected outdoor liquid storage tanks]. The gaseous radioactivity quantities shall be determined following the methodology in [Branch Technical Position (BTP) ETSB 11-5, "Postulated Radioactive Release due to Waste Gas System Leak or Failure"]. The liquid radwaste quantities shall be determined in accordance with [Standard Review Plan, Section 15.7.3, "Postulated Radioactive Release due to Tank Failures"].

5.5.9 <u>Explosive Gas and Storage Tank Radioactivity Monitoring Program</u> (continued)

The program shall include:

- a. The limits for concentrations of hydrogen and oxygen in the [Waste Gas Holdup System] and a surveillance program to ensure the limits are maintained. Such limits shall be appropriate to the system's design criteria (i.e., whether or not the system is designed to withstand a hydrogen explosion).
- b. A surveillance program to ensure that the quantity of radioactivity contained in [each gas storage tank and fed into the offgas treatment system] is less than the amount that would result in a whole body exposure of ≥ 0.5 rem to any individual in an unrestricted area, in the event of [an uncontrolled release of the tanks' contents], and
- c. A surveillance program to ensure that the quantity of radioactivity contained in all outdoor liquid radwaste tanks that are not surrounded by liners, dikes, or walls, capable of holding the tanks' contents and that do not have tank overflows and surrounding area drains connected to the [Liquid Radwaste Treatment System] is less than the amount that would result in concentrations less than the limits of 10 CFR 20, Appendix B, Table 2, Column 2, at the nearest potable water supply and the nearest surface water supply in an unrestricted area, in the event of an uncontrolled release of the tanks' contents.

The provisions of SR 3.0.2 and SR 3.0.3 are applicable to the Explosive Gas and Storage Tank Radioactivity Monitoring Program surveillance frequencies.

5.5.10 Diesel Fuel Oil Testing Program

A diesel fuel oil testing program to implement required testing of both new fuel oil and stored fuel oil shall be established. The program shall include sampling and testing requirements, and acceptance criteria, all in accordance with applicable ASTM Standards. The purpose of the program is to establish the following:

- a. Acceptability of new fuel oil for use prior to addition to storage tanks by determining that the fuel oil has:
 - 1. An API gravity or an absolute specific gravity within limits,
 - 2. A flash point and kinematic viscosity within limits for ASTM 2D fuel oil, and
 - 3. A clear and bright appearance with proper color,

5.5.10 <u>Diesel Fuel Oil Testing Program</u> (continued)

- b. Within 31 days following addition of the new fuel oil to storage tanks, verify that the properties of the new fuel oil, other than those addressed in a., above, are within limits for ASTM 2D fuel oil, and
- c. Total particulate concentration of the fuel oil is \leq 10 mg/l when tested every 31 days in accordance with ASTM D-2276, Method A-2 or A-3.

The provisions of SR 3.0.2 and SR 3.0.3 are applicable to the Diesel Fuel Oil Testing Program test frequencies.

5.5.11 Technical Specifications (TS) Bases Control Program

This program provides a means for processing changes to the Bases of these Technical Specifications.

- a. Changes to the Bases of the TS shall be made under appropriate administrative controls and reviews.
- b. Licensees may make changes to Bases without prior NRC approval provided the changes do not require either of the following:
 - 1. A change in the TS incorporated in the license or
 - 2. A change to the updated FSAR or Bases that requires NRC approval pursuant to 10 CFR 50.59.
- c. The Bases Control Program shall contain provisions to ensure that the Bases are maintained consistent with the FSAR.
- Proposed changes that meet the criteria of Specification 5.5.11b above shall be reviewed and approved by the NRC prior to implementation.
 Changes to the Bases implemented without prior NRC approval shall be provided to the NRC on a frequency consistent with 10 CFR 50.71(e).

5.5.12 Safety Function Determination Program (SFDP)

This program ensures loss of safety function is detected and appropriate actions taken. Upon entry into LCO 3.0.6, an evaluation shall be made to determine if loss of safety function exists. Additionally, other appropriate actions may be taken as a result of the support system inoperability and corresponding exception to entering supported system Condition and Required Actions. This program implements the requirements of LCO 3.0.6. The SFDP shall contain the following:

5.5.12 <u>Safety Function Determination Program</u> (continued)

- a. Provisions for cross train checks to ensure a loss of the capability to perform the safety function assumed in the accident analysis does not go undetected,
- b. Provisions for ensuring the plant is maintained in a safe condition if a loss of function condition exists,
- c. Provisions to ensure that an inoperable supported system's Completion Time is not inappropriately extended as a result of multiple support system inoperabilities, and
- d. Other appropriate limitations and remedial or compensatory actions.

A loss of safety function exists when, assuming no concurrent single failure, no concurrent loss of offsite power, or no concurrent loss of onsite diesel generator(s), a safety function assumed in the accident analysis cannot be performed. For the purpose of this program, a loss of safety function may exist when a support system is inoperable, and:

- a. A required system redundant to the system(s) supported by the inoperable support system is also inoperable,
- b. A required system redundant to the system(s) in turn supported by the inoperable supported system is also inoperable, or
- c. A required system redundant to the support system(s) for the supported systems (a) and (b) above is also inoperable.

The SFDP identifies where a loss of safety function exists. If a loss of safety function is determined to exist by this program, the appropriate Conditions and Required Actions of the LCO in which the loss of safety function exists are required to be entered. When a loss of safety function is caused by the inoperability of a single Technical Specification support system, the appropriate Conditions and Required Actions to enter are those of the support system.

5.5.13 Primary Containment Leakage Rate Testing Program

[OPTION A]

a. A program shall establish the leakage rate testing of the containment as required by 10 CFR 50.54(o) and 10 CFR 50, Appendix J, Option A, as modified by approved exemptions.

5.5.13 <u>Primary Containment Leakage Rate Testing Program</u> (continued)

- b. The maximum allowable containment leakage rate, L_a, at P_a, shall be []% of containment air weight per day.
- c. Leakage rate acceptance criteria are:
 - 1. Containment leakage rate acceptance criterion is $\leq 1.0 L_a$. During the first unit startup following testing in accordance with this program, the leakage rate acceptance criteria are < 0.60 L_a for the Type B and C tests and < 0.75 L_a for Type A tests.
 - 2. Air lock testing acceptance criteria are:
 - a) Overall air lock leakage rate is $\leq [0.05 L_a]$ when tested at $\geq P_a$.
 - b) For each door, leakage rate is $\leq [0.01 L_a]$ when pressurized to $[\geq 10 \text{ psig}]$.
- d. The provisions of SR 3.0.3 are applicable to the Primary Containment Leakage Rate Testing Program.
- e. Nothing in these Technical Specifications shall be construed to modify the testing Frequencies required by 10 CFR 50, Appendix J.

[OPTION B]

- a. A program shall establish the leakage rate testing of the containment as required by 10 CFR 50.54(o) and 10 CFR 50, Appendix J, Option B, as modified by approved exemptions. This program shall be in accordance with the guidelines contained in Regulatory Guide 1.163, "Performance-Based Containment Leak-Test Program," dated September, 1995 [,as modified by the following exceptions:
 - 1. ...]
- The calculated peak containment internal pressure for the design basis loss of coolant accident, P_a, is [45 psig]. The containment design pressure is [50 psig].
- c. The maximum allowable containment leakage rate, L_a, at P_a, shall be []% of containment air weight per day.
- d. Leakage rate acceptance criteria are:

5.5.13 <u>Primary Containment Leakage Rate Testing Program</u> (continued)

- 1. Containment leakage rate acceptance criterion is $\leq 1.0 L_a$. During the first unit startup following testing in accordance with this program, the leakage rate acceptance criteria are < 0.60 L_a for the Type B and C tests and $\leq 0.75 L_a$ for Type A tests.
- 2. Air lock testing acceptance criteria are:
 - a) Overall air lock leakage rate is $\leq [0.05 L_a]$ when tested at $\geq P_a$.
 - b) For each door, leakage rate is \leq [0.01 L_a] when pressurized to [\geq 10 psig].
- e. The provisions of SR 3.0.3 are applicable to the Primary Containment Leakage Rate Testing Program.
- f. Nothing in these Technical Specifications shall be construed to modify the testing Frequencies required by 10 CFR 50, Appendix J.

[OPTION A/B Combined]

a. A program shall establish the leakage rate testing of the containment as required by 10 CFR 50.54(o) and 10 CFR 50, Appendix J. [Type A][Type B and C] test requirements are in accordance with 10 CFR 50, Appendix J, Option A, as modified by approved exemptions. [Type B and C][Type A] test requirements are in accordance with 10 CFR 50, Appendix J, Option B, as modified by approved exemptions. The 10 CFR 50, Appendix J, Option B, as modified by approved exemptions. The 10 CFR 50, Appendix J, Option B test requirements shall be in accordance with the guidelines contained in Regulatory Guide 1.163, "Performance-Based Containment Leak-Test Program," dated September, 1995 [,as modified by the following exceptions:

1. ...]

- The calculated peak containment internal pressure for the design basis loss of coolant accident, P_a, is [45 psig]. The containment design pressure is [50 psig].
- c. The maximum allowable containment leakage rate, L_a, at P_a, shall be []% of containment air weight per day.
- d. Leakage rate acceptance criteria are:

5.5.13 <u>Primary Containment Leakage Rate Testing Program</u> (continued)

- 1. Containment leakage rate acceptance criterion is $\leq 1.0 L_a$. During the first unit startup following testing in accordance with this program, the leakage rate acceptance criteria are $< 0.60 L_a$ for the Type B and C tests and [$< 0.75 L_a$ for Option A Type A tests] [$\leq 0.75 L_a$ for Option B Type A tests].
- 2. Air lock testing acceptance criteria are:
 - a) Overall air lock leakage rate is $\leq [0.05 L_a]$ when tested at $\geq P_a$.
 - b) For each door, leakage rate is \leq [0.01 L_a] when pressurized to \geq [10] psig.
- e. The provisions of SR 3.0.3 are applicable to the Primary Containment Leakage Rate Testing Program.
- f. Nothing in these Technical Specifications shall be construed to modify the testing Frequencies required by 10 CFR 50, Appendix J.

5.5.14 Battery Monitoring and Maintenance Program

This Program provides for battery restoration and maintenance, based on [the recommendations of IEEE Standard 450-1995, "IEEE Recommended Practice for Maintenance, Testing, and Replacement of Vented Lead-Acid Batteries for Stationary Applications," or of the battery manufacturer] of the following:

- a. Actions to restore battery cells with float voltage < [2.13] V, and
- b. Actions to equalize and test battery cells that had been discovered with electrolyte level below the minimum established design limit.

5.6 Reporting Requirements

The following reports shall be submitted in accordance with 10 CFR 50.4.

5.6.1 Occupational Radiation Exposure Report

[A single submittal may be made for a multiple unit station. The submittal should combine sections common to all units at the station.]

A tabulation on an annual basis of the number of station, utility, and other personnel (including contractors), for whom monitoring was performed, receiving an annual deep dose equivalent > 100 mrems and the associated collective deep dose equivalent (reported in person - rem) according to work and job functions (e.g., reactor operations and surveillance, inservice inspection, routine maintenance, special maintenance [describe maintenance], waste processing, and refueling). This tabulation supplements the requirements of 10 CFR 20.2206. The dose assignments to various duty functions may be estimated based on pocket ionization chamber, thermoluminescence dosimeter (TLD), electronic dosimeter, or film badge measurements. Small exposures totaling < 20 percent of the individual total dose need not be accounted for. In the aggregate, at least 80 percent of the total deep dose equivalent received from external sources should be assigned to specific major work functions. The report covering the previous calendar year shall be submitted by April 30 of each year. [The initial report shall be submitted by April 30 of the year following the initial criticality.]

5.6.2 <u>Annual Radiological Environmental Operating Report</u>

[A single submittal may be made for a multiple unit station. The submittal should combine sections common to all units at the station.]

The Annual Radiological Environmental Operating Report covering the operation of the unit during the previous calendar year shall be submitted by May 15 of each year. The report shall include summaries, interpretations, and analyses of trends of the results of the Radiological Environmental Monitoring Program for the reporting period. The material provided shall be consistent with the objectives outlined in the Offsite Dose Calculation Manual (ODCM), and in 10 CFR 50, Appendix I, Sections IV.B.2, IV.B.3, and IV.C.

The Annual Radiological Environmental Operating Report shall include the results of analyses of all radiological environmental samples and of all

5.6.2 <u>Annual Radiological Environmental Operating Report</u> (continued)

environmental radiation measurements taken during the period pursuant to the locations specified in the table and figures in the ODCM, as well as summarized and tabulated results of these analyses and measurements [in the format of the table in the Radiological Assessment Branch Technical Position, Revision 1, November 1979]. In the event that some individual results are not available for inclusion with the report, the report shall be submitted noting and explaining the reasons for the missing results. The missing data shall be submitted in a supplementary report as soon as possible.

5.6.3 Radiological Effluent Release Report

[A single submittal may be made for a multiple unit station. The submittal shall combine sections common to all units at the station; however, for units with separate radwaste systems, the submittal shall specify the releases of radioactive material from each unit.]

The Radioactive Effluent Release Report covering the operation of the unit during the previous year shall be submitted prior to May 1 of each year in accordance with 10 CFR 50.36a. The report shall include a summary of the quantities of radioactive liquid and gaseous effluents and solid waste released from the unit. The material provided shall be consistent with the objectives outlined in the ODCM and Process Control Program and in conformance with 10 CFR 50.36a and 10 CFR Part 50, Appendix I, Section IV.B.1.

5.6.4 Monthly Operating Reports

Routine reports of operating statistics and shutdown experience shall be submitted on a monthly basis no later than the 15th of each month following the calendar month covered by the report.

5.6.5 CORE OPERATING LIMITS REPORT (COLR)

a. Core operating limits shall be established prior to each reload cycle, or prior to any remaining portion of a reload cycle, and shall be documented in the COLR for the following:

[The individual specifications that address core operating limits must be referenced here.]

5.6.5 <u>CORE OPERATING LIMITS REPORT</u> (continued)

b. The analytical methods used to determine the core operating limits shall be those previously reviewed and approved by the NRC, specifically those described in the following documents:

[Identify the Topical Report(s) by number and title or identify the staff Safety Evaluation Report for a plant specific methodology by NRC letter and date. The COLR will contain the complete identification for each of the Technical Specification referenced topical reports used to prepare the COLR (i.e., report number, title, revision, date, and any supplements).]

- c. The core operating limits shall be determined such that all applicable limits (e.g., fuel thermal mechanical limits, core thermal hydraulic limits, Emergency Core Cooling Systems (ECCS) limits, nuclear limits such as SDM, transient analysis limits, and accident analysis limits) of the safety analysis are met.
- d. The COLR, including any midcycle revisions or supplements, shall be provided upon issuance for each reload cycle to the NRC.

5.6.6 Reactor Coolant System (RCS) PRESSURE AND TEMPERATURE LIMITS REPORT (PTLR)

a. RCS pressure and temperature limits for heat up, cooldown, low temperature operation, criticality, and hydrostatic testing as well as heatup and cooldown rates shall be established and documented in the PTLR for the following:

[The individual specifications that address RCS pressure and temperature limits must be referenced here.]

b. The analytical methods used to determine the RCS pressure and temperature limits shall be those previously reviewed and approved by the NRC, specifically those described in the following documents:

[Identify the NRC staff approval document by date.]

c. The PTLR shall be provided to the NRC upon issuance for each reactor vessel fluence period and for any revision or supplement thereto.

5.6.5 <u>RCS PRESSURE AND TEMPERATURE LIMITS REPORT</u> (continued)

- 1. The methodology shall describe how the neutron fluence is calculated (reference new Regulatory Guide when issued).
- 2. The Reactor Vessel Material Surveillance Program shall comply with Appendix H to 10 CFR 50. The reactor vessel material irradiation surveillance specimen removal schedule shall be provided, along with how the specimen examinations shall be used to update the PTLR curves.
- 3. Low Temperature Overpressure Protection (LTOP) System lift setting limits for the Power Operated Relief Valves (PORVs), developed using NRC-approved methodologies may be included in the PTLR.
- 4. The adjusted reference temperature (ART) for each reactor beltline material shall be calculated, accounting for radiation embrittlement, in accordance with Regulatory Guide 1.99, Revision 2.
- 5. The limiting ART shall be incorporated into the calculation of the pressure and temperature limit curves in accordance with NUREG-0800 Standard Review Plan 5.3.2, Pressure-Temperature Limits.
- 6. The minimum temperature requirements of Appendix G to 10 CFR Part 50 shall be incorporated into the pressure and temperature limit curves.
- 7. Licensees who have removed two or more capsules should compare for each surveillance material the measured increase in reference temperature (RT_{NDT}) to the predicted increase in RT_{NDT}; where the predicted increase in RT_{NDT} is based on the mean shift in RT_{NDT} plus the two standard deviation value ($2\sigma_{\Delta}$) specified in Regulatory Guide 1.99, Revision 2. If the measured value exceeds the predicted value (increase RT_{NDT} + $2\sigma_{\Delta}$), the licensee should provide a supplement to the PTLR to demonstrate how the results affect the approved methodology.

5.6.7 Post Accident Monitoring Report

When a report is required by Condition B or G of LCO 3.3.[3.1], "Post Accident Monitoring (PAM) Instrumentation," a report shall be submitted within the following 14 days. The report shall outline the preplanned alternate method of monitoring, the cause of the inoperability, and the plans and schedule for restoring the instrumentation channels of the Function to OPERABLE status.

5.6.7 <u>Post Accident Monitoring Report</u> (continued)

5.7 High Radiation Area

As provided in paragraph 20.1601(c) of 10 CFR Part 20, the following controls shall be applied to high radiation areas in place of the controls required by paragraph 20.1601(a) and (b) of 10 CFR Part 20:

- 5.7.1 <u>High Radiation Areas with Dose Rates Not Exceeding 1.0 rem/hour at 30</u> <u>Centimeters from the Radiation Source or from any Surface Penetrated by the Radiation</u>
 - a. Each entryway to such an area shall be barricaded and conspicuously posted as a high radiation area. Such barricades may be opened as necessary to permit entry or exit of personnel or equipment.
 - b. Access to, and activities in, each such area shall be controlled by means of Radiation Work Permit (RWP) or equivalent that includes specification of radiation dose rates in the immediate work area(s) and other appropriate radiation protection equipment and measures.
 - c. Individuals qualified in radiation protection procedures and personnel continuously escorted by such individuals may be exempted from the requirement for an RWP or equivalent while performing their assigned duties provided that they are otherwise following plant radiation protection procedures for entry to, exit from, and work in such areas.
 - d. Each individual or group entering such an area shall possess:
 - 1. A radiation monitoring device that continuously displays radiation dose rates in the area, or
 - 2. A radiation monitoring device that continuously integrates the radiation dose rates in the area and alarms when the device's dose alarm setpoint is reached, with an appropriate alarm setpoint, or
 - 3. A radiation monitoring device that continuously transmits dose rate and cumulative dose information to a remote receiver monitored by radiation protection personnel responsible for controlling personnel radiation exposure within the area, or
 - 4. A self-reading dosimeter (e.g., pocket ionization chamber or electronic dosimeter) and,
 - Be under the surveillance, as specified in the RWP or equivalent, while in the area, of an individual qualified in radiation protection procedures, equipped with a radiation monitoring device that continuously displays radiation does rates in the area; who is responsible for controlling personnel exposure within the area, or

5.7 High Radiation Area

5.7.1 <u>High Radiation Areas with Dose Rates Not Exceeding 1.0 rem/hour at 30 Centimeters</u> from the Radiation Source or from any Surface Penetrated by the Radiation (continued)

- (ii) Be under the surveillance, as specified in the RWP or equivalent, while in the area, by means of closed circuit television, of personnel qualified in radiation protection procedures, responsible for controlling personnel radiation exposure in the area, and with the means to communicate with individuals in the area who are covered by such surveillance.
- e. Except for individuals qualified in radiation protection procedures, or personnel continuously escorted by such individuals, entry into such areas shall be made only after dose rates in the area have been determined and entry personnel are knowledgeable of them. These continuously escorted personnel will receive a pre-job briefing prior to entry into such areas. This dose rate determination, knowledge, and pre-job briefing does not require documentation prior to initial entry.
- 5.7.2 High Radiation Areas with Dose Rates Greater than 1.0 rem/hour at 30 Centimeters from the Radiation Source or from any Surface Penetrated by the Radiation, but less than 500 rads/hour at 1 Meter from the Radiation Source or from any Surface Penetrated by the Radiation
 - a. Each entryway to such an area shall be conspicuously posted as a high radiation area and shall be provided with a locked or continuously guarded door or gate that prevents unauthorized entry, and, in addition:
 - 1. All such door and gate keys shall be maintained under the administrative control of the shift supervisor, radiation protection manager, or his or her designee.
 - 2. Doors and gates shall remain locked except during periods of personnel or equipment entry or exit.
 - b. Access to, and activities in, each such area shall be controlled by means of an RWP or equivalent that includes specification of radiation does rates in the immediate work area(s) and other appropriate radiation protection equipment and measures.
 - c. Individuals qualified in radiation protection procedures may be exempted from the requirement for an RWP or equivalent while performing radiation surveys in such areas provided that they are otherwise following plant radiation protection procedures for entry to, exit from, and work in such areas.

5.7 High Radiation Area

- 5.7.2 High Radiation Areas with Dose Rates Greater than 1.0 rem/hour at 30 Centimeters from the Radiation Source or from any Surface Penetrated by the Radiation, but less than 500 rads/hour at 1 Meter from the Radiation Source or from any Surface Penetrated by the Radiation (continued)
 - d. Each individual or group entering such an area shall possess one of the following:
 - 1. A radiation monitoring device that continuously integrates the radiation rates in the area and alarms when the device's dose alarm setpoint is reached, with an appropriate alarm setpoint, or
 - 2. A radiation monitoring device that continuously transmits dose rate and cumulative dose information to a remote receiver monitored by radiation protection personnel responsible for controlling personnel radiation exposure within the area with the means to communicate with and control every individual in the area, or
 - 3. A self-reading dosimeter (e.g., pocket ionization chamber or electronic dosimeter) and,
 - Be under the surveillance, as specified in the RWP or equivalent, while in the area, of an individual qualified in radiation protection procedures, equipped with a radiation monitoring device that continuously displays radiation dose rates in the area; who is responsible for controlling personnel exposure within the area, or
 - (ii) Be under the surveillance, as specified in the RWP or equivalent, while in the area, by means of closed circuit television, of personnel qualified in radiation protection procedures, responsible for controlling personnel radiation exposure in the area, and with the means to communicate with and control every individual in the area.
 - 4. In those cases where option (2) and (3), above, are impractical or determined to be inconsistent with the "As Low As is Reasonably Achievable" principle, a radiation monitoring device that continuously displays radiation dose rates in the area.
 - e. Except for individuals qualified in radiation protection procedures, or personnel continuously escorted by such individuals, entry into such areas shall be made only after dose rates in the area have been determined and entry personnel are knowledgeable of them. These continuously escorted personnel will receive a pre-job briefing prior to entry into such areas. This dose rate determination, knowledge, and pre-job briefing does not require documentation prior to initial entry.

5.7 High Radiation Area

- 5.7.2 High Radiation Areas with Dose Rates Greater than 1.0 rem/hour at 30 Centimeters from the Radiation Source or from any Surface Penetrated by the Radiation, but less than 500 rads/hour at 1 Meter from the Radiation Source or from any Surface Penetrated by the Radiation (continued)
 - f. Such individual areas that are within a larger area where no enclosure exists for the purpose of locking and where no enclosure can reasonably be constructed around the individual area need not be controlled by a locked door or gate, nor continuously guarded, but shall be barricaded, conspicuously posted, and a clearly visible flashing light shall be activated at the area as a warning device.