



Duke Power
526 South Church Street
P.O. Box 1006
Charlotte, NC 28201-1006

November 5, 2003

U. S. Nuclear Regulatory Commission
Washington, DC 20555-0001
ATTENTION: Document Control Desk

SUBJECT: Duke Energy Corporation

McGuire Nuclear Station Units 1 and 2
Docket Nos. 50-369 and 50-370

Catawba Nuclear Station Units 1 and 2
Docket Nos. 50-413 and 50-414

License Amendment Request Applicable to Technical Specifications Limiting Condition for Operation (LCO) 3.0.4, Surveillance Requirement (SR) 3.0.4, Other Technical Specifications, and Associated Bases, Regarding MODE Change Limitations, Using the Consolidated Line Item Improvement Process (CLIIP)

In accordance with the provisions of 10 CFR 50.90, Duke Energy Corporation (Duke) is submitting a license amendment request (LAR) for the Facility Operating Licenses and Technical Specifications (TS) for McGuire Nuclear Station Units 1 and 2 and Catawba Nuclear Station Units 1 and 2. The proposed amendment would modify the TS requirements for MODE change limitations in LCO 3.0.4 and SR 3.0.4 and make conforming changes to other TS as listed in Attachment 1. Conforming changes are also being made to all associated Bases affected by this LAR and these Bases changes are included in this submittal package.

Attachment 1 provides a description of the proposed change (including a table of affected TS with a brief description of each change), the requested confirmation of applicability, and plant-specific verifications. Attachment 2 provides the existing TS pages marked up to show the proposed change. Attachment 3 provides revised (clean) TS and Bases pages. Attachment 4 provides a summary of the regulatory commitments made in this

ADD 1

submittal. Attachment 5 provides the existing TS Bases pages marked up to show the proposed change.

In conjunction with the proposed change, the Federal Register Notice¹ also stated that TS requirements for a Bases Control Program, consistent with the TS Bases Control Program described in Section 5.5 of the applicable vendor's standard TS (STS), shall be incorporated into the licensee's TS, if not already in the TS. And similarly, the STS requirements of SR 3.0.1 and associated Bases shall have been adopted. Since McGuire and Catawba have previously converted to the Improved Technical Specifications, all of these plants already have these requirements in their current approved TS. Consequently, it is not necessary to propose any additional changes to the Bases Control Program or to SR 3.0.1 and its associated Bases within this LAR for either of the Duke nuclear stations.

Implementation of this proposed change to the TS will not require revision to the McGuire or Catawba Updated Final Safety Analysis Reports (UFSAR). Since this is a CLLIP submittal, Duke is requesting NRC review and approval of this LAR by March 1, 2004, with implementation to occur following completion of the necessary personnel training, but not later than 120 days following issuance of the approved amendments.

In accordance with Duke administrative procedures and the Quality Assurance Program Topical Report, the site-specific changes contained in this proposed amendment have been reviewed and approved by the applicable McGuire and Catawba Plant Operations Review Committee. This proposed amendment has also been reviewed and approved by the Duke Nuclear Safety Review Board. Pursuant to 10 CFR 50.91, a copy of this amendment request is being sent to the designated official of the State of North Carolina and to the designated official of the State of South Carolina.

¹ 68 FR 16579, April 4, 2003, "Notice of Availability of Model Application Concerning Technical Specification Improvement to Modify Requirements Regarding Mode Change Limitations Using the Consolidated Line Item Improvement Process."

U. S. Nuclear Regulatory Commission
November 5, 2003
Page 3

Inquiries on this matter should be directed to J. S. Warren
at 704-382-4986.

Very truly yours,



W. R. McCollum, Jr.
Senior Vice President, Nuclear Support

Attachments:

Attachment 1 - Description and Assessment

Attachments 2a and 2b - Proposed Technical Specifications
Changes

Attachments 3a and 3b - Revised Technical Specifications and
Bases Pages

Attachment 4 - Regulatory Commitments

Attachments 5a and 5b - Proposed Technical Specifications
Bases Changes

U. S. Nuclear Regulatory Commission
November 5, 2003
Page 4

xc w/Attachments:

L. A. Reyes
U. S. Nuclear Regulatory Commission
Regional Administrator, Region II
Atlanta Federal Center
61 Forsyth St., SW, Suite 23T85
Atlanta, GA 30303

R. E. Martin (Addressee Only)
NRC Senior Project Manager (MNS)
U. S. Nuclear Regulatory Commission
Mail Stop O-8 H12
Washington, DC 20555-0001

S. E. Peters (Addressee Only)
NRC Senior Project Manager (CNS)
U. S. Nuclear Regulatory Commission
Mail Stop O-8 H12
Washington, DC 20555-0001

J. B. Brady
Senior Resident Inspector (MNS)
U. S. Nuclear Regulatory Commission
McGuire Nuclear Site

E. F. Guthrie
Senior Resident Inspector (CNS)
U. S. Nuclear Regulatory Commission
Catawba Nuclear Site

R. Wingard
Division of Radioactive Waste Management
South Carolina Bureau of Land and Waste Management
2600 Bull Street
Columbia, SC 29201

Beverly O. Hall, Section Chief
Radiation Protection Section
1645 Mail Service Center
Raleigh, NC 27699-1645

U. S. Nuclear Regulatory Commission
November 5, 2003
Page 5

W. R. McCollum, Jr., affirms that he is the person who
subscribed his name to the foregoing statement, and that all
the matters and facts set forth herein are true and correct
to the best of his knowledge.



W. R. McCollum, Jr., Senior Vice President

Subscribed and sworn to me: Nov 5, 2003
Date


_____, Notary Public

My commission expires: JAN 22, 2006
Date

SEAL



U. S. Nuclear Regulatory Commission
November 5, 2003
Page 6

bxc w/Attachments:

M. T. Cash
G. D. Gilbert
L. E. Nicholson
K. L. Crane
K. E. Nicholson
J. M. Ferguson (2) - CN01SA
R. V. Gambrell
A. P. Jackson
M. S. Kitlan
NRIA File/ELL
McGuire Master File - MG01DM
Catawba Master File 801.01 - CN04DM

Catawba Owners:

Saluda River Electric Corporation
P. O. Box 929
Laurens, SC 29360-0929

NC Municipal Power Agency No. 1
P. O. Box 29513
Raleigh, NC 27626-0513

T. R. Puryear
NC Electric Membership Corporation
CN03G

Piedmont Municipal Power Agency
121 Village Drive
Greer, SC 29651

Attachment 1

Description and Assessment

1.0 DESCRIPTION

The proposed amendment would modify the McGuire Nuclear Station and Catawba Nuclear Station Technical Specifications (TS) Limiting Condition for Operation (LCO) requirements for MODE change limitations contained in LCO 3.0.4, and the Surveillance Applicability Requirements (SR) contained in SR 3.0.4, and various additional TS that reference LCO 3.0.4 by means of NOTES. The changes are consistent with an NRC-approved Industry Technical Specifications Task Force (TSTF) Standard TS (STS) Traveler¹ as published in the Federal Register^{2,3} and modified by NRC comments.³ The referenced Federal Register notices announced the availability of this TS improvement through the Consolidated Line Item Improvement Process (CLIIP).

2.0 ASSESSMENT

2.1 Applicability of Published Safety Evaluation

Duke Energy Corporation (Duke) has reviewed the safety evaluation published² on August 2, 2002 as part of the CLIIP. This review included a review of the NRC Staff's evaluation as well as the supporting information for the TSTF¹. Duke has concluded that the justifications presented in the TSTF proposal and the safety evaluation prepared by the NRC Staff are applicable to McGuire Units 1 and 2 and Catawba Units 1 and 2. Further, Duke has determined these discussions justify this amendment for incorporation into the McGuire and Catawba TS.

2.2 Optional Changes and Variations

It is noted that there are differences between some TS numbers and titles for those TS that are changed within the TSTF, and the number and title for the corresponding TS for the Duke nuclear stations. Tables 1 and 2, included within Attachment 1, list the TS numbers and titles changed by the TSTF and the

¹ TSTF-359, Revision 9, entitled "Increase Flexibility in MODE Restraints."

² 67 FR 50475, August 2, 2002, "Notice of Opportunity to Comment on Model Safety Evaluation on Technical Specification Improvement to Modify Requirements Regarding Mode Change Limitations Using the Consolidated Line Item Improvement Process."

³ 68 FR 16579, April 4, 2003, "Notice of Availability of Model Application Concerning Technical Specification Improvement to Modify Requirements Regarding Mode Change Limitations Using the Consolidated Line Item Improvement Process."

Attachment 1

Description and Assessment

corresponding McGuire or Catawba TS to which the applicable change was applied. In the left column, as requested in the Federal Register, the tables also provide a brief description of each change being proposed to the McGuire and Catawba TS. Also note that for McGuire and Catawba TS 3.5.3, ECCS - Shutdown, "high head subsystem," as used in the STS and the TSTF, is changed to "centrifugal charging subsystem," in order to agree with the terminology of the current McGuire and Catawba TS. These are Duke's only variations from the TS changes described in the TSTF¹ or from the NRC's model safety evaluation and CLIIP notice as published in the Federal Register.^{2,3}

3.0 REGULATORY ANALYSIS

3.1 No Significant Hazards Consideration Determination

Duke has reviewed the proposed No Significant Hazards Consideration Determination (NSHCD) published in the Federal Register³ as part of the CLIIP. Duke has concluded that the proposed NSHCD presented in the Federal Register notice is applicable to McGuire and Catawba and is hereby incorporated by reference to satisfy the applicable regulations.⁴

3.2 Verification and Commitments

As discussed in the notice of availability published in the Federal Register,³ for this TS improvement, plant-specific verifications were performed as follows:

- Duke has established TS Bases for LCO 3.0.4 and SR 3.0.4 which state that use of the MODE change limitation flexibility established by LCO 3.0.4 and SR 3.0.4 is not to be interpreted as endorsing the failure to exercise the good practice of restoring systems or components to operable status before entering an associated MODE or other specified condition in the TS Applicability.
- The modification also includes changes to the Bases for LCO 3.0.4 and SR 3.0.4 that provide details on how to implement the new requirements. The Bases changes provide guidance

⁴ 10 CFR 50.92, "Issuance of amendment."

Attachment 1

Description and Assessment

for changing MODES or other specified conditions in the Applicability when an LCO is not met. The bases changes describe in detail how:

- LCO 3.0.4.a allows entry into a MODE or other specified condition in the Applicability with the LCO not met when the associated ACTIONS to be entered permit continued operation in the MODE or other specified condition in the Applicability for an unlimited period of time;
- LCO 3.0.4.b allows entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, consideration of the results, determination of the acceptability of entering the MODE or other specified condition in the Applicability, and establishment of risk management actions, if appropriate; and
- LCO 3.0.4.c allows entry into a MODE or other specified condition in the applicability with the LCO not met based on a NOTE in the Specification, which is typically applied to Specifications which describe values and parameters (e.g., RCS Specific Activity), though it may be applied to other Specifications based on plant-specific approval by the NRC.

The bases also state that any risk impact should be managed through the program in place to implement 10 CFR 50.65(a)(4) and its implementation guidance, NRC Regulatory Guide 1.182, "Assessing and Managing Risks Before Maintenance Activities at Nuclear Power Plants," and that the results of the risk assessment shall be considered in determining the acceptability of entering the MODE or other specified condition in the Applicability, and any corresponding risk management actions. In addition, the bases state that upon entry into a MODE or other specified condition in the Applicability with the LCO not met, LCO 3.0.1 and LCO 3.0.2 require entry into the applicable Conditions and Required Actions for no more than the duration of the applicable Completion Time or until the LCO is met or the unit is not within the Applicability of the TS. The bases also state that SR 3.0.4 does not restrict changing MODES or other specified conditions of the Applicability when a Surveillance has

Attachment 1

Description and Assessment

not been performed within the specified Frequency, provided the requirement to declare the LCO not met has been delayed in accordance with SR 3.0.3. Finally, both McGuire and Catawba each already have a bases control program consistent with Section 5.5 of the STS, and each has the equivalent of STS SR 3.0.1 and associated bases.

4.0 ENVIRONMENTAL CONSIDERATION

Duke has reviewed the environmental consideration included in the model safety evaluation dated August 2, 2002 as part of the CLIIP. Duke has determined that the NRC Staff's findings presented in that discussion are applicable to McGuire and Catawba and the environmental consideration is hereby incorporated by reference for this application.

Attachment 1

Description and Assessment

TABLE 1

MCGUIRE

McGuire Technical Specifications and Bases Number/Title and Change Description	TSTF-359, Rev. 9 Standard Technical Specifications and Bases Number/Title
LCO 3.0.4, MODE Restraints Revises this LCO consistent with the TSTF.	LCO 3.0.4, MODE Restraints
SR 3.0.4 Revises this LCO consistent with the TSTF.	SR 3.0.4
3.3.3, Post Accident Monitoring (PAM) Instrumentation Deletes current ACTIONS NOTE which states LCO 3.0.4 is not applicable.	3.3.3, Post Accident Monitoring (PAM) Instrumentation
3.3.4, Remote Shutdown System Deletes current ACTIONS NOTE which states LCO 3.0.4 is not applicable.	3.3.4, Remote Shutdown System
3.4.11, Pressurizer Power Operated Relief Valves (PORVs) Deletes current ACTIONS NOTE which states LCO 3.0.4 is not applicable.	3.4.11, Pressurizer Power Operated Relief Valves (PORVS)
3.4.12, Low Temperature Overpressure Protection (LTOP) System Replaces current ACTIONS NOTE, which now states that LCO 3.0.4 is not applicable, with a new NOTE stating that LCO 3.0.4.b is not applicable when entering MODE 4.	3.4.12, Low Temperature Overpressure Protection (LTOP) System
3.4.15, RCS Leakage Detection Instr. Deletes current ACTIONS NOTE which states LCO 3.0.4 is not applicable.	3.4.15, RCS Leakage Detection Instr.

Attachment 1

Description and Assessment

TABLE 1 (Continued)

MCGUIRE

McGuire Technical Specifications and Bases Number/Title and Change Description	TSTF-359, Rev. 9 Standard Technical Specifications and Bases Number/Title
3.4.16, RCS Specific Activity Replaces current REQUIRED ACTION A.1 NOTE, which now states that LCO 3.0.4 is not applicable, with a new NOTE stating that LCO 3.0.4.c is applicable.	3.4.16, RCS Specific Activity
3.5.3, ECCS – Shutdown Adds a new ACTIONS NOTE stating that LCO 3.0.4.b is not applicable.	3.5.3, ECCS – Shutdown
3.6.7, Hydrogen Recombiners Deletes current REQUIRED ACTION A.1 NOTE which states LCO 3.0.4 is not applicable.	3.6.8, Hydrogen Recombiners (Atmospheric, Subatmospheric, Ice Condenser, and Dual) (if permanently installed)
3.6.8, Hydrogen Skimmer System Deletes current REQUIRED ACTION A.1 NOTE which states that LCO 3.0.4 is not applicable.	3.6.9, Hydrogen Mixing System (HMS) (Atmospheric, Ice Condenser, and Dual)
3.7.4, Steam Generator Power Operated Relief Valves (SG PORVs) Deletes current REQUIRED ACTION A.1 NOTE which states that LCO 3.0.4 is not applicable.	3.7.4, Auxiliary Feedwater (AFW) System Atmospheric Dump Valves
3.7.5, Auxiliary Feedwater (AFW) System Adds a new ACTIONS NOTE stating that LCO 3.0.4.b is not applicable when entering MODE 1.	3.7.5, Auxiliary Feedwater (AFW) System
3.8.1, AC Sources – Operating Adds a new ACTIONS NOTE stating that LCO 3.0.4.b is not applicable to DGs.	3.8.1, AC Sources - Operating

Attachment 1

Description and Assessment

TABLE 2

CATAWBA

Catawba Technical Specifications and Bases Number/Title and Change Description	TSTF-359, Rev. 9 Standard Technical Specifications and Bases Number/Title
LCO 3.0.4, MODE Restraints Revises this LCO consistent with the TSTF.	LCO 3.0.4, MODE Restraints
SR 3.0.4 Revises this LCO consistent with the TSTF.	SR 3.0.4
3.3.3, Post Accident Monitoring (PAM) Instrumentation Deletes current ACTIONS NOTE which states LCO 3.0.4 is not applicable.	3.3.3, Post Accident Monitoring (PAM) Instrumentation
3.3.4, Remote Shutdown System Deletes current ACTIONS NOTE which states LCO 3.0.4 is not applicable.	3.3.4, Remote Shutdown System
3.4.11, Pressurizer Power Operated Relief Valves (PORVs) Deletes current ACTIONS NOTE which states LCO 3.0.4 is not applicable.	3.4.11, Pressurizer Power Operated Relief Valves (PORVS)
3.4.12, Low Temperature Overpressure Protection (LTOP) System Replaces current ACTIONS NOTE, which now states that LCO 3.0.4 is not applicable, with a new NOTE stating that LCO 3.0.4.b is not applicable when entering MODE 4.	3.4.12, Low Temperature Overpressure Protection (LTOP) System
3.4.15, RCS Leakage Detection Instr. Deletes current ACTIONS NOTE which states LCO 3.0.4 is not applicable.	3.4.15, RCS Leakage Detection Instr.

Attachment 1

Description and Assessment

TABLE 2 (Continued)

CATAWBA

Catawba Technical Specifications and Bases Number/Title and Change Description	TSTF-359, Rev. 9 Standard Technical Specifications and Bases Number/Title
3.4.16, RCS Specific Activity Replaces current REQUIRED ACTION A.1 NOTE, which now states that LCO 3.0.4 is not applicable, with a new NOTE stating that LCO 3.0.4.c is applicable.	3.4.16, RCS Specific Activity
3.5.3, ECCS – Shutdown Adds a new ACTIONS NOTE stating that LCO 3.0.4.b is not applicable.	3.5.3, ECCS – Shutdown
3.6.7, Hydrogen Recombiners Deletes current REQUIRED ACTION A.1 NOTE which states LCO 3.0.4 is not applicable.	3.6.8, Hydrogen Recombiners (Atmospheric, Subatmospheric, Ice Condenser, and Dual) (if permanently installed)
3.6.8, Hydrogen Skimmer System Deletes current REQUIRED ACTION A.1 NOTE which states that LCO 3.0.4 is not applicable.	3.6.9, Hydrogen Mixing System (HMS) (Atmospheric, Ice Condenser, and Dual)
3.7.4, Steam Generator Power Operated Relief Valves (SG PORVs) Deletes current REQUIRED ACTION A.1 NOTE which states that LCO 3.0.4 is not applicable.	3.7.4, Auxiliary Feedwater (AFW) System Atmospheric Dump Valves
3.7.5, Auxiliary Feedwater (AFW) System Adds a new ACTIONS NOTE stating that LCO 3.0.4.b is not applicable when entering MODE 1.	3.7.5, Auxiliary Feedwater (AFW) System
3.8.1, AC Sources – Operating Adds a new ACTIONS NOTE stating that LCO 3.0.4.b is not applicable to DGs.	3.8.1, AC Sources - Operating

Attachment 2a

McGuire Units 1 and 2

Proposed Technical Specifications Changes (Mark-up)

3.0 LIMITING CONDITION FOR OPERATION (LCO) APPLICABILITY

LCO 3.0.1 LCOs shall be met during the MODES or other specified conditions in the Applicability, except as provided in LCO 3.0.2 and 3.0.7.

LCO 3.0.2 Upon discovery of a failure to meet an LCO, the Required Actions of the associated Conditions shall be met, except as provided in LCO 3.0.5 and LCO 3.0.6.

If the LCO is met or is no longer applicable prior to expiration of the specified Completion Time(s), completion of the Required Action(s) is not required unless otherwise stated.

LCO 3.0.3 When an LCO is not met and the associated ACTIONS are not met, an associated ACTION is not provided, or if directed by the associated ACTIONS, the unit shall be placed in a MODE or other specified condition in which the LCO is not applicable. Action shall be initiated within 1 hour to place the unit, as applicable, in:

- a. MODE 3 within 7 hours;
- b. MODE 4 within 13 hours; and
- c. MODE 5 within 37 hours.

Exceptions to this Specification are stated in the individual Specifications.

Where corrective measures are completed that permit operation in accordance with the LCO or ACTIONS, completion of the actions required by LCO 3.0.3 is not required.

LCO 3.0.3 is only applicable in MODES 1, 2, 3, and 4.

LCO 3.0.4

When an LCO is not met, entry into a MODE or other specified condition in the Applicability shall not be made except when the associated ACTIONS to be entered permit continued operation in the MODE or other specified condition in the Applicability for an unlimited period of time. This Specification shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS. Exceptions to this Specification are stated in the individual Specifications.

INSERT 1

(continued)

INSERT 1 (LCO 3.0.4) – TSTF 359, REV 9

When an LCO is not met, entry into a MODE or other specified condition in the Applicability shall only be made:

- a. When the associated ACTIONS to be entered permit continued operation in the MODE or other specified condition in the Applicability for an unlimited period of time;
- b. After performance of a risk assessment addressing inoperable systems and components, consideration of the results, determination of the acceptability of entering the MODE or other specified condition in the Applicability, and establishment of risk management actions, if appropriate; exceptions to this Specification are stated in the individual Specifications; or
- c. When an allowance is stated in the individual value, parameter, or other Specification.

This Specification shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS or that are part of a shutdown of the unit.

3.0 SR APPLICABILITY (continued)

SR 3.0.4

Entry into a MODE or other specified condition in the Applicability of an LCO shall not be made unless the LCO's Surveillances have been met within their specified Frequency. This provision shall not prevent entry into MODES or other specified conditions in the Applicability that are required to comply with ACTIONS.

SR 3.0.5

Surveillance Requirements shall apply to each unit individually unless otherwise indicated as stated in LCO 3.0.8 for individual Specifications or whenever certain portions of a Specification contain surveillance parameters different for each unit, which will be identified in parentheses or footnotes.

INSERT 2

INSERT 2 (SR 3.0.4) – TSTF-359, REV 9

Entry into a MODE or other specified condition in the Applicability of an LCO shall only be made when the LCO's Surveillances have been met within their specified Frequency, except as provided by SR 3.0.3. When an LCO is not met due to Surveillances not having been met, entry into a MODE or other specified condition in the Applicability shall only be made in accordance with LCO 3.0.4.

This provision shall not prevent entry into MODES or other specified conditions in the Applicability that are required to comply with ACTIONS or that are part of a shutdown of the unit.

3.3 INSTRUMENTATION

3.3.3 Post Accident Monitoring (PAM) Instrumentation

LCO 3.3.3 The PAM instrumentation for each Function in Table 3.3.3-1 shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

NOTES

1. LCO 3.0.4 is not applicable.

2. Separate Condition entry is allowed for each Function.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more Functions with one or more required channels inoperable.	A.1 Enter the Condition referenced in Table 3.3.3-1 for the channel.	Immediately
B. One or more Functions with one required channel inoperable.	B.1 Restore required channel to OPERABLE status.	30 days
C. Required Action and associated Completion Time of Condition B not met.	C.1 Initiate action in accordance with Specification 5.6.7	Immediately
D. One or more Functions with one required channel inoperable.	D.1 Restore required channel to OPERABLE status.	7 days

(continued)

3.3 INSTRUMENTATION

3.3.4 Remote Shutdown System

LCO 3.3.4 The Remote Shutdown System Functions in Table 3.3.4-1 shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

NOTE 2

1. LCO 3.0.4 is not applicable.

2. Separate Condition entry is allowed for each Function.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more required Functions inoperable.	A.1 Restore required Function to OPERABLE status.	30 days
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3.	6 hours
	<u>AND</u> B.2 Be in MODE 4.	12 hours

3.4 REACTOR COOLANT SYSTEM (RCS)

3.4.11 Pressurizer Power Operated Relief Valves (PORVs)

LCO 3.4.11 Each PORV and associated block valve shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

NOTES

1. Separate Condition entry is allowed for each PORV.

2. LCO 3.0.4 is not applicable.

CONDITION		REQUIRED ACTION	COMPLETION TIME
A.	One or more PORVs inoperable and capable of being manually cycled.	A.1 Close and maintain power to associated block valve.	1 hour
B.	One or two PORVs inoperable and not capable of being manually cycled.	<p>-----NOTE----- Required Actions B.1 and B.2 are not applicable to a PORV made inoperable by Required Action C.2.</p> <p>B.1 Close associated block valves.</p> <p><u>AND</u></p> <p>B.2 Remove power from associated block valves.</p> <p><u>AND</u></p>	<p>1 hour</p> <p>1 hour</p> <p>(continued)</p>

WOG INSERT 1

ACTIONS

NOTE
 LCO 3.0.4 is not applicable.

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. Two centrifugal charging pumps capable of injecting into the RCS.</p> <p><u>OR</u></p> <p>One centrifugal charging pump and one safety injection pump capable of injecting into the RCS.</p> <p><u>OR</u></p> <p>Two safety injection pumps capable of injecting into the RCS.</p>	<p>A.1 NOTE</p> <p>Two centrifugal charging pumps may be capable of injecting into the RCS during pump swap operation for ≤ 15 minutes.</p> <p>Initiate action to verify a maximum of one centrifugal charging pump or one safety injection pump is capable of injecting into the RCS.</p> <p><u>OR</u></p> <p>A.2.1 Verify RHR suction relief valve is OPERABLE and the suction isolation valves are open.</p> <p><u>AND</u></p> <p>A.2.2.1 Verify RCS cold leg temperature $> 167^{\circ}\text{F}$.</p> <p><u>OR</u></p> <p>A.2.2.2 Verify RCS cold leg temperature $> 107^{\circ}\text{F}$ and cooldown rate $< 20^{\circ}\text{F/hr}$.</p> <p><u>OR</u></p>	<p>Immediately</p> <p>Immediately</p> <p>Immediately</p> <p>Immediately</p> <p>(continued)</p>

WOG INSERT 1 (LCO 3.4.12, LTOP) – TSTF-359, REV 9

-----NOTE-----

LCO 3.0.4.b is not applicable when entering MODE 4.

3.4 REACTOR COOLANT SYSTEM (RCS)

3.4.16 RCS Specific Activity

LCO 3.4.16 The specific activity of the reactor coolant shall be within limits.

APPLICABILITY: MODES 1 and 2,
MODE 3 with RCS average temperature (T_{avg}) \geq 500°F.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. DOSE EQUIVALENT I-131 > 1.0 μCi/gm.</p>	<div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;"> <p style="text-align: center;">Note LCO 3.0.4 is not applicable.</p> </div> <p>A.1 Verify DOSE EQUIVALENT I-131 within the acceptable region of Figure 3.4.16-1.</p> <p><u>AND</u></p> <p>A.2 Restore DOSE EQUIVALENT I-131 to within limit.</p>	<div style="border: 1px solid black; border-radius: 50%; padding: 10px; display: inline-block; margin-bottom: 10px;"> <p>INSERT ?</p> </div> <p>Once per 4 hours</p> <p>48 hours</p>
<p>B. Gross specific activity of the reactor coolant not within limit.</p>	<p>B.1 Be in MODE 3 with T_{avg} < 500°F.</p>	<p>6 hours</p>

(continued)

INSERT 7 (RCS SPECIFIC ACTIVITY) – TSTF-359, REV 9

-----NOTE-----

LCO 3.0.4.c is applicable.

3.5 EMERGENCY CORE COOLING SYSTEMS (ECCS)

3.5.3 ECCS—Shutdown

LCO 3.5.3 One ECCS train shall be OPERABLE.

APPLICABILITY: MODE 4.

WOG INSERT 2

ACTIONS ←

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Required ECCS residual heat removal (RHR) subsystem inoperable.	A.1 Initiate action to restore required ECCS RHR subsystem to OPERABLE status.	Immediately
B. Required ECCS centrifugal charging subsystem inoperable.	B.1 Restore required ECCS centrifugal charging subsystem to OPERABLE status.	1 hour
C. Required Action and associated Completion Time of Condition B not met.	C.1 Be in MODE 5.	24 hours

WOG INSERT 2 (LCO 3.5.3, ECCS SHUTDOWN) – TSTF-359, REV 9

-----NOTE-----

LCO 3.0.4.b is not applicable to ECCS centrifugal charging subsystem.

3.6 CONTAINMENT SYSTEMS

3.6.7 Hydrogen Recombiners

LCO 3.6.7 Two hydrogen recombiners shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. One hydrogen recombinder inoperable.</p>	<p>A.1</p> <div style="border: 1px solid black; border-radius: 15px; padding: 5px; margin: 10px auto; width: fit-content;"> <p style="text-align: center;">NOTE LCO 3.0.4 is not applicable.</p> </div> <p>Restore hydrogen recombinder to OPERABLE status.</p>	<p>30 days</p>
<p>B. Required Action and associated Completion Time not met.</p>	<p>B.1 Be in MODE 3.</p>	<p>6 hours</p>

3.6 CONTAINMENT SYSTEMS

3.6.8 Hydrogen Skimmer System (HSS)

LCO 3.6.8 Two HSS trains shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. One HSS train inoperable.</p>	<p>A.1 NOTE LCO 3.0.4 is not applicable Restore HSS train to OPERABLE status.</p>	<p>30 days</p>
<p>B. Required Action and associated Completion Time not met.</p>	<p>B.1 Be in MODE 3.</p>	<p>6 hours</p>


3.7 PLANT SYSTEMS

3.7.4 Steam Generator Power Operated Relief Valves (SG PORVs)

LCO 3.7.4 Three SG PORV lines shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3,
MODE 4 when steam generator is relied upon for heat removal.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. One required SG PORV line inoperable.</p>	<p>A.1  Restore required SG PORV line to OPERABLE status.</p>	<p>7 days</p>
<p>B. Two or more required SG PORV lines inoperable.</p>	<p>B.1 Restore all but one required SG PORV line to OPERABLE status.</p>	<p>24 hours</p>
<p>C. Required Action and associated Completion Time not met.</p>	<p>C.1 Be in MODE 3. <u>AND</u> C.2 Be in MODE 4 without reliance upon steam generator for heat removal.</p>	<p>6 hours 12 hours</p>

3.7 PLANT SYSTEMS

3.7.5 Auxiliary Feedwater (AFW) System

LCO 3.7.5 Three AFW trains shall be OPERABLE.

-----NOTE-----
Only one AFW train, which includes a motor driven pump, is required to be OPERABLE in MODE 4.

APPLICABILITY: MODES 1, 2, and 3,
MODE 4 when steam generator is relied upon for heat removal.

WOG INSERT 3

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One steam supply to turbine driven AFW pump inoperable.	A.1 Restore steam supply to OPERABLE status.	7 days <u>AND</u> 10 days from discovery of failure to meet the LCO
B. One AFW train inoperable in MODE 1, 2 or 3 for reasons other than Condition A.	B.1 Restore AFW train to OPERABLE status.	72 hours <u>AND</u> 10 days from discovery of failure to meet the LCO

(continued)

WOG INSERT 3 (LCO 3.7.5, AFW SYSTEM) – TSTF-359, REV 9

-----NOTE-----

LCO 3.0.4.b is not applicable when entering MODE 1.

3.8 ELECTRICAL POWER SYSTEMS

3.8.1 AC Sources—Operating

LCO 3.8.1 The following AC electrical sources shall be OPERABLE:

- a. Two qualified circuits between the offsite transmission network and the Onsite Essential Auxiliary Power System; and
- b. Two diesel generators (DGs) capable of supplying the Onsite Essential Auxiliary Power Systems;

AND

The automatic load sequencers for Train A and Train B shall be OPERABLE.

APPLICABILITY: MODES 1, 2, 3, and 4.

WOG INSERT 4

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One offsite circuit inoperable.	A.1 Perform SR 3.8.1.1 for OPERABLE offsite circuit.	1 hour
	<u>AND</u>	<u>AND</u>
	A.2 Declare required feature(s) with no offsite power available inoperable when its redundant required feature(s) is inoperable.	Once per 8 hours thereafter
	<u>AND</u>	24 hours from discovery of no offsite power to one train concurrent with inoperability of redundant required feature(s)
	<u>AND</u>	

(continued)

WOG INSERT 4 (LCO 3.8.1, AC SOURCES - OPERATING) – TSTF-359, REV 9

-----NOTE-----

LCO 3.0.4.b is not applicable to DGs.

Attachment 2b

Catawba Units 1 and 2

Proposed Technical Specifications Changes (Mark-up)

3.0 LIMITING CONDITION FOR OPERATION (LCO) APPLICABILITY

LCO 3.0.1 LCOs shall be met during the MODES or other specified conditions in the Applicability, except as provided in LCO 3.0.2 and 3.0.7.

LCO 3.0.2 Upon discovery of a failure to meet an LCO, the Required Actions of the associated Conditions shall be met, except as provided in LCO 3.0.5 and LCO 3.0.6.

If the LCO is met or is no longer applicable prior to expiration of the specified Completion Time(s), completion of the Required Action(s) is not required unless otherwise stated.

LCO 3.0.3 When an LCO is not met and the associated ACTIONS are not met, an associated ACTION is not provided, or if directed by the associated ACTIONS, the unit shall be placed in a MODE or other specified condition in which the LCO is not applicable. Action shall be initiated within 1 hour to place the unit, as applicable, in:

- a. MODE 3 within 7 hours;
- b. MODE 4 within 13 hours; and
- c. MODE 5 within 37 hours.

Exceptions to this Specification are stated in the individual Specifications.

Where corrective measures are completed that permit operation in accordance with the LCO or ACTIONS, completion of the actions required by LCO 3.0.3 is not required.

LCO 3.0.3 is only applicable in MODES 1, 2, 3, and 4.

LCO 3.0.4

When an LCO is not met, entry into a MODE or other specified condition in the Applicability shall not be made except when the associated ACTIONS to be entered permit continued operation in the MODE or other specified condition in the Applicability for an unlimited period of time. This Specification shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS.

Exceptions to this Specification are stated in the individual Specifications.

INSERT 1

(continued)

INSERT 1 (LCO 3.0.4) – TSTF 359, REV 9

When an LCO is not met, entry into a MODE or other specified condition in the Applicability shall only be made:

- a. When the associated ACTIONS to be entered permit continued operation in the MODE or other specified condition in the Applicability for an unlimited period of time;
- b. After performance of a risk assessment addressing inoperable systems and components, consideration of the results, determination of the acceptability of entering the MODE or other specified condition in the Applicability; and establishment of risk management actions, if appropriate; exceptions to this Specification are stated in the individual Specifications; or
- c. When an allowance is stated in the individual value, parameter, or other Specification.

This Specification shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS or that are part of a shutdown of the unit.

3.0 SR APPLICABILITY (continued)

SR 3.0.4

INSERT 2

Entry into a MODE or other specified condition in the Applicability of an LCO shall not be made unless the LCO's Surveillances have been met within their specified Frequency. This provision shall not prevent entry into MODES or other specified conditions in the Applicability that are required to comply with ACTIONS.

SR 3.0.5

Surveillance Requirements shall apply to each unit individually unless otherwise indicated as stated in LCO 3.0.8 for individual Specifications or whenever certain portions of a Specification contain surveillance parameters different for each unit, which will be identified in parentheses or footnotes.

INSERT 2 (SR 3.0.4) – TSTF-359, REV 9

Entry into a MODE or other specified condition in the Applicability of an LCO shall only be made when the LCO's Surveillances have been met within their specified Frequency, except as provided by SR 3.0.3. When an LCO is not met due to Surveillances not having been met, entry into a MODE or other specified condition in the Applicability shall only be made in accordance with LCO 3.0.4.

This provision shall not prevent entry into MODES or other specified conditions in the Applicability that are required to comply with ACTIONS or that are part of a shutdown of the unit.

3.3 INSTRUMENTATION

3.3.3 Post Accident Monitoring (PAM) Instrumentation

LCO 3.3.3 The PAM instrumentation for each Function in Table 3.3.3-1 shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

-----NOTE-----
The Hydrogen Monitors are not required in MODE 3.

ACTIONS

- NOTE-----
1. LCO 3.0.4 is not applicable.
 2. Separate Condition entry is allowed for each Function.
-

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more Functions with one or more required channels inoperable.	A.1 Enter the Condition referenced in Table 3.3.3-1 for the channel.	Immediately
B. One or more Functions with one required channel inoperable.	B.1 Restore required channel to OPERABLE status.	30 days
C. One or more Functions with one required channel inoperable. <u>AND</u> Diverse channel OPERABLE.	C.1 Restore required channel to OPERABLE status.	30 days

(continued)

3.3 INSTRUMENTATION

3.3.4 Remote Shutdown System

LCO 3.3.4 The Remote Shutdown System Functions in Table 3.3.4-1 shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

NOTES

1. LCO 3.0.4 is not applicable.

2. Separate Condition entry is allowed for each Function.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more required Functions inoperable.	A.1 Restore required Function to OPERABLE status.	30 days
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3.	6 hours
	<u>AND</u> B.2 Be in MODE 4.	12 hours

3.4 REACTOR COOLANT SYSTEM (RCS)

3.4.11 Pressurizer Power Operated Relief Valves (PORVs)

LCO 3.4.11 Each PORV and associated block valve shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

NOTES

1. Separate Condition entry is allowed for each PORV.
2. LCO 3.0.4 is not applicable.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more PORVs inoperable and capable of being manually cycled.	A.1 Close and maintain power to associated block valve.	1 hour
B. One or two PORVs inoperable and not capable of being manually cycled.	B.1 Close associated block valves.	1 hour
	<u>AND</u>	
	B.2 Remove power from associated block valves.	1 hour
	<u>AND</u>	
	B.3 Restore PORV(s) to OPERABLE status.	72 hours

(continued)

WOG INSERT 1

ACTIONS

LCO 3.0.4 is not applicable.	NOTE	
------------------------------	------	--

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. Two or more charging pumps capable of injecting into the RCS.</p> <p><u>OR</u></p> <p>One charging pump and one safety injection pump capable of injecting into the RCS.</p> <p><u>OR</u></p> <p>Two or more safety injection pumps capable of injecting into the RCS.</p>	<p>-----NOTE-----</p> <p>Two charging pumps may be capable of injecting into the RCS during pump swap operation for \leq 15 minutes.</p> <hr/> <p>A.1 Initiate action to verify a maximum of one charging pump or one safety injection pump is capable of injecting into the RCS.</p>	<p>Immediately</p>
<p>B. Reactor coolant pump operation not limited as specified in Table 3.4.12-1.</p>	<p>B.1 Initiate action to limit pump operation as specified in Table 3.4.12-1.</p>	<p>Immediately</p>
<p>C. An accumulator not isolated when the accumulator pressure is greater than or equal to the maximum RCS pressure for existing cold leg temperature allowed in Specification 3.4.3.</p>	<p>C.1 Isolate affected accumulator.</p>	<p>1 hour</p>

(continued)

WOG INSERT 1 (LCO 3.4.12, LTOP) – TSTF-359, REV 9

-----NOTE-----

LCO 3.0.4.b is not applicable when entering MODE 4.

3.4 REACTOR COOLANT SYSTEM (RCS)

3.4.15 RCS Leakage Detection Instrumentation

LCO 3.4.15 The following RCS leakage detection instrumentation shall be OPERABLE:

- a. One containment floor and equipment sump level monitor;
- b. One containment atmosphere radioactivity monitor (gaseous or particulate); and
- c. One containment ventilation unit condensate drain tank level monitor.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTIONS

~~NOTE~~
 LCO 3.0.4 is not applicable.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Required containment floor and equipment sump level monitor inoperable.	A.1 Perform SR 3.4.13.1. <u>AND</u> A.2 Restore required containment floor and equipment sump level monitor to OPERABLE status.	Once per 24 hours 30 days

(continued)

3.4 REACTOR COOLANT SYSTEM (RCS)

3.4.16 RCS Specific Activity

LCO 3.4.16 The specific activity of the reactor coolant shall be within limits.

APPLICABILITY: MODES 1 and 2,
MODE 3 with RCS average temperature (T_{avg}) \geq 500°F.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. DOSE EQUIVALENT I-131 > 1.0 μCi/gm.</p>	<p>Note LCO 3.0/4 is not applicable.</p> <p>A.1 Verify DOSE EQUIVALENT I-131 within the acceptable region of Figure 3.4.16-1.</p> <p><u>AND</u></p> <p>A.2 Restore DOSE EQUIVALENT I-131 to within limit.</p>	<p>Once per 4 hours</p> <p>48 hours</p>
<p>B. Gross specific activity of the reactor coolant not within limit.</p>	<p>B.1 Be in MODE 3 with $T_{avg} < 500^\circ\text{F}$.</p>	<p>6 hours</p>

(continued)

INSERT 7 (RCS SPECIFIC ACTIVITY) – TSTF-359, REV 9

-----NOTE-----

LCO 3.0.4.c is applicable.

3.5 EMERGENCY CORE COOLING SYSTEMS (ECCS)

3.5.3 ECCS—Shutdown

LCO 3.5.3 One ECCS train shall be OPERABLE.

APPLICABILITY: MODE 4.

WOG INSERT 2

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Required ECCS residual heat removal (RHR) subsystem inoperable.	A.1 Initiate action to restore required ECCS RHR subsystem to OPERABLE status.	Immediately
B. Required ECCS centrifugal charging subsystem inoperable.	B.1 Restore required ECCS centrifugal charging subsystem to OPERABLE status.	1 hour
C. Required Action and associated Completion Time of Condition B not met.	C.1 Be in MODE 5.	24 hours

WOG INSERT 2 (LCO 3.5.3, ECCS SHUTDOWN) – TSTF-359, REV 9

-----NOTE-----

LCO 3.0.4.b is not applicable to ECCS centrifugal charging subsystem.

3.6 CONTAINMENT SYSTEMS

3.6.7 Hydrogen Recombiners

LCO 3.6.7 Two hydrogen recombiners shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. One hydrogen recombinder inoperable.</p>	<p>A.1</p> <div style="border: 1px solid black; padding: 5px; width: fit-content; margin: 5px 0;"> <p style="text-align: center;">NOTE</p> <p>LCO 3.0.4 is not applicable.</p> </div> <p>Restore hydrogen recombinder to OPERABLE status.</p>	<p>30 days</p>
<p>B. Required Action and associated Completion Time not met.</p>	<p>B.1 Be in MODE 3.</p>	<p>6 hours</p>

3.6 CONTAINMENT SYSTEMS

3.6.8 Hydrogen Skimmer System (HSS)

LCO 3.6.8 Two HSS trains shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. One HSS train inoperable.</p>	<p>A.1</p> <div style="border: 1px solid black; padding: 5px; margin: 10px 0;"> <p style="text-align: center;">-----NOTE----- LCO 3.0.4 is not applicable.</p> </div> <p>Restore HSS train to OPERABLE status.</p>	<p>30 days</p>
<p>B. Required Action and associated Completion Time not met.</p>	<p>B.1 Be in MODE 3.</p>	<p>6 hours</p>


3.7 PLANT SYSTEMS

3.7.4 Steam Generator Power Operated Relief Valves (SG PORVs)

LCO 3.7.4 Four SG PORV lines shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3,
MODE 4 when steam generator is relied upon for heat removal.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One SG PORV line inoperable.	A.1  Restore SG PORV line to OPERABLE status.	7 days
B. Two or more SG PORV lines inoperable.	B.1 Restore all but one SG PORV line to OPERABLE status.	24 hours
C. Required Action and associated Completion Time not met.	C.1 Be in MODE 3. <u>AND</u> C.2 Be in MODE 4 without reliance upon steam generator for heat removal.	6 hours 12 hours

3.7 PLANT SYSTEMS

3.7.5 Auxiliary Feedwater (AFW) System

LCO 3.7.5 Three AFW trains shall be OPERABLE*.

-----NOTE-----
Only one AFW train, which includes a motor driven pump, is required to be OPERABLE in MODE 4.

APPLICABILITY: MODES 1, 2, and 3,
MODE 4 when steam generator is relied upon for heat removal.

ACTIONS

WOG INSERT 3

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One steam supply to turbine driven AFW pump inoperable.	A.1 Restore steam supply to OPERABLE status.	7 days <u>AND</u> 10 days from discovery of failure to meet the LCO
B. One AFW train inoperable in MODE 1, 2 or 3 for reasons other than Condition A.	B.1 Restore AFW train to OPERABLE status.	72 hours* <u>AND</u> 10 days* from discovery of failure to meet the LCO

(continued)

*For each AFW train on Unit 2, the Completion Time that one AFW train can be inoperable as specified by Required Action A.1 may be extended beyond the "72 hours and 10 days from discovery of failure to meet the LCO" up to 288 hours as part of the NSWS system upgrades. System upgrades include maintenance and modification activities associated with the NSWS piping, valves, and branch lines, necessary repairs and/or replacement, and replacement of portions of the NSWS piping to the AFW system. Upon completion of the cleaning, upgrades, and system restoration in refueling outage 1 EOC12, this footnote is no longer applicable.

WOG INSERT 3 (LCO 3.7.5, AFW SYSTEM) – TSTF-359, REV 9

-----**NOTE**-----

LCO 3.0.4.b is not applicable when entering MODE 1.

3.8 ELECTRICAL POWER SYSTEMS

3.8.1 AC Sources—Operating

- LCO 3.8.1 The following AC electrical sources shall be OPERABLE*:
- a. Two qualified circuits between the offsite transmission network and the Onsite Essential Auxiliary Power System; and
 - b. Two diesel generators (DGs) capable of supplying the Onsite Essential Auxiliary Power Systems;

AND

The automatic load sequencers for Train A and Train B shall be OPERABLE.

APPLICABILITY: MODES 1, 2, 3, and 4.

WOG INSERT 4

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One offsite circuit inoperable.	A.1 Perform SR 3.8.1.1 for OPERABLE offsite circuit.	1 hour <u>AND</u> Once per 8 hours thereafter
	A.2 Declare required feature(s) with no offsite power available inoperable when its redundant required feature(s) is inoperable.	24 hours from discovery of no offsite power to one train concurrent with inoperability of redundant required feature(s)
	<u>AND</u>	

(continued)

*For each EDG on Unit 2, the Completion Time that one EDG can be inoperable as specified by Required Action A.1 may be extended beyond the "72 hours and 6 days from failure to meet the LCO" up to 288 hours as part of the NSWS system upgrades. System upgrades include maintenance and modification activities associated with the NSWS piping, valves, and branch lines, necessary repairs and/or replacement, and replacement of portions of the NSWS piping to the AFW system. Upon completion of the cleaning, upgrades, and system restoration in refueling outage 1 EOC12, this footnote is no longer applicable.

WOG INSERT 4 (LCO 3.8.1, AC SOURCES - OPERATING) – TSTF-359, REV 9

-----NOTE-----

LCO 3.0.4.b is not applicable to DGs.

Attachment 3a

McGuire Units 1 and 2

Revised Technical Specifications and Bases Pages

<u>Remove</u>	<u>Insert</u>
3.0-1	3.0-1
3.0-2	3.0-2
3.0-3	3.0-3
3.0-5	3.0-5
3.3.3-1	3.3.3-1
3.3.4-1	3.3.4-1
3.4.11-1	3.4.11-1
3.4.12-2	3.4.12-2
3.4.15-1	3.4.15-1
3.4.16-1	3.4.16-1
3.5.3-1	3.5.3-1
3.6.7-1	3.6.7-1
3.6.8-1	3.6.8-1
3.7.4-1	3.7.4-1
3.7.5-1	3.7.5-1
3.8.1-1	3.8.1-1
B 3.0-4 thru B 3.0-14	B 3.0-4 thru B 3.0-15
B 3.3.3-10	B 3.3.3-10
B 3.3.3-11	B 3.3.3-11
B 3.3.4-3	B 3.3.4-3
B 3.4.11-3	B 3.4.11-3
B 3.4.12-7 thru B 3.4.12-12	B 3.4.12-7 thru B 3.4.12-12
B 3.4.15-3	B 3.4.15-3
B 3.4.16-3	B 3.4.16-3
B 3.4.16-4	B 3.4.16-4
B 3.5.3-2	B 3.5.3-2
B 3.5.3-3	B 3.5.3-2

Attachment 3a

McGuire Units 1 and 2

Revised Technical Specifications and Bases Pages

Remove

B 3.6.7-3
B 3.6.8-3
B.3.7.4-3
B 3.7.5-4
B 3.7.5-5
B 3.7.5-6
B 3.8.1-5
B 3.8.1-6
B 3.8.1-7

Insert

B 3.6.7-3
B 3.6.8-3
B.3.7.4-3
B 3.7.5-4
B 3.7.5-5
B 3.7.5-6
B 3.8.1-5
B 3.8.1-6
B 3.8.1.7

3.0 LCO APPLICABILITY

3.0 LIMITING CONDITION FOR OPERATION (LCO) APPLICABILITY

LCO 3.0.1 LCOs shall be met during the MODES or other specified conditions in the Applicability, except as provided in LCO 3.0.2 and 3.0.7.

LCO 3.0.2 Upon discovery of a failure to meet an LCO, the Required Actions of the associated Conditions shall be met, except as provided in LCO 3.0.5 and LCO 3.0.6.

If the LCO is met or is no longer applicable prior to expiration of the specified Completion Time(s), completion of the Required Action(s) is not required unless otherwise stated.

LCO 3.0.3 When an LCO is not met and the associated ACTIONS are not met, an associated ACTION is not provided, or if directed by the associated ACTIONS, the unit shall be placed in a MODE or other specified condition in which the LCO is not applicable. Action shall be initiated within 1 hour to place the unit, as applicable, in:

- a. MODE 3 within 7 hours;
- b. MODE 4 within 13 hours; and
- c. MODE 5 within 37 hours.

Exceptions to this Specification are stated in the individual Specifications.

Where corrective measures are completed that permit operation in accordance with the LCO or ACTIONS, completion of the actions required by LCO 3.0.3 is not required.

LCO 3.0.3 is only applicable in MODES 1; 2; 3; and 4.

3.0 LCO APPLICABILITY (continued)

LCO 3.0.4 When an LCO is not met, entry into a MODE or other specified condition in the Applicability shall only be made:

- a. When the associated ACTIONS to be entered permit continued operation in the MODE or other specified condition in the Applicability for an unlimited period of time; or
- b. After performance of a risk assessment addressing inoperable systems and components; consideration of the results; determination of the acceptability of entering the MODE or other specified condition in the Applicability, and establishment of risk management actions, if appropriate; exceptions to this Specification are stated in the individual Specifications; or
- c. When an allowance is stated in the individual value, parameter, or other Specification.

This Specification shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS or that are part of a shutdown of the unit.

LCO 3.0.5 Equipment removed from service or declared inoperable to comply with ACTIONS may be returned to service under administrative control solely to perform testing required to demonstrate its OPERABILITY or the OPERABILITY of other equipment. This is an exception to LCO 3.0.2 for the system returned to service under administrative control to perform the required testing to demonstrate OPERABILITY.

LCO 3.0.6 When a supported system LCO is not met solely due to a support system LCO not being met, the Conditions and Required Actions associated with this supported system are not required to be entered. Only the support system LCO ACTIONS are required to be entered. This is an exception to LCO 3.0.2 for the supported system. In this event, additional evaluations and limitations may be required in accordance with Specification 5.5.15, "Safety Function Determination Program (SFDP)." If a loss of safety function is determined to exist by this program, the appropriate Conditions and Required Actions of the LCO in which the loss of safety function exists are required to be entered.

When a support system's Required Action directs a supported system to be declared inoperable or directs entry into Conditions and Required Actions for a supported system, the applicable Conditions and Required Actions shall be entered in accordance with LCO 3.0.2.

(continued)

3.0 LCO APPLICABILITY (continued)

LCO 3.0.7 Test Exception LCOs 3.1.8 and 3.4.17 allow specified Technical Specification (TS) requirements to be changed to permit performance of special tests and operations. Unless otherwise specified, all other TS requirements remain unchanged. Compliance with Test Exception LCOs is optional. When a Test Exception LCO is desired to be met but is not met, the ACTIONS of the Test Exception LCO shall be met. When a Test Exception LCO is not desired to be met, entry into a MODE or other specified condition in the Applicability shall be made in accordance with the other applicable Specifications.

LCO 3.0.8 LCOs including the associated ACTIONS shall apply to each unit individually unless otherwise indicated as follows:

- a. Whenever the LCO refers to systems or components which are shared by both units, the ACTIONS will apply to both units simultaneously;
- b. Whenever the LCO applies to only one unit, this will be identified in the Applicability section of the Specification; and
- c. Whenever certain portions of a Specification contain operating parameters, setpoints etc., which are different for each unit, this will be identified in parentheses or footnotes. (For example, "...flow rate of 54,000 cfm (Unit 1) or 43,000 cfm (Unit 2)...").

3.0 SR APPLICABILITY (continued)

SR 3.0.4 Entry into a MODE or other specified condition in the Applicability of an LCO shall only be made when the LCO's Surveillances have been met within their specified Frequency, except as provided by SR 3.0.3. When an LCO is not met due to Surveillances not having been met, entry into a MODE or other specified condition in the Applicability shall only be made in accordance with LCO 3.0.4.

This provision shall not prevent entry into MODES or other specified conditions in the Applicability that are required to comply with ACTIONS or that are part of a shutdown of the unit.

SR 3.0.5 Surveillance Requirements shall apply to each unit individually unless otherwise indicated as stated in LCO 3.0.8 for individual Specifications or whenever certain portions of a Specification contain surveillance parameters different for each unit, which will be identified in parentheses or footnotes.

3.3 INSTRUMENTATION

3.3.3 Post Accident Monitoring (PAM) Instrumentation

LCO 3.3.3 The PAM instrumentation for each Function in Table 3.3.3-1 shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

-----NOTE-----
Separate Condition entry is allowed for each Function.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more Functions with one or more required channels inoperable.	A.1 Enter the Condition referenced in Table 3.3.3-1 for the channel.	Immediately
B. One or more Functions with one required channel inoperable.	B.1 Restore required channel to OPERABLE status.	30 days
C. Required Action and associated Completion Time of Condition B not met.	C.1 Initiate action in accordance with Specification 5.6.7	Immediately
D. One or more Functions with one required channel inoperable.	D.1 Restore required channel to OPERABLE status.	7 days

(continued)

3.3 INSTRUMENTATION

3.3.4 Remote Shutdown System

LCO 3.3.4 The Remote Shutdown System Functions in Table 3.3.4-1 shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

-----NOTE-----
Separate Condition entry is allowed for each Function.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more required Functions inoperable.	A.1 Restore required Function to OPERABLE status.	30 days
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3.	6 hours
	<u>AND</u> B.2 Be in MODE 4.	12 hours

3.4 REACTOR COOLANT SYSTEM (RCS)

3.4.11 Pressurizer Power Operated Relief Valves (PORVs)

LCO 3.4.11 Each PORV and associated block valve shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

-----NOTE-----
Separate Condition entry is allowed for each PORV.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more PORVs inoperable and capable of being manually cycled.	A.1 Close and maintain power to associated block valve.	1 hour
B. One or two PORVs inoperable and not capable of being manually cycled.	<p>-----NOTE----- Required Actions B.1 and B.2 are not applicable to a PORV made inoperable by Required Action C.2. -----</p> <p>B.1 Close associated block valves.</p> <p><u>AND</u></p> <p>B.2 Remove power from associated block valves.</p> <p><u>AND</u></p>	<p>1 hour</p> <p>1 hour</p> <p>(continued)</p>

ACTIONS

-----NOTE-----
 LCO 3.0.4.b is not applicable when entering MODE 4.

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. Two centrifugal charging pumps capable of injecting into the RCS.</p> <p><u>OR</u></p> <p>One centrifugal charging pump and one safety injection pump capable of injecting into the RCS.</p> <p><u>OR</u></p> <p>Two safety injection pumps capable of injecting into the RCS.</p>	<p>A.1 -----NOTE----- Two centrifugal charging pumps may be capable of injecting into the RCS during pump swap operation for ≤ 15 minutes.</p> <p>-----</p> <p>Initiate action to verify a maximum of one centrifugal charging pump or one safety injection pump is capable of injecting into the RCS.</p> <p><u>OR</u></p> <p>A.2.1 Verify RHR suction relief valve is OPERABLE and the suction isolation valves are open.</p> <p><u>AND</u></p> <p>A.2.2.1 Verify RCS cold leg temperature $> 167^{\circ}\text{F}$.</p> <p><u>OR</u></p> <p>A.2.2.2 Verify RCS cold leg temperature $> 107^{\circ}\text{F}$ and cooldown rate $< 20^{\circ}\text{F/hr}$.</p> <p><u>OR</u></p>	<p>Immediately</p> <p>Immediately</p> <p>Immediately</p> <p>Immediately</p> <p>(continued)</p>

3.4 REACTOR COOLANT SYSTEM (RCS)

3.4.15 RCS Leakage Detection Instrumentation

LCO 3.4.15 The following RCS leakage detection instrumentation shall be OPERABLE:

- a. The containment floor and equipment sump level monitoring system;
- b. One containment atmosphere gaseous radioactivity monitor; and
- c. Either the containment ventilation condensate drain tank level monitor or the containment atmosphere particulate radioactivity monitor.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A.1 Containment floor and equipment sump level monitoring system inoperable.	A.1 Perform SR 3.4.13.1. <u>AND</u> A.2 Restore containment floor and equipment sump level monitoring system to OPERABLE status.	Once per 24 hours 30 days

(continued)

3.4 REACTOR COOLANT SYSTEM (RCS)

3.4.16 RCS Specific Activity

LCO 3.4.16 The specific activity of the reactor coolant shall be within limits.

APPLICABILITY: MODES 1 and 2,
MODE 3 with RCS average temperature (T_{avg}) \geq 500°F.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. DOSE EQUIVALENT I-131 $>$ 1.0 μ Ci/gm.	<p>-----Note----- LCO 3.0.4.c is applicable. -----</p> <p>A.1 Verify DOSE EQUIVALENT I-131 within the acceptable region of Figure 3.4.16-1.</p> <p><u>AND</u></p> <p>A.2 Restore DOSE EQUIVALENT I-131 to within limit.</p>	<p>Once per 4 hours</p> <p>48 hours</p>
B. Gross specific activity of the reactor coolant not within limit.	B.1 Be in MODE 3 with T_{avg} $<$ 500°F.	6 hours

(continued)

3.5 EMERGENCY CORE COOLING SYSTEMS (ECCS)

3.5.3 ECCS — Shutdown

LCO 3.5.3 One ECCS train shall be OPERABLE.

APPLICABILITY: MODE 4.

ACTIONS

NOTE

LCO 3.0.4.b is not applicable to ECCS centrifugal charging subsystem.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Required ECCS residual heat removal (RHR) subsystem inoperable.	A.1 Initiate action to restore required ECCS RHR subsystem to OPERABLE status.	Immediately
B. Required ECCS centrifugal charging subsystem inoperable.	B.1 Restore required ECCS centrifugal charging subsystem to OPERABLE status.	1 hour
C. Required Action and associated Completion Time of Condition B not met.	C.1 Be in MODE 5.	24 hours

3.6 CONTAINMENT SYSTEMS

3.6.7 Hydrogen Recombiners

LCO 3.6.7 Two hydrogen recombiners shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One hydrogen recombiner inoperable.	A.1 Restore hydrogen recombiner to OPERABLE status	30 days
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3.	6 hours

3.6 CONTAINMENT SYSTEMS

3.6.8 Hydrogen Skimmer System (HSS)

LCO 3.6.8 Two HSS trains shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One HSS train inoperable.	A.1 Restore HSS train to OPERABLE status.	30 days
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3.	6 hours

3.7 PLANT SYSTEMS

3.7.4 Steam Generator Power Operated Relief Valves (SG PORVs)

LCO 3.7.4 Three SG PORV lines shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3,
MODE 4 when steam generator is relied upon for heat removal.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One required SG PORV line inoperable.	A.1 Restore required SG PORV line to OPERABLE status.	7 days
B. Two or more required SG PORV lines inoperable.	B.1 Restore all but one required SG PORV line to OPERABLE status.	24 hours
C. Required Action and associated Completion Time not met.	C.1 Be in MODE 3. <u>AND</u> C.2 Be in MODE 4 without reliance upon steam generator for heat removal.	6 hours 12 hours

3.7 PLANT SYSTEMS

3.7.5 Auxiliary Feedwater (AFW) System

LCO 3.7.5 Three AFW trains shall be OPERABLE.

-----NOTE-----

Only one AFW train, which includes a motor-driven pump, is required to be OPERABLE in MODE 4.

APPLICABILITY: MODES 1, 2, and 3,
MODE 4 when steam generator is relied upon for heat removal.

ACTIONS

-----NOTE-----

LCO 3.0.4.b is not applicable when entering MODE 1.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One steam supply to turbine driven AFW pump inoperable.	A.1 Restore steam supply to OPERABLE status.	7 days <u>AND</u> 10 days from discovery of failure to meet the LCO
B. One AFW train inoperable in MODE 1, 2 or 3 for reasons other than Condition A.	B.1 Restore AFW train to OPERABLE status.	72 hours <u>AND</u> 10 days from discovery of failure to meet the LCO

(continued)

3.8 ELECTRICAL POWER SYSTEMS

3.8.1 AC Sources — Operating

LCO 3.8.1 The following AC electrical sources shall be OPERABLE:

- a. Two qualified circuits between the offsite transmission network and the Onsite Essential Auxiliary Power System; and
- b. Two diesel generators (DGs) capable of supplying the Onsite Essential Auxiliary Power Systems;

AND

The automatic load sequencers for Train A and Train B shall be OPERABLE.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTIONS

-----NOTE-----

LCO 3.0.4.b is not applicable to DGs.

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. One offsite circuit inoperable.</p>	<p>A.1 Perform SR 3.8.1.1 for OPERABLE offsite circuit.</p> <p><u>AND</u></p> <p>A.2 Declare required feature(s) with no offsite power available inoperable when its redundant required feature(s) is inoperable.</p> <p><u>AND</u></p>	<p>1 hour</p> <p><u>AND</u></p> <p>Once per 8 hours thereafter</p> <p>24 hours from discovery of no offsite power to one train concurrent with inoperability of redundant required feature(s)</p> <p>(continued)</p>

BASES

LCO 3.0.3 (continued)

The time limits of Specification 3.0.3 allow 37 hours for the unit to be in MODE 5 when a shutdown is required during MODE 1 operation. If the unit is in a lower MODE of operation when a shutdown is required, the time limit for reaching the next lower MODE applies. If a lower MODE is reached in less time than allowed, however, the total allowable time to reach MODE 5, or other applicable MODE, is not reduced. For example, if MODE 3 is reached in 2 hours, then the time allowed for reaching MODE 4 is the next 11 hours, because the total time for reaching MODE 4 is not reduced from the allowable limit of 13 hours. Therefore, if remedial measures are completed that would permit a return to MODE 1, a penalty is not incurred by having to reach a lower MODE of operation in less than the total time allowed.

In MODES 1, 2, 3, and 4, LCO 3.0.3 provides actions for Conditions not covered in other Specifications. The requirements of LCO 3.0.3 do not apply in MODES 5 and 6 because the unit is already in the most restrictive Condition required by LCO 3.0.3. The requirements of LCO 3.0.3 do not apply in other specified conditions of the Applicability (unless in MODE 1, 2, 3, or 4) because the ACTIONS of individual Specifications sufficiently define the remedial measures to be taken.

Exceptions to LCO 3.0.3 are provided in instances where requiring a unit shutdown, in accordance with LCO 3.0.3, would not provide appropriate remedial measures for the associated condition of the unit. An example of this is in LCO 3.7.13, "Spent Fuel Pool (SFP) Water Level." LCO 3.7.13 has an Applicability of "During movement of irradiated fuel assemblies in the spent fuel pool." Therefore, this LCO can be applicable in any or all MODES. If the LCO and the Required Actions of LCO 3.7.13 are not met while in MODE 1, 2, or 3, there is no safety benefit to be gained by placing the unit in a shutdown condition. The Required Action of LCO 3.7.13 of "Suspend movement of irradiated fuel assemblies in the spent fuel pool" is the appropriate Required Action to complete in lieu of the actions of LCO 3.0.3. These exceptions are addressed in the individual Specifications.

LCO 3.0.4 LCO 3.0.4 establishes limitations on changes in MODES or other specified conditions in the Applicability when an LCO is not met. It allows placing the unit in a MODE or other specified condition stated in that Applicability (e.g., the Applicability desired to be entered) when unit conditions are such that the requirements of the LCO would not be met, in accordance with LCO 3.0.4.a, LCO 3.0.4.b, or LCO 3.0.4.c.

LCO 3.0.4.a allows entry into a MODE or other specified condition in the Applicability with the LCO not met when the associated ACTIONS to be entered permit continued operation in the MODE or other specified condition in the Applicability for an unlimited period of time. Compliance

BASES

LCO 3.0.4 (continued)

with Required Actions that permit continued operation of the unit for an unlimited period of time in a MODE or other specified condition provides an acceptable level of safety for continued operation. This is without regard to the status of the unit before or after the MODE change. Therefore, in such cases, entry into a MODE or other specified condition in the Applicability may be made in accordance with the provisions of the Required Actions.

LCO 3.0.4.b allows entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, consideration of the results, determination of the acceptability of entering the MODE or other specified condition in the Applicability, and establishment of risk management actions, if appropriate.

The risk assessment may use quantitative, qualitative, or blended approaches, and the risk assessment will be conducted using the plant program, procedures, and criteria in place to implement 10 CFR 50.65(a)(4), which requires that risk impacts of maintenance activities to be assessed and managed. The risk assessments, for the purposes of LCO 3.0.4.b, must take into account all inoperable Technical Specifications equipment regardless of whether the equipment is included in the normal 10 CFR 50.65(a)(4) risk assessment scope. The risk assessments will be conducted using the procedures and guidance endorsed by Regulatory Guide 1.182, "Assessing and Managing Risk Before Maintenance Activities at Nuclear Power Plants." Regulatory Guide 1.182 endorses the guidance in Section 11 of NUMARC 93-01, "Industry Guideline for Monitoring the Effectiveness of Maintenance at Nuclear Power Plants." These documents address general guidance for conduct of the risk assessment, quantitative and qualitative guidelines for establishing risk management actions, and example risk management actions. These include actions to plan and conduct other activities in a manner that controls overall risk; increased risk awareness by shift and management personnel, actions to reduce the duration of the condition, actions to minimize the magnitude of risk increases (establishment of backup success paths or compensatory measures); and determination that the proposed MODE change is acceptable. Consideration should also be given to the probability of completing restoration such that the requirements of the LCO would be met prior to the expiration of ACTIONS Completion Times that would require exiting the Applicability.

LCO 3.0.4.b may be used with single, or multiple systems and components unavailable. NUMARC 93-01 provides guidance relative to consideration of simultaneous unavailability of multiple systems and components.

BASES

LCO 3.0.4 (continued)

The results of the risk assessment shall be considered in determining the acceptability of entering the MODE or other specified condition in the Applicability, and any corresponding risk management actions. The LCO 3.0.4.b risk assessments do not have to be documented.

The Technical Specifications allow continued operation with equipment unavailable in MODE 1 for the duration of the Completion Time. Since this is allowable, and since in general the risk impact in that particular MODE bounds the risk of transitioning into and through the applicable MODES or other specified conditions in the Applicability of the LCO, the use of the LCO 3.0.4.b allowance should be generally acceptable, as long as the risk is assessed and managed as stated above. However, there is a small subset of systems and components that have been determined to be more important to risk and use of the LCO 3.0.4.b allowance is prohibited. The LCOs governing these system and components contain Notes prohibiting the use of LCO 3.0.4.b by stating that LCO 3.0.4.b is not applicable.

LCO 3.0.4.c allows entry into a MODE or other specified condition in the Applicability with the LCO not met based on a Note in the Specification which states LCO 3.0.4.c is applicable. These specific allowances permit entry into MODES or other specified conditions in the Applicability when the associated ACTIONS to be entered do not provide for continued operation for an unlimited period of time and a risk assessment has not been performed. This allowance may apply to all the ACTIONS or to a specific Required Action of a Specification. The risk assessments performed to justify the use of LCO 3.0.4.b usually only consider systems and components. For this reason, LCO 3.0.4.c is typically applied to Specifications which describe values and parameters (e.g., RCS Specific Activity).

The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or components to OPERABLE status before entering an associated MODE or other specified condition in the Applicability.

The provisions of LCO 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS. In addition, the provisions of LCO 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that result from any unit shutdown. In this context, a unit shutdown is defined as a change in MODE or other specified condition in the Applicability associated with transitioning from MODE 1 to MODE 2, MODE 2 to MODE 3, MODE 3 to MODE 4, and MODE 4 to MODE 5.

BASES

LCO 3.0.4
(continued)

Upon entry into a MODE or other specified condition in the Applicability with the LCO not met, LCO 3.0.1 and LCO 3.0.2 require entry into the applicable Conditions and Required Actions until the condition is resolved, until the LCO is met, or until the unit is not within the Applicability of the Technical Specification.

Surveillances do not have to be performed on the associated inoperable equipment (or on variables outside the specified limits), as permitted by SR 3.0.1. Therefore, utilizing LCO 3.0.4 is not a violation of SR 3.0.1 or SR 3.0.4 for any Surveillances that have not been performed on inoperable equipment. However, SRs must be met to ensure OPERABILITY prior to declaring the associated equipment OPERABLE (or variable within limits) and restoring compliance with the affected LCO.

LCO 3.0.5

LCO 3.0.5 establishes the allowance for restoring equipment to service under administrative controls when it has been removed from service or declared inoperable to comply with ACTIONS. The sole purpose of this Specification is to provide an exception to LCO 3.0.2 (e.g., to not comply with the applicable Required Action(s)) to allow the performance of SRs to demonstrate:

- a. The OPERABILITY of the equipment being returned to service; or
- b. The OPERABILITY of other equipment.

The administrative controls ensure the time the equipment is returned to service in conflict with the requirements of the ACTIONS is limited to the time absolutely necessary to perform the allowed SRs. This Specification does not provide time to perform any other preventive or corrective maintenance.

An example of demonstrating the OPERABILITY of the equipment being returned to service is reopening a containment isolation valve that has been closed to comply with Required Actions and must be reopened to perform the SRs.

An example of demonstrating the OPERABILITY of other equipment is taking an inoperable channel or trip system out of the tripped condition to prevent the trip function from occurring during the performance of an SR on another channel in the other trip system. A similar example of demonstrating the OPERABILITY of other equipment is taking an inoperable channel or trip system out of the tripped condition to permit the logic to function and indicate the appropriate response during the performance of an SR on another channel in the same trip system.

BASES

LCO 3.0.6

LCO 3.0.6 establishes an exception to LCO 3.0.2 for support systems that have an LCO specified in the Technical Specifications (TS). This exception is provided because LCO 3.0.2 would require that the Conditions and Required Actions of the associated inoperable supported system LCO be entered solely due to the inoperability of the support system. This exception is justified because the actions that are required to ensure the unit is maintained in a safe condition are specified in the support system LCO's Required Actions. These Required Actions may include entering the supported system's Conditions and Required Actions or may specify other Required Actions.

When a support system is inoperable and there is an LCO specified for it in the TS, the supported system(s) are required to be declared inoperable if determined to be inoperable as a result of the support system inoperability. However, it is not necessary to enter into the supported systems' Conditions and Required Actions unless directed to do so by the support system's Required Actions. The potential confusion and inconsistency of requirements related to the entry into multiple support and supported systems' LCOs' Conditions and Required Actions are eliminated by providing all the actions that are necessary to ensure the unit is maintained in a safe condition in the support system's Required Actions.

However, there are instances where a support system's Required Action may either direct a supported system to be declared inoperable or direct entry into Conditions and Required Actions for the supported system. This may occur immediately or after some specified delay to perform some other Required Action. Regardless of whether it is immediate or after some delay, when a support system's Required Action directs a supported system to be declared inoperable or directs entry into Conditions and Required Actions for a supported system, the applicable Conditions and Required Actions shall be entered in accordance with LCO 3.0.2.

Specification 5.5.15, "Safety Function Determination Program (SFDP)," ensures loss of safety function is detected and appropriate actions are taken. Upon entry into LCO 3.0.6, an evaluation shall be made to determine if loss of safety function exists. Additionally, other limitations, remedial actions, or compensatory actions may be identified as a result of the support system inoperability and corresponding exception to entering supported system Conditions and Required Actions. The SFDP implements the requirements of LCO 3.0.6.

Cross train checks to identify a loss of safety function for those support systems that support multiple and redundant safety systems are required. The cross train check verifies that the supported systems of the redundant OPERABLE support system are OPERABLE, thereby ensuring safety function is retained. If this evaluation determines that a loss of

BASES

LCO 3.0.6
(continued) safety function exists, the appropriate Conditions and Required Actions of the LCO in which the loss of safety function exists are required to be entered.

LCO 3.0.7 There are certain special tests and operations required to be performed at various times over the life of the unit. These special tests and operations are necessary to demonstrate select unit performance characteristics, to perform special maintenance activities, and to perform special evolutions. Test Exception LCOs 3.1.8 and 3.4.17 allow specified Technical Specification (TS) requirements to be changed to permit performances of these special tests and operations, which otherwise could not be performed if required to comply with the requirements of these TS. Unless otherwise specified, all the other TS requirements remain unchanged. This will ensure all appropriate requirements of the MODE or other specified condition not directly associated with or required to be changed to perform the special test or operation will remain in effect.

The Applicability of a Test Exception LCO represents a condition not necessarily in compliance with the normal requirements of the TS. Compliance with Test Exception LCOs is optional. A special operation may be performed either under the provisions of the appropriate Test Exception LCO or under the other applicable TS requirements. If it is desired to perform the special operation under the provisions of the Test Exception LCO, the requirements of the Test Exception LCO shall be followed.

LCO 3.0.8 LCO 3.0.8 delineates the applicability of each specification to Unit 1 and Unit 2 operations.

B 3.0 SURVEILLANCE REQUIREMENT (SR) APPLICABILITY

BASES

SRs SR 3.0.1 through SR 3.0.5 establish the general requirements applicable to all Specifications and apply at all times, unless otherwise stated.

SR 3.0.1 SR 3.0.1 establishes the requirement that SRs must be met during the MODES or other specified conditions in the Applicability for which the requirements of the LCO apply, unless otherwise specified in the individual SRs. This Specification is to ensure that Surveillances are performed to verify the OPERABILITY of systems and components; and that variables are within specified limits. Failure to meet a Surveillance within the specified Frequency, in accordance with SR 3.0.2, constitutes a failure to meet an LCO.

Systems and components are assumed to be OPERABLE when the associated SRs have been met. Nothing in this Specification, however, is to be construed as implying that systems or components are OPERABLE when:

- a. The systems or components are known to be inoperable, although still meeting the SRs; or
- b. The requirements of the Surveillance(s) are known not to be met between required Surveillance performances.

Surveillances do not have to be performed when the unit is in a MODE or other specified condition for which the requirements of the associated LCO are not applicable, unless otherwise specified. The SRs associated with a test exception are only applicable when the test exception is used as an allowable exception to the requirements of a Specification.

Unplanned events may satisfy the requirements (including applicable acceptance criteria) for a given SR. In this case, the unplanned event may be credited as fulfilling the performance of the SR. This allowance includes those SRs whose performance is normally precluded in a given MODE or other specified condition.

Surveillances, including Surveillances invoked by Required Actions, do not have to be performed on inoperable equipment because the ACTIONS define the remedial measures that apply. Surveillances have to be met and performed in accordance with SR 3.0.2, prior to returning equipment to OPERABLE status.

BASES

SR 3.0.1 (continued)

Upon completion of maintenance, appropriate post maintenance testing is required to declare equipment OPERABLE. This includes ensuring applicable Surveillances are not failed and their most recent performance is in accordance with SR 3.0.2. Post maintenance testing may not be possible in the current MODE or other specified conditions in the Applicability due to the necessary unit parameters not having been established. In these situations, the equipment may be considered OPERABLE provided testing has been satisfactorily completed to the extent possible and the equipment is not otherwise believed to be incapable of performing its function. This will allow operation to proceed to a MODE or other specified condition where other necessary post maintenance tests can be completed.

SR 3.0.2 SR 3.0.2 establishes the requirements for meeting the specified Frequency for Surveillances and any Required Action with a Completion Time that requires the periodic performance of the Required Action on a "once per ..." interval.

SR 3.0.2 permits a 25% extension of the interval specified in the Frequency. This extension facilitates Surveillance scheduling and considers plant operating conditions that may not be suitable for conducting the Surveillance (e.g., transient conditions or other ongoing Surveillance or maintenance activities).

The 25% extension does not significantly degrade the reliability that results from performing the Surveillance at its specified Frequency. This is based on the recognition that the most probable result of any particular Surveillance being performed is the verification of conformance with the SRs. The exceptions to SR 3.0.2 are those Surveillances for which the 25% extension of the interval specified in the Frequency does not apply. These exceptions are stated in the individual Specifications. The requirements of regulations take precedence over the TS.

An example of where SR 3.0.2 does not apply is in the Containment Leakage Rate Testing Program. This program establishes testing requirements and frequencies in accordance with requirements of regulations. The TS cannot in and of themselves extend a test interval specified in regulations.

As stated in SR 3.0.2, the 25% extension also does not apply to the initial portion of a periodic Completion Time that requires performance on a

BASES

SR 3.0.2 (continued)

"once per ..." basis. The 25% extension applies to each performance after the initial performance. The initial performance of the Required Action, whether it is a particular Surveillance or some other remedial action, is considered a single action with a single Completion Time. One reason for not allowing the 25% extension to this Completion Time is that such an action usually verifies that no loss of function has occurred by checking the status of redundant or diverse components or the action accomplishes the function of the inoperable equipment in an alternative manner.

The provisions of SR 3.0.2 are not intended to be used repeatedly merely as an operational convenience to extend Surveillance intervals (other than those consistent with refueling intervals) or periodic Completion Time intervals beyond those specified.

SR 3.0.3

SR 3.0.3 establishes the flexibility to defer declaring affected equipment inoperable or an affected variable outside the specified limits when a Surveillance has not been completed within the specified Frequency. A delay period of up to 24 hours or up to the limit of the specified Frequency, whichever is greater, applies from the point in time that it is discovered that the Surveillance has not been performed in accordance with SR 3.0.2, and not at the time that the specified Frequency was not met.

This delay period provides adequate time to complete Surveillances that have been missed. This delay period permits the completion of a Surveillance before complying with Required Actions or other remedial measures that might preclude completion of the Surveillance.

The basis for this delay period includes consideration of unit conditions, adequate planning, availability of personnel, the time required to perform the Surveillance, the safety significance of the delay in completing the required Surveillance, and the recognition that the most probable result of any particular Surveillance being performed is the verification of conformance with the requirements.

When a Surveillance with a Frequency based not on time intervals, but upon specified unit conditions, operating situations, or requirements of regulations (e.g., prior to entering MODE 1 after each fuel loading, or in accordance with 10 CFR 50, Appendix J, as modified by approved exemptions, etc.) is discovered to not have been performed when specified, SR 3.0.3 allows for the full delay period of up to the specified Frequency to

BASES

perform the Surveillance. However, since there is not a time interval specified, the missed Surveillance should be performed at the first reasonable opportunity.

SR 3.0.3 provides a time limit for, and allowances for the performance of, Surveillances that become applicable as a consequence of MODE changes imposed by Required Actions.

Failure to comply with specified Frequencies for SRs is expected to be an infrequent occurrence. Use of the delay period established by SR 3.0.3 is a flexibility which is not intended to be used as an operational convenience to extend Surveillance intervals. While up to 24 hours or the limit of the specified Frequency is provided to perform the missed Surveillance, it is expected that the missed Surveillance will be performed at the first reasonable opportunity. The determination of the first reasonable opportunity should include consideration of the impact on plant risk (from delaying the Surveillance as well as any plant configuration changes required or shutting the plant down to perform the Surveillance) and impact on any analysis assumptions, in addition to unit conditions, planning, availability of personnel, and the time required to perform the Surveillance. This risk impact should be managed through the program in place to implement 10 CFR 50.65(a)(4) and its implementation guidance, NRC Regulatory Guide 1.182, 'Assessing and Managing Risk Before Maintenance Activities at Nuclear Power Plants.' This Regulatory Guide addresses consideration of temporary and aggregate risk impacts, determination of risk management action thresholds, and risk management action up to and including plant shutdown. The missed Surveillance should be treated as an emergent condition as discussed in the Regulatory Guide. The risk evaluation may use quantitative, qualitative, or blended methods. The degree of depth and rigor of the evaluation should be commensurate with the importance of the component. Missed Surveillances for important components should be analyzed quantitatively. If the results of the risk evaluation determine the risk increase is significant, this evaluation should be used to determine the safest course of action. All missed Surveillances will be placed in the licensee's Corrective Action Program.

If a Surveillance is not completed within the allowed delay period, then the equipment is considered inoperable or the variable is considered outside the specified limits and the Completion Times of the Required Actions for the applicable LCO Conditions begin immediately upon expiration of the delay period. If a Surveillance is failed within the delay period, then the equipment is inoperable, or the variable is outside the specified limits and the Completion Times of the Required Actions for the applicable LCO Conditions begin immediately upon the failure of the Surveillance.

BASES

Completion of the Surveillance within the delay period allowed by this Specification, or within the Completion Time of the ACTIONS, restores compliance with SR 3.0.1.

SR 3.0.4

SR 3.0.4 establishes the requirement that all applicable SRs must be met before entry into a MODE or other specified condition in the Applicability.

This Specification ensures that system and component OPERABILITY requirements and variable limits are met before entry into MODES or other specified conditions in the Applicability for which these systems and components ensure safe operation of the unit. The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or components to OPERABLE status before entering an associated MODE or other specified condition in the Applicability.

A provision is included to allow entry into a MODE or other specified condition in the Applicability when an LCO is not met due to Surveillance not being met in accordance with LCO 3.0.4.

However, in certain circumstances, failing to meet an SR will not result in SR 3.0.4 restricting a MODE change or other specified condition change. When a system, subsystem, division, component, device, or variable is inoperable or outside its specified limits, the associated SR(s) are not required to be performed, per SR 3.0.1, which states that surveillances do not have to be performed on inoperable equipment. When equipment is inoperable, SR 3.0.4 does not apply to the associated SR(s) since the requirement for the SR(s) to be performed is removed. Therefore, failing to perform the Surveillance(s) within the specified Frequency does not result in an SR 3.0.4 restriction to changing MODES or other specified conditions of the Applicability. However, since the LCO is not met in this instance, LCO 3.0.4 will govern any restrictions that may (or may not) apply to MODE or other specified condition changes. SR 3.0.4 does not restrict changing MODES or other specified conditions of the Applicability when a Surveillance has not been performed within the specified Frequency, provided the requirement to declare the LCO not met has been delayed in accordance with SR 3.0.3.

The provisions of SR 3.0.4 shall not prevent entry into MODES or other specified conditions in the Applicability that are required to comply with ACTIONS. In addition, the provisions of SR 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that result from any unit shutdown. In this context, a unit shutdown is defined as a change in MODE or other

BASES

LCO 3.0.4 (continued)

specified condition in the Applicability associated with transitioning from MODE 1 to MODE 2, MODE 2 to MODE 3, MODE 3 to MODE 4, and MODE 4 to MODE 5.

The precise requirements for performance of SRs are specified such that exceptions to SR 3.0.4 are not necessary. The specific time frames and conditions necessary for meeting the SRs are specified in the Frequency, in the Surveillance, or both. This allows performance of Surveillances when the prerequisite condition(s) specified in a Surveillance procedure require entry into the MODE or other specified condition in the Applicability of the associated LCO prior to the performance or completion of a Surveillance. A Surveillance that could not be performed until after entering the LCO's Applicability, would have its Frequency specified such that it is not "due" until the specific conditions needed are met. Alternately, the Surveillance may be stated in the form of a Note, as not required (to be met or performed) until a particular event, condition, or time has been reached. Further discussion of the specific formats of SRs' annotation is found in Section 1.4, Frequency.

SR 3.0.5 SR 3.0.5 delineates the applicability of the surveillance activities to Unit 1 and Unit 2 operations.

BASES

LCO (continued)

Two channels of Steam Line Pressure are required OPERABLE.

20. Refueling Water Storage Tank Level

RWST level monitoring is provided to ensure an adequate supply of water to the safety injection and spray pumps during the switchover to cold leg recirculation.

Three channels of RWST level are provided. Two channels are required OPERABLE by the LCO.

21. DG Heat Exchanger NSWS Flow

Flow indicators are provided in each of the NSWS trains to indicate cooling water flow through the respective train DG. These indicators are provided for operators to manually control flow to the DG heat exchanger. One flow indicator is required OPERABLE on each train.

22. Containment Spray Heat Exchanger NSWS Flow

Flow indicators are provided in each of the NSWS trains to indicate cooling water flow through the respective train containment spray heat exchangers. These indicators are provided for operators to manually control flow to the heat exchanger. One flow indicator is required OPERABLE on each train.

APPLICABILITY: The PAM instrumentation LCO is applicable in MODES 1, 2, and 3. These variables are related to the diagnosis and pre-planned actions required to mitigate DBAs. The applicable DBAs are assumed to occur in MODES 1, 2, and 3. In MODES 4, 5, and 6, unit conditions are such that the likelihood of an event that would require PAM instrumentation is low; therefore, the PAM instrumentation is not required to be OPERABLE in these MODES.

BASES

ACTIONS

A Note has been added in the ACTIONS to clarify the application of Completion Time rules. The Conditions of this Specification may be entered independently for each Function listed on Table 3.3.3-1. When the Required Channels in Table 3.3.3-1 are specified (e.g., on a per steam line, per loop, per SG, etc., basis), then the Condition may be entered separately for each steam line, loop, SG, etc., as appropriate. The Completion Time(s) of the inoperable channel(s) of a Function will be tracked separately for each Function starting from the time the Condition was entered for that Function.

A.1

Condition A applies to all PAM instrument Functions. Condition A addresses the situation when one or more required channels for one or more Functions are inoperable. The Required Action is to refer to Table 3.3.3-1 and take the appropriate Required Actions for the PAM instrumentation affected. The Completion Times are those from the referenced Conditions and Required Actions.

B.1

Condition B applies when one or more Functions have one required channel that is inoperable. Required Action B.1 requires restoring the inoperable channel to OPERABLE status within 30 days. The 30 day Completion Time is based on operating experience and takes into account the remaining OPERABLE channel, the passive nature of the instrument (no critical automatic action is assumed to occur from these instruments); and the low probability of an event requiring PAM instrumentation during this interval. Condition B is not applicable to functions with a single required channel.

C.1

Condition C applies when the Required Action and associated Completion Time for Condition B are not met. This Required Action specifies initiation of actions in Specification 5.6.7, which requires a written report to be submitted to the NRC immediately. This report

BASES

APPLICABILITY (continued)

This LCO is not applicable in MODE 4, 5, or 6. In these MODES, the facility is already subcritical and in a condition of reduced RCS energy. Under these conditions, considerable time is available to restore necessary instrument control functions if control room instruments or controls become unavailable.

ACTIONS

A Note has been added to the ACTIONS to clarify the application of Completion Time rules. Separate Condition entry is allowed for each Function listed on Table 3.3.4-1. The Completion Time(s) of the inoperable channel(s)/train(s) of a Function will be tracked separately for each Function starting from the time the Condition was entered for that Function.

A.1

Condition A addresses the situation where one or more required Functions of the Remote Shutdown System are inoperable. This includes any Function listed in Table 3.3.4-1 as well as the control and transfer switches.

The Required Action is to restore the required Function to OPERABLE status within 30 days. The Completion Time is based on operating experience and the low probability of an event that would require evacuation of the control room.

B.1 and B.2

If the Required Action and associated Completion Time of Condition A is not met, the unit must be brought to a MODE in which the LCO does not apply. To achieve this status, the unit must be brought to at least MODE 3 within 6 hours and to MODE 4 within 12 hours. The allowed Completion Times are reasonable, based on operating experience, to reach the required unit conditions from full power conditions in an orderly manner and without challenging unit systems.

BASES

APPLICABILITY (continued)

Pressure increases are less prominent in MODE 3 because the core input energy is reduced, but the RCS pressure is high. Therefore, the LCO is applicable in MODES 1, 2, and 3. The LCO is not applicable in MODE 4 when both pressure and core energy are decreased and the pressure surges become much less significant. The PORV setpoint is reduced for $HLTOP$ in MODES 4 $\leq 300^\circ\text{F}$, 5, and 6 with the reactor vessel head in place. LCO 3.4:12 addresses the PORV requirements in these MODES.

ACTIONS A Note has been added to clarify that all pressurizer PORVs are treated as separate entities, each with separate Completion Times (i.e., the Completion Time is on a component basis).

A.1

With the PORVs inoperable and capable of being manually cycled, either the PORVs must be restored or the flow path isolated within 1 hour. The block valves should be closed but power must be maintained to the associated block valves, since removal of power would render the block valve inoperable. Although a PORV may be designated inoperable, it may be able to be manually opened and closed, and therefore, able to perform its function. PORV inoperability may be due to seat leakage or other causes that do not prevent manual use and do not create a possibility for a small break LOCA. For these reasons, the block valve may be closed but the Action requires power be maintained to the valve. This Condition is only intended to permit operation of the plant for a limited period of time not to exceed the next refueling outage (MODE 6) so that maintenance can be performed on the PORVs to eliminate the problem condition. Normally, the PORVs should be available for automatic mitigation of overpressure events and should be returned to OPERABLE status prior to entering startup (MODE 2).

Quick access to the PORV for pressure control can be made when power remains on the closed block valve. The Completion Time of 1 hour is based on plant operating experience that has shown that minor problems can be corrected or closure accomplished in this time period.

BASES

APPLICABILITY (continued)

The Applicability is modified by a Note stating that accumulator isolation is only required when the accumulator pressure is more than or at the maximum RCS pressure for the existing temperature, as allowed by the P/T limit curves. This Note permits the accumulator discharge isolation valve Surveillance to be performed only under these pressure and temperature conditions.

ACTIONS A Note prohibits the application of LCO 3.0.4.b to an inoperable LTOP system. There is an increased risk associated with entering MODE 4 from MODE 5 with LTOP inoperable and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

A.1, A.2.1, A.2.2.1, A.2.2.2., A.3, and A.4

With two centrifugal charging pumps, safety injection pumps, or a combination of each, capable of injecting into the RCS, RCS overpressurization is possible.

To immediately initiate action to restore restricted coolant input capability to the RCS reflects the urgency of removing the RCS from this condition. Two pumps may be capable of injecting into the RCS provided the RHR suction relief valve is OPERABLE with the RCS cold leg temperature > 167°F or > 107°F and cooldown rate limited to 20°F, or if two PORVs are secured open with the associated block valves open and power removed, or with an RCS vent of 4.5 square inches. For cases where no reactor coolant pumps are in operation, RCS cold leg temperature limits are to be met by monitoring of BOTH the WR Cold Leg temperatures and Residual Heat Removal Heat Exchanger discharge temperature. With both PORVS and block valves secured open, or with an RCS vent of 4.5 square inches, there are no credible single failures to limit the flow relief capacity. For the RHR relief valve to be OPERABLE, the RHR suction isolation valves must be open and the relief valve setpoint at 450 psig consistent with the safety analysis. The RHR suction relief valves are spring loaded, bellows type water relief valves with pressure tolerances and accumulation limits established by Section III of the American Society of Mechanical Engineers (ASME) Code (Ref. 3) for Class 2 relief valves.

Required Action A.1 is modified by a Note that permits two centrifugal charging pumps capable of RCS injection for ≤ 15 minutes to allow for pump swaps.

BASES

ACTIONS (continued)

B.1, C.1, and C.2

An unisolated accumulator requires isolation within 1 hour. This is only required when the accumulator pressure is at or more than the maximum

RCS pressure for the existing temperature allowed by the P/T limit curves.

If isolation is needed and cannot be accomplished in 1 hour, Required Action C.1 and Required Action C.2 provide two options, either of which must be performed in the next 12 hours. By increasing the RCS temperature to $> 300^{\circ}\text{F}$, an accumulator pressure of 639 psig cannot exceed the LTOP limits if the accumulators are fully injected.

Depressurizing the accumulators below the LTOP limit also gives this protection.

The Completion Times are based on operating experience that these activities can be accomplished in these time periods and on engineering evaluations indicating that an event requiring LTOP is not likely in the allowed times.

D.1

In MODE 4 when any RCS cold leg temperature is $\leq 300^{\circ}\text{F}$, with one PORV inoperable, the PORV must be restored to OPERABLE status within a Completion Time of 7 days. Two PORVs are required to provide low temperature overpressure mitigation while withstanding a single failure of an active component.

The Completion Time considers the facts that only one of the PORVs is required to mitigate an overpressure transient and that the likelihood of an active failure of the remaining valve path during this time period is very low.

E.1 and E.2

The consequences of operational events that will overpressurize the RCS are more severe at lower temperature (Ref. 8). Thus, with one of the two PORVs inoperable in MODE 5 or in MODE 6 with the head on, all operations which could lead to a water solid pressurizer must be suspended immediately and the Completion Time to restore two valves to OPERABLE status is 24 hours.

BASES

ACTIONS (continued)

The Completion Time represents a reasonable time to investigate and repair several types of relief valve failures without exposure to a lengthy period with only one OPERABLE PORV to protect against overpressure events.

F.1 and F.2

If the Required Actions and associated Completion Times of Condition E are not met, then alternative actions are necessary to establish the required redundancy in relief capacity. This is accomplished by verifying that the RHR relief valve is OPERABLE and the RHR suction isolation valves open and the RCS cold leg temperature > 167°F. For cases where no reactor coolant pumps are in operation, RCS cold leg temperature limits are to be met by monitoring of BOTH the WR Cold Leg temperatures and Residual Heat Removal Heat Exchanger discharge temperature. The Completion Time of 1 hour reflects the importance of restoring the required redundancy at lower RCS temperatures.

G.1

The RCS must be depressurized and a vent must be established within 8 hours when:

- a. Both required PORVs are inoperable; or
- b. A Required Action and associated Completion Time of Condition C, D, E, or F is not met; or
- c. The LTOP System is inoperable for any reason other than Condition A, B, C, D, E, or F.

The vent must be sized ≥ 2.75 square inches to ensure that the flow capacity is greater than that required for the worst case mass input transient reasonable during the applicable MODES. This action is needed to protect the RCPB from a low temperature overpressure event and a possible brittle failure of the reactor vessel.

The Completion Time considers the time required to place the plant in this Condition and the relatively low probability of an overpressure event

BASES

ACTIONS (continued)

during this time period due to increased operator awareness of administrative control requirements.

SURVEILLANCE REQUIREMENTS SR 3.4.12.1 and SR 3.4.12.2

To minimize the potential for a low temperature overpressure event by limiting the mass input capability, all but one centrifugal charging pump or one safety injection pump are verified incapable of injecting into the RCS and the accumulator discharge isolation valves are verified closed and power removed (See Ref. 10).

The centrifugal charging pump and safety injection pump are rendered incapable of injecting into the RCS through removing the power from the pumps by racking the breakers out under administrative control. An alternate method of LTOP control may be employed using at least two independent means to prevent a pump start such that a single failure or single action will not result in an injection into the RCS. This may be accomplished through two valves in the discharge flow path being closed.

The Frequency of 12 hours is sufficient, considering other indications and alarms available to the operator in the control room, to verify the required status of the equipment.

SR 3.4.12.3

The RHR suction relief valve shall be demonstrated OPERABLE by verifying the RHR suction isolation valves are open and by testing it in accordance with the Inservice Testing Program. This Surveillance is only required to be performed if the RHR suction relief valve is being used to meet the Required Actions of this LCO.

The RHR suction valves are verified to be opened every 12 hours. The Frequency is considered adequate in view of other administrative controls such as valve status indications available to the operator in the control room that verify the RHR suction valves remain open.

The ASME Code, Section XI (Ref. 9), test per Inservice Testing Program verifies OPERABILITY by proving proper relief valve mechanical motion and by measuring and, if required, adjusting the lift setpoint.

BASES

SURVEILLANCE REQUIREMENTS (continued)

SR 3.4.12.4

The RCS vent of ≥ 2.75 square inches is proven OPERABLE by verifying its open condition either:

- a. Once every 12 hours for a valve that cannot be locked.
- b. Once every 31 days for a valve that is locked, sealed, or secured in position. A removed pressurizer safety valve fits this category.

The passive vent arrangement must only be open to be OPERABLE. This Surveillance is required to be performed if the vent is being used to satisfy the pressure relief requirements of the LCO 3.4.12b.

SR 3.4.12.5

The PORV block valve must be verified open every 72 hours to provide the flow path for each required PORV to perform its function when actuated. The valve must be remotely verified open in the main control room. This Surveillance is performed if the PORV satisfies the LCO.

The block valve is a remotely controlled, motor operated valve. The power to the valve operator is not required removed, and the manual operator is not required locked in the inactive position. Thus, the block valve can be closed in the event the PORV develops excessive leakage or does not close (sticks open) after relieving an overpressure situation.

The 72 hour Frequency is considered adequate in view of other administrative controls available to the operator in the control room, such as valve position indication, that verify that the PORV block valve remains open.

SR 3.4.12.6

Performance of a COT is required within 12 hours after decreasing RCS temperature to $\leq 300^\circ\text{F}$ and every 31 days on each required PORV to verify and, as necessary, adjust its lift setpoint. The COT will verify the setpoint is within the allowed maximum limits. PORV actuation could depressurize the RCS and is not required.

The 12 hour Frequency considers the unlikelihood of a low temperature overpressure event during this time.

BASES

SURVEILLANCE REQUIREMENTS (continued)

A Note has been added indicating that this SR is required to be met 12 hours after decreasing RCS cold leg temperature to $\leq 300^{\circ}\text{F}$. The test must be performed within 12 hours after entering the LTOP MODES.

SR 3.4.12.7

Performance of a CHANNEL CALIBRATION on each required PORV actuation channel is required every 18 months to adjust the whole channel so that it responds and the valve opens within the required range and accuracy to known input.

REFERENCES

1. 10 CFR 50, Appendix G.
2. Generic Letter 88-11.
3. ASME, Boiler and Pressure Vessel Code, Section III.
4. UFSAR, Section 5.2.
5. 10 CFR 50, Section 50.46.
6. 10 CFR 50, Appendix K.
7. 10 CFR 50.36, Technical Specifications, (c)(2)(ii).
8. Generic Letter 90-06.
9. ASME, Boiler and Pressure Vessel Code, Section XI.
10. Duke letter to NRC, "Cold Leg Accumulator Isolation Valves", dated September 8, 1987.

BASES

APPLICABLE SAFETY ANALYSES (continued)

The safety significance of RCS LEAKAGE varies widely depending on its source, rate, and duration. Therefore, detecting and monitoring RCS LEAKAGE into the containment area is necessary. Quickly separating the identified LEAKAGE from the unidentified LEAKAGE provides quantitative information to the operators, allowing them to take corrective action should a leakage occur detrimental to the safety of the unit and the public.

RCS leakage detection instrumentation satisfies Criterion 1 of 10 CFR 50.36 (Ref. 4).

LCO One method of protecting against large RCS leakage derives from the ability of instruments to rapidly detect extremely small leaks. This LCO requires instruments of diverse monitoring principles to be OPERABLE to provide a high degree of confidence that extremely small leaks are detected in time to allow actions to place the plant in a safe condition, when RCS LEAKAGE indicates possible RCPB degradation.

The LCO is satisfied when monitors of diverse measurement means are available. Thus, the containment floor and equipment sump level monitoring system and a gaseous radioactivity monitor, in combination with a containment ventilation condensate drain tank level monitor or particulate radioactivity monitor, provides an acceptable minimum.

APPLICABILITY Because of elevated RCS temperature and pressure in MODES 1, 2, 3, and 4, RCS leakage detection instrumentation is required to be OPERABLE.

In MODE 5 or 6, the temperature is to be $\leq 200^\circ\text{F}$ and pressure is maintained low or at atmospheric pressure. Since the temperatures and pressures are far lower than those for MODES 1, 2, 3, and 4, the likelihood of leakage and crack propagation are much smaller. Therefore, the requirements of this LCO are not applicable in MODES 5 and 6.

BASES

LCO

The specific iodine activity is limited to 1.0 $\mu\text{Ci/gm}$ DOSE EQUIVALENT I-131, and the gross specific activity in the reactor coolant is limited to the number of $\mu\text{Ci/gm}$ equal to 100 divided by \bar{E} (average disintegration energy of the sum of the average beta and gamma energies of the coolant nuclides). The limit on DOSE EQUIVALENT I-131 ensures the 2 hour thyroid dose to an individual at the site boundary during the Design Basis Accident (DBA) will be a small fraction of the allowed thyroid dose. The limit on gross specific activity ensures the 2 hour whole body dose to an individual at the site boundary during the DBA will be a small fraction of the allowed whole body dose.

The SGTR accident analysis (Ref. 2) shows that the 2 hour site boundary dose levels are within acceptable limits. Violation of the LCO may result in reactor coolant radioactivity levels that could, in the event of an SGTR, lead to site boundary doses that exceed the 10 CFR 100 dose guideline limits.

APPLICABILITY

In MODES 1 and 2, and in MODE 3 with RCS average temperature $\geq 500^\circ\text{F}$, operation within the LCO limits for DOSE EQUIVALENT I-131 and gross specific activity are necessary to contain the potential consequences of an SGTR to within the acceptable site boundary dose values.

For operation in MODE 3 with RCS average temperature $< 500^\circ\text{F}$, and in MODES 4 and 5, the release of radioactivity in the event of a SGTR is unlikely since the saturation pressure of the reactor coolant is below the lift pressure settings of the main steam safety valves.

ACTIONS

A.1 and A.2

With the DOSE EQUIVALENT I-131 greater than the LCO limit, samples at intervals of 4 hours must be taken to demonstrate that the limits of Figure 3.4.16-1 are not exceeded. The Completion Time of 4 hours is required to obtain and analyze a sample. Sampling is done to continue to provide a trend.

The DOSE EQUIVALENT I-131 must be restored to within limits within 48 hours. The Completion Time of 48 hours is required, if the limit violation resulted from normal iodine spiking.

A Note permits the use of the provisions of LCO 3.0.4.c. This allowance permits entry into the applicable MODE(S) while relying on the ACTIONS.

BASES

ACTIONS (continued)

B.1

With the gross specific activity in excess of the allowed limit, the unit must be placed in a MODE in which the requirement does not apply.

The change within 6 hours to MODE 3 and RCS average temperature < 500°F lowers the saturation pressure of the reactor coolant below the setpoints of the main steam safety valves and prevents venting the SG to the environment in an SGTR event. The allowed Completion Time of 6 hours is reasonable, based on operating experience, to reach MODE 3 below 500°F from full power conditions in an orderly manner and without challenging plant systems.

C.1

If a Required Action and the associated Completion Time of Condition A is not met or if the DOSE EQUIVALENT I-131 is in the unacceptable region of Figure 3.4.16-1, the reactor must be brought to MODE 3 with RCS average temperature < 500°F within 6 hours. The Completion Time of 6 hours is reasonable, based on operating experience, to reach MODE 3 below 500°F from full power conditions in an orderly manner and without challenging plant systems.

**SURVEILLANCE
REQUIREMENTS**

SR 3.4.16.1

SR 3.4.16.1 requires performing a gamma isotopic analysis as a measure of the gross specific activity of the reactor coolant at least once every 7 days. A gross radioactivity analysis shall consist of the quantitative measurement of the total specific activity of the reactor coolant except for radionuclides with half-lives less than 10 minutes and all radioiodines. The total specific activity shall be the sum of the beta-gamma activity in the sample within 2 hours after the sample is taken and extrapolated back to when the sample was taken. Determination of the contributors to the gross specific activity shall be based upon those energy peaks identifiable with a 95% confidence level. The latest available data may be used for pure beta-emitting radionuclides. This Surveillance provides an indication of any increase in gross specific activity.

BASES

LCO (continued)

ECCS pumps and their respective supply headers to each of the four cold leg injection nozzles. In the long term, this flow path may be switched to take its supply from the containment sump and to deliver its flow to the RCS hot and cold legs.

APPLICABILITY In MODES 1, 2, and 3, the OPERABILITY requirements for ECCS are covered by LCO 3.5.2.

In MODE 4 with RCS temperature below 350°F, one OPERABLE ECCS train is acceptable without single failure consideration, on the basis of the stable reactivity of the reactor and the limited core cooling requirements.

In MODES 5 and 6, plant conditions are such that the probability of an event requiring ECCS injection is extremely low. Core cooling requirements in MODE 5 are addressed by LCO 3.4.7, "RCS Loops—MODE 5, Loops Filled," and LCO 3.4.8, "RCS Loops—MODE 5, Loops Not Filled." MODE 6 core cooling requirements are addressed by LCO 3.9.5, "Residual Heat Removal (RHR) and Coolant Circulation—High Water Level," and LCO 3.9.6, "Residual Heat Removal (RHR) and Coolant Circulation—Low Water Level."

ACTIONS A Note prohibits the application of LCO 3.0.4.b to an inoperable ECCS centrifugal charging subsystem when entering MODE 4. There is an increased risk associated with entering MODE 4 from MODE 5 with an inoperable ECCS centrifugal charging subsystem and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

A.1

With no ECCS RHR subsystem OPERABLE, the plant is not prepared to respond to a loss of coolant accident or to continue a cooldown using the RHR pumps and heat exchangers. The Completion Time of immediately to initiate actions that would restore at least one ECCS RHR subsystem to OPERABLE status ensures that prompt action is taken to restore the required cooling capacity. Normally, in MODE 4, reactor decay heat is removed from the RCS by an RHR loop. If no RHR loop is OPERABLE for this function, reactor decay heat must be removed by some alternate method, such as use of the steam generators. The alternate means of heat removal must continue until the inoperable RHR loop components can be restored to operation so that decay heat removal is continuous.

BASES

ACTIONS
(continued)

With both RHR pumps and heat exchangers inoperable, it would be unwise to require the plant to go to MODE 5, where the only available heat removal system is the RHR. Therefore, the appropriate action is to initiate measures to restore one ECCS RHR subsystem and to continue the actions until the subsystem is restored to OPERABLE status.

B.1

With no ECCS high head subsystem OPERABLE, due to the inoperability of the centrifugal charging pump or flow path from the RWST, the plant is not prepared to provide high pressure response to Design Basis Events requiring SI. The 1-hour Completion Time to restore at least one ECCS high head subsystem to OPERABLE status ensures that prompt action is taken to provide the required cooling capacity or to initiate actions to place the plant in MODE 5, where an ECCS train is not required.

C.1

When the Required Actions of Condition B cannot be completed within the required Completion Time, a controlled shutdown should be initiated. Twenty-four hours is a reasonable time, based on operating experience, to reach MODE 5 in an orderly manner and without challenging plant systems or operators.

SURVEILLANCE
REQUIREMENTS

SR 3.5.3.1

The applicable Surveillance descriptions from Bases 3.5.2 apply. This SR is modified by a Note that allows an RHR train to be considered OPERABLE during PIV testing and alignment and operation for decay heat removal, if capable of being manually realigned (remote or local) to the ECCS mode of operation and not otherwise inoperable. This allows operation in the RHR mode during MODE 4, if necessary.

REFERENCES

The applicable references from Bases 3.5.2 apply.

BASES

APPLICABILITY (continued)

In MODES 3 and 4, both the hydrogen production rate and the total hydrogen produced after a LOCA would be less than that calculated for the DBA LOCA. Also, because of the limited time in these MODES, the probability of an accident requiring the hydrogen recombiners is low. Therefore, the hydrogen recombiners are not required in MODE 3 or 4.

In MODES 5 and 6, the probability and consequences of a LOCA are low, due to the pressure and temperature limitations in these MODES. Therefore, hydrogen recombiners are not required in these MODES.

ACTIONS

A.1

With one containment hydrogen recombiner inoperable, the inoperable recombiner must be restored to OPERABLE status within 30 days. In this condition, the remaining OPERABLE hydrogen recombiner is adequate to perform the hydrogen control function. However, the overall reliability is reduced because a single failure in the OPERABLE recombiner could result in reduced hydrogen control capability. The 30 day Completion Time is based on the availability of the other hydrogen recombiner, the small probability of a LOCA occurring (that would generate an amount of hydrogen that exceeds the flammability limit), and the amount of time available after a LOCA (should one occur) for operator action to prevent hydrogen accumulation from exceeding the flammability limit.

B.1

If the inoperable hydrogen recombiner(s) cannot be restored to OPERABLE status within the required Completion Time, the plant must be brought to a MODE in which the LCO does not apply. To achieve this status, the plant must be brought to at least MODE 3 within 6 hours. The Completion Time of 6 hours is reasonable, based on operating experience, to reach MODE 3 from full power conditions in an orderly manner and without challenging plant systems.

BASES

APPLICABILITY (continued)

the DBA LOCA. Also, because of the limited time in these MODES, the probability of an accident requiring the HSS is low. Therefore, the HSS is not required in MODE 3 or 4.

In MODES 5 and 6, the probability and consequences of a LOCA or steam line break (SLB) are reduced due to the pressure and temperature limitations in these MODES. Therefore, the HSS is not required in these MODES.

ACTIONS**A.1**

With one HSS train inoperable, the inoperable train must be restored to OPERABLE status within 30 days. In this Condition, the remaining OPERABLE HSS train is adequate to perform the hydrogen mixing function. However, the overall reliability is reduced because a single failure in the OPERABLE train could result in reduced hydrogen mixing capability. The 30 day Completion Time is based on the availability of the other HSS train, the small probability of a LOCA or SLB occurring (that would generate an amount of hydrogen that exceeds the flammability limit), the amount of time available after a LOCA or SLB (should one occur) for operator action to prevent hydrogen accumulation from exceeding the flammability limit, and the availability of the hydrogen recombiners and Hydrogen Mitigation System.

B.1

If an inoperable HSS train cannot be restored to OPERABLE status within the required Completion Time, the plant must be brought to a MODE in which the LCO does not apply. To achieve this status, the plant must be brought to at least MODE 3 within 6 hours. The allowed Completion Time of 6 hours is reasonable, based on operating experience, to reach MODE 3 from full power conditions in an orderly manner and without challenging plant systems.

BASES

ACTIONS

A.1

With one required SG PORV line inoperable, action must be taken to restore OPERABLE status within 7 days. The 7 day Completion Time allows for the redundant capability afforded by the remaining OPERABLE SG PORV lines, a nonsafety grade backup in the Steam Dump System, and MSSVs.

B.1

With two or more SG PORV lines inoperable, action must be taken to restore all but one SG PORV line to OPERABLE status. Since the block valve can be closed to isolate an SG PORV, some repairs may be possible with the unit at power. The 24 hour Completion Time is reasonable to repair inoperable SG PORV lines, based on the availability of the Steam Dump System and MSSVs, and the low probability of an event occurring during this period that would require the SG PORV lines.

C.1 and C.2

If the SG PORV lines cannot be restored to OPERABLE status within the associated Completion Time, the unit must be placed in a MODE in which the LCO does not apply. To achieve this status, the unit must be placed in at least MODE 3 within 6 hours, and in MODE 4, without reliance upon steam generator for heat removal, within 12 hours. The allowed Completion Times are reasonable, based on operating experience, to reach the required unit conditions from full power conditions in an orderly manner and without challenging unit systems.

**SURVEILLANCE
REQUIREMENTS**

SR 3.7.4.1

To perform a controlled cooldown of the RCS, the SG PORVs must be able to be opened manually using the handwheel and throttled through their full range. This SR ensures that the SG PORVs are tested through a full cycle at least once per fuel cycle. Performance of inservice testing or use of an SG PORV during a unit cooldown may satisfy this requirement. Operating experience has shown that these components usually pass the Surveillance when performed at the 18 month Frequency. The Frequency is acceptable from a reliability standpoint.

LCO (continued)

The LCO is modified by a Note indicating that one AFW train, which includes a motor driven pump, is required to be OPERABLE in MODE 4. This is because of the reduced heat removal requirements and short period of time in MODE 4 during which the AFW is required and the insufficient steam available in MODE 4 to power the turbine driven AFW pump.

APPLICABILITY

In MODES 1, 2, and 3, the AFW System is required to be OPERABLE in the event that it is called upon to function when the MFW is lost. In addition, the AFW System is required to supply enough makeup water to replace the steam generator secondary inventory lost as the unit cools to MODE 4 conditions.

In MODE 4 the AFW System may be used for heat removal via the steam generators.

In MODE 5 or 6, the steam generators are not normally used for heat removal, and the AFW System is not required.

ACTIONS

A Note prohibits the application of LCO 3.0.4.b to an inoperable AFW train when entering MODE 1. There is an increased risk associated with entering MODE 1 with an AFW train inoperable and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

A.1

If one of the two steam supplies to the turbine driven AFW train is inoperable, action must be taken to restore OPERABLE status within 7 days in MODES 1, 2, and 3. The 7-day Completion Time is reasonable, based on the following reasons:

- a. The redundant OPERABLE steam supply to the turbine driven AFW pump;
- b. The availability of redundant OPERABLE motor driven AFW pumps; and
- c. The low probability of an event occurring that requires the inoperable steam supply to the turbine driven AFW pump.

ACTIONS (continued)

The second Completion Time for Required Action A.1 establishes a limit on the maximum time allowed for any combination of Conditions to be inoperable during any continuous failure to meet this LCO.

The 10 day Completion Time provides a limitation time allowed in this specified Condition after discovery of failure to meet the LCO. This limit is considered reasonable for situations in which Conditions A and B are entered concurrently. The AND connector between 7 days and 10 days dictates that both Completion Times apply simultaneously, and the more restrictive must be met.

B.1

With one of the required AFW trains (pump or flow path) inoperable in MODE 1, 2, or 3 for reasons other than Condition A, action must be taken to restore OPERABLE status within 72 hours. This Condition includes the loss of two steam supply lines to the turbine driven AFW pump. The 72 hour Completion Time is reasonable, based on redundant capabilities afforded by the AFW System, time needed for repairs, and the low probability of a DBA occurring during this time period.

The second Completion Time for Required Action B.1 establishes a limit on the maximum time allowed for any combination of Conditions to be inoperable during any continuous failure to meet this LCO.

The 10 day Completion Time provides a limitation time allowed in this specified Condition after discovery of failure to meet the LCO. This limit is considered reasonable for situations in which Conditions A and B are entered concurrently. The AND connector between 72 hours and 10 days dictates that both Completion Times apply simultaneously, and the more restrictive must be met.

C.1 and C.2

When Required Action A.1 or B.1 cannot be completed within the required Completion Time, or if two AFW trains are inoperable in MODE 1, 2, or 3, the unit must be placed in a MODE in which the LCO does not apply. To achieve this status, the unit must be placed in at least MODE 3 within 6 hours, and in MODE 4 within 12 hours.

The allowed Completion Times are reasonable, based on operating experience, to reach the required unit conditions from full power conditions in an orderly manner and without challenging unit systems.

In MODE 4 with two AFW trains inoperable, operation is allowed to continue because only one motor driven pump AFW train is required in

ACTIONS (continued)

accordance with the Note that modifies the LCO. Although not required, the unit may continue to cool down and initiate RHR.

D.1

If all three AFW trains are inoperable in MODE 1, 2, or 3, the unit is in a seriously degraded condition with no safety related means for conducting a cooldown, and only limited means for conducting a cooldown with nonsafety related equipment. In such a condition, the unit should not be perturbed by any action, including a power change, that might result in a trip. The seriousness of this condition requires that action be started immediately to restore one AFW train to OPERABLE status.

Required Action D.1 is modified by a Note indicating that all required MODE changes or power reductions are suspended until one AFW train is restored to OPERABLE status. In this case, LCO 3.0.3 is not applicable because it could force the unit into a less safe condition.

E.1

In MODE 4, either the reactor coolant pumps or the RHR loops can be used to provide forced circulation. This is addressed in LCO 3.4.6, "RCS Loops—MODE 4." With one required AFW train with a motor driven pump inoperable, action must be taken to immediately restore the inoperable train to OPERABLE status. The immediate Completion Time is consistent with LCO 3.4.6.

**SURVEILLANCE
REQUIREMENTS****SR 3.7.5.1**

Verifying the correct alignment for manual, power operated, and automatic valves in the AFW System water and steam supply flow paths provides assurance that the proper flow paths will exist for AFW operation. This SR does not apply to valves that are locked, sealed, or otherwise secured in position, since they are verified to be in the correct position prior to locking, sealing, or securing. This SR also does not apply to valves that cannot be inadvertently misaligned, such as check valves. This Surveillance does not require any testing or valve manipulation; rather, it involves verification that those valves capable of being mispositioned are in the correct position. The SR is also modified by a note that excludes automatic valves when THERMAL POWER is \leq 10% RTP. Some automatic valves may be in a throttled position to support low power operation.

The 31 day Frequency is based on engineering judgment, is consistent with the procedural controls governing valve operation, and ensures correct valve positions.

BASES

LCO (continued)

Each DG must be capable of starting, accelerating to rated speed and voltage, and connecting to its respective ESF bus on detection of bus undervoltage. This will be accomplished within 11 seconds. Each DG must also be capable of accepting required loads within the assumed loading sequence intervals, and continue to operate until offsite power can be restored to the ESF buses. These capabilities are required to be met from a variety of initial conditions such as DG in standby with the engine hot and DG in standby with the engine at ambient conditions. Additional DG capabilities must be demonstrated to meet required Surveillance, e.g., capability of the DG to revert to standby status on an ECCS signal while operating in parallel test mode.

Proper sequencing of loads is a function of Sequencer OPERABILITY. Proper load shedding is a function of DG OPERABILITY. Proper tripping of non-essential loads is a function of AC Bus OPERABILITY (Condition A of Technical Specification 3.8.9).

The AC sources in one train must be separate and independent (to the extent possible) of the AC sources in the other train. For the DGs, separation and independence are complete.

APPLICABILITY

The AC sources and sequencers are required to be OPERABLE in MODES 1, 2, 3, and 4 to ensure that:

- a. Acceptable fuel design limits and reactor coolant pressure boundary limits are not exceeded as a result of AOOs or abnormal transients; and
- b. Adequate core cooling is provided and containment OPERABILITY and other vital functions are maintained in the event of a postulated DBA.

The AC power requirements for MODES 5 and 6 are covered in LCO 3.8.2, "AC Sources—Shutdown."

ACTIONS

A Note prohibits the application of LCO 3.0.4.b to an inoperable DG. There is an increased risk associated with entering a MODE or other specified condition in the Applicability with an inoperable DG and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

A.1

To ensure a highly reliable power source remains with one offsite circuit inoperable, it is necessary to verify the OPERABILITY of the remaining

BASES

APPLICABILITY (continued)

Pressure increases are less prominent in MODE 3 because the core input energy is reduced, but the RCS pressure is high. Therefore, the LCO is applicable in MODES 1, 2, and 3. The LCO is not applicable in MODE 4 when both pressure and core energy are decreased and the pressure surges become much less significant. The PORV setpoint is reduced for LTOP in MODES 4 \leq 300°F, 5, and 6 with the reactor vessel head in place. LCO 3.4.12 addresses the PORV requirements in these MODES.

ACTIONS

A

Note ~~0~~ has been added to clarify that all pressurizer PORVs are treated as separate entities, each with separate Completion Times (i.e., the Completion Time is on a component basis). The exception for LCO 3.0.4, Note 2, permits entry into MODES 1, 2, and 3 to perform cycling of the PORVs or block valves to verify their OPERABLE status. Testing is not performed in lower MODES.

A.1

With the PORVs inoperable and capable of being manually cycled, either the PORVs must be restored or the flow path isolated within 1 hour. The block valves should be closed but power must be maintained to the associated block valves, since removal of power would render the block valve inoperable. Although a PORV may be designated inoperable, it may be able to be manually opened and closed, and therefore, able to perform its function. PORV inoperability may be due to seat leakage or other causes that do not prevent manual use and do not create a possibility for a small break LOCA. For these reasons, the block valve may be closed but the Action requires power be maintained to the valve. This Condition is only intended to permit operation of the plant for a limited period of time not to exceed the next refueling outage (MODE 6) so that maintenance can be performed on the PORVs to eliminate the problem condition. Normally, the PORVs should be available for automatic mitigation of overpressure events and should be returned to OPERABLE status prior to entering startup (MODE 2).

Quick access to the PORV for pressure control can be made when power remains on the closed block valve. The Completion Time of 1 hour is based on plant operating experience that has shown that minor problems can be corrected or closure accomplished in this time period.

BASES

APPLICABILITY (continued)

The Applicability is modified by a Note stating that accumulator isolation is only required when the accumulator pressure is more than or at the maximum RCS pressure for the existing temperature, as allowed by the P/T limit curves. This Note permits the accumulator discharge isolation valve Surveillance to be performed only under these pressure and temperature conditions.

ACTIONS

~~LCO 3.0.4 is not applicable for entry into LTOP operation.~~

A.1, A.2.1, A.2.2.1, A.2.2.2., A.3, and A.4

WOG
INSERT 1B

With two centrifugal charging pumps, safety injection pumps, or a combination of each, capable of injecting into the RCS, RCS overpressurization is possible.

To immediately initiate action to restore restricted coolant input capability to the RCS reflects the urgency of removing the RCS from this condition. Two pumps may be capable of injecting into the RCS provided the RHR suction relief valve is OPERABLE with the RCS cold leg temperature > 167°F or > 107°F and cooldown rate limited to 20°F, or if two PORVs are secured open with the associated block valves open and power removed, or with an RCS vent of 4.5 square inches. For cases where no reactor coolant pumps are in operation, RCS cold leg temperature limits are to be met by monitoring of BOTH the WR Cold Leg temperatures and Residual Heat Removal Heat Exchanger discharge temperature. With both PORVS and block valves secured open, or with an RCS vent of 4.5 square inches, there are no credible single failures to limit the flow relief capacity. For the RHR relief valve to be OPERABLE, the RHR suction isolation valves must be open and the relief valve setpoint at 450 psig consistent with the safety analysis. The RHR suction relief valves are spring loaded, bellows type water relief valves with pressure tolerances and accumulation limits established by Section III of the American Society of Mechanical Engineers (ASME) Code (Ref. 3) for Class 2 relief valves.

Required Action A.1 is modified by a Note that permits two centrifugal charging pumps capable of RCS injection for ≤ 15 minutes to allow for pump swaps.

B.1, C.1, and C.2

An unisolated accumulator requires isolation within 1 hour. This is only required when the accumulator pressure is at or more than the maximum

BASES

APPLICABLE SAFETY ANALYSES (continued)

The safety significance of RCS LEAKAGE varies widely depending on its source, rate, and duration. Therefore, detecting and monitoring RCS LEAKAGE into the containment area is necessary. Quickly separating the identified LEAKAGE from the unidentified LEAKAGE provides quantitative information to the operators, allowing them to take corrective action should a leakage occur detrimental to the safety of the unit and the public.

RCS leakage detection instrumentation satisfies Criterion 1 of 10 CFR 50.36 (Ref. 4).

LCO

One method of protecting against large RCS leakage derives from the ability of instruments to rapidly detect extremely small leaks. This LCO requires instruments of diverse monitoring principles to be OPERABLE to provide a high degree of confidence that extremely small leaks are detected in time to allow actions to place the plant in a safe condition, when RCS LEAKAGE indicates possible RCPB degradation.

The LCO is satisfied when monitors of diverse measurement means are available. Thus, the containment floor and equipment sump level monitoring system and a gaseous radioactivity monitor, in combination with a containment ventilation condensate drain tank level monitor or particulate radioactivity monitor, provides an acceptable minimum.

APPLICABILITY

Because of elevated RCS temperature and pressure in MODES 1, 2, 3, and 4, RCS leakage detection instrumentation is required to be OPERABLE.

In MODE 5 or 6, the temperature is to be $\leq 200^{\circ}\text{F}$ and pressure is maintained low or at atmospheric pressure. Since the temperatures and pressures are far lower than those for MODES 1, 2, 3, and 4, the likelihood of leakage and crack propagation are much smaller. Therefore, the requirements of this LCO are not applicable in MODES 5 and 6.

ACTIONS

The Required Actions are modified by a Note that indicates that the provisions of LCO 3.0.4 are not applicable. As a result, a MODE change is allowed when the containment floor and equipment sump level monitoring system and required radiation monitors are inoperable. This allowance is provided because other instrumentation is available to monitor RCS leakage.

WOG INSERT 1B (LCO 3.4.12, LTOP) – TSTF-359, REV 9

A Note prohibits the application of LCO 3.0.4.b to an inoperable LTOP system. There is an increased risk associated with entering MODE 4 from MODE 5 with LTOP inoperable and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

BASES

LCO

The specific iodine activity is limited to 1.0 $\mu\text{Ci/gm}$ DOSE EQUIVALENT I-131, and the gross specific activity in the reactor coolant is limited to the number of $\mu\text{Ci/gm}$ equal to 100 divided by \bar{E} (average disintegration energy of the sum of the average beta and gamma energies of the coolant nuclides). The limit on DOSE EQUIVALENT I-131 ensures the 2 hour thyroid dose to an individual at the site boundary during the Design Basis Accident (DBA) will be a small fraction of the allowed thyroid dose. The limit on gross specific activity ensures the 2 hour whole body dose to an individual at the site boundary during the DBA will be a small fraction of the allowed whole body dose.

The SGTR accident analysis (Ref. 2) shows that the 2 hour site boundary dose levels are within acceptable limits. Violation of the LCO may result in reactor coolant radioactivity levels that could, in the event of an SGTR, lead to site boundary doses that exceed the 10 CFR 100 dose guideline limits.

APPLICABILITY

In MODES 1 and 2, and in MODE 3 with RCS average temperature $\geq 500^\circ\text{F}$, operation within the LCO limits for DOSE EQUIVALENT I-131 and gross specific activity are necessary to contain the potential consequences of an SGTR to within the acceptable site boundary dose values.

For operation in MODE 3 with RCS average temperature $< 500^\circ\text{F}$, and in MODES 4 and 5, the release of radioactivity in the event of a SGTR is unlikely since the saturation pressure of the reactor coolant is below the lift pressure settings of the main steam safety valves.

ACTIONS

A.1 and A.2

With the DOSE EQUIVALENT I-131 greater than the LCO limit, samples at intervals of 4 hours must be taken to demonstrate that the limits of Figure 3.4.16-1 are not exceeded. The Completion Time of 4 hours is required to obtain and analyze a sample. Sampling is done to continue to provide a trend.

The DOSE EQUIVALENT I-131 must be restored to within limits within 48 hours. The Completion Time of 48 hours is required, if the limit violation resulted from normal iodine spiking.

INSERT 8

~~A Note to the Required Actions of Condition A excludes the MODE change restriction of LCO 3.0.4. This exception allows entry into the applicable MODE(S) while relying on the ACTIONS even though the ACTIONS may eventually require plant shutdown. This exception is acceptable due to the significant conservatism incorporated into the~~

BASES

ACTIONS (continued)

~~specific activity limit, the low probability of an event which is limiting due to exceeding this limit, and the ability to restore transient specific activity excursions while the plant remains at, or proceeds to power operation.~~

INSERT 8

B.1

With the gross specific activity in excess of the allowed limit, the unit must be placed in a MODE in which the requirement does not apply.

The change within 6 hours to MODE 3 and RCS average temperature < 500°F lowers the saturation pressure of the reactor coolant below the setpoints of the main steam safety valves and prevents venting the SG to the environment in an SGTR event. The allowed Completion Time of 6 hours is reasonable, based on operating experience, to reach MODE 3 below 500°F from full power conditions in an orderly manner and without challenging plant systems.

C.1

If a Required Action and the associated Completion Time of Condition A is not met or if the DOSE EQUIVALENT I-131 is in the unacceptable region of Figure 3.4.16-1, the reactor must be brought to MODE 3 with RCS average temperature < 500°F within 6 hours. The Completion Time of 6 hours is reasonable, based on operating experience, to reach MODE 3 below 500°F from full power conditions in an orderly manner and without challenging plant systems.

SURVEILLANCE
REQUIREMENTS

SR 3.4.16.1

SR 3.4.16.1 requires performing a gamma isotopic analysis as a measure of the gross specific activity of the reactor coolant at least once every 7 days. A gross radioactivity analysis shall consist of the quantitative measurement of the total specific activity of the reactor coolant except for radionuclides with half-lives less than 10 minutes and all radioiodines. The total specific activity shall be the sum of the beta-gamma activity in the sample within 2 hours after the sample is taken and extrapolated back to when the sample was taken. Determination of the contributors to the gross specific activity shall be based upon those energy peaks identifiable with a 95% confidence level. The latest available data may be used for pure beta-emitting radionuclides. This Surveillance provides an indication of any increase in gross specific activity.

INSERT 8 (RCS SPECIFIC ACTIVITY BASES) – TSTF-359, REV 9

A Note permits the use of the provisions of LCO 3.0.4.c. This allowance permits entry into the applicable MODE(S) while relying on the ACTIONS.

BASES

LCO (continued)

ECCS pumps and their respective supply headers to each of the four cold leg injection nozzles. In the long term, this flow path may be switched to take its supply from the containment sump and to deliver its flow to the RCS hot and cold legs.

APPLICABILITY: In MODES 1, 2, and 3, the OPERABILITY requirements for ECCS are covered by LCO 3.5.2.

In MODE 4 with RCS temperature below 350°F, one OPERABLE ECCS train is acceptable without single failure consideration, on the basis of the stable reactivity of the reactor and the limited core cooling requirements.

In MODES 5 and 6, plant conditions are such that the probability of an event requiring ECCS injection is extremely low. Core cooling requirements in MODE 5 are addressed by LCO 3.4.7, "RCS Loops—MODE 5, Loops Filled," and LCO 3.4.8, "RCS Loops—MODE 5, Loops Not Filled." MODE 6 core cooling requirements are addressed by LCO 3.9.5, "Residual Heat Removal (RHR) and Coolant Circulation—High Water Level," and LCO 3.9.6, "Residual Heat Removal (RHR) and Coolant Circulation—Low Water Level."

ACTIONS

A.1

WOG
INSERT 2B

With no ECCS RHR subsystem OPERABLE, the plant is not prepared to respond to a loss of coolant accident or to continue a cooldown using the RHR pumps and heat exchangers. The Completion Time of immediately to initiate actions that would restore at least one ECCS RHR subsystem to OPERABLE status ensures that prompt action is taken to restore the required cooling capacity. Normally, in MODE 4, reactor decay heat is removed from the RCS by an RHR loop. If no RHR loop is OPERABLE for this function, reactor decay heat must be removed by some alternate method, such as use of the steam generators. The alternate means of heat removal must continue until the inoperable RHR loop components can be restored to operation so that decay heat removal is continuous.

With both RHR pumps and heat exchangers inoperable, it would be unwise to require the plant to go to MODE 5, where the only available heat removal system is the RHR. Therefore, the appropriate action is to initiate measures to restore one ECCS RHR subsystem and to continue the actions until the subsystem is restored to OPERABLE status.

WOG INSERT 2B (LCO 3.5.3, ECCS SHUTDOWN) – TSTF-359, REV 9

A Note prohibits the application of LCO 3.0.4.b to an inoperable ECCS centrifugal charging subsystem when entering MODE 4. There is an increased risk associated with entering MODE 4 from MODE 5 with an inoperable ECCS centrifugal charging subsystem and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

BASES

APPLICABILITY (continued)

In MODES 3 and 4, both the hydrogen production rate and the total hydrogen produced after a LOCA would be less than that calculated for the DBA LOCA. Also, because of the limited time in these MODES, the probability of an accident requiring the hydrogen recombiners is low. Therefore, the hydrogen recombiners are not required in MODE 3 or 4.

In MODES 5 and 6, the probability and consequences of a LOCA are low, due to the pressure and temperature limitations in these MODES. Therefore, hydrogen recombiners are not required in these MODES.

ACTIONS

A.1

With one containment hydrogen recombiner inoperable, the inoperable recombiner must be restored to OPERABLE status within 30 days. In this condition, the remaining OPERABLE hydrogen recombiner is adequate to perform the hydrogen control function. However, the overall reliability is reduced because a single failure in the OPERABLE recombiner could result in reduced hydrogen control capability. The 30 day Completion Time is based on the availability of the other hydrogen recombiner, the small probability of a LOCA occurring (that would generate an amount of hydrogen that exceeds the flammability limit), and the amount of time available after a LOCA (should one occur) for operator action to prevent hydrogen accumulation from exceeding the flammability limit.

Required Action A.1 has been modified by a Note that states the provisions of LCO 3.0.4 are not applicable. As a result, a MODE change is allowed when one recombiner is inoperable. This allowance is based on the availability of the other hydrogen recombiner, the small probability of a LOCA occurring (that would generate an amount of hydrogen that exceeds the flammability limit), and the amount of time available after a LOCA (should one occur) for operator action to prevent hydrogen accumulation from exceeding the flammability limit.

B.1

If the inoperable hydrogen recombiner(s) cannot be restored to OPERABLE status within the required Completion Time, the plant must be brought to a MODE in which the LCO does not apply. To achieve this status, the plant must be brought to at least MODE 3 within 6 hours. The Completion Time of 6 hours is reasonable, based on operating experience, to reach MODE 3 from full power conditions in an orderly manner and without challenging plant systems.

BASES

APPLICABILITY (continued)

the DBA LOCA. Also, because of the limited time in these MODES, the probability of an accident requiring the HSS is low. Therefore, the HSS is not required in MODE 3 or 4.

In MODES 5 and 6, the probability and consequences of a LOCA or steam line break (SLB) are reduced due to the pressure and temperature limitations in these MODES. Therefore, the HSS is not required in these MODES.

ACTIONS

A.1

With one HSS train inoperable, the inoperable train must be restored to OPERABLE status within 30 days. In this Condition, the remaining OPERABLE HSS train is adequate to perform the hydrogen mixing function. However, the overall reliability is reduced because a single failure in the OPERABLE train could result in reduced hydrogen mixing capability. The 30 day Completion Time is based on the availability of the other HSS train, the small probability of a LOCA or SLB occurring (that would generate an amount of hydrogen that exceeds the flammability limit), the amount of time available after a LOCA or SLB (should one occur) for operator action to prevent hydrogen accumulation from exceeding the flammability limit, and the availability of the hydrogen recombiners and Hydrogen Mitigation System.

~~Required Action A.1 has been modified by a Note that states the provisions of LCO 3.0.4 are not applicable. As a result, a MODE change is allowed when one HSS train is inoperable. This allowance is based on the availability of the other HSS train, the small probability of a LOCA or SLB occurring (that would generate an amount of hydrogen that exceeds the flammability limit), and the amount of time available after a LOCA or SLB (should one occur) for operator action to prevent hydrogen accumulation from exceeding the flammability limit.~~

B.1

If an inoperable HSS train cannot be restored to OPERABLE status within the required Completion Time, the plant must be brought to a MODE in which the LCO does not apply. To achieve this status, the plant must be brought to at least MODE 3 within 6 hours. The allowed Completion Time of 6 hours is reasonable, based on operating experience, to reach MODE 3 from full power conditions in an orderly manner and without challenging plant systems.

BASES

ACTIONS

A.1

With one required SG PORV line inoperable, action must be taken to restore OPERABLE status within 7 days. The 7 day Completion Time allows for the redundant capability afforded by the remaining OPERABLE SG PORV lines, a nonsafety grade backup in the Steam Dump System, and MSSVs. Required Action A.1 is modified by a Note indicating that LCO 3.0.4 does not apply.

B.1

With two or more SG PORV lines inoperable, action must be taken to restore all but one SG PORV line to OPERABLE status. Since the block valve can be closed to isolate an SG PORV, some repairs may be possible with the unit at power. The 24 hour Completion Time is reasonable to repair inoperable SG PORV lines, based on the availability of the Steam Dump System and MSSVs, and the low probability of an event occurring during this period that would require the SG PORV lines.

C.1 and C.2

If the SG PORV lines cannot be restored to OPERABLE status within the associated Completion Time, the unit must be placed in a MODE in which the LCO does not apply. To achieve this status, the unit must be placed in at least MODE 3 within 6 hours, and in MODE 4, without reliance upon steam generator for heat removal, within 12 hours. The allowed Completion Times are reasonable, based on operating experience, to reach the required unit conditions from full power conditions in an orderly manner and without challenging unit systems.

SURVEILLANCE
REQUIREMENTS

SR 3.7.4.1

To perform a controlled cooldown of the RCS, the SG PORVs must be able to be opened manually using the handwheel and throttled through their full range. This SR ensures that the SG PORVs are tested through a full cycle at least once per fuel cycle. Performance of inservice testing or use of an SG PORV during a unit cooldown may satisfy this requirement. Operating experience has shown that these components usually pass the Surveillance when performed at the 18 month Frequency. The Frequency is acceptable from a reliability standpoint.

LCO (continued)

The LCO is modified by a Note indicating that one AFW train, which includes a motor driven pump, is required to be OPERABLE in MODE 4. This is because of the reduced heat removal requirements and short period of time in MODE 4 during which the AFW is required and the insufficient steam available in MODE 4 to power the turbine driven AFW pump.

APPLICABILITY

In MODES 1, 2, and 3, the AFW System is required to be OPERABLE in the event that it is called upon to function when the MFW is lost. In addition, the AFW System is required to supply enough makeup water to replace the steam generator secondary inventory, lost as the unit cools to MODE 4 conditions.

In MODE 4 the AFW System may be used for heat removal via the steam generators.

In MODE 5 or 6, the steam generators are not normally used for heat removal, and the AFW System is not required.

ACTIONS

WOG
INSERT 3B

A.1

If one of the two steam supplies to the turbine driven AFW train is inoperable, action must be taken to restore OPERABLE status within 7 days in MODES 1, 2, and 3. The 7 day Completion Time is reasonable, based on the following reasons:

- a. The redundant OPERABLE steam supply to the turbine driven AFW pump;
- b. The availability of redundant OPERABLE motor driven AFW pumps; and
- c. The low probability of an event occurring that requires the inoperable steam supply to the turbine driven AFW pump.

The second Completion Time for Required Action A.1 establishes a limit on the maximum time allowed for any combination of Conditions to be inoperable during any continuous failure to meet this LCO.

The 10 day Completion Time provides a limitation time allowed in this specified Condition after discovery of failure to meet the LCO. This limit

WOG INSERT 3B (LCO 3.7.5, AFW SYSTEM) – TSTF-359, REV 9

A Note prohibits the application of LCO 3.0.4.b to an inoperable AFW train when entering MODE 1. There is an increased risk associated with entering MODE 1 with an AFW train inoperable and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

BASES
LCO (continued)

Each DG must be capable of starting, accelerating to rated speed and voltage, and connecting to its respective ESF bus on detection of bus undervoltage. This will be accomplished within 11 seconds. Each DG must also be capable of accepting required loads within the assumed loading sequence intervals, and continue to operate until offsite power can be restored to the ESF buses. These capabilities are required to be met from a variety of initial conditions such as DG in standby with the engine hot and DG in standby with the engine at ambient conditions. Additional DG capabilities must be demonstrated to meet required Surveillance, e.g., capability of the DG to revert to standby status on an ECCS signal while operating in parallel test mode.

Proper sequencing of loads is a function of Sequencer OPERABILITY. Proper load shedding is a function of DG OPERABILITY. Proper tripping of non-essential loads is a function of AC Bus OPERABILITY (Condition A of Technical Specification 3.8.9).

The AC sources in one train must be separate and independent (to the extent possible) of the AC sources in the other train. For the DGs, separation and independence are complete.

APPLICABILITY

The AC sources and sequencers are required to be OPERABLE in MODES 1, 2, 3, and 4 to ensure that:

- a. Acceptable fuel design limits and reactor coolant pressure boundary limits are not exceeded as a result of AOOs or abnormal transients; and
- b. Adequate core cooling is provided and containment OPERABILITY and other vital functions are maintained in the event of a postulated DBA.

The AC power requirements for MODES 5 and 6 are covered in LCO 3.8.2, "AC Sources—Shutdown."

ACTIONS

WOG
INSERT 4B

A.1

To ensure a highly reliable power source remains with one offsite circuit inoperable, it is necessary to verify the OPERABILITY of the remaining required offsite circuit on a more frequent basis. Since the Required Action only specifies "perform," a failure of SR 3.8.1.1 acceptance criteria does not result in a Required Action not met. However, if a second required circuit fails SR 3.8.1.1, the second offsite circuit is inoperable, and Condition C, for two offsite circuits inoperable, is entered.

WOG INSERT 4B (LCO 3.8.1, AC SOURCES - OPERATING) – TSTF-359, REV 9

A Note prohibits the application of LCO 3.0.4.b to an inoperable DG. There is an increased risk associated with entering a MODE or other specified condition in the Applicability with an inoperable DG and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

Attachment 5b

Catawba Units 1 and 2

Proposed Technical Specifications Bases Changes (Mark-up)

BASES

LCO 3.0.3 (continued)

unit is in a lower MODE of operation when a shutdown is required, the time limit for reaching the next lower MODE applies. If a lower MODE is reached in less time than allowed, however, the total allowable time to reach MODE 5, or other applicable MODE, is not reduced. For example, if MODE 3 is reached in 2 hours, then the time allowed for reaching MODE 4 is the next 11 hours, because the total time for reaching MODE 4 is not reduced from the allowable limit of 13 hours. Therefore, if remedial measures are completed that would permit a return to MODE 1, a penalty is not incurred by having to reach a lower MODE of operation in less than the total time allowed.

In MODES 1, 2, 3, and 4, LCO 3.0.3 provides actions for Conditions not covered in other Specifications. The requirements of LCO 3.0.3 do not apply in MODES 5 and 6 because the unit is already in the most restrictive Condition required by LCO 3.0.3. The requirements of LCO 3.0.3 do not apply in other specified conditions of the Applicability (unless in MODE 1, 2, 3, or 4) because the ACTIONS of individual Specifications sufficiently define the remedial measures to be taken.

Exceptions to LCO 3.0.3 are provided in instances where requiring a unit shutdown, in accordance with LCO 3.0.3, would not provide appropriate remedial measures for the associated condition of the unit. An example of this is in LCO 3.7.14, "Spent Fuel Pool (SFP) Water Level." LCO 3.7.14 has an Applicability of "During movement of irradiated fuel assemblies in the spent fuel pool." Therefore, this LCO can be applicable in any or all MODES. If the LCO and the Required Actions of LCO 3.7.14 are not met while in MODE 1, 2, or 3, there is no safety benefit to be gained by placing the unit in a shutdown condition. The Required Action of LCO 3.7.14 of "Suspend movement of irradiated fuel assemblies in the spent fuel pool" is the appropriate Required Action to complete in lieu of the actions of LCO 3.0.3. These exceptions are addressed in the individual Specifications.

LCO 3.0.4

LCO 3.0.4 establishes limitations on changes in MODES or other specified conditions in the Applicability when an LCO is not met. It precludes placing the unit in a MODE or other specified condition stated in that Applicability (e.g., Applicability desired to be entered) when the following exist:

- a. Unit conditions are such that the requirements of the LCO would not be met in the Applicability desired to be entered; and

INSERT 3

BASES

LCO 3.0.4 (continued)

- b. Continued noncompliance with the LCO requirements, if the Applicability were entered, would result in the unit being required to exit the Applicability desired to be entered to comply with the Required Actions.

Compliance with Required Actions that permit continued operation of the unit for an unlimited period of time in a MODE or other specified condition provides an acceptable level of safety for continued operation. This is without regard to the status of the unit before or after the MODE change. Therefore, in such cases, entry into a MODE or other specified condition in the Applicability may be made in accordance with the provisions of the Required Actions. The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or components to OPERABLE status before entering an associated MODE or other specified condition in the Applicability.

The provisions of LCO 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS.

Exceptions to LCO 3.0.4 are stated in the individual Specifications. The exceptions allow entry into MODES or other specified conditions in the Applicability when the associated ACTIONS to be entered do not provide for continued operation for an unlimited period of time. Exceptions may apply to all the ACTIONS or to a specific Required Action of a Specification.

Surveillances do not have to be performed on the associated inoperable equipment (or on variables outside the specified limits), as permitted by SR 3.0.1. Therefore, changing MODES or other specified conditions while in an ACTIONS Condition, in compliance with LCO 3.0.4 or where an exception to LCO 3.0.4 is stated, is not a violation of SR 3.0.1 or SR 3.0.4 for those Surveillances that do not have to be performed due to the associated inoperable equipment. However, SRs must be met to ensure OPERABILITY prior to declaring the associated equipment OPERABLE (or variable within limits) and restoring compliance with the affected LCO.

INSERT 3

LCO 3.0.5

LCO 3.0.5 establishes the allowance for restoring equipment to service under administrative controls when it has been removed from service or declared inoperable to comply with ACTIONS. The sole purpose of this Specification is to provide an exception to LCO 3.0.2 (e.g., to not comply

INSERT 3 (LCO 3.0.4 BASES) – TSTF-359, REV 9

LCO 3.0.4 establishes limitations on changes in MODES or other specified conditions in the Applicability when an LCO is not met. It allows placing the unit in a MODE or other specified condition stated in that Applicability (e.g., the Applicability desired to be entered) when unit conditions are such that the requirements of the LCO would not be met, in accordance with LCO 3.0.4.a, LCO 3.0.4.b, or LCO 3.0.4.c.

LCO 3.0.4.a allows entry into a MODE or other specified condition in the Applicability with the LCO not met when the associated ACTIONS to be entered permit continued operation in the MODE or other specified condition in the Applicability for an unlimited period of time. Compliance with Required Actions that permit continued operation of the unit for an unlimited period of time in a MODE or other specified condition provides an acceptable level of safety for continued operation. This is without regard to the status of the unit before or after the MODE change. Therefore, in such cases, entry into a MODE or other specified condition in the Applicability may be made in accordance with the provisions of the Required Actions.

LCO 3.0.4.b allows entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, consideration of the results, determination of the acceptability of entering the MODE or other specified condition in the Applicability, and establishment of risk management actions, if appropriate.

The risk assessment may use quantitative, qualitative, or blended approaches, and the risk assessment will be conducted using the plant program, procedures, and criteria in place to implement 10 CFR 50.65(a)(4), which requires that risk impacts of maintenance activities to be assessed and managed. The risk assessment, for the purposes of LCO 3.0.4 (b), must take into account all inoperable Technical Specification equipment regardless of whether the equipment is included in the normal 10 CFR 50.65(a)(4) risk assessment scope. The risk assessments will be conducted using the procedures and guidance endorsed by Regulatory Guide 1.182, "Assessing and Managing Risk Before Maintenance Activities at Nuclear Power Plants." Regulatory Guide 1.182 endorses the guidance in Section 11 of NUMARC 93-01, "Industry Guideline for Monitoring the Effectiveness of Maintenance at Nuclear Power Plants." These documents address general guidance for conduct of the risk assessment, quantitative and qualitative guidelines for establishing risk management actions, and example risk management actions. These include actions to plan and conduct other activities in a manner that controls overall risk, increased risk awareness by shift and management personnel, actions to reduce the duration of the condition, actions to minimize the magnitude of risk increases (establishment of backup success paths or compensatory measures), and determination that the proposed MODE change is acceptable. Consideration should also be given to the probability of completing restoration such that the requirements of the LCO would be met prior to the expiration of ACTIONS Completion Times that would require exiting the Applicability.

INSERT 3 (LCO 3.0.4 BASES) – TSTF-359, REV 9

LCO 3.0.4.b may be used with single, or multiple systems and components unavailable. NUMARC 93-01 provides guidance relative to consideration of simultaneous unavailability of multiple systems and components.

The results of the risk assessment shall be considered in determining the acceptability of entering the MODE or other specified condition in the Applicability, and any corresponding risk management actions. The LCO 3.0.4.b risk assessments do not have to be documented.

The Technical Specifications allow continued operation with equipment unavailable in MODE 1 for the duration of the Completion Time. Since this is allowable, and since in general the risk impact in that particular MODE bounds the risk of transitioning into and through the applicable MODES or other specified conditions in the Applicability of the LCO, the use of the LCO 3.0.4.b allowance should be generally acceptable, as long as the risk is assessed and managed as stated above. However, there is a small subset of systems and components that have been determined to be more important to risk and use of the LCO 3.0.4.b allowance is prohibited. The LCOs governing these system and components contain Notes prohibiting the use of LCO 3.0.4.b by stating that LCO 3.0.4.b is not applicable.

LCO 3.0.4.c allows entry into a MODE or other specified condition in the Applicability with the LCO not met based on a Note in the Specification which states LCO 3.0.4.c is applicable. These specific allowances permit entry into MODES or other specified conditions in the Applicability when the associated ACTIONS to be entered do not provide for continued operation for an unlimited period of time and a risk assessment has not been performed. This allowance may apply to all the ACTIONS or to a specific Required Action of a Specification. The risk assessments performed to justify the use of LCO 3.0.4.b usually only consider systems and components. For this reason, LCO 3.0.4.c is typically applied to Specifications which describe values and parameters (e.g., RCS Specific Activity).

The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or components to OPERABLE status before entering an associated MODE or other specified condition in the Applicability.

The provisions of LCO 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS. In addition, the provisions of LCO 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that result from any unit shutdown. In this context, a unit shutdown is defined as a change in MODE or other specified condition in the Applicability associated with transitioning from MODE 1 to MODE 2, MODE 2 to MODE 3, MODE 3 to MODE 4, and MODE 4 to MODE 5.

INSERT 3 (LCO 3.0.4 BASES) – TSTF-359, REV 9

Upon entry into a MODE or other specified condition in the Applicability with the LCO not met, LCO 3.0.1 and LCO 3.0.2 require entry into the applicable Conditions and Required Actions until the Condition is resolved, until the LCO is met, or until the unit is not within the Applicability of the Technical Specification.

Surveillances do not have to be performed on the associated inoperable equipment (or on variables outside the specified limits), as permitted by SR 3.0.1. Therefore, utilizing LCO 3.0.4 is not a violation of SR 3.0.1 or SR 3.0.4 for any Surveillances that have not been performed on inoperable equipment. However, SRs must be met to ensure OPERABILITY prior to declaring the associated equipment OPERABLE (or variable within limits) and restoring compliance with the affected LCO.

BASES

SR 3.0.3 (continued)

Completion of the Surveillance within the delay period allowed by this Specification, or within the Completion Time of the ACTIONS, restores compliance with SR 3.0.1.

SR 3.0.4

SR 3.0.4 establishes the requirement that all applicable SRs must be met before entry into a MODE or other specified condition in the Applicability.

This Specification ensures that system and component OPERABILITY requirements and variable limits are met before entry into MODES or other specified conditions in the Applicability for which these systems and components ensure safe operation of the unit.

The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or component to OPERABLE status before entering an associated MODE or other specified condition in the Applicability.

However, in certain circumstances, failing to meet an SR will not result in SR 3.0.4 restricting a MODE change or other specified condition change. When a system, subsystem, division, component, device, or variable is inoperable or outside its specified limits, the associated SR(s) are not required to be performed, per SR 3.0.1, which states that surveillances do not have to be performed on inoperable equipment. When equipment is inoperable, SR 3.0.4 does not apply to the associated SR(s) since the requirement for the SR(s) to be performed is removed. Therefore, failing to perform the Surveillance(s) within the specified Frequency does not result in an SR 3.0.4 restriction to changing MODES or other specified conditions of the Applicability. However, since the LCO is not met in this instance, LCO 3.0.4 will govern any restrictions that may (or may not) apply to MODE or other specified condition changes.

The provisions of SR 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS.

The precise requirements for performance of SRs are specified such that exceptions to SR 3.0.4 are not necessary. The specific time frames and conditions necessary for meeting the SRs are specified in the Frequency, in the Surveillance, or both. This allows performance of Surveillances when the prerequisite condition(s) specified in a Surveillance procedure require entry into the MODE or other specified condition in the Applicability of the associated LCO prior to the performance or completion of a Surveillance. A Surveillance that could not be performed until after entering the LCO Applicability, would have its Frequency specified such that it is not "due" until the specific conditions needed are

INSERT 4

BASES

SR 3.0.4 (continued)

INSERT 4 → met. Alternately, the Surveillance may be stated in the form of a Note as not required (to be met or performed) until a particular event, condition, or time has been reached. Further discussion of the specific formats of SRs' annotation is found in Section 1.4, Frequency.

SR 3.0.5

SR 3.0.5 delineates the applicability of the surveillance activities to Unit 1 and Unit 2 operations.

INSERT 4 (SR 3.0.4 BASES) – TSTF-359, REV 9

SR 3.0.4 establishes the requirement that all applicable SRs must be met before entry into a MODE or other specified condition in the Applicability.

This Specification ensures that system and component OPERABILITY requirements and variable limits are met before entry into MODES or other specified conditions in the Applicability for which these systems and components ensure safe operation of the unit. The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or components to OPERABLE status before entering an associated MODE or other specified condition in the Applicability.

A provision is included to allow entry into a MODE or other specified condition in the Applicability when an LCO is not met due to Surveillance not being met in accordance with LCO 3.0.4.

However, in certain circumstances, failing to meet an SR will not result in SR 3.0.4 restricting a MODE change or other specified condition change. When a system, subsystem, division, component, device, or variable is inoperable or outside its specified limits, the associated SR(s) are not required to be performed, per SR 3.0.1, which states that surveillances do not have to be performed on inoperable equipment. When equipment is inoperable, SR 3.0.4 does not apply to the associated SR(s) since the requirement for the SR(s) to be performed is removed. Therefore, failing to perform the Surveillance(s) within the specified Frequency does not result in an SR 3.0.4 restriction to changing MODES or other specified conditions of the Applicability.

However, since the LCO is not met in this instance, LCO 3.0.4 will govern any restrictions that may (or may not) apply to MODE or other specified condition changes. SR 3.0.4 does not restrict changing MODES or other specified conditions of the Applicability when a Surveillance has not been performed within the specified Frequency, provided the requirement to declare the LCO not met has been delayed in accordance with SR 3.0.3.

The provisions of SR 3.0.4 shall not prevent entry into MODES or other specified conditions in the Applicability that are required to comply with ACTIONS. In addition, the provisions of SR 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that result from any unit shutdown. In this context, a unit shutdown is defined as a change in MODE or other specified condition in the Applicability associated with transitioning from MODE 1 to MODE 2, MODE 2 to MODE 3, MODE 3 to MODE 4, and MODE 4 to MODE 5.

INSERT 4 (SR 3.0.4 BASES) – TSTF-359, REV 9

The precise requirements for performance of SRs are specified such that exceptions to SR 3.0.4 are not necessary. The specific time frames and conditions necessary for meeting the SRs are specified in the Frequency, in the Surveillance, or both. This allows performance of Surveillances when the prerequisite condition(s) specified in a Surveillance procedure require entry into the MODE or other specified condition in the Applicability of the associated LCO prior to the performance or completion of a Surveillance. A Surveillance that could not be performed until after entering the LCO's Applicability, would have its Frequency specified such that it is not "due" until the specific conditions needed are met. Alternately, the Surveillance may be stated in the form of a Note, as not required (to be met or performed) until a particular event, condition, or time has been reached. Further discussion of the specific formats of SRs' annotation is found in Section 1.4, Frequency.

BASES

APPLICABILITY (continued)

The Hydrogen Monitors are not required to be OPERABLE in MODE 3.

ACTIONS

Note 1 has been added in the ACTIONS to exclude the MODE change restriction of LCO 3.0.4. This exception allows entry into the applicable MODE while relying on the ACTIONS even though the ACTIONS may eventually require unit shutdown. This exception is acceptable due to the passive function of the instruments, the operator's ability to respond to an accident using alternate instruments and methods, and the low probability of an event requiring these instruments. Note 2 has been added in the ACTIONS to clarify the application of Completion Time rules. The Conditions of this Specification may be entered independently for each Function listed on Table 3.3.3-1. When the Required Channels in Table 3.3.3-1 are specified (e.g., on a per steam line, per loop, per SG, etc., basis), then the Condition may be entered separately for each steam line, loop, SG, etc., as appropriate. The Completion Time(s) of the inoperable channel(s) of a Function will be tracked separately for each Function starting from the time the Condition was entered for that Function. (A)

A.1

Condition A applies to all PAM instrument Functions. Condition A addresses the situation when one or more required channels for one or more Functions are inoperable. The Required Action is to refer to Table 3.3.3-1 and take the appropriate Required Actions for the PAM instrumentation affected. The Completion Times are those from the referenced Conditions and Required Actions.

B.1

Condition B applies when one or more Functions have one required channel that is inoperable. Required Action A.1 requires restoring the inoperable channel to OPERABLE status within 30 days. The 30 day Completion Time is based on operating experience and takes into account the remaining OPERABLE channel, the passive nature of the instrument (no critical automatic action is assumed to occur from these instruments), and the low probability of an event requiring PAM instrumentation during this interval.

BASES

APPLICABILITY The Remote Shutdown System LCO is applicable in MODES 1, 2, and 3. This is required so that the unit can be placed and maintained in MODE 3 for an extended period of time from a location other than the control room.

This LCO is not applicable in MODE 4, 5, or 6. In these MODES, the facility is already subcritical and in a condition of reduced RCS energy. Under these conditions, considerable time is available to restore necessary instrument control functions if control room instruments or controls become unavailable.

ACTIONS

Note 1 is included which excludes the MODE change restriction of LCO 3.0.4. This exception allows entry into an applicable MODE while relying on the ACTIONS even though the ACTIONS may eventually require a unit shutdown. This exception is acceptable due to the low probability of an event requiring the Remote Shutdown System and because the equipment can generally be repaired during operation without significant risk of spurious trip.

(A)

Note 2 has been added to the ACTIONS to clarify the application of Completion Time rules. Separate Condition entry is allowed for each Function listed on Table 3.3.4-1. The Completion Time(s) of the inoperable channel(s)/train(s) of a Function will be tracked separately for each Function starting from the time the Condition was entered for that Function.

A.1

Condition A addresses the situation where one or more required Functions of the Remote Shutdown System are inoperable. This includes any Function listed in Table 3.3.4-1 as well as the control and transfer switches.

The Required Action is to restore the required Function to OPERABLE status within 30 days. The Completion Time is based on operating experience and the low probability of an event that would require evacuation of the control room.

BASES

APPLICABILITY (continued)

Pressure increases are less prominent in MODE 3 because the core input energy is reduced, but the RCS pressure is high. Therefore, the LCO is applicable in MODES 1, 2, and 3. The LCO is not applicable in MODE 4 when both pressure and core energy are decreased and the pressure surges become much less significant. The PORV setpoint is reduced for LTOP in MODES 4 \leq 285°F, 5, and 6 with the reactor vessel head in place. LCO 3.4.12 addresses the PORV requirements in these MODES.

ACTIONS

(A) →

Note 1 has been added to clarify that all pressurizer PORVs are treated as separate entities, each with separate Completion Times (i.e., the Completion Time is on a component basis). The exception for LCO 3.0.4, Note 2, permits entry into MODES 1, 2, and 3 to perform cycling of the PORVs or block valves to verify their OPERABLE status. Testing is not performed in lower MODES.

A.1

With the PORVs inoperable and capable of being manually cycled, either the PORVs must be restored or the flow path isolated within 1 hour. The block valves should be closed but power must be maintained to the associated block valves, since removal of power would render the block valve inoperable. Although a PORV may be designated inoperable, it may be able to be manually opened and closed, and therefore, able to perform its function. PORV inoperability may be due to seat leakage or other causes that do not prevent manual use and do not create a possibility for a small break LOCA. For these reasons, the block valve may be closed but the Action requires power be maintained to the valve. This Condition is only intended to permit operation of the plant for a limited period of time not to exceed the next refueling outage (MODE 6) so that maintenance can be performed on the PORVs to eliminate the problem condition. Normally, the PORVs should be available for automatic mitigation of overpressure events and should be returned to OPERABLE status prior to entering startup (MODE 2).

Quick access to the PORV for pressure control can be made when power remains on the closed block valve. The Completion Time of 1 hour is based on plant operating experience that has shown that minor problems can be corrected or closure accomplished in this time period.

BASES

LCO (continued)

- b. A depressurized RCS and an RCS vent.

An RCS vent is OPERABLE when open with an area of ≥ 4.5 square inches.

Each of these methods of overpressure prevention is capable of mitigating the limiting LTOP transient.

APPLICABILITY

This LCO is applicable in MODE 4 when any RCS cold leg temperature is $\leq 285^\circ\text{F}$, in MODE 5, and in MODE 6 when the reactor vessel head is on. The pressurizer safety valves provide overpressure protection that meets the Reference 1 P/T limits above 285°F . When the reactor vessel head is off, overpressurization cannot occur.

LCO 3.4.3 provides the operational P/T limits for all MODES. LCO 3.4.10, "Pressurizer Safety Valves," requires the OPERABILITY of the pressurizer safety valves that provide overpressure protection during MODES 1, 2, and 3, and MODE 4 above 285°F .

Low temperature overpressure prevention is most critical during shutdown when the RCS is water solid, and a mass or heat input transient can cause a very rapid increase in RCS pressure when little or no time allows operator action to mitigate the event.

The Applicability is modified by a Note stating that accumulator isolation is only required when the accumulator pressure is more than or at the maximum RCS pressure for the existing temperature, as allowed by the P/T limit curves. This Note permits the accumulator discharge isolation valve Surveillance to be performed only under these pressure and temperature conditions.

ACTIONS

LCO 3.0.4 is not applicable for entry into LTOP operation.

WOG
INSERT 1B

A.1

With two or more charging pumps, two safety injection pumps, or one safety injection pump and one charging pump capable of injecting into the RCS, RCS overpressurization is possible.

To immediately initiate action to restore restricted coolant input capability to the RCS reflects the urgency of removing the RCS from this condition.

WOG INSERT 1B (LCO 3.4.12, LTOP) – TSTF-359, REV 9

A Note prohibits the application of LCO 3.0.4.b to an inoperable LTOP system. There is an increased risk associated with entering MODE 4 from MODE 5 with LTOP inoperable and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

BASES

APPLICABLE SAFETY ANALYSES (continued)

information to the operators, allowing them to take corrective action should a leakage occur detrimental to the safety of the unit and the public. RCS leakage detection instrumentation satisfies Criterion 1 of 10 CFR 50.36 (Ref. 4).

LCO

One method of protecting against large RCS leakage derives from the ability of instruments to rapidly detect extremely small leaks. This LCO requires instruments of diverse monitoring principles to be OPERABLE to provide a high degree of confidence that extremely small leaks are detected in time to allow actions to place the plant in a safe condition, when RCS LEAKAGE indicates possible RCPB degradation.

The LCO is satisfied when monitors of diverse measurement means are available. Thus, the containment floor and equipment sump level monitor, in combination with a gaseous or particulate radioactivity monitor and a containment ventilation unit condensate drain tank level monitor, provides an acceptable minimum.

APPLICABILITY

Because of elevated RCS temperature and pressure in MODES 1, 2, 3, and 4, RCS leakage detection instrumentation is required to be OPERABLE.

In MODE 5 or 6, the temperature is to be $\leq 200^{\circ}\text{F}$ and pressure is maintained low or at atmospheric pressure. Since the temperatures and pressures are far lower than those for MODES 1, 2, 3, and 4, the likelihood of leakage and crack propagation are much smaller. Therefore, the requirements of this LCO are not applicable in MODES 5 and 6.

ACTIONS

The Required Actions are modified by a Note that indicates that the provisions of LCO 3.0.4 are not applicable. As a result, a MODE change is allowed when the containment floor and equipment sump level monitor and required radiation monitors are inoperable. This allowance is provided because other instrumentation is available to monitor RCS leakage.

A.1 and A.2

With the required containment floor and equipment sump level monitor inoperable, no other form of sampling can provide the equivalent information; however, the containment atmosphere radioactivity monitor

BASES

LCO

The specific iodine activity is limited to 1.0 $\mu\text{Ci/gm}$ DOSE EQUIVALENT I-131, and the gross specific activity in the reactor coolant is limited to the number of $\mu\text{Ci/gm}$ equal to 100 divided by \bar{E} (average disintegration energy of the sum of the average beta and gamma energies of the coolant nuclides). The limit on DOSE EQUIVALENT I-131 ensures the 2 hour thyroid dose to an individual at the site boundary during the Design Basis Accident (DBA) will be a small fraction of the allowed thyroid dose. The limit on gross specific activity ensures the 2 hour whole body dose to an individual at the site boundary during the DBA will be a small fraction of the allowed whole body dose.

The SGTR accident analysis (Ref. 2) shows that the 2 hour site boundary dose levels are within acceptable limits. Violation of the LCO may result in reactor coolant radioactivity levels that could, in the event of an SGTR, lead to site boundary doses that exceed the 10 CFR 100 dose guideline limits.

APPLICABILITY

In MODES 1 and 2, and in MODE 3 with RCS average temperature $\geq 500^\circ\text{F}$, operation within the LCO limits for DOSE EQUIVALENT I-131 and gross specific activity are necessary to contain the potential consequences of an SGTR to within the acceptable site boundary dose values.

For operation in MODE 3 with RCS average temperature $< 500^\circ\text{F}$, and in MODES 4 and 5, the release of radioactivity in the event of a SGTR is unlikely since the saturation pressure of the reactor coolant is below the lift pressure settings of the main steam safety valves.

ACTIONS

A.1 and A.2

With the DOSE EQUIVALENT I-131 greater than the LCO limit, samples at intervals of 4 hours must be taken to demonstrate that the limits of Figure 3.4.16-1 are not exceeded. The Completion Time of 4 hours is required to obtain and analyze a sample. Sampling is done to continue to provide a trend.

The DOSE EQUIVALENT I-131 must be restored to within limits within 48 hours. The Completion Time of 48 hours is required, if the limit violation resulted from normal iodine spiking.

INSERT 8

~~A Note to the Required Actions of Condition A excludes the MODE change restriction of LCO 3.0.4. This exception allows entry into the applicable MODE(S) while relying on the ACTIONS even though the ACTIONS may eventually require plant shutdown. This exception is acceptable due to the significant conservatism incorporated into the~~

allowance

INSERT 8 (RCS SPECIFIC ACTIVITY BASES) – TSTF-359, REV 9

A Note permits the use of the provisions of LCO 3.0.4.c. This allowance permits entry into the applicable MODE(S) while relying on the ACTIONS.

BASES

LCO (continued)

ECCS pumps and their respective supply headers to each of the four cold leg injection nozzles. In the long term, this flow path may be switched to take its supply from the containment sump and to deliver its flow to the RCS hot and cold legs.

APPLICABILITY

In MODES 1, 2, and 3, the OPERABILITY requirements for ECCS are covered by LCO 3.5.2.

In MODE 4 with RCS temperature below 350°F, one OPERABLE ECCS train is acceptable without single failure consideration, on the basis of the stable reactivity of the reactor and the limited core cooling requirements.

In MODES 5 and 6, plant conditions are such that the probability of an event requiring ECCS injection is extremely low. Core cooling requirements in MODE 5 are addressed by LCO 3.4.7, "RCS Loops—MODE 5, Loops Filled," and LCO 3.4.8, "RCS Loops—MODE 5, Loops Not Filled." MODE 6 core cooling requirements are addressed by LCO 3.9.4, "Residual Heat Removal (RHR) and Coolant Circulation—High Water Level," and LCO 3.9.5, "Residual Heat Removal (RHR) and Coolant Circulation—Low Water Level."

ACTIONS

A.1

WOG
INSERT 2B

With no ECCS RHR subsystem OPERABLE, the plant is not prepared to respond to a loss of coolant accident or to continue a cooldown using the RHR pumps and heat exchangers. The Completion Time of immediately to initiate actions that would restore at least one ECCS RHR subsystem to OPERABLE status ensures that prompt action is taken to restore the required cooling capacity. Normally, in MODE 4, reactor decay heat is removed from the RCS by an RHR loop. If no RHR loop is OPERABLE for this function, reactor decay heat must be removed by some alternate method, such as use of the steam generators. The alternate means of heat removal must continue until the inoperable RHR loop components can be restored to operation so that decay heat removal is continuous.

With both RHR pumps and heat exchangers inoperable, it would be unwise to require the plant to go to MODE 5, where the only available heat removal system is the RHR. Therefore, the appropriate action is to initiate measures to restore one ECCS RHR subsystem and to continue the actions until the subsystem is restored to OPERABLE status..

WOG INSERT 2B (LCO 3.5.3, ECCS SHUTDOWN) – TSTF-359, REV 9

A Note prohibits the application of LCO 3.0.4.b to an inoperable ECCS centrifugal charging subsystem when entering MODE 4. There is an increased risk associated with entering MODE 4 from MODE 5 with an inoperable ECCS centrifugal charging subsystem and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

BASES

LCO (continued)

Operation with at least one hydrogen recombiner ensures that the post LOCA hydrogen concentration can be prevented from exceeding the flammability limit.

APPLICABILITY: In MODES 1 and 2, two hydrogen recombiners are required to control the hydrogen concentration within containment below its flammability limit of 4.0 v/o following a LOCA, assuming a worst case single failure.

In MODES 3 and 4, both the hydrogen production rate and the total hydrogen produced after a LOCA would be less than that calculated for the DBA LOCA. Also, because of the limited time in these MODES, the probability of an accident requiring the hydrogen recombiners is low. Therefore, the hydrogen recombiners are not required in MODE 3 or 4.

In MODES 5 and 6, the probability and consequences of a LOCA are low, due to the pressure and temperature limitations in these MODES. Therefore, hydrogen recombiners are not required in these MODES.

ACTIONS

A.1

With one containment hydrogen recombiner inoperable, the inoperable recombiner must be restored to OPERABLE status within 30 days. In this condition, the remaining OPERABLE hydrogen recombiner is adequate to perform the hydrogen control function. However, the overall reliability is reduced because a single failure in the OPERABLE recombiner could result in reduced hydrogen control capability. The 30 day Completion Time is based on the availability of the other hydrogen recombiner, the small probability of a LOCA occurring (that would generate an amount of hydrogen that exceeds the flammability limit), and the amount of time available after a LOCA (should one occur) for operator action to prevent hydrogen accumulation from exceeding the flammability limit.

Required Action A.1 has been modified by a Note that states the provisions of LCO 3.0.4 are not applicable. As a result, a MODE change is allowed when one recombiner is inoperable. This allowance is based on the availability of the other hydrogen recombiner, the small probability of a LOCA occurring (that would generate an amount of hydrogen that

BASES

ACTIONS (continued)

exceeds the flammability limit), and the amount of time available after a LOCA (should one occur) for operator action to prevent hydrogen accumulation from exceeding the flammability limit.

B.1

If the inoperable hydrogen recombiner(s) cannot be restored to OPERABLE status within the required Completion Time, the plant must be brought to a MODE in which the LCO does not apply. To achieve this status, the plant must be brought to at least MODE 3 within 6 hours. The Completion Time of 6 hours is reasonable; based on operating experience, to reach MODE 3 from full power conditions in an orderly manner and without challenging plant systems.

SURVEILLANCE REQUIREMENTS **SR 3.6.7.1**

Performance of a system functional test for each hydrogen recombinder ensures the recombiners are operational and can attain and sustain the temperature necessary for hydrogen recombination. In particular, this SR verifies that the minimum heater sheath temperature increases to $\geq 700^{\circ}\text{F}$ in ≤ 90 minutes. After reaching 700°F , the power is increased to maximum power for approximately 2 minutes and power is verified to be ≥ 60 kW.

Industry operating experience has shown that these components usually pass the Surveillance when performed at the 18 month Frequency. Therefore, the Frequency was concluded to be acceptable from a reliability standpoint.

SR 3.6.7.2

This SR ensures there are no physical problems that could affect recombinder operation. Since the recombiners are mechanically passive, they are not subject to mechanical failure. The only credible failure involves loose wiring or structural connections; deposits of foreign materials, etc.

A visual inspection is sufficient to determine abnormal conditions that could cause such failures. The 18 month Frequency for this SR was developed considering the incidence of hydrogen recombiners failing the SR in the past is low.

BASES

APPLICABILITY (continued)

In MODE 3 or 4, both the hydrogen production rate and the total hydrogen produced after a LOCA would be less than that calculated for the DBA LOCA. Also, because of the limited time in these MODES, the probability of an accident requiring the HSS is low. Therefore, the HSS is not required in MODE 3 or 4.

In MODES 5 and 6, the probability and consequences of a LOCA or steam line break (SLB) are reduced due to the pressure and temperature limitations in these MODES. Therefore, the HSS is not required in these MODES.

ACTIONS

A.1

With one HSS train inoperable, the inoperable train must be restored to OPERABLE status within 30 days. In this Condition, the remaining OPERABLE HSS train is adequate to perform the hydrogen mixing function. However, the overall reliability is reduced because a single failure in the OPERABLE train could result in reduced hydrogen mixing capability. The 30 day Completion Time is based on the availability of the other HSS train, the small probability of a LOCA or SLB occurring (that would generate an amount of hydrogen that exceeds the flammability limit), the amount of time available after a LOCA or SLB (should one occur) for operator action to prevent hydrogen accumulation from exceeding the flammability limit, and the availability of the hydrogen recombiners and hydrogen igniters.

Required Action A.1 has been modified by a Note that states the provisions of LCO 3.0.4 are not applicable. As a result, a MODE change is allowed when one HSS train is inoperable. This allowance is based on the availability of the other HSS train, the small probability of a LOCA or SLB occurring (that would generate an amount of hydrogen that exceeds the flammability limit), and the amount of time available after a LOCA or SLB (should one occur) for operator action to prevent hydrogen accumulation from exceeding the flammability limit.

B.1

If an inoperable HSS train cannot be restored to OPERABLE status within the required Completion Time, the plant must be brought to a MODE in which the LCO does not apply. To achieve this status, the plant

BASES

LCO (continued)

An SG PORV is considered OPERABLE when it is capable of providing controlled relief of the main steam flow and capable of fully opening and closing on demand using the nitrogen gas supply.

APPLICABILITY

In MODES 1, 2, and 3, and in MODE 4, when a steam generator is being relied upon for heat removal, the SG PORVs are required to be OPERABLE.

In MODE 5 or 6, an SGTR is not a credible event.

ACTIONS

A.1

With one SG PORV line inoperable, action must be taken to restore OPERABLE status within 7 days. The 7 day Completion Time allows for the redundant capability afforded by the remaining OPERABLE SG PORV lines, a nonsafety grade backup in the Steam Dump System, and MSSVs. Required Action A.1 is modified by a Note indicating that LCO 3.0.4 does not apply.

B.1

With two or more SG PORV lines inoperable, action must be taken to restore all but one SG PORV line to OPERABLE status. Since the block valve can be closed to isolate an SG PORV, some repairs may be possible with the unit at power. The 24 hour Completion Time is reasonable to repair inoperable SG PORV lines, based on the availability of the Steam Dump System and MSSVs, and the low probability of an event occurring during this period that would require the SG PORV lines.

C.1 and C.2

If the SG PORV lines cannot be restored to OPERABLE status within the associated Completion Time, the unit must be placed in a MODE in which the LCO does not apply. To achieve this status, the unit must be placed in at least MODE 3 within 6 hours, and in MODE 4, without reliance upon steam generator for heat removal, within 12 hours. The allowed Completion Times are reasonable, based on operating experience, to reach the required unit conditions from full power conditions in an orderly manner and without challenging unit systems.

BASES

LCO (continued)

The AFW System is configured into three trains. The AFW System is considered OPERABLE when the components and flow paths required to provide redundant AFW flow to the steam generators are OPERABLE. This requires that the two motor driven AFW pumps be OPERABLE in two diverse paths, each supplying AFW to separate steam generators. The turbine driven AFW pump is required to be OPERABLE with redundant steam supplies from two main steam lines upstream of the MSIVs, and shall be capable of supplying AFW to any of the steam generators. The piping, valves, instrumentation, and controls in the required flow paths also are required to be OPERABLE. The NSWs assured source of water supply is configured into two trains. The turbine driven AFW pump receives NSWs from both trains of NSWs, therefore, the loss of one train of assured source renders only one AFW train inoperable. The remaining NSWs train provides an OPERABLE assured source to the other motor driven pump and the turbine driven pump.

The LCO is modified by a Note indicating that one AFW train, which includes a motor driven pump, is required to be OPERABLE in MODE 4. This is because of the reduced heat removal requirements and short period of time in MODE 4 during which the AFW is required and the insufficient steam available in MODE 4 to power the turbine driven AFW pump.

APPLICABILITY

In MODES 1, 2, and 3, the AFW System is required to be OPERABLE in the event that it is called upon to function when the MFW is lost. In addition, the AFW System is required to supply enough makeup water to replace the steam generator secondary inventory, lost as the unit cools to MODE 4 conditions.

In MODE 4 the AFW System may be used for heat removal via the steam generators.

In MODE 5 or 6, the steam generators are not normally used for heat removal, and the AFW System is not required.

ACTIONS

A.1

WOG
INSERT 3B

If one of the two steam supplies to the turbine driven AFW train is inoperable, action must be taken to restore OPERABLE status within 7 days. The 7 day Completion Time is reasonable, based on the following reasons:

WOG INSERT 3B (LCO 3.7.5, AFW SYSTEM) – TSTF-359, REV 9

A Note prohibits the application of LCO 3.0.4.b to an inoperable AFW train when entering MODE 1. There is an increased risk associated with entering MODE 1 with an AFW train inoperable and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

BASES

APPLICABILITY (continued)

- b. Adequate core cooling is provided and containment OPERABILITY and other vital functions are maintained in the event of a postulated DBA.

The AC power requirements for MODES 5 and 6 are covered in LCO 3.8.2, "AC Sources—Shutdown."

ACTIONS

WOG
INSERT 4B

A.1

To ensure a highly reliable power source remains with one offsite circuit inoperable, it is necessary to verify the OPERABILITY of the remaining required offsite circuit on a more frequent basis. Since the Required Action only specifies "perform," a failure of SR 3.8.1.1 acceptance criteria does not result in a Required Action not met. However, if a second required circuit fails SR 3.8.1.1, the second offsite circuit is inoperable, and Condition C, for two offsite circuits inoperable, is entered.

A.2

Required Action A.2, which only applies if the train cannot be powered from an offsite source, is intended to provide assurance that an event coincident with a single failure of the associated DG will not result in a complete loss of safety function of critical redundant required features.

These features are powered from the redundant AC electrical power train. This includes motor driven auxiliary feedwater pumps. The turbine driven auxiliary feedwater pump is required to be considered a redundant required feature, and, therefore, required to be determined OPERABLE by this Required Action. Three independent AFW pumps are required to ensure the availability of decay heat removal capability for all events accompanied by a loss of offsite power and a single failure. System design is such that the remaining OPERABLE motor driven auxiliary feedwater pump is not by itself capable of providing 100% of the auxiliary feedwater flow assumed in the safety analysis.

The Completion Time for Required Action A.2 is intended to allow the operator time to evaluate and repair any discovered inoperabilities. This Completion Time also allows for an exception to the normal "time zero" for beginning the allowed outage time "clock." In this Required Action, the Completion Time only begins on discovery that both:

WOG INSERT 4B (LCO 3.8.1, AC SOURCES - OPERATING) – TSTF-359, REV 9

A Note prohibits the application of LCO 3.0.4.b to an inoperable DG. There is an increased risk associated with entering a MODE or other specified condition in the Applicability with an inoperable DG and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

BASES

ACTIONS (continued)

required offsite circuit on a more frequent basis. Since the Required Action only specifies "perform," a failure of SR 3.8.1.1 acceptance criteria does not result in a Required Action not met. However, if a second required circuit fails SR 3.8.1.1, the second offsite circuit is inoperable, and Condition C, for two offsite circuits inoperable, is entered.

A.2

Required Action A.2, which only applies if the train cannot be powered from an offsite source, is intended to provide assurance that an event coincident with a single failure of the associated DG will not result in a complete loss of safety function of critical redundant required features. These features are powered from the redundant AC electrical power train. This includes motor driven auxiliary feedwater pumps. The turbine driven auxiliary feedwater pump is required to be considered a redundant required feature, and, therefore, required to be determined OPERABLE by this Required Action. Three independent AFW pumps are required to ensure the availability of decay heat removal capability for all events accompanied by a loss of offsite power and a single failure. System design is such that the remaining OPERABLE motor driven auxiliary feedwater pump is not by itself capable of providing 100% of the auxiliary feedwater flow assumed in the safety analysis.

The Completion Time for Required Action A.2 is intended to allow the operator time to evaluate and repair any discovered inoperabilities. This Completion Time also allows for an exception to the normal "time zero" for beginning the allowed outage time "clock." In this Required Action, the Completion Time only begins on discovery that both:

- a. The train has no offsite power supplying its loads; and
- b. A required feature on the other train is inoperable.

If at any time during the existence of Condition A (one offsite circuit inoperable) a redundant required feature subsequently becomes inoperable, this Completion Time begins to be tracked.

Discovering no offsite power to one train of the onsite Class 1E Electrical Power Distribution System coincident with one or more inoperable required support or supported features, or both, that are associated with the other train that has offsite power, results in starting the Completion Times for the Required Action. Twenty-four hours is acceptable because it minimizes risk while allowing time for restoration before subjecting the unit to transients associated with shutdown.

The remaining OPERABLE offsite circuit and DGs are adequate to supply electrical power to Train A and Train B of the onsite Class 1E Distribution System. The 24 hour Completion Time takes into account the component OPERABILITY of the redundant counterpart to the inoperable required

BASES

ACTIONS (continued)

feature. Additionally, the 24 hour Completion Time takes into account the capacity and capability of the remaining AC sources, a reasonable time for repairs, and the low probability of a DBA occurring during this period.

A.3

According to Regulatory Guide 1.93 (Ref. 7), operation may continue in Condition A for a period that should not exceed 72 hours. With one offsite circuit inoperable, the reliability of the offsite system is degraded, and the potential for a loss of offsite power is increased, with attendant potential for a challenge to the unit safety systems. In this Condition, however, the remaining OPERABLE offsite circuit and DGs are adequate to supply electrical power to the onsite Class 1E Distribution System.

The 72 hour Completion Time takes into account the capacity and capability of the remaining AC sources, a reasonable time for repairs, and the low probability of a DBA occurring during this period.

The second Completion Time for Required Action A.3 establishes a limit on the maximum time allowed for any combination of required AC power sources to be inoperable during any single contiguous occurrence of failing to meet the LCO. If Condition A is entered while, for instance, a DG is inoperable and that DG is subsequently returned OPERABLE, the LCO may already have been not met for up to 72 hours. This could lead to a total of 144 hours, since initial failure to meet the LCO, to restore the offsite circuit. At this time, a DG could again become inoperable, the circuit restored OPERABLE, and an additional 72 hours (for a total of 9 days) allowed prior to complete restoration of the LCO. The 6 day Completion Time provides a limit on the time allowed in a specified condition after discovery of failure to meet the LCO. This limit is considered reasonable for situations in which Conditions A and B are entered concurrently. The "AND" connector between the 72 hour and 6 day Completion Times means that both Completion Times apply simultaneously, and the more restrictive Completion Time must be met.

As in Required Action A.2, the Completion Time allows for an exception to the normal "time zero" for beginning the allowed outage time "clock." This will result in establishing the "time zero" at the time that the LCO was initially not met, instead of at the time Condition A was entered.

B.1

To ensure a highly reliable power source remains with an inoperable DG, it is necessary to verify the availability of the offsite circuits on a more frequent basis. Since the Required Action only specifies "perform," a

Attachment 3b

Catawba Units 1 and 2

Revised Technical Specifications and Bases Pages

<u>Remove</u>	<u>Insert</u>
3.0-1	3.0-1
3.0-2	3.0-2
3.0-3	3.0-3
3.0-5	3.0-5
3.3.3-1	3.3.3-1
3.3.4-1	3.3.4-1
3.4.11-1	3.4.11-1
3.4.12-2	3.4.12-2
3.4.15-1	3.4.15-1
3.4.16-1	3.4.16-1
3.5.3-1	3.5.3-1
3.6.7-1	3.6.7-1
3.6.8-1	3.6.8-1
3.7.4-1	3.7.4-1
3.7.5-1	3.7.5-1
3.8.1-1	3.8.1-1
B 3.0-4 thru B 3.0-14	B 3.0-4 thru B 3.0-15
B 3.3.3-12	B 3.3.3-12
B 3.3.4-3	B 3.3.4-3
B 3.3.4-4	B 3.3.4-4
B 3.4.11-3	B 3.4.11-3
B 3.4.12-7 thru B 3.4.12-11	B 3.4.12-7 thru B 3.4.12-11
B 3.4.15-3	B 3.4.15-3
B 3.4.16-3	B 3.4.16-3
B 3.4.16-4	B 3.4.16-4
B 3.5.3-2	B 3.5.3-2
B 3.5.3-3	B 3.5.3-3

Attachment 3b

Catawba Units 1 and 2

Revised Technical Specifications and Bases Pages

<u>Remove</u>	<u>Insert</u>
B 3.6.7-3	B 3.6.7-3
B 3.6.7-4	B 3.6.7-4
B 3.6.8-3	B 3.6.8-3
B 3.6.8-4	B 3.6.8-4
B.3.7.4-3	B 3.7.4-3
B.3.7.5-4	B 3.7.5-4
B 3.7.5-5	B 3.7.5-5
B 3.7.5-6	B 3.7.5-6
B 3.8.1-5	B 3.8.1-5
thru	thru
B 3.8.1-8	B 3.8.1-8

3.0 LCO APPLICABILITY (continued)

3.0 LIMITING CONDITION FOR OPERATION (LCO) APPLICABILITY

LCO 3.0.1 LCOs shall be met during the MODES or other specified conditions in the Applicability, except as provided in LCO 3.0.2 and 3.0.7.

LCO 3.0.2 Upon discovery of a failure to meet an LCO, the Required Actions of the associated Conditions shall be met, except as provided in LCO 3.0.5 and LCO 3.0.6.

If the LCO is met or is no longer applicable prior to expiration of the specified Completion Time(s), completion of the Required Action(s) is not required unless otherwise stated.

LCO 3.0.3 When an LCO is not met and the associated ACTIONS are not met, an associated ACTION is not provided, or if directed by the associated ACTIONS, the unit shall be placed in a MODE or other specified condition in which the LCO is not applicable. Action shall be initiated within 1 hour to place the unit, as applicable, in:

- a. MODE 3 within 7 hours;
- b. MODE 4 within 13 hours; and
- c. MODE 5 within 37 hours.

Exceptions to this Specification are stated in the individual Specifications.

Where corrective measures are completed that permit operation in accordance with the LCO or ACTIONS, completion of the actions required by LCO 3.0.3 is not required.

LCO 3.0.3 is only applicable in MODES 1, 2, 3, and 4.

(continued)

3.0 LCO APPLICABILITY (continued)

LCO 3.0.4 When an LCO is not met, entry into a MODE or other specified condition in the Applicability shall only be made:

- a. When the associated ACTIONS to be entered permit continued operation in the MODE or other specified condition in the Applicability for an unlimited period of time; or
- b. After performance of a risk assessment addressing inoperable systems and components, consideration of the results, determination of the acceptability of entering the MODE or other specified condition in the Applicability, and establishment of risk management actions, if appropriate; exceptions to this Specification are stated in the individual Specifications; or
- c. When an allowance is stated in the individual value, parameter, or other Specification.

 This Specification shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS or that are part of a shutdown of the unit.

LCO 3.0.5 Equipment removed from service or declared inoperable to comply with ACTIONS may be returned to service under administrative control solely to perform testing required to demonstrate its OPERABILITY or the OPERABILITY of other equipment. This is an exception to LCO 3.0.2 for the system returned to service under administrative control to perform the required testing to demonstrate OPERABILITY.

(continued)

3.0 LCO APPLICABILITY (continued)

LCO 3.0.6 When a supported system LCO is not met solely due to a support system LCO not being met, the Conditions and Required Actions associated with this supported system are not required to be entered. Only the support system LCO ACTIONS are required to be entered. This is an exception to LCO 3.0.2 for the supported system. In this event, additional evaluations and limitations may be required in accordance with Specification 5.5.15, "Safety Function Determination Program (SFDP)." If a loss of safety function is determined to exist by this program, the appropriate Conditions and Required Actions of the LCO in which the loss of safety function exists are required to be entered.

When a support system's Required Action directs a supported system to be declared inoperable or directs entry into Conditions and Required Actions for a supported system, the applicable Conditions and Required Actions shall be entered in accordance with LCO 3.0.2.

LCO 3.0.7 Test Exception LCOs 3.1.8 and 3.4.17 allow specified Technical Specification (TS) requirements to be changed to permit performance of special tests and operations. Unless otherwise specified, all other TS requirements remain unchanged. Compliance with Test Exception LCOs is optional. When a Test Exception LCO is desired to be met but is not met, the ACTIONS of the Test Exception LCO shall be met. When a Test Exception LCO is not desired to be met, entry into a MODE or other specified condition in the Applicability shall be made in accordance with the other applicable Specifications.

LCO 3.0.8 LCOs including the associated ACTIONS shall apply to each unit individually unless otherwise indicated as follows:

- a. Whenever the LCO refers to systems or components which are shared by both units, the ACTIONS will apply to both units simultaneously;
- b. Whenever the LCO applies to only one unit, this will be identified in the Applicability section of the Specification; and
- c. Whenever certain portions of a Specification contain operating parameters, setpoints etc., which are different for each unit, this will be identified in parentheses or footnotes. (For example, "...flow rate of 54,000 cfm (Unit 1) or 43,000 cfm (Unit 2)...").

SR Applicability (continued)

SR 3.0.4 Entry into a MODE or other specified condition in the Applicability of an LCO shall only be made when the LCO's Surveillances have been met within their specified Frequency, except as provided by SR 3.0.3. When an LCO is not met due to Surveillances not having been met, entry into a MODE or other specified condition in the Applicability shall only be made in accordance with LCO 3.0.4

 This provision shall not prevent entry into MODES or other specified conditions in the Applicability that are required to comply with ACTIONS or that are part of a shutdown of the unit.

SR 3.0.5 Surveillance Requirements shall apply to each unit individually unless otherwise indicated as stated in LCO 3.0.8 for individual Specifications or whenever certain portions of a Specification contain surveillance parameters different for each unit, which will be identified in parentheses or footnotes.

3.3 INSTRUMENTATION

3.3.3 Post Accident Monitoring (PAM) Instrumentation

LCO 3.3.3 The PAM instrumentation for each Function in Table 3.3.3-1 shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

-----NOTE-----
The Hydrogen Monitors are not required in MODE 3.

ACTIONS

-----NOTE-----
Separate Condition entry is allowed for each Function.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more Functions with one or more required channels inoperable.	A.1 Enter the Condition referenced in Table 3.3.3-1 for the channel.	Immediately
B. One or more Functions with one required channel inoperable.	B.1 Restore required channel to OPERABLE status.	30 days
C. One or more Functions with one required channel inoperable. <u>AND</u> Diverse channel OPERABLE.	C.1 Restore required channel to OPERABLE status.	30 days

(continued)

3.3 INSTRUMENTATION

3.3.4 Remote Shutdown System

LCO 3.3.4 The Remote Shutdown System Functions in Table 3.3.4-1 shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

-----NOTE-----
Separate Condition entry is allowed for each Function.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more required Functions inoperable.	A.1 Restore required Function to OPERABLE status.	30 days
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3.	6 hours
	<u>AND</u> B.2 Be in MODE 4.	12 hours

3.4 REACTOR COOLANT SYSTEM (RCS)

3.4.11 Pressurizer Power Operated Relief Valves (PORVs)

LCO 3.4.11 Each PORV and associated block valve shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

-----NOTES-----

Separate Condition entry is allowed for each PORV.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more PORVs inoperable and capable of being manually cycled.	A.1 Close and maintain power to associated block valve.	1 hour
B. One or two PORVs inoperable and not capable of being manually cycled.	B.1 Close associated block valves.	1 hour
	<u>AND</u>	
	B.2 Remove power from associated block valves.	1 hour
	<u>AND</u>	
	B.3 Restore PORV(s) to OPERABLE status.	72 hours

(continued)

ACTIONS

-----NOTE-----
 LCO 3.0.4.b is not applicable when entering MODE 4.

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. Two or more charging pumps capable of injecting into the RCS.</p> <p><u>OR</u></p> <p>One charging pump and one safety injection pump capable of injecting into the RCS.</p> <p><u>OR</u></p> <p>Two or more safety injection pumps capable of injecting into the RCS.</p>	<p>-----NOTE-----</p> <p>Two charging pumps may be capable of injecting into the RCS during pump swap operation for \leq 15 minutes.</p> <p>-----</p> <p>A.1 Initiate action to verify a maximum of one charging pump or one safety injection pump is capable of injecting into the RCS.</p>	<p>Immediately</p>
<p>B. Reactor coolant pump operation not limited as specified in Table 3.4.12-1.</p>	<p>B.1 Initiate action to limit pump operation as specified in Table 3.4.12-1.</p>	<p>Immediately</p>
<p>C. An accumulator not isolated when the accumulator pressure is greater than or equal to the maximum RCS pressure for existing cold leg temperature allowed in Specification 3.4.3.</p>	<p>C.1 Isolate affected accumulator.</p>	<p>1 hour</p>

(continued)

3.4 REACTOR COOLANT SYSTEM (RCS)

3.4.15 RCS Leakage Detection Instrumentation

LCO 3.4.15 The following RCS leakage detection instrumentation shall be OPERABLE:

- a. One containment floor and equipment sump level monitor;
- b. One containment atmosphere radioactivity monitor (gaseous or particulate); and
- c. One containment ventilation unit condensate drain tank level monitor.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. Required containment floor and equipment sump level monitor inoperable.</p>	<p>A.1 Perform SR 3.4.13.1. <u>AND</u> A.2 Restore required containment floor and equipment sump level monitor to OPERABLE status.</p>	<p>Once per 24 hours 30 days</p>

(continued)

3.4 REACTOR COOLANT SYSTEM (RCS)

3.4.16 RCS Specific Activity

LCO 3.4.16 The specific activity of the reactor coolant shall be within limits.

APPLICABILITY: MODES 1 and 2,
MODE 3 with RCS average temperature (T_{avg}) \geq 500°F.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. DOSE EQUIVALENT I-131 $>$ 1.0 μCi/gm.</p>	<p>-----Note----- LCO 3.0.4.c is applicable. -----</p> <p>A.1 Verify DOSE EQUIVALENT I-131 within the acceptable region of Figure 3.4.16-1.</p> <p><u>AND</u></p> <p>A.2 Restore DOSE EQUIVALENT I-131 to within limit.</p>	<p>Once per 4 hours</p> <p>48 hours</p>
<p>B. Gross specific activity of the reactor coolant not within limit.</p>	<p>B.1 Be in MODE 3 with $T_{avg} <$ 500°F.</p>	<p>6 hours</p>

(continued)

3.5 EMERGENCY CORE COOLING SYSTEMS (ECCS)

3.5.3 ECCS—Shutdown

LCO 3.5.3 One ECCS train shall be OPERABLE.

APPLICABILITY: MODE 4.

ACTIONS

NOTE

LCO 3.0.4.b is not applicable to ECCS centrifugal charging subsystem.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Required ECCS residual heat removal (RHR) subsystem inoperable.	A.1 Initiate action to restore required ECCS RHR subsystem to OPERABLE status.	Immediately
B. Required ECCS centrifugal charging subsystem inoperable.	B.1 Restore required ECCS centrifugal charging subsystem to OPERABLE status.	1 hour
C. Required Action and associated Completion Time of Condition B not met.	C.1 Be in MODE 5.	24 hours

3.6 CONTAINMENT SYSTEMS

3.6.7 Hydrogen Recombiners

LCO 3.6.7 Two hydrogen recombiners shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One hydrogen recombiner inoperable.	A.1 Restore hydrogen recombiner to OPERABLE status.	30 days
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3.	6 hours

3.6 CONTAINMENT SYSTEMS

3.6.8 Hydrogen Skimmer System (HSS)

LCO 3.6.8 Two HSS trains shall be OPERABLE.

APPLICABILITY: MODES 1 and 2.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One HSS train inoperable.	A.1 Restore HSS train to OPERABLE status	30 days
B. Required Action and associated Completion Time not met.	B.1 Be in MODE 3.	6 hours

3.7 PLANT SYSTEMS

3.7.4 Steam Generator Power Operated Relief Valves (SG PORVs)

LCO 3.7.4 Four SG PORV lines shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3,
MODE 4 when steam generator is relied upon for heat removal.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One SG PORV line inoperable.	A.1 Restore SG PORV line to OPERABLE status.	7 days
B. Two or more SG PORV lines inoperable.	B.1 Restore all but one SG PORV line to OPERABLE status.	24 hours
C. Required Action and associated Completion Time not met.	C.1 Be in MODE 3. <u>AND</u> C.2 Be in MODE 4 without reliance upon steam generator for heat removal.	6 hours 12 hours

3.7 PLANT SYSTEMS

3.7.5 Auxiliary Feedwater (AFW) System

LCO 3.7.5 Three AFW trains shall be OPERABLE*.

-----NOTE-----

Only one AFW train, which includes a motor driven pump, is required to be OPERABLE in MODE 4.

APPLICABILITY: MODES 1, 2, and 3,
MODE 4 when steam generator is relied upon for heat removal.

ACTIONS

-----NOTE-----

LCO 3.0.4.b is not applicable when entering MODE 1.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One steam supply to turbine driven AFW pump inoperable.	A.1 Restore steam supply to OPERABLE status.	7 days <u>AND</u> 10 days from discovery of failure to meet the LCO
B. One AFW train inoperable in MODE 1, 2 or 3 for reasons other than Condition A.	B.1 Restore AFW train to OPERABLE status.	72 hours* <u>AND</u> 10 days* from discovery of failure to meet the LCO

(continued)

*For each Unit, the Completion Time that AFW train 'A' can be inoperable as specified by Required Action B.1 may be extended beyond the "72 hours and 10 days from discovery of failure to meet the LCO" up to "168 hours and 10 days from discovery of failure to meet the LCO" as part of the NSWWS system upgrades. System upgrades include maintenance and modification activities associated with replacement of portions of the train 'A' NSWWS piping via modification CE-71424. Upon completion of the pipe replacement and system restoration this footnote is no longer applicable.

3.8 ELECTRICAL POWER SYSTEMS

3.8.1 AC Sources—Operating.

LCO 3.8.1 The following AC electrical sources shall be OPERABLE*:

- a. Two qualified circuits between the offsite transmission network and the Onsite Essential Auxiliary Power System; and
- b. Two diesel generators (DGs) capable of supplying the Onsite Essential Auxiliary Power Systems;

AND

The automatic load sequencers for Train A and Train B shall be OPERABLE.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTIONS

-----NOTE-----

LCO 3.0.4.b is not applicable to DGs.

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One offsite circuit inoperable.	<p>A.1 Perform SR 3.8.1.1 for OPERABLE offsite circuit.</p> <p><u>AND</u></p> <p>A.2 Declare required feature(s) with no offsite power available inoperable when its redundant required feature(s) is inoperable.</p> <p><u>AND</u></p>	<p>1 hour</p> <p><u>AND</u></p> <p>Once per 8 hours thereafter</p> <p>24 hours from discovery of no offsite power to one train concurrent with inoperability of redundant required feature(s)</p> <p>(continued)</p>

*For each Unit, the Completion Time that the 'A' EDG can be inoperable as specified by Required Action B.4 may be extended beyond the "72 hours and 6 days from discovery of failure to meet the LCO" up to 168 hours as part of the NSWS system upgrades. System upgrades and modification activities associated with replacement of portions of the train 'A' NSWS piping via modification CE-71424. Upon completion of the pipe replacement and system restoration this footnote is no longer applicable.

BASES

LCO 3.0.3 (continued)

unit is in a lower MODE of operation when a shutdown is required, the time limit for reaching the next lower MODE applies. If a lower MODE is reached in less time than allowed, however, the total allowable time to reach MODE 5, or other applicable MODE, is not reduced. For example, if MODE 3 is reached in 2 hours, then the time allowed for reaching MODE 4 is the next 11 hours, because the total time for reaching MODE 4 is not reduced from the allowable limit of 13 hours. Therefore, if remedial measures are completed that would permit a return to MODE 1, a penalty is not incurred by having to reach a lower MODE of operation in less than the total time allowed.

In MODES 1, 2, 3, and 4, LCO 3.0.3 provides actions for Conditions not covered in other Specifications. The requirements of LCO 3.0.3 do not apply in MODES 5 and 6 because the unit is already in the most restrictive Condition required by LCO 3.0.3. The requirements of LCO 3.0.3 do not apply in other specified conditions of the Applicability (unless in MODE 1, 2, 3, or 4) because the ACTIONS of individual Specifications sufficiently define the remedial measures to be taken.

Exceptions to LCO 3.0.3 are provided in instances where requiring a unit shutdown, in accordance with LCO 3.0.3, would not provide appropriate remedial measures for the associated condition of the unit. An example of this is in LCO 3.7.14, "Spent Fuel Pool (SFP) Water Level." LCO 3.7.14 has an Applicability of "During movement of irradiated fuel assemblies in the spent fuel pool." Therefore, this LCO can be applicable in any or all MODES. If the LCO and the Required Actions of LCO 3.7.14 are not met while in MODE 1, 2, or 3, there is no safety benefit to be gained by placing the unit in a shutdown condition. The Required Action of LCO 3.7.14 of "Suspend movement of irradiated fuel assemblies in the spent fuel pool" is the appropriate Required Action to complete in lieu of the actions of LCO 3.0.3. These exceptions are addressed in the individual Specifications.

LCO 3.0.4 LCO 3.0.4 establishes limitations on changes in MODES or other specified conditions in the Applicability when an LCO is not met. It allows placing the unit in a MODE or other specified condition stated in that Applicability (e.g., the Applicability desired to be entered) when unit conditions are such that the requirements of the LCO would not be met, in accordance with LCO 3.0.4.a, LCO 3.0.4.b, or LCO 3.0.4.c.

LCO 3.0.4.a allows entry into MODE or other specified condition in the Applicability with the LCO not met when the associated ACTIONS to be entered permit continued operation in the MODE or other specified

BASES

LCO 3.0.4 (continued)

condition in the Applicability for an unlimited period of time. Compliance with Required Actions that permit continued operation of the unit for an unlimited period of time in a MODE or other specified condition provides an acceptable level of safety for continued operation. This is without regard to the status of the unit before or after the MODE change. Therefore, in such cases, entry into a MODE or other specified condition in the Applicability may be made in accordance with provisions of the Required Actions..

LCO 3.0.4.b allows entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, consideration of the results, determination of the acceptability of entering the MODE or other specified condition in the Applicability, and establishment of risk management actions, if appropriate..

The risk assessment may use quantitative, qualitative, or blended approaches, the risk assessment will be conducted using the plant program, procedures, and criteria in place to implement 10 CFR 50.65(a)(4), which requires that risk impacts of maintenance activities to be assessed and managed. The risk assessments, for the purposes of LCO 3.0.4.b, must take into account all inoperable Technical Specification equipment regardless of whether the equipment is included in the normal 10 CFR 50.65(a)(4) risk assessment scope. The risk assessments will be conducted using the procedures and guidance endorsed by Regulatory Guide 1.182, "Assessing and Managing Risk Before Maintenance Activities at a Nuclear Power Plants." Regulatory Guide 1.182 endorses the guidance in Section 11 of NUMARC 93-01, "Industry Guideline for Monitoring the Effectiveness of Maintenance at Nuclear Power Plants." These documents address general guidance for conduct of the risk assessment, quantitative and qualitative guidelines for establishing risk management actions, and example risk management actions. These include actions to plan and conduct other activities in a manner that controls overall risk, increased risk awareness by shift and management personnel, actions to reduce the duration of the condition, actions to minimize the magnitude or risk increases (establishment of backup success paths or compensatory measures), and determination that the proposed MODE change is acceptable. Consideration should also be given to the probability of completing restoration such that the requirements of the LCO would be met prior to the expiration of ACTIONS Completion Times that would require exiting the Applicability.

LCO 3.0.4.b may be used with single, or multiple systems and components unavailable. NUMARC 93-01 provides guidance relative to consideration of simultaneous unavailability of multiple systems and components.

BASES

LCO 3.0.4 (continued)

The results of the risk assessment shall be considered in determining the acceptability of entering the MODE or other specified condition in the Applicability, and any corresponding risk management actions. The LCO 3.0.4.b risk assessments do not have to be documented.

The Technical Specifications allow continued operation with equipment unavailable in MODE 1 for the duration of the Completion Time. Since this is allowable, and since in general the risk impact in that particular MODE bounds the risk of transitioning into and through the applicable MODES or other specified conditions in the Applicability of the LCO, the use of the LCO 3.0.4.b allowance should be generally acceptable, as long as the risk is assessed and managed as stated above. However, there is a small subset of systems and components that have been determined to be more important to risk and use of the LCO 3.0.4.b allowance is prohibited. The LCOs governing these system and components contain Notes prohibiting the use of LCO 3.0.4.b by stating that LCO 3.0.4.b is not applicable.

LCO 3.0.4.c allows entry into a MODE or other specified condition in the Applicability with the LCO not met based on a Note in the Specification which states LCO 3.0.4.c is applicable. These specific allowances permit entry into MODES or other specified conditions in the Applicability when the associated ACTIONS to be entered do not provide for continued operation for an unlimited period of time and a risk assessment has not been performed. This allowance may apply to all the ACTIONS or to a specific Required Action of a Specification. The risk assessments performed to justify the use of LCO 3.0.4.b usually only consider systems and components. For this reason, LCO 3.0.4.c is typically applied to Specifications which describe values and parameters (e.g., RCS Specific Activity).

The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or components to OPERABLE status before entering an associated MODE or other specified condition in the Applicability.

The provisions of LCO 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS. In addition, the provisions of LCO 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that result from any unit shutdown. In this context, a unit shutdown is defined as a change in MODE or other specified condition in the Applicability associated with transitioning from MODE 1 to MODE 2, MODE 2 to MODE 3, MODE 3 to MODE 4, and MODE 4 to MODE 5.

BASES

LCO 3.0.4
(continued)

Upon entry into a MODE or other specified condition in the Applicability with the LCO not met, LCO 3.0.1 and LCO 3.0.2 require entry into the applicable Conditions and Required Actions until the condition is resolved, until the LCO is met, or until the unit is not within the Applicability of the Technical Specification.

Surveillances do not have to be performed on the associated inoperable equipment (or on variables outside the specified limits), as permitted by SR 3.0.1. Therefore, utilizing LCO 3.0.4 is not a violation of SR 3.0.1 or SR 3.0.4 for any Surveillances that have not been performed on inoperable equipment. However, SRs must be met to ensure OPERABILITY prior to declaring the associated equipment OPERABLE (or variable within limits) and restoring compliance with the affected LCO.

LCO 3.0.5

LCO 3.0.5 establishes the allowance for restoring equipment to service under administrative controls when it has been removed from service or declared inoperable to comply with ACTIONS. The sole purpose of this Specification is to provide an exception to LCO 3.0.2 (e.g., to not comply with the applicable Required Action(s)) to allow the performance of SRs to demonstrate:

- a. The OPERABILITY of the equipment being returned to service; or
- b. The OPERABILITY of other equipment.

The administrative controls ensure the time the equipment is returned to service in conflict with the requirements of the ACTIONS is limited to the time absolutely necessary to perform the allowed SRs. This Specification does not provide time to perform any other preventive or corrective maintenance.

An example of demonstrating the OPERABILITY of the equipment being returned to service is reopening a containment isolation valve that has been closed to comply with Required Actions and must be reopened to perform the SRs.

An example of demonstrating the OPERABILITY of other equipment is taking an inoperable channel or trip system out of the tripped condition to prevent the trip function from occurring during the performance of an SR on another channel in the other trip system. A similar example of demonstrating the OPERABILITY of other equipment is taking an inoperable channel or trip system out of the tripped condition to permit the logic to function and indicate the appropriate response during the performance of an SR on another channel in the same trip system.

BASES

LCO 3.0.6

LCO 3.0.6 establishes an exception to LCO 3.0.2 for support systems that have an LCO specified in the Technical Specifications (TS). This exception is provided because LCO 3.0.2 would require that the Conditions and Required Actions of the associated inoperable supported system LCO be entered solely due to the inoperability of the support system. This exception is justified because the actions that are required to ensure the unit is maintained in a safe condition are specified in the support system LCO's Required Actions. These Required Actions may include entering the supported system's Conditions and Required Actions or may specify other Required Actions.

When a support system is inoperable and there is an LCO specified for it in the TS, the supported system(s) are required to be declared inoperable if determined to be inoperable as a result of the support system inoperability. However, it is not necessary to enter into the supported systems' Conditions and Required Actions unless directed to do so by the support system's Required Actions. The potential confusion and inconsistency of requirements related to the entry into multiple support and supported systems' LCOs' Conditions and Required Actions are eliminated by providing all the actions that are necessary to ensure the unit is maintained in a safe condition in the support system's Required Actions.

However, there are instances where a support system's Required Action may either direct a supported system to be declared inoperable or direct entry into Conditions and Required Actions for the supported system. This may occur immediately or after some specified delay to perform some other Required Action. Regardless of whether it is immediate or after some delay, when a support system's Required Action directs a supported system to be declared inoperable or directs entry into Conditions and Required Actions for a supported system, the applicable Conditions and Required Actions shall be entered in accordance with LCO 3.0.2.

Specification 5.5.15, "Safety Function Determination Program (SFDP)," ensures loss of safety function is detected and appropriate actions are taken. Upon entry into LCO 3.0.6, an evaluation shall be made to determine if loss of safety function exists. Additionally, other limitations, remedial actions, or compensatory actions may be identified as a result of the support system inoperability and corresponding exception to entering supported system Conditions and Required Actions. The SFDP implements the requirements of LCO 3.0.6.

Cross train checks to identify a loss of safety function for those support systems that support multiple and redundant safety systems are required. The cross train check verifies that the supported systems of the redundant OPERABLE support system are OPERABLE, thereby ensuring

BASES

LCO 3.0.6
(continued) safety function is retained. If this evaluation determines that a loss of safety function exists, the appropriate Conditions and Required Actions of the LCO in which the loss of safety function exists are required to be entered.

LCO 3.0.7 There are certain special tests and operations required to be performed at various times over the life of the unit. These special tests and operations are necessary to demonstrate select unit performance characteristics, to perform special maintenance activities, and to perform special evolutions. Test Exception LCOs 3.1.8 and 3.4.17 allow specified Technical Specification (TS) requirements to be changed to permit performances of these special tests and operations, which otherwise could not be performed if required to comply with the requirements of these TS. Unless otherwise specified, all the other TS requirements remain unchanged. This will ensure all appropriate requirements of the MODE or other specified condition not directly associated with or required to be changed to perform the special test or operation will remain in effect.

The Applicability of a Test Exception LCO represents a condition not necessarily in compliance with the normal requirements of the TS. Compliance with Test Exception LCOs is optional. A special operation may be performed either under the provisions of the appropriate Test Exception LCO or under the other applicable TS requirements. If it is desired to perform the special operation under the provisions of the Test Exception LCO, the requirements of the Test Exception LCO shall be followed.

LCO 3.0.8 LCO 3.0.8 delineates the applicability of each specification to Unit 1 and Unit 2 operations.

B 3.0 SURVEILLANCE REQUIREMENT (SR) APPLICABILITY

BASES

SRs SR 3.0.1 through SR 3.0.5 establish the general requirements applicable to all Specifications and apply at all times; unless otherwise stated.

SR 3.0.1 SR 3.0.1 establishes the requirement that SRs must be met during the MODES or other specified conditions in the Applicability for which the requirements of the LCO apply, unless otherwise specified in the individual SRs. This Specification is to ensure that Surveillances are performed to verify the OPERABILITY of systems and components, and that variables are within specified limits. Failure to meet a Surveillance within the specified Frequency, in accordance with SR 3.0.2, constitutes a failure to meet an LCO.

Systems and components are assumed to be OPERABLE when the associated SRs have been met. Nothing in this Specification, however, is to be construed as implying that systems or components are OPERABLE when:

- a. The systems or components are known to be inoperable, although still meeting the SRs; or
- b. The requirements of the Surveillance(s) are known not to be met between required Surveillance performances.

Surveillances do not have to be performed when the unit is in a MODE or other specified condition for which the requirements of the associated LCO are not applicable, unless otherwise specified. The SRs associated with a test exception are only applicable when the test exception is used as an allowable exception to the requirements of a Specification.

Unplanned events may satisfy the requirements (including applicable acceptance criteria) for a given SR. In this case, the unplanned event may be credited as fulfilling the performance of the SR. This allowance includes those SRs whose performance is normally precluded in a given MODE or other specified condition.

Surveillances, including Surveillances invoked by Required Actions, do not have to be performed on inoperable equipment because the ACTIONS define the remedial measures that apply. Surveillances have to be met and performed in accordance with SR 3.0.2, prior to returning equipment to OPERABLE status.

BASES

SR 3.0.1 (continued)

Upon completion of maintenance, appropriate post maintenance testing is required to declare equipment OPERABLE. This includes ensuring applicable Surveillances are not failed and their most recent performance is in accordance with SR 3.0.2. Post maintenance testing may not be possible in the current MODE or other specified conditions in the Applicability due to the necessary unit parameters not having been established. In these situations, the equipment may be considered OPERABLE provided testing has been satisfactorily completed to the extent possible and the equipment is not otherwise believed to be incapable of performing its function. This will allow operation to proceed to a MODE or other specified condition where other necessary post maintenance tests can be completed.

SR 3.0.2

SR 3.0.2 establishes the requirements for meeting the specified Frequency for Surveillances and any Required Action with a Completion Time that requires the periodic performance of the Required Action on a "once per . . ." interval.

SR 3.0.2 permits a 25% extension of the interval specified in the Frequency. This extension facilitates Surveillance scheduling and considers plant operating conditions that may not be suitable for conducting the Surveillance (e.g., transient conditions or other ongoing Surveillance or maintenance activities).

The 25% extension does not significantly degrade the reliability that results from performing the Surveillance at its specified Frequency. This is based on the recognition that the most probable result of any particular Surveillance being performed is the verification of conformance with the SRs. The exceptions to SR 3.0.2 are those Surveillances for which the 25% extension of the interval specified in the Frequency does not apply. These exceptions are stated in the individual Specifications. The requirements of regulations take precedence over the TS. An example of where SR 3.0.2 does not apply is in the Containment Leakage Rate Testing Program. This program establishes testing requirements and Frequencies in accordance with the requirements of regulations. The TS cannot in and of themselves extend a test interval specified in the regulations.

As stated in SR 3.0.2, the 25% extension also does not apply to the initial portion of a periodic Completion Time that requires performance on a

BASES

SR 3.0.2 (continued)

"once per ..." basis. The 25% extension applies to each performance after the initial performance. The initial performance of the Required Action, whether it is a particular Surveillance or some other remedial action, is considered a single action with a single Completion Time. One reason for not allowing the 25% extension to this Completion Time is that such an action usually verifies that no loss of function has occurred by checking the status of redundant or diverse components or the action accomplishes the function of the inoperable equipment in an alternative manner.

The provisions of SR 3.0.2 are not intended to be used repeatedly merely as an operational convenience to extend Surveillance intervals (other than those consistent with refueling intervals) or periodic Completion Time intervals beyond those specified.

SR 3.0.3

SR 3.0.3 establishes the flexibility to defer declaring affected equipment inoperable or an affected variable outside the specified limits when a Surveillance has not been completed within the specified Frequency. A delay period of up to 24 hours or up to the limit of the specified Frequency, whichever is greater, applies from the point in time that it is discovered that the Surveillance has not been performed in accordance with SR 3.0.2, and not at the time that the specified Frequency was not met.

This delay period provides adequate time to complete Surveillances that have been missed. This delay period permits the completion of a Surveillance before complying with Required Actions or other remedial measures that might preclude completion of the Surveillance.

The basis for this delay period includes consideration of unit conditions, adequate planning, availability of personnel, the time required to perform the Surveillance, the safety significance of the delay in completing the required Surveillance, and the recognition that the most probable result of any particular Surveillance being performed is the verification of conformance with the requirements.

When a Surveillance with a Frequency based not on time intervals, but upon specified unit conditions, operating situations, or requirements of regulations (e.g., prior to entering MODE 1 after each fuel loading, or in accordance with 10 CFR 50, Appendix J, as modified by approved exemptions, etc.) is discovered to not have been performed when specified, SR 3.0.3 allows for the full delay period of up to the specified Frequency to perform the Surveillance. However, since there is not a time interval specified, the missed Surveillance should be performed at

BASES

SR 3.0.3 (continued)

the first reasonable opportunity.

SR 3.0.3 provides a time limit for, and allowances for the performance of, Surveillances that become applicable as a consequence of MODE changes imposed by Required Actions.

Failure to comply with specified Frequencies for SRs is expected to be an infrequent occurrence. Use of the delay period established by SR 3.0.3 is a flexibility which is not intended to be used as an operational convenience to extend Surveillance intervals. While up to 24 hours or the limit of the specified Frequency is provided to perform the missed Surveillance, it is expected that the missed Surveillance will be performed at the first reasonable opportunity. The determination of the first reasonable opportunity should include consideration of the impact on plant risk (from delaying the Surveillance as well as any plant configuration changes required or shutting the plant down to perform the Surveillance) and impact on any analysis assumptions, in addition to unit conditions; planning, availability of personnel, and the time required to perform the Surveillance. This risk impact should be managed through the program in place to implement 10 CFR 50.65(a)(4) and its implementation guidance, NRC Regulatory Guide 1.182, "Assessing and Managing Risk Before Maintenance Activities at Nuclear Power Plants." This Regulatory Guide addresses consideration of temporary and aggregate risk impacts, determination of risk management action thresholds, and risk management action up to and including plant shutdown. The missed Surveillance should be treated as an emergent condition as discussed in the Regulatory Guide. The risk evaluation may use quantitative, qualitative, or blended methods. The degree of depth and rigor of the evaluation should be commensurate with the importance of the component. Missed Surveillances for important components should be analyzed quantitatively. If the results of the risk evaluation determine the risk increase is significant, this evaluation should be used to determine the safest course of action. All missed Surveillances will be placed in the licensee's Corrective Action Program.

If a Surveillance is not completed within the allowed delay period, then the equipment is considered inoperable or the variable is considered outside the specified limits and the Completion Times of the Required Actions for the applicable LCO Conditions begin immediately upon expiration of the delay period. If a Surveillance is failed within the delay period, then the equipment is inoperable, or the variable is outside the specified limits and the Completion Times of the Required Actions for the applicable LCO Conditions begin immediately upon the failure of the Surveillance.

BASES

SR 3.0.3 (continued)

Completion of the Surveillance within the delay period allowed by this Specification, or within the Completion Time of the ACTIONS, restores compliance with SR 3.0.1.

SR 3.0.4 SR 3.0.4 establishes the requirement that all applicable SRs must be met before entry into a MODE or other specified condition in the Applicability.

This Specification ensures that system and component OPERABILITY requirements and variable limits are met before entry into MODES or other specified conditions in the Applicability for which these systems and components ensure safe operation of the unit. The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or components to OPERABLE status before entering an associated MODE or other specified condition in the Applicability.

A provision is included to allow entry into a MODE or other specified condition in the Applicability when an LCO is not met due to Surveillance not being met in accordance with LCO 3.0.4.

However, in certain circumstances, failing to meet an SR will not result in SR 3.0.4 restricting a MODE change or other specified condition change. When a system, subsystem, division, component, device, or variable is inoperable or outside its specified limits, the associated SR(s) are not required to be performed, per SR 3.0.1, which states that surveillances do not have to be performed on inoperable equipment. When equipment is inoperable, SR 3.0.4 does not apply to the associated SR(s) since the requirement for the SR(s) to be performed is removed. Therefore, failing to perform the Surveillance(s) within the specified Frequency does not result in an SR 3.0.4 restriction to changing MODES or other specified conditions of the Applicability. However, since the LCO is not met in this instance, LCO 3.0.4 will govern any restrictions that may (or may not) apply to MODE or other specified condition changes. SR 3.0.4 does not restrict changing MODES or other specified conditions of the Applicability when a Surveillance has not been performed within the specified Frequency, provided the requirement to declare the LCO not met has been delayed in accordance with SR 3.0.3.

The provisions of SR 3.0.4 shall not prevent entry into MODES or other specified conditions in the Applicability that are required to comply with ACTIONS. In addition, the provisions of SR 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that result from any unit shutdown. In this context, a unit shutdown is defined as a change in MODE or other specified condition in the Applicability associated with transitioning from MODE 1 to MODE 2, MODE 2 to

BASES

SR 3.0.4 (continued)

MODE 3, MODE 3 to MODE 4, and MODE 4 to MODE 5,

The precise requirements for performance of SRs are specified such that exceptions to SR 3.0.4 are not necessary. The specific time frames and conditions necessary for meeting the SRs are specified in the Frequency, in the Surveillance, or both. This allows performance of Surveillances when the prerequisite condition(s) specified in a Surveillance procedure require entry into the MODE or other specified condition in the Applicability of the associated LCO prior to the performance or completion of a Surveillance. A Surveillance that could not be performed until after entering the LCO's Applicability, would have its Frequency specified such that it is not "due" until the specific conditions needed are met. Alternately, the Surveillance may be stated in the form of a Note, as not required (to be met or performed) until a particular event, condition, or time has been reached. Further discussion of the specific formats of SRs' annotation is found in Section 1.4, Frequency

SR 3.0.5 SR 3.0.5 delineates the applicability of the surveillance activities to Unit 1 and Unit 2 operations.

BASES

APPLICABILITY (continued)

The Hydrogen Monitors are not required to be OPERABLE in MODE 3.

ACTIONS A Note has been added in the ACTIONS to clarify the application of Completion Time rules. The Conditions of this Specification may be entered independently for each Function listed on Table 3.3.3-1. When the Required Channels in Table 3.3.3-1 are specified (e.g., on a per steam line, per loop, per SG, etc., basis), then the Condition may be entered separately for each steam line, loop, SG, etc., as appropriate. The Completion Time(s) of the inoperable channel(s) of a Function will be tracked separately for each Function starting from the time the Condition was entered for that Function.

A.1

Condition A applies to all PAM instrument Functions. Condition A addresses the situation when one or more required channels for one or more Functions are inoperable. The Required Action is to refer to Table 3.3.3-1 and take the appropriate Required Actions for the PAM instrumentation affected. The Completion Times are those from the referenced Conditions and Required Actions.

B.1

Condition B applies when one or more Functions have one required channel that is inoperable. Required Action A.1 requires restoring the inoperable channel to OPERABLE status within 30 days. The 30 day Completion Time is based on operating experience and takes into account the remaining OPERABLE channel, the passive nature of the instrument (no critical automatic action is assumed to occur from these instruments), and the low probability of an event requiring PAM instrumentation during this interval.

BASES

APPLICABILITY The Remote Shutdown System LCO is applicable in MODES 1, 2, and 3. This is required so that the unit can be placed and maintained in MODE 3 for an extended period of time from a location other than the control room.

This LCO is not applicable in MODE 4, 5, or 6. In these MODES, the facility is already subcritical and in a condition of reduced RCS energy. Under these conditions, considerable time is available to restore necessary instrument control functions if control room instruments or controls become unavailable.

ACTION A Note has been added to the ACTIONS to clarify the application of Completion Time rules. Separate Condition entry is allowed for each Function listed on Table 3.3.4-1. The Completion Time(s) of the inoperable channel(s)/train(s) of a Function will be tracked separately for each Function starting from the time the Condition was entered for that Function.

A.1

Condition A addresses the situation where one or more required Functions of the Remote Shutdown System are inoperable. This includes any Function listed in Table 3.3.4-1 as well as the control and transfer switches.

The Required Action is to restore the required Function to OPERABLE status within 30 days. The Completion Time is based on operating experience and the low probability of an event that would require evacuation of the control room.

B.1 and B.2

If the Required Action and associated Completion Time of Condition A is not met, the unit must be brought to a MODE in which the LCO does not apply. To achieve this status, the unit must be brought to at least MODE 3 within 6 hours and to MODE 4 within 12 hours. The allowed Completion Times are reasonable, based on operating experience, to reach the required unit conditions from full power conditions in an orderly manner and without challenging unit systems.

BASES

**SURVEILLANCE
REQUIREMENTS**

SR 3.3.4.1

Performance of the CHANNEL CHECK once every 31 days ensures that a gross failure of instrumentation has not occurred. A CHANNEL CHECK is normally a comparison of the parameter indicated on one channel to a similar parameter on other channels. It is based on the assumption that instrument channels monitoring the same parameter should read approximately the same value. Significant deviations between the two instrument channels could be an indication of excessive instrument drift in one of the channels or of something even more serious. CHANNEL CHECK will detect gross channel failure; thus, it is key to verifying that the instrumentation continues to operate properly between each CHANNEL CALIBRATION.

Agreement criteria are determined by the unit staff, based on a combination of the channel instrument uncertainties, including indication and readability. If the channels are within the criteria, it is an indication that the channels are OPERABLE. If a channel is outside the criteria, it may be an indication that the sensor or the signal processing equipment has drifted outside its limit.

As specified in the Surveillance, a CHANNEL CHECK is only required for those channels which are normally energized.

The Frequency of 31 days is based upon operating experience which demonstrates that channel failure is rare. The CHANNEL CHECK supplements less formal, but more frequent, checks of channels during normal operational use of the displays associated with the LCO required channels.

BASES

APPLICABILITY (continued)

Pressure increases are less prominent in MODE 3 because the core input energy is reduced, but the RCS pressure is high. Therefore, the LCO is applicable in MODES 1, 2, and 3. The LCO is not applicable in MODE 4 when both pressure and core energy are decreased and the pressure surges become much less significant. The PORV setpoint is reduced for LTOP in MODES 4 \leq 285°F, 5, and 6 with the reactor vessel head in place. LCO 3.4.12 addresses the PORV requirements in these MODES.

ACTIONS A Note has been added to clarify that all pressurizer PORVs are treated as separate entities, each with separate Completion Times (i.e., the Completion Time is on a component basis).

A.1

With the PORVs inoperable and capable of being manually cycled, either the PORVs must be restored or the flow path isolated within 1 hour. The block valves should be closed but power must be maintained to the associated block valves, since removal of power would render the block valve inoperable. Although a PORV may be designated inoperable, it may be able to be manually opened and closed, and therefore, able to perform its function. PORV inoperability may be due to seat leakage or other causes that do not prevent manual use and do not create a possibility for a small break LOCA. For these reasons, the block valve may be closed but the Action requires power be maintained to the valve. This Condition is only intended to permit operation of the plant for a limited period of time not to exceed the next refueling outage (MODE 6) so that maintenance can be performed on the PORVs to eliminate the problem condition. Normally, the PORVs should be available for automatic mitigation of overpressure events and should be returned to OPERABLE status prior to entering startup (MODE 2).

Quick access to the PORV for pressure control can be made when power remains on the closed block valve. The Completion Time of 1 hour is based on plant operating experience that has shown that minor problems can be corrected or closure accomplished in this time period.

BASES

LCO (continued)

- b. A depressurized RCS and an RCS vent.

An RCS vent is OPERABLE when open with an area of ≥ 4.5 square inches.

Each of these methods of overpressure prevention is capable of mitigating the limiting LTOP transient.

APPLICABILITY This LCO is applicable in MODE 4 when any RCS cold leg temperature is $\leq 285^\circ\text{F}$, in MODE 5, and in MODE 6 when the reactor vessel head is on. The pressurizer safety valves provide overpressure protection that meets the Reference 1 P/T limits above 285°F . When the reactor vessel head is off, overpressurization cannot occur.

LCO 3.4.3 provides the operational P/T limits for all MODES. LCO 3.4.10, "Pressurizer Safety Valves," requires the OPERABILITY of the pressurizer safety valves that provide overpressure protection during MODES 1, 2, and 3, and MODE 4 above 285°F .

Low temperature overpressure prevention is most critical during shutdown when the RCS is water solid, and a mass or heat input transient can cause a very rapid increase in RCS pressure when little or no time allows operator action to mitigate the event.

The Applicability is modified by a Note stating that accumulator isolation is only required when the accumulator pressure is more than or at the maximum RCS pressure for the existing temperature, as allowed by the P/T limit curves. This Note permits the accumulator discharge isolation valve Surveillance to be performed only under these pressure and temperature conditions.

ACTIONS A Note prohibits the application of LCO 3.0.4.b to an inoperable LTOP system. There is an increased risk associated with entering MODE 4 from MODE 5 with LTOP inoperable and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

A.1

With two or more charging pumps, two safety injection pumps, or one safety injection pump and one charging pump capable of injecting into the

BASES

ACTIONS (continued)

RCS, RCS overpressurization is possible.

To immediately initiate action to restore restricted coolant input capability to the RCS reflects the urgency of removing the RCS from this condition.

Required Action A.1 is modified by a Note that permits two charging pumps capable of RCS injection for ≤ 15 minutes to allow for pump swaps.

B.1

With RCP operation not limited in accordance with Table 3.4.12-1, RCS overpressurization is possible.

To immediately initiate action to limit pump operation reflects the urgency of removing the RCS from this condition.

C.1, D.1, and D.2

An unisolated accumulator requires isolation within 1 hour. This is only required when the accumulator pressure is at or more than the maximum RCS pressure for the existing temperature allowed by the P/T limit curves.

If isolation is needed and cannot be accomplished in 1 hour, Required Action D.1 and Required Action D.2 provide two options, either of which must be performed in the next 12 hours. By increasing the RCS temperature to $> 285^{\circ}\text{F}$, an accumulator pressure of 678 psig cannot exceed the LTOP limits if the accumulators are fully injected. Depressurizing the accumulators below the LTOP limit also gives this protection.

The Completion Times are based on operating experience that these activities can be accomplished in these time periods and on engineering evaluations indicating that an event requiring LTOP is not likely in the allowed times.

E.1

In MODE 4 when any RCS cold leg temperature is $\leq 285^{\circ}\text{F}$, with one PORV inoperable, the PORV must be restored to OPERABLE status within a Completion Time of 7 days. Two PORVs are required to provide low temperature overpressure mitigation while withstanding a single failure of an active component.

BASES

ACTIONS (continued)

The Completion Time considers the facts that only one of the PORVs is required to mitigate an overpressure transient and that the likelihood of an active failure of the remaining valve path during this time period is very low.

F.1

The consequences of operational events that will overpressurize the RCS are more severe at lower temperature (Ref. 7). Thus, with one of the two PORVs inoperable in MODE 5 or in MODE 6 with the head on Completion Time to restore two valves to OPERABLE status is 24 hours.

The Completion Time represents a reasonable time to investigate and repair several types of relief valve failures without exposure to a lengthy period with only one OPERABLE PORV to protect against overpressure events.

G.1

The RCS must be depressurized and a vent must be established within 8 hours when:

- a. Both PORVs are inoperable; or
- b. A Required Action and associated Completion Time of Condition A, D, E, or F is not met; or
- c. The LTOP System is inoperable for any reason other than Condition A, C, D, E, or F.

The vent must be sized ≥ 4.5 square inches to ensure that the flow capacity is greater than that required for the worst case mass input transient reasonable during the applicable MODES. This action is needed to protect the RCPB from a low temperature overpressure event and a possible brittle failure of the reactor vessel.

The Completion Time considers the time required to place the plant in this Condition and the relatively low probability of an overpressure event during this time period due to increased operator awareness of administrative control requirements.

**SURVEILLANCE
REQUIREMENTS**

SR 3.4.12.1 and SR 3.4.12.2

To minimize the potential for a low temperature overpressure event by

BASES

SURVEILLANCE REQUIREMENTS (continued)

limiting the mass input capability, all but one charging or safety injection pump is verified incapable of injecting into the RCS and the accumulator discharge isolation valves are verified closed and power removed.

The pumps are rendered incapable of injecting into the RCS through removing the power from the pumps by racking the breakers out under administrative control. An alternate method of LTOP control may be employed using at least two independent means to prevent a pump start such that a single failure or single action will not result in an injection into the RCS. This may be accomplished through two valves in the discharge flow path being closed.

The Frequency of 12 hours is sufficient, considering other indications and alarms available to the operator in the control room, to verify the required status of the equipment.

SR 3.4.12.3

The RCS vent of ≥ 4.5 square inches is proven OPERABLE by verifying its open condition either:

- a. Once every 12 hours for a valve that cannot be locked.
- b. Once every 31 days for a valve that is locked, sealed, or secured in position. A removed pressurizer safety valve fits this category.

The passive vent arrangement must only be open to be OPERABLE. This Surveillance is required to be performed if the vent is being used to satisfy the pressure relief requirements of the LCO 3.4.12b.

SR 3.4.12.4

The PORV block valve must be verified open every 72 hours to provide the flow path for each required PORV to perform its function when actuated. The valve must be remotely verified open in the main control room. This Surveillance is performed if the PORV satisfies the LCO.

The block valve is a remotely controlled, motor operated valve. The power to the valve operator is not required removed, and the manual operator is not required locked in the inactive position. Thus, the block valve can be closed in the event the PORV develops excessive leakage or does not close (sticks open) after relieving an overpressure situation.

The 72 hour Frequency is considered adequate in view of other

BASES

SURVEILLANCE REQUIREMENTS (continued)

administrative controls available to the operator in the control room, such as valve position indication, that verify that the PORV block valve remains open.

SR 3.4.12.5

Performance of a COT is required within 12 hours after decreasing RCS temperature to $\leq 285^{\circ}\text{F}$ and every 31 days on each required PORV to verify and, as necessary, adjust its lift setpoint. The COT will verify the setpoint is within the allowed maximum limits. PORV actuation could depressurize the RCS and is not required.

The 12-hour Frequency considers the unlikelihood of a low temperature overpressure event during this time.

A Note has been added indicating that this SR is required to be met 12 hours after decreasing RCS cold leg temperature to $\leq 285^{\circ}\text{F}$. The COT cannot be performed until in the LTOP MODES when the PORV lift setpoint can be reduced to the LTOP setting. The test must be performed within 12 hours after entering the LTOP MODES.

SR 3.4.12.6

Performance of a CHANNEL CALIBRATION on each required PORV actuation channel is required every 18 months to adjust the whole channel so that it responds and the valve opens within the required range and accuracy to known input.

REFERENCES

1. 10 CFR 50, Appendix G.
2. Generic Letter 88-11.
3. UFSAR, Section 5.2
4. 10 CFR 50, Section 50.46.
5. 10 CFR 50, Appendix K.
6. 10 CFR 50.36, Technical Specifications, (c)(2)(ii).
7. Generic Letter 90-06.

BASES

APPLICABLE SAFETY ANALYSES (continued)

information to the operators, allowing them to take corrective action should a leakage occur detrimental to the safety of the unit and the public. RCS leakage detection instrumentation satisfies Criterion 1 of 10 CFR 50.36 (Ref. 4).

LCO One method of protecting against large RCS leakage derives from the reliability of instruments to rapidly detect extremely small leaks. This LCO requires instruments of diverse monitoring principles to be OPERABLE to provide a high degree of confidence that extremely small leaks are detected in time to allow actions to place the plant in a safe condition, when RCS LEAKAGE indicates possible RCPB degradation.

The LCO is satisfied when monitors of diverse measurement means are available. Thus, the containment floor and equipment sump level monitor, in combination with a gaseous or particulate radioactivity monitor and a containment ventilation unit condensate drain tank level monitor, provides an acceptable minimum.

APPLICABILITY Because of elevated RCS temperature and pressure in MODES 1, 2, 3, and 4, RCS leakage detection instrumentation is required to be OPERABLE.

In MODE 5 or 6, the temperature is to be $\leq 200^{\circ}\text{F}$ and pressure is maintained low or at atmospheric pressure. Since the temperatures and pressures are far lower than those for MODES 1, 2, 3, and 4, the likelihood of leakage and crack propagation are much smaller. Therefore, the requirements of this LCO are not applicable in MODES 5 and 6.

ACTIONS A.1 and A.2

With the required containment floor and equipment sump level monitor inoperable, no other form of sampling can provide the equivalent information; however, the containment atmosphere radioactivity monitor

BASES

LCO The specific iodine activity is limited to 1.0 $\mu\text{Ci/gm}$ DOSE EQUIVALENT I-131, and the gross specific activity in the reactor coolant is limited to the number of $\mu\text{Ci/gm}$ equal to 100 divided by \bar{E} (average disintegration energy of the sum of the average beta and gamma energies of the coolant nuclides). The limit on DOSE EQUIVALENT I-131 ensures the 2 hour thyroid dose to an individual at the site boundary during the Design Basis Accident (DBA) will be a small fraction of the allowed thyroid dose. The limit on gross specific activity ensures the 2 hour whole body dose to an individual at the site boundary during the DBA will be a small fraction of the allowed whole body dose.

The SGTR accident analysis (Ref. 2) shows that the 2-hour site boundary dose levels are within acceptable limits. Violation of the LCO may result in reactor coolant radioactivity levels that could, in the event of an SGTR, lead to site boundary doses that exceed the 10 CFR 100 dose guideline limits.

APPLICABILITY: In MODES 1 and 2, and in MODE 3 with RCS average temperature $\geq 500^\circ\text{F}$, operation within the LCO limits for DOSE EQUIVALENT I-131 and gross specific activity are necessary to contain the potential consequences of an SGTR to within the acceptable site boundary dose values.

For operation in MODE 3 with RCS average temperature $< 500^\circ\text{F}$, and in MODES 4 and 5, the release of radioactivity in the event of a SGTR is unlikely since the saturation pressure of the reactor coolant is below the lift pressure settings of the main steam safety valves.

ACTIONS A.1 and A.2

With the DOSE EQUIVALENT I-131 greater than the LCO limit, samples at intervals of 4 hours must be taken to demonstrate that the limits of Figure 3.4.16-1 are not exceeded. The Completion Time of 4 hours is required to obtain and analyze a sample. Sampling is done to continue to provide a trend.

The DOSE EQUIVALENT I-131 must be restored to within limits within 48 hours. The Completion Time of 48 hours is required, if the limit violation resulted from normal iodine spiking.

A Note permits the use of the provisions of LCO 3.0.4.c. This allowance permits entry into the applicable MODE(S) while relying on the ACTIONS. This allowance is acceptable due to the significant conservatism incorporated into the specific activity limit, the low probability of an event which is limiting due to exceeding this limit, and the ability to restore transient specific activity excursions while the plant remains at, or proceeds to power operation.

BASES

ACTIONS (continued)

B.1

With the gross specific activity in excess of the allowed limit, the unit must be placed in a MODE in which the requirement does not apply.

The change within 6 hours to MODE 3 and RCS average temperature < 500°F lowers the saturation pressure of the reactor coolant below the setpoints of the main steam safety valves and prevents venting the SG to the environment in an SGTR event. The allowed Completion Time of 6 hours is reasonable, based on operating experience, to reach MODE 3 below 500°F from full power conditions in an orderly manner and without challenging plant systems.

C.1

If a Required Action and the associated Completion Time of Condition A is not met or if the DOSE EQUIVALENT I-131 is in the unacceptable region of Figure 3.4.16-1, the reactor must be brought to MODE 3 with RCS average temperature < 500°F within 6 hours. The Completion Time of 6 hours is reasonable, based on operating experience, to reach MODE 3 below 500°F from full power conditions in an orderly manner and without challenging plant systems.

SURVEILLANCE REQUIREMENTS SR 3.4.16.1

SR 3.4.16.1 requires performing a gamma isotopic analysis as a measure of the gross specific activity of the reactor coolant at least once every 7 days. A gross radioactivity analysis shall consist of the quantitative measurement of the total specific activity of the reactor coolant except for radionuclides with half-lives less than 10 minutes and all radioiodines. The total specific activity shall be the sum of the beta-gamma activity in the sample within 2 hours after the sample is taken and extrapolated back to when the sample was taken. Determination of the contributors to the gross specific activity shall be based upon those energy peaks identifiable with a 95% confidence level. The latest available data may be used for pure beta-emitting radionuclides. This Surveillance provides an indication of any increase in gross specific activity.

BASES

LCO (continued)

- ECCS pumps and their respective supply headers to each of the four cold leg injection nozzles. In the long term, this flow path may be switched to take its supply from the containment sump and to deliver its flow to the RCS hot and cold legs.
-

APPLICABILITY In MODES 1, 2, and 3, the OPERABILITY requirements for ECCS are covered by LCO 3.5.2.

In MODE 4 with RCS temperature below 350°F, one OPERABLE ECCS train is acceptable without single-failure consideration, on the basis of the stable reactivity of the reactor and the limited core cooling requirements.

In MODES 5 and 6, plant conditions are such that the probability of an event requiring ECCS injection is extremely low. Core cooling requirements in MODE 5 are addressed by LCO 3.4.7, "RCS Loops—MODE 5, Loops Filled," and LCO 3.4.8, "RCS Loops—MODE 5, Loops Not Filled." MODE 6 core cooling requirements are addressed by LCO 3.9.4, "Residual Heat Removal (RHR) and Coolant Circulation—High Water Level," and LCO 3.9.5, "Residual Heat Removal (RHR) and Coolant Circulation—Low Water Level."

ACTIONS A Note prohibits the application of LCO 3.0.4.b to an inoperable ECCS centrifugal charging subsystem when entering MODE 4. There is an increased risk associated with entering MODE 4 from MODE 5 with an inoperable ECCS centrifugal charging subsystem and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

A.1

With no ECCS RHR subsystem OPERABLE, the plant is not prepared to respond to a loss of coolant accident or to continue a cooldown using the RHR pumps and heat exchangers. The Completion Time of immediately to initiate actions that would restore at least one ECCS RHR subsystem to OPERABLE status ensures that prompt action is taken to restore the required cooling capacity. Normally, in MODE 4, reactor decay heat is removed from the RCS by an RHR loop. If no RHR loop is OPERABLE for this function, reactor decay heat must be removed by some alternate method, such as use of the steam generators. The alternate means of

BASES

ACTIONS (continued)

heat removal must continue until the inoperable RHR loop components can be restored to operation so that decay heat removal is continuous.

With both RHR pumps and heat exchangers inoperable, it would be unwise to require the plant to go to MODE 5, where the only available heat removal system is the RHR. Therefore, the appropriate action is to initiate measures to restore one ECCS RHR subsystem and to continue the actions until the subsystem is restored to OPERABLE status.

B.1

With no ECCS high head subsystem OPERABLE, due to the inoperability of the centrifugal charging pump or flow path from the RWST, the plant is not prepared to provide high pressure response to Design Basis Events requiring SI. The 1-hour Completion Time to restore at least one ECCS high head subsystem to OPERABLE status ensures that prompt action is taken to provide the required cooling capacity or to initiate actions to place the plant in MODE 5, where an ECCS train is not required.

C.1

When the Required Actions of Condition B cannot be completed within the required Completion Time, a controlled shutdown should be initiated. Twenty-four hours is a reasonable time, based on operating experience, to reach MODE 5 in an orderly manner and without challenging plant systems or operators.

**SURVEILLANCE
REQUIREMENTS**

SR 3.5.3.1

The applicable Surveillance descriptions from Bases 3.5.2 apply. This SR is modified by a Note that allows an RHR train to be considered OPERABLE during alignment and operation for decay heat removal, if capable of being manually realigned (remote or local) to the ECCS mode of operation and not otherwise inoperable. This allows operation in the RHR mode during MODE 4, if necessary.

REFERENCES

The applicable references from Bases 3.5.2 apply.

BASES

LCO (continued)

Operation with at least one hydrogen recombiner ensures that the post LOCA hydrogen concentration can be prevented from exceeding the flammability limit.

APPLICABILITY In MODES 1 and 2, two hydrogen recombiners are required to control the hydrogen concentration within containment below its flammability limit of 4.0 v/o following a LOCA, assuming a worst case single failure.

In MODES 3 and 4, both the hydrogen production rate and the total hydrogen produced after a LOCA would be less than that calculated for the DBA LOCA. Also, because of the limited time in these MODES, the probability of an accident requiring the hydrogen recombiners is low. Therefore, the hydrogen recombiners are not required in MODE 3 or 4.

In MODES 5 and 6, the probability and consequences of a LOCA are low, due to the pressure and temperature limitations in these MODES. Therefore, hydrogen recombiners are not required in these MODES.

ACTIONS

A.1

With one containment hydrogen recombiner inoperable, the inoperable recombiner must be restored to OPERABLE status within 30 days. In this condition, the remaining OPERABLE hydrogen recombiner is adequate to perform the hydrogen control function. However, the overall reliability is reduced because a single failure in the OPERABLE recombiner could result in reduced hydrogen control capability. The 30 day Completion Time is based on the availability of the other hydrogen recombiner, the small probability of a LOCA occurring (that would generate an amount of hydrogen that exceeds the flammability limit), and the amount of time available after a LOCA (should one occur) for operator action to prevent hydrogen accumulation from exceeding the flammability limit.

BASES

ACTIONS (continued)

B.1

If the inoperable hydrogen recombiner(s) cannot be restored to OPERABLE status within the required Completion Time, the plant must be brought to a MODE in which the LCO does not apply. To achieve this status, the plant must be brought to at least MODE 3 within 6 hours. The Completion Time of 6 hours is reasonable, based on operating experience; to reach MODE 3 from full power conditions in an orderly manner and without challenging plant systems.

SURVEILLANCE REQUIREMENTS **SR 3.6.7.1**

Performance of a system functional test for each hydrogen recombiner ensures the recombiners are operational and can attain and sustain the temperature necessary for hydrogen recombination. In particular, this SR verifies that the minimum heater sheath temperature increases to $\geq 700^{\circ}\text{F}$ in ≤ 90 minutes. After reaching 700°F , the power is increased to maximum power for approximately 2 minutes and power is verified to be ≥ 60 kW.

Industry operating experience has shown that these components usually pass the Surveillance when performed at the 18 month Frequency. Therefore, the Frequency was concluded to be acceptable from a reliability standpoint.

SR 3.6.7.2

This SR ensures there are no physical problems that could affect recombiner operation. Since the recombiners are mechanically passive, they are not subject to mechanical failure. The only credible failure involves loose wiring or structural connections, deposits of foreign materials, etc.

A visual inspection is sufficient to determine abnormal conditions that could cause such failures. The 18 month Frequency for this SR was developed considering the incidence of hydrogen recombiners failing the SR in the past is low.

BASES

APPLICABILITY (continued)

In MODE 3 or 4, both the hydrogen production rate and the total hydrogen produced after a LOCA would be less than that calculated for the DBA LOCA. Also, because of the limited time in these MODES, the probability of an accident requiring the HSS is low. Therefore, the HSS is not required in MODE 3 or 4.

In MODES 5 and 6, the probability and consequences of a LOCA or steam line break (SLB) are reduced due to the pressure and temperature limitations in these MODES. Therefore, the HSS is not required in these MODES.

ACTIONS**A.1**

With one HSS train inoperable, the inoperable train must be restored to OPERABLE status within 30 days. In this Condition, the remaining OPERABLE HSS train is adequate to perform the hydrogen mixing function. However, the overall reliability is reduced because a single failure in the OPERABLE train could result in reduced hydrogen mixing capability. The 30 day Completion Time is based on the availability of the other HSS train, the small probability of a LOCA or SLB occurring (that would generate an amount of hydrogen that exceeds the flammability limit); the amount of time available after a LOCA or SLB (should one occur) for operator action to prevent hydrogen accumulation from exceeding the flammability limit; and the availability of the hydrogen recombiners and hydrogen ignitors.

B.1

If an inoperable HSS train cannot be restored to OPERABLE status within the required Completion Time, the plant must be brought to a MODE in which the LCO does not apply. To achieve this status, the plant must be brought to at least MODE 3 within 6 hours. The allowed Completion Time of 6 hours is reasonable; based on operating experience, to reach MODE 3 from full power conditions in an orderly manner and without challenging plant systems.

BASES

**SURVEILLANCE
REQUIREMENTS**

SR 3.6.8.1

Operating each HSS train for ≥ 15 minutes ensures that each train is OPERABLE and that all associated controls are functioning properly. It also ensures that blockage, fan and/or motor failure, or excessive vibration can be detected for corrective action. The 92 day Frequency is consistent with Inservice Testing Program Surveillance Frequencies, operating experience, the known reliability of the fan motors and controls, and the two train redundancy available.

SR 3.6.8.2

Verifying HSS fan motor current at rated speed with the motor operated suction valves closed is indicative of overall fan motor performance. Since these fans are required to function during post-accident situations, the air density that the fans experience during surveillance testing will be different than the air density following a LOCA. An air density adjustment will be made to the average fan motor current test data before it is compared to the Technical Specification SR acceptance criteria. Such inservice tests confirm component OPERABILITY, trend performance, and detect incipient failures by indicating abnormal performance. The Frequency of 92 days was based on operating experience which has shown this Frequency to be acceptable.

SR 3.6.8.3

This SR verifies the motor operated suction valves open upon receipt of a Containment Pressure = High/High signal and associated time delay and that the HSS fans receive a start permissive when the valves start to open. The Frequency of 92 days was based on operating experience which has shown this Frequency to be acceptable.

BASES

LCO (continued)

An SG PORV is considered OPERABLE when it is capable of providing controlled relief of the main steam flow and capable of fully opening and closing on demand using the nitrogen gas supply.

APPLICABILITY

In MODES 1, 2, and 3, and in MODE 4, when a steam generator is being relied upon for heat removal, the SG PORVs are required to be OPERABLE.

In MODE 5 or 6, an SGTR is not a credible event.

ACTIONS

A.1

With one SG PORV line inoperable, action must be taken to restore OPERABLE status within 7 days. The 7 day Completion Time allows for the redundant capability afforded by the remaining OPERABLE SG PORV lines, a nonsafety grade backup in the Steam Dump System, and MSSVs.

B.1

With two or more SG PORV lines inoperable, action must be taken to restore all but one SG PORV line to OPERABLE status. Since the block valve can be closed to isolate an SG PORV, some repairs may be possible with the unit at power. The 24 hour Completion Time is reasonable to repair inoperable SG PORV lines, based on the availability of the Steam Dump System and MSSVs, and the low probability of an event occurring during this period that would require the SG PORV lines.

C.1 and C.2

If the SG PORV lines cannot be restored to OPERABLE status within the associated Completion Time, the unit must be placed in a MODE in which the LCO does not apply. To achieve this status, the unit must be placed in at least MODE 3 within 6 hours, and in MODE 4, without reliance upon steam generator for heat removal, within 12 hours. The allowed Completion Times are reasonable, based on operating experience, to reach the required unit conditions from full power conditions in an orderly manner and without challenging unit systems.

BASES

LCO (continued)

The AFW System is configured into three trains. The AFW System is considered OPERABLE when the components and flow paths required to provide redundant AFW flow to the steam generators are OPERABLE. This requires that the two motor driven AFW pumps be OPERABLE in two diverse paths, each supplying AFW to separate steam generators. The turbine driven AFW pump is required to be OPERABLE with redundant steam supplies from two main steam lines upstream of the MSIVs, and shall be capable of supplying AFW to any of the steam generators. The piping, valves, instrumentation, and controls in the required flow paths also are required to be OPERABLE. The NSWS assured source of water supply is configured into two trains. The turbine driven AFW pump receives NSWS from both trains of NSWS, therefore, the loss of one train of assured source renders only one AFW train inoperable. The remaining NSWS train provides an OPERABLE assured source to the other motor driven pump and the turbine driven pump.

The LCO is modified by a Note indicating that one AFW train, which includes a motor driven pump, is required to be OPERABLE in MODE 4. This is because of the reduced heat removal requirements and short period of time in MODE 4 during which the AFW is required and the insufficient steam available in MODE 4 to power the turbine driven AFW pump.

APPLICABILITY: In MODES 1, 2, and 3, the AFW System is required to be OPERABLE in the event that it is called upon to function when the MFW is lost. In addition, the AFW System is required to supply enough makeup water to replace the steam generator secondary inventory, lost as the unit cools to MODE 4 conditions.

In MODE 4 the AFW System may be used for heat removal via the steam generators.

In MODE 5 or 6, the steam generators are not normally used for heat removal, and the AFW System is not required.

ACTIONS

A Note prohibits the application of LCO 3.0.4.b to an inoperable AFW train when entering MODE 1. There is an increased risk associated with entering MODE 1 with an AFW train inoperable and the provisions of LCO 3.0.4.b, which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, should not be applied in this circumstance.

BASES

ACTIONS (continued)

A.1

If one of the two steam supplies to the turbine driven AFW train is inoperable, action must be taken to restore OPERABLE status within 7 days. The 7 day Completion Time is reasonable, based on the following reasons:

- a. The redundant OPERABLE steam supply to the turbine driven AFW pump;
- b. The availability of redundant OPERABLE motor driven AFW pumps; and
- c. The low probability of an event occurring that requires the inoperable steam supply to the turbine driven AFW pump.

The second Completion Time for Required Action A.1 establishes a limit on the maximum time allowed for any combination of Conditions to be inoperable during any continuous failure to meet this LCO.

The 10 day Completion Time provides a limitation time allowed in this specified Condition after discovery of failure to meet the LCO. This limit is considered reasonable for situations in which Conditions A and B are entered concurrently. The AND connector between 7 days and 10 days dictates that both Completion Times apply simultaneously, and the more restrictive must be met.

B.1

With one of the required AFW trains (pump or flow path) inoperable in MODE 1; 2; or 3 for reasons other than Condition A, action must be taken to restore OPERABLE status within 72 hours. This Condition includes the loss of two steam supply lines to the turbine driven AFW pump. The 72 hour Completion Time is reasonable, based on redundant capabilities afforded by the AFW System, time needed for repairs, and the low probability of a DBA occurring during this time period.

The second Completion Time for Required Action B.1 establishes a limit on the maximum time allowed for any combination of Conditions to be inoperable during any continuous failure to meet this LCO.

The 10 day Completion Time provides a limitation time allowed in this specified Condition after discovery of failure to meet the LCO. This limit is considered ACTIONS reasonable for situations in which Conditions A

BASES

ACTIONS (continued)

and B are entered concurrently. The AND connector between 72 hours and 10 days dictates that both Completion Times apply simultaneously, and the more restrictive must be met.

C.1 and C.2

When Required Action A:1 or B:1 cannot be completed within the required Completion Time, or if two AFW trains are inoperable in MODE 1, 2, or 3, the unit must be placed in a MODE in which the LCO does not apply. To achieve this status, the unit must be placed in at least MODE 3 within 6 hours, and in MODE 4 within 12 hours.

The allowed Completion Times are reasonable, based on operating experience, to reach the required unit conditions from full power conditions in an orderly manner and without challenging unit systems.

In MODE 4 with two AFW trains inoperable, operation is allowed to continue because only one motor driven pump AFW train is required in accordance with the Note that modifies the LCO. Although not required, the unit may continue to cool down and initiate RHR.

D.1

If all three AFW trains are inoperable in MODE 1, 2, or 3, the unit is in a seriously degraded condition with no safety-related means for conducting a cooldown, and only limited means for conducting a cooldown with nonsafety-related equipment. In such a condition, the unit should not be perturbed by any action, including a power change, that might result in a trip. The seriousness of this condition requires that action be started immediately to restore one AFW train to OPERABLE status.

Required Action D.1 is modified by a Note indicating that all required MODE changes or power reductions are suspended until one AFW train is restored to OPERABLE status. In this case, LCO 3.0.3 is not applicable because it could force the unit into a less safe condition.

E.1

In MODE 4, either the reactor coolant pumps or the RHR loops can be used to provide forced circulation. This is addressed in LCO 3.4.6, "RCS Loops—MODE 4." With one required AFW train inoperable, action must be taken to immediately restore the inoperable train to OPERABLE status. The immediate Completion Time is consistent with LCO 3.4.6.

BASES

APPLICABILITY (continued)

- b. Adequate core cooling is provided and containment OPERABILITY and other vital functions are maintained in the event of a postulated DBA.

The AC power requirements for MODES 5 and 6 are covered in LCO 3.8.2, "AC Sources—Shutdown."

ACTIONS

A Note Prohibits the application of LCO 3.0.4.b to an inoperable DG. There is an increased risk associated with entering a MODE or other specified condition in the Applicability with an inoperable DG and the provisions of LCO 3.0.4.b; which allow entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components; should not be applied in this circumstance.

A.1

To ensure a highly reliable power source remains with one offsite circuit inoperable, it is necessary to verify the OPERABILITY of the remaining required offsite circuit on a more frequent basis. Since the Required Action only specifies "perform," a failure of SR 3.8.1.1 acceptance criteria does not result in a Required Action not met. However, if a second required circuit fails SR 3.8.1.1, the second offsite circuit is inoperable, and Condition C, for two offsite circuits inoperable, is entered.

A.2

Required Action A.2, which only applies if the train cannot be powered from an offsite source, is intended to provide assurance that an event coincident with a single failure of the associated DG will not result in a complete loss of safety function of critical redundant required features.

These features are powered from the redundant AC electrical power train. This includes motor driven auxiliary feedwater pumps. The turbine driven auxiliary feedwater pump is required to be considered a redundant required feature, and, therefore, required to be determined OPERABLE by this Required Action. Three independent AFW pumps are required to ensure the availability of decay heat removal capability for all events accompanied by a loss of offsite power and a single failure. System design is such that the remaining OPERABLE motor driven auxiliary feedwater pump is not by itself capable of providing 100% of the auxiliary

BASES

ACTIONS (continued)

feedwater flow assumed in the safety analysis.

The Completion Time for Required Action A.2 is intended to allow the operator time to evaluate and repair any discovered inoperabilities. This Completion Time also allows for an exception to the normal "time zero" for beginning the allowed outage time "clock." In this Required Action, the Completion Time only begins on discovery that both:

- a. The train has no offsite power supplying its loads; and
- b. A required feature on the other train is inoperable.

If at any time during the existence of Condition A (one offsite circuit inoperable) a redundant required feature subsequently becomes inoperable, this Completion Time begins to be tracked.

Discovering no offsite power to one train of the onsite Class 1E Electrical Power Distribution System coincident with one or more inoperable required support or supported features, or both, that are associated with the other train that has offsite power, results in starting the Completion Times for the Required Action. Twenty-four hours is acceptable because it minimizes risk while allowing time for restoration before subjecting the unit to transients associated with shutdown.

The remaining OPERABLE offsite circuit and DGs are adequate to supply electrical power to Train A and Train B of the onsite Class 1E Distribution System. The 24 hour Completion Time takes into account the component OPERABILITY of the redundant counterpart to the inoperable required feature. Additionally, the 24 hour Completion Time takes into account the capacity and capability of the remaining AC sources, a reasonable time for repairs, and the low probability of a DBA occurring during this period.

A.3

According to Regulatory Guide 1.93 (Ref. 7), operation may continue in Condition A for a period that should not exceed 72 hours. With one offsite circuit inoperable, the reliability of the offsite system is degraded, and the potential for a loss of offsite power is increased, with attendant potential for a challenge to the unit safety systems. In this Condition, however, the remaining OPERABLE offsite circuit and DGs are adequate to supply electrical power to the onsite Class 1E Distribution System.

The 72 hour Completion Time takes into account the capacity and

BASES

ACTIONS (continued)

capability of the remaining AC sources, a reasonable time for repairs, and the low probability of a DBA occurring during this period.

The second Completion Time for Required Action A.3 establishes a limit on the maximum time allowed for any combination of required AC power sources to be inoperable during any single contiguous occurrence of failing to meet the LCO. If Condition A is entered while, for instance, a DG is inoperable and that DG is subsequently returned OPERABLE, the LCO may already have been not met for up to 72 hours. This could lead to a total of 144 hours, since initial failure to meet the LCO, to restore the offsite circuit. At this time, a DG could again become inoperable; the circuit restored OPERABLE; and an additional 72 hours (for a total of 9 days) allowed prior to complete restoration of the LCO. The 6 day Completion Time provides a limit on the time allowed in a specified condition after discovery of failure to meet the LCO. This limit is considered reasonable for situations in which Conditions A and B are entered concurrently. The "AND" connector between the 72 hour and 6 day Completion Times means that both Completion Times apply simultaneously, and the more restrictive Completion Time must be met.

As in Required Action A.2, the Completion Time allows for an exception to the normal "time zero" for beginning the allowed outage time "clock." This will result in establishing the "time zero" at the time that the LCO was initially not met, instead of at the time Condition A was entered.

B.1

To ensure a highly reliable power source remains with an inoperable DG, it is necessary to verify the availability of the offsite circuits on a more frequent basis. Since the Required Action only specifies "perform," a failure of SR 3.8.1.1 acceptance criteria does not result in a Required Action being not met. However, if a circuit fails to pass SR 3.8.1.1, it is inoperable. Upon offsite circuit inoperability, additional Conditions and Required Actions must then be entered.

B.2

Required Action B.2 is intended to provide assurance that a loss of offsite power, during the period that a DG is inoperable, does not result in a complete loss of safety function of critical systems. These features are designed with redundant safety related trains. This includes motor driven auxiliary feedwater pumps. The turbine driven auxiliary feedwater pump is required to be considered a redundant required feature, and, therefore,

BASES

ACTIONS (continued)

required to be determined OPERABLE by this Required Action. Three independent AFW pumps are required to ensure the availability of decay heat removal capability for all events accompanied by a loss of offsite power and a single failure. System design is such that the remaining OPERABLE motor driven auxiliary feedwater pump is not by itself capable of providing 100% of the auxiliary feedwater flow assumed in the safety analysis. Redundant required feature failures consist of inoperable features associated with a train, redundant to the train that has an inoperable DG.

The Completion Time for Required Action B.2 is intended to allow the operator time to evaluate and repair any discovered inoperabilities. This Completion Time also allows for an exception to the normal "time zero" for beginning the allowed outage time "clock." In this Required Action, the Completion Time only begins on discovery that both:

- a. An inoperable DG exists; and
- b. A required feature on the other train (Train A or Train B) is inoperable.

If at any time during the existence of this Condition (one DG inoperable) a required feature subsequently becomes inoperable, this Completion Time would begin to be tracked.

Discovering one required DG inoperable coincident with one or more inoperable required support or supported features, or both, that are associated with the OPERABLE DG, results in starting the Completion Time for the Required Action. Four hours from the discovery of these events existing concurrently is Acceptable because it minimizes risk while allowing time for restoration before subjecting the unit to transients associated with shutdown.

In this Condition, the remaining OPERABLE DG and offsite circuits are adequate to supply electrical power to the onsite Class 1E Distribution System. Thus, on a component basis, single failure protection for the required feature's function may have been lost; however, function has not been lost. The 4 hour Completion Time takes into account the OPERABILITY of the redundant counterpart to the inoperable required feature. Additionally, the 4 hour Completion Time takes into account the capacity and capability of the remaining AC sources, a reasonable time for repairs, and the low probability of a DBA occurring during this period.

Attachment 4

List of Regulatory Commitments

The following table identifies those actions committed to by Duke Energy Corporation (Duke) in this document. Any other statements in this submittal are provided for informational purposes and are not considered to be regulatory commitments. Please direct questions regarding these commitments to J. S. Warren at (704) 382-4986.

REGULATORY COMMITMENTS	Due Date/Event
Duke will implement the approved amendments and associated Bases at McGuire and Catawba Nuclear Stations following completion of the necessary personnel training, but no later than 120 days following NRC issuance of the approved amendments.	120 days following issuance.
Duke will establish a Bases control program at McGuire and Catawba Nuclear Stations consistent with the Technical Specifications (TS) Bases Control Program described in Section 5.5 of the applicable vendor's Standard TS (STS).	Completed.
Duke will establish the equivalent of STS SR 3.0.1 at McGuire and Catawba Nuclear Stations.	Completed.

Attachment 5a

McGuire Units 1 and 2

Proposed Technical Specifications Bases Changes (Mark-up)

BASES

LCO 3.0.3 (continued)

The time limits of Specification 3.0.3 allow 37 hours for the unit to be in MODE 5 when a shutdown is required during MODE 1 operation. If the unit is in a lower MODE of operation when a shutdown is required, the time limit for reaching the next lower MODE applies. If a lower MODE is reached in less time than allowed, however, the total allowable time to reach MODE 5, or other applicable MODE, is not reduced. For example, if MODE 3 is reached in 2 hours, then the time allowed for reaching MODE 4 is the next 11 hours, because the total time for reaching MODE 4 is not reduced from the allowable limit of 13 hours. Therefore, if remedial measures are completed that would permit a return to MODE 1, a penalty is not incurred by having to reach a lower MODE of operation in less than the total time allowed.

In MODES 1, 2, 3, and 4, LCO 3.0.3 provides actions for Conditions not covered in other Specifications. The requirements of LCO 3.0.3 do not apply in MODES 5 and 6 because the unit is already in the most restrictive Condition required by LCO 3.0.3. The requirements of LCO 3.0.3 do not apply in other specified conditions of the Applicability (unless in MODE 1, 2, 3, or 4) because the ACTIONS of individual Specifications sufficiently define the remedial measures to be taken.

Exceptions to LCO 3.0.3 are provided in instances where requiring a unit shutdown, in accordance with LCO 3.0.3, would not provide appropriate remedial measures for the associated condition of the unit. An example of this is in LCO 3.7.13, "Spent Fuel Pool (SFP) Water Level." LCO 3.7.13 has an Applicability of "During movement of irradiated fuel assemblies in the spent fuel pool." Therefore, this LCO can be applicable in any or all MODES. If the LCO and the Required Actions of LCO 3.7.13 are not met while in MODE 1, 2, or 3, there is no safety benefit to be gained by placing the unit in a shutdown condition. The Required Action of LCO 3.7.13 of "Suspend movement of irradiated fuel assemblies in the spent fuel pool" is the appropriate Required Action to complete in lieu of the actions of LCO 3.0.3. These exceptions are addressed in the individual Specifications.

LCO 3.0.4

LCO 3.0.4 establishes limitations on changes in MODES or other specified conditions in the Applicability when an LCO is not met. It precludes placing the unit in a MODE or other specified condition stated in that Applicability (e.g., Applicability desired to be entered) when the following exist:

INSERT 3

BASES

LCO 3.0.4 (continued)

- a. Unit conditions are such that the requirements of the LCO would not be met in the Applicability desired to be entered; and
- b. Continued noncompliance with the LCO requirements, if the Applicability were entered, would result in the unit being required to exit the Applicability desired to be entered to comply with the Required Actions.

Compliance with Required Actions that permit continued operation of the unit for an unlimited period of time in a MODE or other specified condition provides an acceptable level of safety for continued operation. This is without regard to the status of the unit before or after the MODE change. Therefore, in such cases, entry into a MODE or other specified condition in the Applicability may be made in accordance with the provisions of the Required Actions. The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or components to OPERABLE status before entering an associated MODE or other specified condition in the Applicability.

The provisions of LCO 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS.

Exceptions to LCO 3.0.4 are stated in the individual Specifications. The exceptions allow entry into MODES or other specified conditions in the Applicability when the associated ACTIONS to be entered do not provide for continued operation for an unlimited period of time. Exceptions may apply to all the ACTIONS or to a specific Required Action of a Specification.

Surveillances do not have to be performed on the associated inoperable equipment (or on variables outside the specified limits), as permitted by SR 3.0.1. Therefore, changing MODES or other specified conditions while in an ACTIONS Condition, in compliance with LCO 3.0.4 or where an exception to LCO 3.0.4 is stated, is not a violation of SR 3.0.1 or SR 3.0.4 for those Surveillances that do not have to be performed due to the associated inoperable equipment. However, SRs must be met to ensure OPERABILITY prior to declaring the associated equipment OPERABLE (or variable within limits) and restoring compliance with the affected LCO.

INSERT 3

INSERT 3 (LCO 3.0.4 BASES) – TSTF-359, REV 9

LCO 3.0.4 establishes limitations on changes in MODES or other specified conditions in the Applicability when an LCO is not met. It allows placing the unit in a MODE or other specified condition stated in that Applicability (e.g., the Applicability desired to be entered) when unit conditions are such that the requirements of the LCO would not be met, in accordance with LCO 3.0.4.a, LCO 3.0.4.b, or LCO 3.0.4.c.

LCO 3.0.4.a allows entry into a MODE or other specified condition in the Applicability with the LCO not met when the associated ACTIONS to be entered permit continued operation in the MODE or other specified condition in the Applicability for an unlimited period of time. Compliance with Required Actions that permit continued operation of the unit for an unlimited period of time in a MODE or other specified condition provides an acceptable level of safety for continued operation. This is without regard to the status of the unit before or after the MODE change. Therefore, in such cases, entry into a MODE or other specified condition in the Applicability may be made in accordance with the provisions of the Required Actions.

LCO 3.0.4.b allows entry into a MODE or other specified condition in the Applicability with the LCO not met after performance of a risk assessment addressing inoperable systems and components, consideration of the results, determination of the acceptability of entering the MODE or other specified condition in the Applicability, and establishment of risk management actions, if appropriate.

The risk assessment may use quantitative, qualitative, or blended approaches, and the risk assessment will be conducted using the plant program, procedures, and criteria in place to implement 10 CFR 50.65(a)(4), which requires that risk impacts of maintenance activities to be assessed and managed. The risk assessment, for the purposes of LCO 3.0.4 (b), must take into account all inoperable Technical Specification equipment regardless of whether the equipment is included in the normal 10 CFR 50.65(a)(4) risk assessment scope. The risk assessments will be conducted using the procedures and guidance endorsed by Regulatory Guide 1.182, "Assessing and Managing Risk Before Maintenance Activities at Nuclear Power Plants." Regulatory Guide 1.182 endorses the guidance in Section 11 of NUMARC 93-01, "Industry Guideline for Monitoring the Effectiveness of Maintenance at Nuclear Power Plants." These documents address general guidance for conduct of the risk assessment, quantitative and qualitative guidelines for establishing risk management actions, and example risk management actions. These include actions to plan and conduct other activities in a manner that controls overall risk, increased risk awareness by shift and management personnel, actions to reduce the duration of the condition, actions to minimize the magnitude of risk increases (establishment of backup success paths or compensatory measures), and determination that the proposed MODE change is acceptable. Consideration should also be given to the probability of completing restoration such that the requirements of the LCO would be met prior to the expiration of ACTIONS Completion Times that would require exiting the Applicability.

INSERT 3 (LCO 3.0.4 BASES) – TSTF-359, REV 9

LCO 3.0.4.b may be used with single, or multiple systems and components unavailable. NUMARC 93-01 provides guidance relative to consideration of simultaneous unavailability of multiple systems and components.

The results of the risk assessment shall be considered in determining the acceptability of entering the MODE or other specified condition in the Applicability, and any corresponding risk management actions. The LCO 3.0.4.b risk assessments do not have to be documented.

The Technical Specifications allow continued operation with equipment unavailable in MODE 1 for the duration of the Completion Time. Since this is allowable, and since in general the risk impact in that particular MODE bounds the risk of transitioning into and through the applicable MODES or other specified conditions in the Applicability of the LCO, the use of the LCO 3.0.4.b allowance should be generally acceptable, as long as the risk is assessed and managed as stated above. However, there is a small subset of systems and components that have been determined to be more important to risk and use of the LCO 3.0.4.b allowance is prohibited. The LCOs governing these system and components contain Notes prohibiting the use of LCO 3.0.4.b by stating that LCO 3.0.4.b is not applicable.

LCO 3.0.4.c allows entry into a MODE or other specified condition in the Applicability with the LCO not met based on a Note in the Specification which states LCO 3.0.4.c is applicable. These specific allowances permit entry into MODES or other specified conditions in the Applicability when the associated ACTIONS to be entered do not provide for continued operation for an unlimited period of time and a risk assessment has not been performed. This allowance may apply to all the ACTIONS or to a specific Required Action of a Specification. The risk assessments performed to justify the use of LCO 3.0.4.b usually only consider systems and components. For this reason, LCO 3.0.4.c is typically applied to Specifications which describe values and parameters (e.g., RCS Specific Activity).

The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or components to OPERABLE status before entering an associated MODE or other specified condition in the Applicability.

The provisions of LCO 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS. In addition, the provisions of LCO 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that result from any unit shutdown. In this context, a unit shutdown is defined as a change in MODE or other specified condition in the Applicability associated with transitioning from MODE 1 to MODE 2, MODE 2 to MODE 3, MODE 3 to MODE 4, and MODE 4 to MODE 5.

INSERT 3 (LCO 3.0.4 BASES) – TSTF-359, REV 9

Upon entry into a MODE or other specified condition in the Applicability with the LCO not met, LCO 3.0.1 and LCO 3.0.2 require entry into the applicable Conditions and Required Actions until the Condition is resolved, until the LCO is met, or until the unit is not within the Applicability of the Technical Specification.

Surveillances do not have to be performed on the associated inoperable equipment (or on variables outside the specified limits), as permitted by SR 3.0.1. Therefore, utilizing LCO 3.0.4 is not a violation of SR 3.0.1 or SR 3.0.4 for any Surveillances that have not been performed on inoperable equipment. However, SRs must be met to ensure OPERABILITY prior to declaring the associated equipment OPERABLE (or variable within limits) and restoring compliance with the affected LCO.

BASES

Completion of the Surveillance within the delay period allowed by this Specification, or within the Completion Time of the ACTIONS, restores compliance with SR 3.0.1.

SR 3.0.4

INSERT 4

SR 3.0.4 establishes the requirement that all applicable SRs must be met before entry into a MODE or other specified condition in the Applicability.

This Specification ensures that system and component OPERABILITY requirements and variable limits are met before entry into MODES or other specified conditions in the Applicability for which these systems and components ensure safe operation of the unit.

The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or component to OPERABLE status before entering an associated MODE or other specified condition in the Applicability.

However, in certain circumstances, failing to meet an SR will not result in SR 3.0.4 restricting a MODE change or other specified condition change. When a system, subsystem, division, component, device, or variable is inoperable or outside its specified limits, the associated SR(s) are not required to be performed, per SR 3.0.1, which states that surveillances do not have to be performed on inoperable equipment. When equipment is inoperable, SR 3.0.4 does not apply to the associated SR(s) since the requirement for the SR(s) to be performed is removed. Therefore, failing to perform the Surveillance(s) within the specified Frequency does not result in an SR 3.0.4 restriction to changing MODES or other specified conditions of the Applicability. However, since the LCO is not met in this instance, LCO 3.0.4 will govern any restrictions that may (or may not) apply to MODE or other specified condition changes.

The provisions of SR 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that are required to comply with ACTIONS.

The precise requirements for performance of SRs are specified such that exceptions to SR 3.0.4 are not necessary. The specific time frames and conditions necessary for meeting the SRs are specified in the Frequency, in the Surveillance, or both. This allows performance of Surveillances when the prerequisite condition(s) specified in a Surveillance procedure require entry into the MODE or other specified condition in the Applicability of the associated LCO prior to the performance or completion of a Surveillance. A Surveillance that could not be performed until

BASES

INSERT 4

after entering the LCO Applicability, would have its Frequency specified such that it is not "due" until the specific conditions needed are met. Alternately, the Surveillance may be stated in the form of a Note as not required (to be met or performed) until a particular event, condition, or time has been reached. Further discussion of the specific formats of SRs' annotation is found in Section 1.4, Frequency.

SR 3.0.5

SR 3.0.5 delineates the applicability of the surveillance activities to Unit 1 and Unit 2 operations.

INSERT 4 (SR 3.0.4 BASES) – TSTF-359, REV 9

SR 3.0.4 establishes the requirement that all applicable SRs must be met before entry into a MODE or other specified condition in the Applicability.

This Specification ensures that system and component OPERABILITY requirements and variable limits are met before entry into MODES or other specified conditions in the Applicability for which these systems and components ensure safe operation of the unit. The provisions of this Specification should not be interpreted as endorsing the failure to exercise the good practice of restoring systems or components to OPERABLE status before entering an associated MODE or other specified condition in the Applicability.

A provision is included to allow entry into a MODE or other specified condition in the Applicability when an LCO is not met due to Surveillance not being met in accordance with LCO 3.0.4.

However, in certain circumstances, failing to meet an SR will not result in SR 3.0.4 restricting a MODE change or other specified condition change. When a system, subsystem, division, component, device, or variable is inoperable or outside its specified limits, the associated SR(s) are not required to be performed, per SR 3.0.1, which states that surveillances do not have to be performed on inoperable equipment. When equipment is inoperable, SR 3.0.4 does not apply to the associated SR(s) since the requirement for the SR(s) to be performed is removed. Therefore, failing to perform the Surveillance(s) within the specified Frequency does not result in an SR 3.0.4 restriction to changing MODES or other specified conditions of the Applicability. However, since the LCO is not met in this instance, LCO 3.0.4 will govern any restrictions that may (or may not) apply to MODE or other specified condition changes. SR 3.0.4 does not restrict changing MODES or other specified conditions of the Applicability when a Surveillance has not been performed within the specified Frequency, provided the requirement to declare the LCO not met has been delayed in accordance with SR 3.0.3.

The provisions of SR 3.0.4 shall not prevent entry into MODES or other specified conditions in the Applicability that are required to comply with ACTIONS. In addition, the provisions of SR 3.0.4 shall not prevent changes in MODES or other specified conditions in the Applicability that result from any unit shutdown. In this context, a unit shutdown is defined as a change in MODE or other specified condition in the Applicability associated with transitioning from MODE 1 to MODE 2, MODE 2 to MODE 3, MODE 3 to MODE 4, and MODE 4 to MODE 5.

INSERT 4 (SR 3.0.4 BASES) – TSTF-359, REV 9

The precise requirements for performance of SRs are specified such that exceptions to SR 3.0.4 are not necessary. The specific time frames and conditions necessary for meeting the SRs are specified in the Frequency, in the Surveillance, or both. This allows performance of Surveillances when the prerequisite condition(s) specified in a Surveillance procedure require entry into the MODE or other specified condition in the Applicability of the associated LCO prior to the performance or completion of a Surveillance. A Surveillance that could not be performed until after entering the LCO's Applicability, would have its Frequency specified such that it is not "due" until the specific conditions needed are met. Alternately, the Surveillance may be stated in the form of a Note, as not required (to be met or performed) until a particular event, condition, or time has been reached. Further discussion of the specific formats of SRs' annotation is found in Section 1.4, Frequency.

BASES

LCO (continued)

Two channels of Steam Line Pressure are required OPERABLE.

20. Refueling Water Storage Tank Level

RWST level monitoring is provided to ensure an adequate supply of water to the safety injection and spray pumps during the switchover to cold leg recirculation.

Three channels of RWST level are provided. Two channels are required OPERABLE by the LCO.

21. DG Heat Exchanger NSWS Flow

Flow indicators are provided in each of the NSWS trains to indicate cooling water flow through the respective train DG. These indicators are provided for operators to manually control flow to the DG heat exchanger. One flow indicator is required OPERABLE on each train.

22. Containment Spray Heat Exchanger NSWS Flow

Flow indicators are provided in each of the NSWS trains to indicate cooling water flow through the respective train containment spray heat exchangers. These indicators are provided for operators to manually control flow to the heat exchanger. One flow indicator is required OPERABLE on each train.

APPLICABILITY

The PAM instrumentation LCO is applicable in MODES 1, 2, and 3. These variables are related to the diagnosis and pre-planned actions required to mitigate DBAs. The applicable DBAs are assumed to occur in MODES 1, 2, and 3. In MODES 4, 5, and 6, unit conditions are such that the likelihood of an event that would require PAM instrumentation is low; therefore, the PAM instrumentation is not required to be OPERABLE in these MODES.

ACTIONS

Note 1 has been added in the ACTIONS to exclude the MODE change restriction of LCO 3.0.4. This exception allows entry into the applicable MODE while relying on the ACTIONS even though the ACTIONS may eventually require unit shutdown. This exception is acceptable due to the

BASES

ACTIONS (continued)

passive function of the instruments, the operator's ability to respond to an accident using alternate instruments and methods, and the low probability of an event requiring these instruments.

A

Note (2) has been added in the ACTIONS to clarify the application of Completion Time rules. The Conditions of this Specification may be entered independently for each Function listed on Table 3.3.3-1. When the Required Channels in Table 3.3.3-1 are specified (e.g., on a per steam line, per loop, per SG, etc., basis), then the Condition may be entered separately for each steam line, loop, SG, etc., as appropriate. The Completion Time(s) of the inoperable channel(s) of a Function will be tracked separately for each Function starting from the time the Condition was entered for that Function.

A.1

Condition A applies to all PAM instrument Functions. Condition A addresses the situation when one or more required channels for one or more Functions are inoperable. The Required Action is to refer to Table 3.3.3-1 and take the appropriate Required Actions for the PAM instrumentation affected. The Completion Times are those from the referenced Conditions and Required Actions.

B.1

Condition B applies when one or more Functions have one required channel that is inoperable. Required Action B.1 requires restoring the inoperable channel to OPERABLE status within 30 days. The 30 day Completion Time is based on operating experience and takes into account the remaining OPERABLE channel, the passive nature of the instrument (no critical automatic action is assumed to occur from these instruments), and the low probability of an event requiring PAM instrumentation during this interval. Condition B is not applicable to functions with a single required channel.

C.1

Condition C applies when the Required Action and associated Completion Time for Condition B are not met. This Required Action specifies initiation of actions in Specification 5.6.7, which requires a written report to be submitted to the NRC immediately. This report

BASES

APPLICABILITY (continued)

This LCO is not applicable in MODE 4, 5, or 6. In these MODES, the facility is already subcritical and in a condition of reduced RCS energy. Under these conditions, considerable time is available to restore necessary instrument control functions if control room instruments or controls become unavailable.

ACTIONS

Note 1 is included which excludes the MODE change restriction of LCO 3.0.4. This exception allows entry into an applicable MODE while relying on the ACTIONS even though the ACTIONS may eventually require a unit shutdown. This exception is acceptable due to the low probability of an event requiring the Remote Shutdown System and because the equipment can generally be repaired during operation without significant risk of spurious trip.

A

Note 2 has been added to the ACTIONS to clarify the application of Completion Time rules. Separate Condition entry is allowed for each Function listed on Table 3.3.4-1. The Completion Time(s) of the inoperable channel(s)/train(s) of a Function will be tracked separately for each Function starting from the time the Condition was entered for that Function.

A.1

Condition A addresses the situation where one or more required Functions of the Remote Shutdown System are inoperable. This includes any Function listed in Table 3.3.4-1 as well as the control and transfer switches.

The Required Action is to restore the required Function to OPERABLE status within 30 days. The Completion Time is based on operating experience and the low probability of an event that would require evacuation of the control room.

B.1 and B.2

If the Required Action and associated Completion Time of Condition A is not met, the unit must be brought to a MODE in which the LCO does not apply. To achieve this status, the unit must be brought to at least MODE 3 within 6 hours and to MODE 4 within 12 hours. The allowed Completion Times are reasonable, based on operating experience, to reach the required unit conditions from full power conditions in an orderly manner and without challenging unit systems.