

December 5, 2003

Mr. Harold B. Ray  
Executive Vice President  
Southern California Edison Company  
San Onofre Nuclear Generating Station  
P.O. Box 128  
San Clemente, CA 92674-0128

SUBJECT: SAN ONOFRE GENERATING STATION, UNITS 2 AND 3 – JUSTIFICATION  
REQUIRED FOR MECHANICAL NOZZLE SEAL ASSEMBLY (MNSA) TO BE  
USED AS A PERMANENT REPAIR

Dear Mr. Ray:

The mechanical nozzle seal assembly (MNSA) is a mechanical device that industry is using to provide both sealing and structural integrity for leaking nozzle connections. Currently, MNSAs have been installed on the exterior surfaces of reactor coolant pressure boundary components, as an alternative to weld repairs for leaks in small diameter J-groove welded Alloy 600 instrument nozzles and thermal sleeves. The NRC has accepted MNSA repairs on a temporary basis for two operating cycles. A number of licensees have requested and have been granted NRC approval extending the temporary MNSA repairs beyond the two operating cycles for additional cycles on the same basis as that on which initial approval was granted.

It is the position of the NRC staff that should a licensee decide to keep a MNSA in service beyond the period for which temporary approval has already been granted, the licensee shall provide a justification which supports the approval of the MNSA as a permanent repair. The licensee's justification should include an analysis of the pressure boundary component to which the MNSA is attached and an inservice inspection program to be maintained throughout the licensed life of the facility. The licensee's justification should be submitted for NRC staff review and approval no later than one year prior to the expiration of its existing temporary repair approval period. Additional guidance regarding what information should be included in a licensee's justification is provided in the enclosure.

If you have any questions, or need clarification, you can call me (301-415-1395), Steve Dembek (301-415-1455), or Brian Benney (301-415-3764).

Sincerely,

*/RA/*

Herbert Berkow, Director  
Project Directorate IV  
Division of Licensing Project Management  
Office of Nuclear Reactor Regulation

Docket Nos. 50-361 and 50-362

Enclosure: Analysis and Inspection Criteria

cc w/encl: See next page

December 5, 2003

Mr. Harold B. Ray  
Executive Vice President  
Southern California Edison Company  
San Onofre Nuclear Generating Station  
P.O. Box 128  
San Clemente, CA 92674-0128

**SUBJECT: SAN ONOFRE GENERATING STATION, UNITS 2 AND 3 – JUSTIFICATION  
REQUIRED FOR MECHANICAL NOZZLE SEAL ASSEMBLY (MNSA) TO BE  
USED AS A PERMANENT REPAIR**

Dear Mr. Ray:

The mechanical nozzle seal assembly (MNSA) is a mechanical device that industry is using to provide both sealing and structural integrity for leaking nozzle connections. Currently, MNSAs have been installed on the exterior surfaces of reactor coolant pressure boundary components, as an alternative to weld repairs for leaks in small diameter J-groove welded Alloy 600 instrument nozzles and thermal sleeves. The NRC has accepted MNSA repairs on a temporary basis for two operating cycles. A number of licensees have requested and have been granted NRC approval extending the temporary MNSA repairs beyond the two operating cycles for additional cycles on the same basis as that on which initial approval was granted.

It is the position of the NRC staff that should a licensee decide to keep a MNSA in service beyond the period for which temporary approval has already been granted, the licensee shall provide a justification which supports the approval of the MNSA as a permanent repair. The licensee's justification should include an analysis of the pressure boundary component to which the MNSA is attached and an inservice inspection program to be maintained throughout the licensed life of the facility. The licensee's justification should be submitted for NRC staff review and approval no later than one year prior to the expiration of its existing temporary repair approval period. Additional guidance regarding what information should be included in a licensee's justification is provided in the enclosure.

If you have any questions, or need clarification, you can call me (301-415-1395), Steve Dembek (301-415-1455), or Brian Benney (301-415-3764).

Sincerely,

**/RA/**

Herbert Berkow, Director  
Project Directorate IV  
Division of Licensing Project Management  
Office of Nuclear Reactor Regulation

Docket Nos. 50-361 and 50-362

Enclosure: Analysis and Inspection Criteria

cc w/encl: See next page

DISTRIBUTION:

PUBLIC Belliot  
PDIV-2 Reading  
RidsNrrDlpmPdiv (HBerkow)  
RidsNrrPMBBenney  
RidsNrrPMBPham  
RidsNrrLAMMcAlister  
RidsOgcRp  
RidsAcrsAcnwMailCenter  
WBateman  
MMitchell

**ACCESSION NO.: ML033450196**

**NRR-106**

**\*See Previous Concurrence**

OFFICE	PDIV-2/PM	PDIV-2/LA*	EMCB/SC*	OGC*	PDIV-2/SC	PDIV/D
NAME	BBenney	EPeyton	BBateman	AFernandez	SDembek	HBerkow
DATE	12/5/03	10/24/03	10/24/03	11/24/03	12/5/03	12/5/03

San Onofre Nuclear Generating Station, Units 2 and 3

cc:

Mr. Raymond Waldo, Plant Manager  
Nuclear Generation  
Southern California Edison Company  
San Onofre Nuclear Generating Station  
P. O. Box 128  
San Clemente, CA 92674-0128

Mr. Douglas K. Porter  
Southern California Edison Company  
2244 Walnut Grove Avenue  
Rosemead, CA 91770

Mr. David Spath, Chief  
Division of Drinking Water and  
Environmental Management  
P. O. Box 942732  
Sacramento, CA 94234-7320

Chairman, Board of Supervisors  
County of San Diego  
1600 Pacific Highway, Room 335  
San Diego, CA 92101

Eileen M. Teichert, Esq.  
Supervising Deputy City Attorney  
City of Riverside  
3900 Main Street  
Riverside, CA 92522

Mr. Gary L. Nolff  
Power Projects/Contracts Manager  
Riverside Public Utilities  
2911 Adams Street  
Riverside, CA 92504

Regional Administrator, Region IV  
U.S. Nuclear Regulatory Commission  
611 Ryan Plaza Drive, Suite 400  
Arlington, TX 76011-8064

Mr. Michael Olson  
San Diego Gas & Electric Company  
P.O. Box 1831  
San Diego, CA 92112-4150

Mr. Ed Bailey, Radiation Program Director  
Radiologic Health Branch  
State Department of Health Services  
Post Office Box 942732 (MS 178)  
Sacramento, CA 94327-7320

Resident Inspector/San Onofre NPS  
c/o U.S. Nuclear Regulatory Commission  
Post Office Box 4329  
San Clemente, CA 92674

Mayor  
City of San Clemente  
100 Avenida Presidio  
San Clemente, CA 92672

Mr. Dwight E. Nunn, Vice President  
Southern California Edison Company  
San Onofre Nuclear Generating Station  
P.O. Box 128  
San Clemente, CA 92674-0128

Mr. James D. Boyd, Commissioner  
California Energy Commission  
1516 Ninth Street (MS 31)  
Sacramento, CA 95814

Mr. Joseph J. Wambold, Vice President  
Southern California Edison Company  
San Onofre Nuclear Generating Station  
P.O. Box 128  
San Clemente, CA 92674-0128

## ANALYSIS AND INSPECTION CRITERIA

### Analysis of Pressure Boundary Component

The qualification by analysis of the pressure boundary component to which the mechanical nozzle seal assembly (MNSA) is attached by threaded bolts or tie-rods should be based on the calculation of the primary and secondary membrane, bending and shear stresses calculated from a detailed 3-D finite element analysis. The finite element model should encompass the instrument or heater nozzle through-wall hole and the adjacent tapped holes, and for MNSA-2, the machined counterbore within the nozzle hole.

The qualification should include and be based on the following:

- A list of all plant unique pressure boundary design conditions and operating transients, showing operating pressure, mean wall temperature, and wall temperature gradient, for the pressure boundary component.
- Detailed calculation of the load in the highest-loaded bolts or tie-rods, resulting from preloading, maximum operating loads, including seismic loads, and accounting for non-linear loading and unloading load-deformation characteristics of the gasket and Belleville washer packs.
- Demonstration that the primary and secondary stresses resulting from the finite element analysis meet the ASME Section III NB-3200 stress intensity limits and appropriate special stress limits, under all design loading and service condition mechanical and thermal transients, including the effects on the tapped holes due to the highest bolt or tie-rod loads, and demonstration that the Class 1 fatigue analysis of the pressure boundary will not exceed the Code prescribed cumulative usage factor limit of 1.0 for the life of the plant.
- Demonstration that there is no interaction between adjacent pressure boundary regions where MNSAs are mounted.
- ASME Section III minimum wall thickness requirements at the deepest point in the counterbore should be met.
- Demonstration that the ASME Section III NB-3300 area reinforcement requirements are met.
- Reconciliation of the owner's construction code and the replacement code.

### Inservice Inspection

Identify what inservice inspection program will be implemented to ensure that the structural and leakage integrity of the MNSA will be maintained throughout the licensed life of the facility. The proposed program should include consideration of the potential for leakage from the MNSA, as well as the potential for leakage from other sources which could impact the integrity of the MNSA. The proposed program should address the type of inspections (e.g., a visual examination VT-2 with insulation removed), inspection scope, periodicity of inspections, inspection qualification, and inspection acceptance criteria.

Identify what inservice inspection program will be implemented to ensure that the structural integrity of the MNSA bolting and threaded holes in the component to which the MNSA is attached will be maintained throughout the licensed life of the facility. The proposed inspections should be designed to detect cracking of the bolting and in the threaded hole due to fatigue, stress corrosion cracking, etc. Disassembly of the MNSA in order to conduct the inspections should be considered. The proposed program should address the type of inspections, inspection scope, periodicity of inspections, inspection qualification, and inspection acceptance criteria.

Identify what inservice inspection program will be implemented to ensure that corrosion detrimental to the structural integrity of the component to which the MNSA is attached will not occur due to exposure of low alloy/carbon steel material in the bore of the penetration throughout the licensed life of the facility. The proposed program should address the type of inspections, inspection scope, periodicity of inspections, inspection qualification, and inspection acceptance criteria.