

**BASALT WASTE ISOLATION PROJECT**

**BASALT QUALITY ASSURANCE  
REQUIREMENTS DOCUMENT  
(BQARD)**

**REVISION 3  
DECEMBER 1987**


DOCUMENT MONITOR:

  
\_\_\_\_\_  
C. K. Kasch, Quality Systems Division AMC Date  
U.S. Department of Energy - Richland, WA 1/11/88

REVIEWED:

  
\_\_\_\_\_  
R. P. Saget, Quality Systems Director, AMC Date  
U.S. Department of Energy - Richland, WA 1/11/88

APPROVED:

  
\_\_\_\_\_  
J. H. Anttonen, Assistant Manager for Date  
Office of Commercial Nuclear Waste  
U.S. Department of Energy - Richland, WA 1/12/88

**BASALT QUALITY ASSURANCE REQUIREMENTS DOCUMENT**

**("BQARD")**

**- FOREWORD -**

"... Some of these projects have experienced problems in plant quality--parts of the plants were built incorrectly. Some of these projects experienced problems in the assurance of quality--the utility was unable to demonstrate whether its plant was built correctly..."

(Extracted from Chapter 1, NUREG 1055, "Improving Quality and the Assurance of Quality in the Design and Construction of Nuclear Power Plants" a.k.a, "The NRC Ford Amendment Study.")

"As used in this appendix, 'quality assurance' comprises all those planned and systematic actions necessary to provide adequate confidence that a structure, system, or component will perform satisfactorily in service. Quality assurance includes quality control, which comprises those quality assurance actions related to the physical characteristics of a material, structure, component, or system to predetermined requirements."

(Extracted from Title 10, Chapter I, Code of Federal Regulations, Part 50, Appendix B, Introduction.)

BASALT QUALITY ASSURANCE REQUIREMENTS DOCUMENT ("BQARD")  
For Site Characterization Activities  
and/or  
Design and Construction of a High Level Waste Repository

INTRODUCTION

1. PURPOSE. For items or activities "important to safety or waste isolation" (i.e., "Q-list items or activities, and certain other items/activities assigned a "Level I" designation through use of the Graded Quality Assurance (QA) Methodology), the BQARD:
  - a. Identifies and consolidates federally mandated QA programmatic requirements into a single document;
  - b. Provides guidance and consistency in interpretation of QA programmatic requirements;
  - c. Provides Basalt Waste Isolation Project (BWIP) specific QA requirements and
  - d. Provides baseline control for BWIP participant Site Characterization and/or Design/Construction QA Programs.
  
2. BQARD ORGANIZATION. Each criteria within this document is comprised of two parts. The first part of the right column, entitled "BWIP Project Implementation," provides a discussion of the intent of the criteria requirements in implementing the elements that comprise a viable system. This part of each criterion is guidance and does not contain any DOE, NQA-1, or NRC requirements. It is recognized there may be other equally acceptable methods of meeting the requirements.

The second part of each criterion begins with the 10 CFR 50 Appendix B criterion listed in the left column with the discrete QA requirements that shall apply during site characterization and construction. Under each Appendix B requirement is additional guidance provided by the Nuclear Regulatory Commission (NRC) Review Plan on how the NRC will review to the Appendix "B" requirement when applied to site characterization activities.

The column on the right side contains BWIP interpretations and implementing requirements. It frequently references NQA-1-1986 Supplements which are applicable to and not in conflict with the NRC Review Plan guidance on the left side.

Discrete QA requirements that apply to site characterization and licensable construction are included in the BQARD. It is anticipated that participants performing construction work "Important to Safety or Waste Isolation" will have (or be required to comply with codes that require) NRC acceptable QA Programs (for example, NCA 4000 of the B&PV codes, section III). To amplify further, if a participant already has "N stamp" authority, the construction BQARD should cause minor, if any, changes to that QA Program.

3. BQARD SOURCE DOCUMENTS. The QA requirements included within the BQARD are from several documents:
  - a. 10 CFR 60
  - b. 10 CFR 50, Appendix B
  - c. NRC Review Plan: QA Programs for Site Characterization of High Level Nuclear Waste Repositories, dated June 1984
  - d. QA Management Policies and Requirements, OCRWM, October 1985 (DOE/RW/0032)
  - e. QA Plan for High-Level Radioactive Waste Repositories, OGR/B-3, Rev. 1, August 1986 and Supplements
  - f. DOE Order 5700.6B, "Quality Assurance" and DOE-RL Order 5700.1A, "Quality Assurance"
  - g. DOE Order 4700.1, "Project Management System"
  - h. ANSI/ASME NQA-1 1986
  - i. Federal Acquisition Regulation (FAR) Part 46, "Quality Assurance"
  - j. DOE Order 5000.3, Unusual Occurrence Reporting System.
4. UTILIZATION OF NQA-1 WITHIN THE BQARD. QA Programs that meet the requirements of 10 CFR 50, Appendix B will meet all of the 18 Basic Requirements of NQA-1. Therefore, the BQARD (for Level I site characterization activities) utilizes 10 CFR 50 Appendix B, the 18 NQA-1 Basic Requirements, the NQA-1 supplements, and the NRC Review Plan, to define QA Program requirements. Further, certain NQA-1 appendices identified as nonmandatory in the source document are included verbatim (except for title) as requirements in the BQARD, in order to preclude misunderstandings.

5. **ADDITIONAL GUIDANCE** Participants should note that the NRC is providing additional guidance in several areas directly affecting site characterization QA activities. The additional NRC guidance is in the areas of:
- a. Qualification of previously acquired data
  - b. Peer reviews
  - c. The Q-list

There are also a number of supplements to the Office of Geologic Repository (OGR) QA Plan that have been incorporated by reference within the appropriate criterion where other requirements did not provide this information.

6. **REVISION STATUS OF BQARD.** Revisions to the BQARD will be made by individual page revision. Each page will have a page number and revision number. The Table of Contents will identify individual pages by title or criterion number, indicating page number, revision number, and issue date.

CONTENTS

	<u>Page Number</u>	<u>Revision Number</u>	<u>Issue Date</u>
Abstract	1	3	Mar 1987
	2	3	Mar 1987
	3	3	Mar 1987
DOE-RL Approval	1	3	Mar 1987
Foreword	1	0	Feb 1986
Introduction	1	3	Dec 1987
	2	3	Dec 1987
	3	3	Dec 1987
Contents	1	3	Mar 1987
	2	3	Mar 1987
	3	3	Mar 1987
Criterion 1.0 Organization	1	0	Feb 1986
	2	2	Mar 1987
	3	2	Mar 1987
	4	2	Mar 1987
	5	2	Mar 1987
	6	2	Mar 1987
	7	2	Mar 1987
	8	2	Mar 1987
	9	2	Mar 1987
	10	2	Mar 1987
	11	2	Mar 1987
	12	2	Mar 1987
	13	2	Mar 1987
Criterion 2.0 Quality Assurance	1	1	Nov 1986
	2	0	Feb 1986
	3	2	Mar 1987
	4	2	Mar 1987
	5	2	Mar 1987
	6	2	Mar 1987
	7	2	Mar 1987
	8	2	Mar 1987
	9	2	Mar 1987
	10	2	Mar 1987
	11	0	Feb 1986
	12	0	Feb 1986
	13	1	Mar 1987
	14	1	Mar 1987
	15	1	Mar 1987
	16	1	Mar 1987
17	2	Mar 1987	
18	3	Mar 1987	
19	1	Mar 1987	

		<u>Page Number</u>	<u>Revision Number</u>	<u>Issue Date</u>	
Criterion 3.0	Design Control	1	0	Feb 1986	
		2	3	Dec 1987	x
		3	2	Mar 1987	
		4	2	Mar 1987	
		5	2	Mar 1987	
		6	2	Mar 1987	
		7	2	Mar 1987	
		8	3	Dec 1987	
		9	3	Dec 1987	x
		10	2	Mar 1987	
		11	3	Dec 1987	x
		12	2	Mar 1987	
Criterion 4.0	Procurement Document Control	1	1	Mar 1987	
		2	2	Mar 1987	
		3	2	Mar 1987	
		4	2	Mar 1987	
Criterion 5.0	Instructions, Procedures, and Drawings	1	2	Mar 1987	
		2	2	Mar 1987	
		3	2	Mar 1987	
Criterion 6.0	Document Control	1	2	Mar 1987	
		2	2	Mar 1987	
		3	2	Mar 1987	
		4	2	Mar 1987	
Criterion 7.0	Control of Purchase Material, Equipment, and Services	1	2	Mar 1987	
		2	2	Mar 1987	
		3	2	Mar 1987	
		4	3	Mar 1987	
		5	2	Mar 1987	
		6	2	Mar 1987	
		7	1	Mar 1987	
Criterion 8.0	Identification and Control of Materials, Parts, and Components	1	2	Mar 1987	
		2	3	Mar 1987	
		3	2	Mar 1987	
		4	2	Mar 1987	
Criterion 9.0	Control of Special Processes	1	2	Mar 1987	
		2	2	Mar 1987	
		3	2	Mar 1987	
Criterion 10.0	Inspection	1	2	Mar 1987	
		2	3	Mar 1987	x
		3	3	Mar 1987	
		4	3	Dec 1987	
		5	3	Dec 1987	x
		6	2	Mar 1987	
		7	2	Mar 1987	
		8	2	Mar 1987	
		9	2	Mar 1987	

	<u>Page Number</u>	<u>Revision Number</u>	<u>Issue Date</u>	
Criterion 11.0 Test Control	1	1	Feb 1986	ix
	2	2	Mar 1987	i
	3	3	Dec 1987	ix
	4	2	Mar 1987	
	5	2	Mar 1987	
	6	2	Mar 1987	
	7	2	Mar 1987	
	8	2	Mar 1987	
Criterion 12.0 Control of Measuring and Test Equipment	1	2	Mar 1987	
	2	3	Mar 1987	
	3	2	Mar 1987	
	4	2	Mar 1987	
Criterion 13.0 Handling, Shipping, and Storage	1	2	Mar 1987	
	2	3	Dec 1987	ix
	3	2	Mar 1987	
Criterion 14.0 Inspection, Test, and Operating Status	1	2	Mar 1987	
	2	2	Mar 1987	
	3	3	Dec 1987	ix
	4	3	Mar 1987	
Criterion 15.0 Nonconforming Materials, Parts, or Components	1	2	Mar 1987	
	2	2	Mar 1987	
	3	3	Mar 1987	ix
	4	2	Mar 1987	
Criterion 16.0 Corrective Action	1	2	Mar 1987	
	2	2	Mar 1987	
	3	2	Mar 1987	
	4	2	Mar 1987	
Criterion 17.0 Quality Assurance Records	1	2	Mar 1987	
	2	2	Mar 1987	
	3	2	Mar 1987	
	4	2	Mar 1987	
	5	2	Mar 1987	
	6	2	Mar 1987	
	7	3	Mar 1987	
Criterion 18.0 Audits	1	2	Mar 1987	
	2	2	Mar 1987	
	3	2	Mar 1987	
	4	2	Mar 1987	
	5	2	Mar 1987	
	6	3	Mar 1987	
	7	3	Mar 1987	ix

BQARD  
CRITERION 1: ORGANIZATION  
REVISION 0 (sheet 1 of 13)

Requirement	BWIP Project Implementation
	<p data-bbox="1391 310 1732 343" style="text-align: center;"><b>Site Characterization</b></p> <p data-bbox="1093 370 2030 783">The intent of this criterion during site characterization is to establish requirements for critical areas of each participant contractor's organization in order to ensure that project activities are accomplished within a defined and controlled organizational structure. The criterion requires a defined organizational structure that delineates (a) overall responsibilities, (b) delegation of work, (c) evaluation of performance, (d) management controls and effective lines of communication, (e) interfaces, (f) management positions and responsibilities for each organizational element, (g) quality assurance personnel independence, (h) policies, (i) verification of performance, and (j) access to management.</p> <p data-bbox="1272 816 1859 849" style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p data-bbox="1093 875 2008 1229">It is expected that potentially licenseable construction will be performed coincident with BWIP site characterization activities. Those participants who will perform both construction and site characterization work shall establish a project organization meeting Site Characterization Criterion 1. Construction only participants performing level I construction work shall, to the extent practical, establish a project organization that conforms to the requirements of Site Characterization Criterion 1. Deviations, and the alternate method of providing equivalent control, will be documented.</p> <p data-bbox="1093 1262 2008 1394">NOTE: "Contractor" as used in this BQARD refers to all contractors, subcontractors, vendors, consultants, agents or agencies, and institutions performing work covered by the quality assurance program.</p>

BOARD  
CRITERION 1: ORGANIZATION - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 2 of 13)

Requirement	BWIP Project Implementation
<p data-bbox="87 310 1051 355"><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="87 371 1051 446">The applicant shall be responsible for the establishment and execution of the quality assurance program.</p> <p data-bbox="87 528 1051 569"><b>NRC REVIEW PLAN SECTION 1.1</b></p> <p data-bbox="87 594 1051 850">The responsibility for the overall program is retained and exercised by the DOE at a level which is commensurate with the level of the DOE official who will submit the license application. While the line organization is responsible for performing quality affecting activities properly, the QA organization shall verify the proper performance of work through implementation of appropriate QA controls.</p>	<p data-bbox="1051 379 2038 421">This requirement shall be implemented as stated.</p> <p data-bbox="1051 446 2038 512">For site characterization, additional guidance has been provided in Section 1.1 of the NRC Review Plan.</p> <p data-bbox="1051 602 2038 702">This requirement shall be implemented as stated. In addition, Supplement 1S-1, Section 2.1 of NQA-1-1986 shall be implemented.</p>

BQARD  
**CRITERION 1: ORGANIZATION - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 3 of 13)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 2: 10 CFR 50 APPENDIX B</b></p> <p>The applicant may delegate to others, such as contractors, agents, or consultants, the work of establishing and executing the quality assurance program, or any part thereof, but shall retain responsibility therefor.</p> <p><b>NRC REVIEW PLAN SECTION 1.2</b></p> <p>DOE describes major delegation of work involved in establishing and implementing the QA program or any part thereof to other organizations.</p> <p><b>NRC REVIEW PLAN SECTION 1.3</b></p> <p>DOE describes how responsibility is exercised for the overall QA program. The extent of management responsibility and authority from DOE headquarters and from the field office should be addressed.</p> <p><b>NRC REVIEW PLAN SECTION 1.4</b></p> <p>DOE evaluates the performance of work delegated to other organizations. This shall include audits of the prime contractor's QA program and audits of representative subcontractors, consultants, vendors, and laboratories furnishing equipment or services to the prime contractor or DOE. The frequency and method of evaluation should be specified.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Section 1.2 through 1.6 of the NRC Review Plan.</p> <p>This requirement shall be implemented as stated. In addition, Supplement 1S-1, Section 2.2 of NQA-1-1986 shall be implemented.</p> <p>This requirement shall be implemented as stated. In addition, Supplement 1S-1, Section 3 of NQA-1-1986 shall be implemented.</p> <p>This requirement shall be implemented as stated. In addition, Supplement 1S-1, Section 2 of NQA-1-1986 shall be implemented.</p>

BQARD  
CRITERION 1: ORGANIZATION - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 4 of 13)

Requirement	BWIP Project Implementation
<p><b>NRC REVIEW PLAN SECTION 1.5</b></p> <p>Qualified individual(s) or organization element(s) are identified within DOE's organization as responsible for the quality of the delegated work prior to initiation of activities.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>
<p><b>NRC REVIEW PLAN SECTION 1.6</b></p> <p>Clear management controls and effective lines of communication exist for QA activities between DOE and its contractors, to assure direction of the QA program.</p>	<p>This requirement shall be implemented as stated. In addition, Supplement 1S-1, Section 3 of NQA-1-1986 shall be implemented.</p>

BQARD  
**CRITERION 1: ORGANIZATION - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 5 of 13)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 3: 10 CFR 50 APPENDIX B</b></p> <p>The authority and duties of persons and organizations performing activities affecting the safety-related functions of structures, systems, and components shall be clearly established and delineated in writing.</p> <p><b>NRC REVIEW PLAN SECTION 1.7</b></p> <p>Organization charts clearly identify all the "onsite" and "offsite" organizational elements which function under the cognizance of the QA program and the lines of responsibility.</p> <p><b>NRC REVIEW PLAN SECTION 1.9</b></p> <p>DOE and its prime contractor describe the QA responsibilities of each of the organizational elements noted on the organization charts.</p> <p><b>NRC REVIEW PLAN SECTION 1.10</b></p> <p>DOE and its prime contractor identify a management position within each respective organization that retains overall authority and responsibility for the QA program. This position, occupied by an individual with appropriate management and QA knowledge and experience has the following characteristics:</p> <p>a. Is at the same or higher organizational level as the highest line manager directly responsible for performing activities affecting quality (such as design, engineering, site investigations, procurement, manufacturing, etc.) and is sufficiently independent from cost and schedule.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Sections 1.7, 1.9, 1.10, and 1.15 of the NRC Review Plan.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p>This requirement shall be implemented as stated. In addition, Supplement 1S-1, Section 3 of NQA-1-1986 shall be implemented.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>

BQARD  
CRITERION 1: ORGANIZATION - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 6 of 13)

Requirement	BWIP Project Implementation
<p>b. Has effective communication channels with other senior management positions.</p> <p>c. Has responsibility for approval of QA manual(s), changes thereto, and interpretations thereof.</p> <p>d. Has no other duties or responsibilities unrelated to QA that would prevent full attention to QA matters.</p> <p>NRC REVIEW PLAN SECTION 1.15</p> <p>The persons responsible for directing and managing the overall QA program are identified and have appropriate organizational position, responsibilities, and authority to exercise proper control over the QA program. These individuals are free from non-QA duties and can thus give full attention to assuring that the QA program is being effectively implemented.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>

BQARD  
CRITERION 1: ORGANIZATION - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 7 of 13)

Requirement	BWIP Project Implementation
<p data-bbox="97 323 687 360">REQUIREMENT 4: 10 CFR 50 APPENDIX B</p> <p data-bbox="97 389 1023 480">These activities include both the performing functions of attaining quality objectives and the quality assurance functions.</p> <p data-bbox="97 550 540 586">NRC REVIEW PLAN SECTION 1.8</p> <p data-bbox="97 616 987 844">The QA organization is involved in the aspects of the high-level waste repository program that affect safety and waste isolation. The extent of QA controls is determined by the QA staff in combination with the line staff and is dependent upon the specific activity, its complexity, and its importance to safety or waste isolation as defined in 10 CFR Part 60.2.</p>	<p data-bbox="1070 398 1842 434">This requirement shall be implemented as stated.</p> <p data-bbox="1070 464 1959 526">For site characterization, additional guidance has been provided in Section 1.8 of the NRC Review Plan.</p> <p data-bbox="1070 621 1974 783">This requirement shall be implemented as stated. In addition, Supplement 1S-1, Section 2 of NQA-1-1986 shall be implemented. The requirements and methodology for formulating a Q-List and application of Graded QA are delineated in OGR/B-3, Supplements 3 and 8.</p>



BQARD  
**CRITERION 1: ORGANIZATION - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 9 of 13)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 6: 10 CFR 50 APPENDIX B</b></p> <p>The persons and organizations performing quality assurance functions shall have sufficient authority and organizational freedom to identify quality problems; to initiate, recommend, or provide solutions; and to verify implementation of solutions.</p> <p><b>NRC REVIEW PLAN SECTION 1.12</b></p> <p>Persons and organizations performing QA functions have direct access to management levels which will assure the ability to:</p> <ul style="list-style-type: none"> <li>a. Identify quality problems.</li> <li>b. Initiate, recommend, or provide solutions through designated channels.</li> <li>c. Verify implementation of solutions.</li> <li>d. Stop unsatisfactory work.</li> </ul> <p>The persons and organizations with the above authority are identified and a description of how those actions are carried out is provided.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Section 1.12, 1.13, and 1.14 of the NRC Review Plan.</p> <p>This requirement shall be implemented as stated. In addition, this requirement is also addressed in NQA-1-1986, Basic Requirement 1.</p>
<p><b>NRC REVIEW PLAN SECTION 1.13</b></p> <p>Provisions are established for the resolution of disputes involving quality arising from a difference of opinion between QA personnel and other department personnel.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>

BOARD  
CRITERION 1: ORGANIZATION - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 10 of 13)

Requirement	BWIP Project Implementation
<p data-bbox="102 299 563 338">NRC REVIEW PLAN SECTION 1.14</p> <p data-bbox="102 365 995 437">Policies regarding the implementation of the QA program are documented and made mandatory.</p>	<p data-bbox="1074 376 1868 470">This requirement is not specifically addressed in HQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>

BOARD  
CRITERION 1: ORGANIZATION - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 11 of 13)

Requirement	BWIP Project Implementation
<p data-bbox="108 307 697 340"><b>REQUIREMENT 7: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="108 370 1017 558">Such persons and organizations performing quality assurance functions shall report to a management level such that this required authority and organizational freedom, including sufficient independence from cost and schedule when opposed to safety considerations, are provided.</p>	<p data-bbox="1087 376 1853 409">This requirement shall be implemented as stated.</p> <p data-bbox="1087 439 2017 598">For site characterization, additional guidance has been provided in Section 1.15 of the NRC Review Plan (see sheet 6 of this criterion). In addition, this requirement shall be implemented in accordance with NQA-1-1986, Basic Requirement 1.</p>

BQARD  
CRITERION 1: ORGANIZATION - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 12 of 13)

Requirement	BWIP Project Implementation
<p>REQUIREMENT 8: 10 CFR 50 APPENDIX B</p> <p>Because of the many variables involved, such as the number of personnel, the type of activity being performed, and the location or locations where activities are performed, the organizational structure for executing the quality assurance program may take various forms provided that the person and organizations assigned the quality assurance functions have this required authority and organizational freedom.</p>	<p>This requirement shall be implemented as stated. In addition, Supplement 1S-1, Section 3 of NQA-1-1986 shall be implemented.</p>

BQARD  
CRITERION 1: ORGANIZATION - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 13 of 13)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 9: 10 CFR 50 APPENDIX B</b></p> <p>Irrespective of the organizational structure, the individual(s) assigned the responsibility for assuring effective execution of any portion of the quality assurance program at any location where activities subject to this Appendix are being performed shall have direct access to such levels of management as may be necessary to perform this function.</p>	<p>This requirement shall be implemented as stated. In addition, Supplement 1S-1, Section 3 of NQA-1-1986 shall be implemented.</p>

BOARD  
CRITERION 2: QUALITY ASSURANCE PROGRAM  
REVISION 1 (sheet 1 of 19)

Requirement	BWIP Project Implementation
	<p style="text-align: center;">Site Characterization</p> <p>The intent of this criterion during site characterization is to require DOE-RL (BWIP Division) to establish a comprehensive quality assurance program that controls both the design and construction of all items and activities important to safety or waste isolation, in order to ensure the adequacy of the completed repository facility. Consequently, each BWIP participant shall establish a complementary quality assurance program, consistent with its assigned scope of work. All quality assurance programs established shall meet the programmatic requirements identified within this criterion, along with the additional requirements included within the remaining seventeen (17) criteria of 10 CFR 50, Appendix B. Note that the NRC Review Plan, as incorporated herein, provides an acceptable means of meeting many of the Appendix B programmatic requirements.</p> <p>In addition, NQA-1-1986 also provides an acceptable means of meeting Appendix B programmatic requirements, provided NQA-1 is applicable to the site characterization activity being considered and is not in conflict with NRC Review Plan guidance.</p> <p>The NRC makes a distinction between (1) administrative QA procedures and (2) detailed technical or implementing procedures. Quality assurance administrative procedures provide instructions for implementation and application of the 18 criteria of 10 CFR Part 50 Appendix B. These apply to all technical program areas (e.g., procedures for test plan development). The detailed technical</p>

BOARD  
CRITERION 2: QUALITY ASSURANCE PROGRAM  
REVISION 0 (sheet 2 of 19)

Requirement	BWIP Project Implementation
	<p>(implementing) procedures are developed by technically qualified personnel in accordance with the requirements specified in the administrative quality assurance procedures. These contain instructions for actual performance of testing and investigations (e.g., hydrologic pump tests, setting a packer).</p> <p>In order to meet the stated requirements, the QA and technical organizations shall define the QA controls to be applied to specific items and activities using a defined, graded approach in accordance with importance to safety or waste isolation as defined in 10 CFR Part 60.2. Implementing procedures shall be prepared, controlled, and mandated through a policy statement signed by management. Management shall be required to assess the adequacy of the QA program through frequent contact with the program and a documented annual performance assessment.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>It is expected that potentially licenseable construction will be performed coincident with BWIP site characterization activities. Those participants who will perform both construction and site characterization work shall establish a project QA program meeting Site Characterization Criterion 2. Construction only participants performing level I construction work shall, to the extent practical, establish a project QA Program that conforms to the requirements of Site Characterization Criterion 2. Deviations and the alternate method of providing equivalent control, will be documented.</p>

BQARD  
**CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 3 of 19)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p>The applicant shall establish at the earliest practicable time, consistent with the schedule for accomplishing the activities, a quality assurance program which complies with the requirements of this appendix.</p> <p><b>NRC REVIEW PLAN SECTION 2.5</b></p> <p>The QA organization and the necessary technical organizations participate early in the QA program definition stage to determine and identify the extent QA controls are to be applied to specific items and activities. This effort involves applying a defined graded approach in accordance with importance to safety or waste isolation as defined in 10 CFR Part 60.2 and affects such disciplines as design, data analysis (such as performance assessment), procurement, document control, inspections, tests, special processes, records, audits, and others described in 10 CFR Part 50, Appendix B.</p> <p><b>NRC REVIEW PLAN SECTION 2.6</b></p> <p>Existing or proposed QA procedures and detailed technical procedures are identified and documented reflecting that each criterion of 10 CFR Part 50, Appendix B, appropriate to specific items and activities, will be met.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Section 2.5 and 2.6 of the NRC Review Plan.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p>The methodology for formulating a Q-List and the application of a Graded QA Program and the requirements imposed by Headquarters-OGR are as delineated in the Quality Assurance Plan for High-Level Radioactive Waste Repositories (OGR/B-3), Supplements 3 and 8.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>

BOARD  
CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 4 of 19)

Requirement	BWIP Project Implementation
<p data-bbox="102 310 691 348"><b>REQUIREMENT 2: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="102 373 1006 508">This program shall be documented by written policies, procedures, or instructions and shall be carried out throughout plant life in accordance with those policies, procedures, or instructions.</p> <p data-bbox="102 533 542 571"><b>NRC REVIEW PLAN SECTION 2.3</b></p> <p data-bbox="102 596 1006 797">Provisions are established to assure that technical and quality assurance procedures required to implement the QA program are consistent with QA program requirements and are properly documented, controlled, and mandated through a policy statement or equivalent document signed by a responsible official.</p> <p data-bbox="102 822 542 860"><b>NRC REVIEW PLAN SECTION 2.4</b></p> <p data-bbox="102 885 953 984">The QA organization reviews and documents concurrence with the quality-related procedures relative to QA requirements.</p> <p data-bbox="102 1009 921 1108">The term "quality-related" refers to the quality of items "important to safety" or "important to waste isolation."</p>	<p data-bbox="1074 381 1847 419">This requirement shall be implemented as stated.</p> <p data-bbox="1074 444 1964 515">For site characterization, additional guidance has been provided in Section 2.3 and 2.4 of the NRC Review Plan.</p> <p data-bbox="1074 604 1868 703">This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p data-bbox="1074 893 1868 992">This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>

BOARD  
**CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 5 of 19)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 3: 10 CFR 50 APPENDIX B</b></p> <p>The applicant shall identify the structures, systems, and components to be covered by the quality assurance program and the major organizations participating in the program, together with the designated functions of these organizations.</p> <p><b>NRC REVIEW PLAN SECTION 2.1</b></p> <p>The QA program includes all items and activities important to safety and waste isolation as defined in 10 CFR Part 60.2. The items and activities covered by the QA program are identified and the rationale provided for determining how items or activities are important to safety or waste isolation, as defined in 10 CFR Part 60.2. These terms are defined as numerical performance objectives and standards. The rationale should include systems analyses that are used to determine what specific items and activities are covered.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Section 2.1 of the NRC Review Plan.</p> <p>This requirement is not specifically addressed in HQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p>The methodology for formulating a Q-List is imposed by Headquarters-OGR as delineated in the QA Plan for High-Level Radioactive Waste Repositories (OGR/B-3), Supplement 3.</p>

BQARD  
CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 6 of 19)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 4: 10 CFR 50 APPENDIX B</b></p> <p>The quality assurance program shall provide control over activities affecting the quality of the identified structures, systems, and components, to an extent consistent with their importance to safety.</p> <p><b>NRC REVIEW PLAN SECTION 2.2</b></p> <p>The QA program includes a commitment that all development, control, and/or use of computer programs will be conducted in accordance with the QA program. Guidance for the content of documentation of computer codes is provided by NUREG-0856, "Final Technical Position on Documentation of Computer Codes for High-Level Waste Management."</p>	<p>The requirements and methodology for formulating a Q-List and application of Graded QA are contained in the Headquarters-OGR QA Plan for High-Level Radioactive Waste Repositories (OGR/B-3), Supplements 3 and 8.</p> <p>For site characterization, additional guidance has been provided in Section 2.2 of the NRC Review Plan.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated. (This is incorporated in Criterion 3 controls.)</p>

BOARD  
CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 7 of 19)

Requirement	BWIP Project Implementation
<p data-bbox="114 307 704 348">REQUIREMENT 5: 10 CFR 50 APPENDIX B</p> <p data-bbox="114 370 1023 442">Activities affecting quality shall be accomplished under suitably controlled conditions.</p>	<p data-bbox="1087 381 1996 447">This requirement shall be implemented in accordance with HQA-1-1986, Basic Requirement 2.</p>

BQARD  
CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 8 of 19)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 6: 10 CFR 50 APPENDIX B</b></p> <p>Controlled conditions include the use of appropriate equipment; suitable environmental conditions for accomplishing the activity, such as adequate cleanness; and assurance that all prerequisites for the given activity have been satisfied.</p>	<p>This requirement shall be implemented in accordance with NQA-1-1986, Basic Requirement 2.</p>

BQARD  
CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 9 of 19)

Requirement	BWIP Project Implementation
<p data-bbox="95 305 691 338"><b>REQUIREMENT 7: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="95 371 989 503">The program shall take into account the need for special controls, processes, test equipment, tools, and skills to attain the required quality, and the need for verification of quality by inspection and test.</p>	<p data-bbox="1074 371 1979 437">This requirement shall be implemented in accordance with NQA-1-1986, Basic Requirement 2.</p>

BQARD  
**CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION**  
 REVISION 2 (sheet 10 of 19)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 8: 10 CFR 50 APPENDIX B</b></p> <p>The program shall provide for indoctrination and training of personnel performing activities affecting quality as necessary to assure that suitable proficiency is achieved and maintained.</p> <p><b>NRC REVIEW PLAN SECTION 2.8</b></p> <p>Indoctrination, training, and qualification in programs are established such that:</p> <ol style="list-style-type: none"> <li>a. Personnel responsible for performing quality-related activities are instructed as to the purpose, scope, and implementation of the quality-related manuals, instructions and procedures.</li> <li>b. Personnel verifying activities affecting quality are qualified in the principles, techniques, and requirements of the activity being performed.</li> <li>c. For formal training and qualification programs, documentation includes the objective, content of the program, attendees, and date of attendance.</li> <li>d. Appropriate management monitors the performance of individuals involved in activities affecting quality and determines the need for retraining and/or replacement. A system of annual appraisal and evaluation can satisfy this criterion.</li> <li>e. Qualified personnel are certified in accordance with applicable codes and standards.</li> </ol>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Section 2.8 of the NRC Review Plan.</p> <ol style="list-style-type: none"> <li>1. NQA-1-1986 addresses personnel <u>performing</u> quality-related activities in Basic Requirement 2 and Supplement 2S-4. This requirement shall be met by implementing the requirements of 2.8a, c, d, and when applicable, e, in cases such as welder certification, etc., as stated. Additional requirements are specified in OGR/B-3, Supplement 1, Section 5.0.</li> <li>2. For personnel <u>verifying</u> quality-related activities, Requirements a, b, c, d, and e shall be implemented. NQA-1-1986 provides supplemental guidance as follows:                     <ul style="list-style-type: none"> <li>Design Reviewers - Supplement 3S-1, Section 4</li> <li>Inspectors - Supplements 2S-1 and/or 2S-2</li> <li>Auditors - Supplement 2S-3</li> <li>Indoctrination and Training - Supplement 2S-4.</li> </ul> <p>Note that the Review Plan Criterion 3.8 provides qualification standards for peer reviewers.</p> <p>In addition, the prospective lead auditor shall have verifiable evidence that a minimum of 10 credits under the following score system have been accumulated (DOE-RL).</p> <ol style="list-style-type: none"> <li>1. <u>Education (4 Credits Maximum)</u> <ul style="list-style-type: none"> <li>Associate degree from an accredited institution: score one (1) credit, or if the degree is in</li> </ul> </li> </ol> </li> </ol>

**BQARD**  
**CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION**  
**REVISION 0 (sheet 11 of 19)**

Requirement	BWIP Project Implementation
	<p>engineering, physical sciences, mathematics, or quality assurance, score two (2) credits; or a bachelor's degree from an accredited institution: score two (2) credits, or if the degree is in engineering, physical sciences, mathematics, or quality assurance, score three (3) credits; in addition, score one (1) credit for a master's degree in engineering, physical sciences, business management, or quality assurance from an accredited institution.</p> <p><b>2. <u>Experience (9 Credits Maximum)</u></b></p> <p>Technical experience in engineering, manufacturing, construction, operation, or maintenance: score one (1) credit for each full year, with a maximum of five (5) credits for this aspect of experience.</p> <p>If two (2) years of this experience have been in the nuclear field, score one (1) additional credit; or</p> <p>If two (2) years of this experience have been in quality assurance, score two (2) additional credits; or</p> <p>If two (2) years of this experience have been in auditing, score three (3) additional credits; or</p> <p>If two (2) years of this experience have been in nuclear quality assurance, score three (3) additional credits; or</p> <p>If two (2) years of this experience have been in nuclear quality assurance auditing, score four (4) additional credits.</p>

BOARD  
**CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION**  
 REVISION 0 (sheet 12 of 19)

Requirement	BWIP Project Implementation
	<p>3. <u>Other Credentials of Professional Competence</u>  <u>(2 Credits Maximum)</u></p> <p>For certification of competency in engineering, science, or quality assurance specialties issued and approved by a State Agency or National Professional or Technical Society: score two (2) credits.</p> <p>4. <u>Rights of Management (2 Credits Maximum)</u></p> <p>The lead auditor's employer may grant up to two (2) credits for other performance factors applicable to auditing that may not be explicitly called out in this appendix. Examples of these factors are leadership, sound judgment, maturity, analytical ability, tenacity, past performance, and quality assurance training courses.</p> <p>The sample form shown in NQA-1 may be utilized as a record of lead auditor qualification.</p> <p>In addition, the following requirements on the qualifications of inspection and test (verification) personnel are made mandatory (DOE-RL):</p> <p>NOTE: NQA-1 uses "Test and Inspection personnel" in the context of verifiers of previously completed work. For site characterization, test personnel actually perform the site characterization tests (refer to Criterion XI), not verify them, and thus are not required to meet these specific qualifications. However, personnel assigned to the testing organization and designated by the testing supervisor to be an "in-process inspector," shall have the qualifications identified herein (as well as other required qualifications, see Review Plan 2.8(b) that are consistent with the in-process inspection tasks assigned.</p>

BQARD  
**CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION**  
 REVISION 1 (sheet 13 of 19)

Requirement	BWIP Project Implementation
	<p>"In-process inspectors" shall have no direct responsibility in performing the work being inspected/verified. The inspection function may be part of the line organization provided the QA organization performs periodic surveillance to verify sufficient independence from the individuals who performed the activity.</p> <p><b>1. FUNCTIONAL QUALIFICATIONS</b></p> <p>Three levels of qualification shall be utilized depending on the complexity of the functions involved. The recommendations for each level are not limiting with regard to organizational position or professional status but, rather, are limiting with regard to functional activities.</p> <p><b>1.1 Level I Personnel Capabilities</b></p> <p>A Level I person shall be capable of performing and documenting the results of inspections or tests that are required to be performed in accordance with documented procedures, acceptance standards, and/or industry practices as defined in user's written procedures.</p> <p><b>1.2 Level II Personnel Capabilities</b></p> <p>A Level II person shall have all of the capabilities of a Level I person for the inspection or test category or class in question. Additionally, a Level II person shall have demonstrated capabilities in planning inspections and tests; in setting up tests, including preparation and setup of related equipment, as appropriate; in supervising or maintaining surveillance over the inspections and tests; in supervising and certifying lower level</p>

BQARD  
**CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION**  
 REVISION 1 (sheet 14 of 19)

Requirement	BWIP Project Implementation
	<p>personnel; and in evaluating the validity and acceptability of inspection and test results.</p> <p><b>1.3 Level III Personnel Capabilities</b></p> <p>A Level III person shall have all of the capabilities of a Level II person for the inspection or test category or class in question. In addition, the individual shall also be capable of evaluating the adequacy of specific programs used to train and certify inspection and test personnel whose qualifications are covered in this requirement. In addition a Level III person shall review and approve inspection and test procedures, evaluating the adequacy of such procedures to accomplish test and inspection objectives.</p> <p><b>2. EDUCATION AND EXPERIENCE QUALIFICATIONS</b></p> <p>These education and experience recommendations shall be considered with recognition that other factors commensurate with the scope, complexity, or special nature of the activity may provide reasonable assurance that a person can competently perform a particular task. Other factors that may demonstrate capability in a given job are previous performance or satisfactory completion of capability testing. These factors and the basis for their equivalency shall be documented.</p> <p><b>2.1 Level I</b></p> <p><b>2.1.1</b> Two years of related experience in equivalent inspection or testing activities; or</p>

BOARD  
**CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION**  
 REVISION 1 (sheet 15 of 19)

Requirement	BWIP Project Implementation
	<p>2.1.2 High school graduation and six months of related experience in equivalent inspection or testing activities; or</p> <p>2.1.3 Completion of college level work leading to an associate degree in a related discipline plus three months of related experience in equivalent inspection or testing activities.</p> <p>2.2 Level II</p> <p>2.2.1 One year of satisfactory performance as a Level I in the corresponding inspection or test category or class; or</p> <p>2.2.2 High school graduation plus three years of related experience in equivalent inspection or testing activities; or</p> <p>2.2.3 Completion of college level work leading to an associate degree in a related discipline plus one year of related experience in equivalent inspection or testing activities; or</p> <p>2.2.4 Graduation from a four-year college plus six months of related experience in equivalent inspection or testing activities.</p> <p>2.3 Level III</p> <p>2.3.1 Six years of satisfactory performance as a Level II in the corresponding inspection or test category or class; or</p> <p>2.3.2 High school graduation plus ten years of related experience in equivalent inspection or testing activities; or high school graduation plus</p>

BOARD  
CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION  
REVISION 1 (sheet 16 of 19)

Requirement	BWIP Project Implementation
	<p>eight years of experience in equivalent inspection or testing activities with at least two years as Level II and with at least two years associated with nuclear facilities--or, if not, at least sufficient training to be acquainted with the relevant quality assurance aspects of a nuclear facility; or</p> <p>2.3.3 Completion of college level work leading to an associate degree and seven years of related experience in equivalent inspection or testing activities, with at least two years of this experience associated with nuclear facilities or, if not, at least sufficient training to be acquainted with the relevant quality assurance aspects of a nuclear facility; or</p> <p>2.3.4 Graduation from a four-year college plus five years of related experience in equivalent inspection or testing activities, with at least two years of this experience associated with nuclear facilities--or, if not, at least sufficient training to be acquainted with the relevant quality assurance aspects of a nuclear facility.</p>

**BQARD**  
**CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 17 of 19)**

Requirement	BWIP. Project Implementation
<p><b>REQUIREMENT 9: 10 CFR 50 APPENDIX B</b></p> <p>The applicant shall regularly review the status and adequacy of the quality assurance program.</p>	<p>This requirement shall be met by implementing all the requirements of NRC Review Plan Section 1.4 as addressed in Criterion 1, Requirement 2 of the BQARD and Requirement 10 of this criterion of the BQARD.</p> <p>In addition, management assessments of the QA program shall be implemented as specified in OGR/B-3, QA Plan, Section 4.4.</p>

BQARD  
**CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION**  
**REVISION 3 (sheet 18 of 19)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 10: 10 CFR 50 APPENDIX B</b></p> <p>Management of other organizations participating in the quality assurance program shall regularly review the status and adequacy of that part of the quality assurance program which they are executing.</p> <p><b>NRC REVIEW PLAN SECTION 2.7</b></p> <p>A description is provided of how management (above or outside the QA organization) regularly assesses the scope, status, adequacy, and compliance of the QA program to 10 CFR Part 50, Appendix B. These measures should include:</p> <ul style="list-style-type: none"> <li>a. Frequent contact with program status through reports, meetings, and/or audits.</li> <li>b. Performance of an annual assessment which is preplanned and documented with corrective action identified and tracked.</li> </ul>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Section 2.7 of the NRC Review Plan.</p> <p>Additional requirements for the overview of QA activities are specified in OGR/B-3, Supplement 2.</p> <p>This requirement is addressed in NQA-1-1986, Basic Requirement 2. Therefore, this requirement shall be implemented as stated.</p> <p>Also refer to Criterion 15, Requirement 2 and Criterion 16, Requirement 1.</p> <p>In addition, participants shall submit audit schedules, schedule revisions, and audit reports to the integrating contractor (HQ-OGR).</p> <p>Management assessments shall be conducted at least annually for determining (a) the effectiveness of the system of management controls that are established to achieve and ensure quality and (b) the adequacy of resources and personnel provided to the QA program. Management shall verify that the QA program is being effectively implemented and that personnel are trained to the QA requirements of the program. Copies of the report of management assessments generated by participant contractors shall be provided to DOE-RL.</p>

BOARD  
CRITERION 2: QUALITY ASSURANCE PROGRAM - FOR SITE CHARACTERIZATION  
REVISION 1 (sheet 19 of 19)

Requirement	BWIP Project Implementation
	<p>Management assessments shall be performed by HQ-OGR, the project offices and their major contractors. Each organization shall develop its internal procedures for the planning, organizing, performing, and documenting the management assessment conducted, including the analysis and reporting of the results and the tracking of recommendations (OGR/B-3 QA Plan, Section 4.4).</p>

BQARD  
CRITERION 3: DESIGN CONTROL  
REVISION 0 (sheet 1 of 12)

Requirement	BWIP Project Implementation
	<p data-bbox="1349 310 1689 340" style="text-align: center;"><b>Site Characterization</b></p> <p data-bbox="1034 373 2002 723">The intent of this criterion during site characterization is to establish the requirements for controls over the repository design activities in order to ensure that (a) design products to be used during site characterization data collection/testing/analysis (e.g., detailed procedures or data analysis computer programs) are correct and consistent with repository conceptual design, and (b) resultant repository design products are correct and consistent with the analyzed data obtained through site characterization activities. Refer to Review Plan Section 3.1 of this Criterion (sheet 2) for additional information.</p> <p data-bbox="1236 756 1810 786" style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p data-bbox="1034 819 2002 1136">The intent of this criterion during construction is to establish the requirements for controls over the repository definitive design processes, in order to ensure that applicable regulatory requirements and design bases (in part derived from site characterization activities) are correctly translated into construction specifications, drawings, procedures, and instructions (definitive design products), and that any subsequent change to a verified definitive design product is consistent with the original correct translation.</p> <p data-bbox="1034 1169 2002 1559">It is expected that definitive design for potentially licenseable construction will be performed coincident with BWIP site characterization design work. Those participants who will perform both construction and site characterization design work shall establish Design Controls meeting site characterization Criterion 3. Those participants performing only definitive design for Level I construction work shall establish those design controls required by the specific code or standard to be met, and, to the extent practical, shall conform to the requirements of Site Characterization Criterion 3. Deviations, and the alternate method of providing equivalent control, will be documented.</p>



BOARD  
CRITERION 3: DESIGN CONTROL - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 3 of 12)

Requirement	BWIP Project Implementation
<p data-bbox="108 320 555 353"><b>NRC REVIEW PLAN SECTION 3.2</b></p> <p data-bbox="108 381 1017 761">The design control program is implemented at the time of submission of the Site Characterization Plan and includes design and design activities as described in 3.1 (of the NRC Review Plan). It provides for the correct translation of applicable regulatory requirements and design bases into design, procurement, and procedural documents. Performance requirements are specified for repository system components to support: (a) identification of which items are important to waste isolation; (b) establishment of a graded QA approach; and (c) establishment of data gathering and analysis needs.</p>	<p data-bbox="1081 389 1923 485">This requirement shall be implemented as stated. In addition, Supplement 3S-1, Sections 2, 3, and 7 of NQA-1-1986 shall be implemented.</p> <p data-bbox="1081 518 2002 645">In addition, performance assessment and allocation, and changes thereto, based on data analysis results, shall be controlled in accordance with the applicable requirements of the System Engineering Management Plan. (DOE-RL)</p>

BOARD  
CRITERION 3: DESIGN CONTROL - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 4 of 12)

Requirement	BWIP Project Implementation
<p data-bbox="119 315 704 351"><b>REQUIREMENT 2: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="119 376 1023 508">These measures shall include provisions to assure that appropriate quality standards are specified and included in design documents and that deviations from such standards are controlled.</p> <p data-bbox="119 571 561 607"><b>NRC REVIEW PLAN SECTION 3.6</b></p> <p data-bbox="119 637 1023 797">Procedures require that design drawings, specifications, criteria, and analysis be reviewed by the QA organization to assure that the documents are prepared, reviewed, and approved in accordance with documented procedures and quality assurance requirements.</p>	<p data-bbox="1087 384 2013 450">This requirement shall be met by implementing NQA-1-1986, Supplement 3S-1, Section 2.</p> <p data-bbox="1087 480 1981 546">For site characterization, additional guidance has been provided in Section 3.6 of the NRC Review Plan.</p> <p data-bbox="1087 637 1885 736">This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>

BQARD  
CRITERION 3: DESIGN CONTROL - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 5 of 12)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 3: 10 CFR 50 APPENDIX B</b></p> <p>Measures shall also be established for the selection and review for suitability of application of materials, parts, equipment, and processes that are essential to the safety-related functions of the structures, systems, and components.</p>	<p>This requirement shall be met by implementing NQA-1-1986, Supplement 3S-1.</p> <p>In addition, requirements for the methodology for formulating a Q-List are as specified in OGR/B-3, Supplement 3.</p>

BOARD  
CRITERION 3: DESIGN CONTROL - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 6 of 12)

Requirement	BWIP Project Implementation
<p data-bbox="114 299 700 341">REQUIREMENT 4: 10 CFR 50 APPENDIX B</p> <p data-bbox="114 366 1024 475">Measures shall be established for the identification and control of design interfaces and for coordination among participating design organizations.</p> <p data-bbox="114 559 556 601">NRC REVIEW PLAN SECTION 3.5</p> <p data-bbox="114 626 894 727">Interface controls among organizations or groups involved in design development and other design activities are described.</p>	<p data-bbox="1095 374 1864 408">This requirement shall be implemented as stated.</p> <p data-bbox="1095 441 1936 542">For site characterization, the NRC has provided additional guidance in Section 3.5 of the NRC Review Plan.</p> <p data-bbox="1095 635 1994 735">This requirement shall be implemented as stated. In addition, Supplement 3S-1, Section 6 of NQA-1-1986 shall be implemented.</p>

BOARD  
CRITERION 3: DESIGN CONTROL - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 7 of 12)

Requirement	BWIP Project Implementation
<p data-bbox="95 305 1059 346"><b>REQUIREMENT 5: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="95 363 1059 512">These measures shall include the establishment of procedures among participating design organizations for the review, approval, release, distribution, and revision of documents involving design interfaces.</p> <p data-bbox="95 578 1059 627"><b>NRC REVIEW PLAN SECTION 3.3</b></p> <p data-bbox="95 644 1059 759">Organizational responsibilities are described for preparing, reviewing, approving, verifying, and validating design and design information documents.</p>	<p data-bbox="1068 363 2038 446">This requirement shall be met by implementing Supplement 3S-1, Section 6 of NQA-1-1986.</p> <p data-bbox="1068 462 2038 561">For site characterization, the NRC has provided additional guidance in Section 3.3 of the NRC Review Plan.</p> <p data-bbox="1068 644 2038 792">This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated. In addition, design/engineering "holds" shall be included (DOE-RL).</p> <p data-bbox="1068 809 2038 1007">Note the use of the word "validating." It pertains to the design of computer codes, as discussed in NUREG 0856 in the definitions of "validating" and "verifying" when used in the context of computer codes, to provide assurance that a model is a correct representation of the process or system for which it is intended.</p>

BOARD  
**CRITERION 3: DESIGN CONTROL - FOR SITE CHARACTERIZATION**  
**REVISION 3 (sheet 8 of 12)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 6: 10 CFR 50 APPENDIX B</b></p> <p>The design control measures shall provide for verifying or checking the adequacy of design, such as by the performance of design reviews, by the use of alternate or simplified calculational methods, or by the performance of a suitable testing program.</p>	<p>This requirement shall be met by implementing the requirements of NQA-1-1986, Supplement 3S-1, Section 4.</p> <p>For site characterization, the NRC has provided additional guidance in Sections 3.4 and 3.8 of the NRC Review Plan.</p>
<p><b>NRC REVIEW PLAN SECTION 3.4</b></p> <p>Errors and deficiencies in approved design and design information documents are documented, and action is taken to assure that all errors and deficiencies are corrected.</p>	<p>This requirement shall be met by implementing the requirements of NQA-1-1986, Supplement 3S-1, Section 5.</p>
<p><b>NRC REVIEW PLAN SECTION 3.8</b></p> <p>For design or design activities which involve use of untried or state-of-the-art testing and analysis procedures and methods or where detailed technical criteria and requirements do not exist or are being developed, a peer review should be conducted. The procedures defining the selection process for a peer group, and the process by which the peer group conducts its review should be described. A peer review is a critical review performed by personnel who are independent of, but have expertise equivalent to, those who performed the work. Outside consultants are retained for needed expertise, where required.</p>	<p>This method of design verification is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented. Requirements for the control of peer reviews conducted for geologic repository project shall be as specified in the BWIP QA Plan Section 3.5.</p>

BOARD  
**CRITERION 3: DESIGN CONTROL - FOR SITE CHARACTERIZATION**  
**REVISION 3 (sheet 9 of 12)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 7: 10 CFR 50 APPENDIX B</b></p> <p>The verifying or checking process shall be performed by individuals or groups other than those who performed the original design, but who may be from the same organization.</p> <p><b>NRC REVIEW PLAN SECTION 3.7</b></p> <p>Procedures are established and described for verification of designs and design activities, the verifier of which is qualified and not directly responsible for the design, (i.e., not the performer or his immediate supervisor). In exceptional cases, the designer's immediate supervisor can, however, perform the verification, provided:</p> <ul style="list-style-type: none"> <li>(a) The supervisor is the only technically qualified individual.</li> <li>(b) The need is individually documented and approved in advance with concurrence of the Quality Assurance manager.</li> </ul> <p>It is preferable to have qualified personnel not associated with the responsible design organization conduct verification activities.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, the NRC has provided additional guidance for this requirement in Sections 3.7 and 3.9 of the NRC Review Plan.</p> <p>This requirement shall be implemented as stated. In addition, Supplement 3S-1, Section 4 of NQA-1-1986 shall be implemented.</p>
<p><b>NRC REVIEW PLAN SECTION 3.9</b></p> <p>The responsibilities of the verifier, the areas and features to be verified, the pertinent considerations to be verified, and the extent of documentation are identified in the procedures.</p>	<p>This requirement shall be met by implementing the requirements of NQA-1-1986, Supplement 3S-1, Sections 4 and 7.</p>

BQARD  
CRITERION 3: DESIGN CONTROL - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 10 of 12)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 8: 10 CFR 50 APPENDIX B</b></p> <p>Where a test program is used to verify the adequacy of a specific design feature in lieu of other verifying or checking processes, it shall include suitable qualification testing of a prototype unit under the most adverse design conditions.</p>	<p>This requirement shall be met by implementing the requirements of Supplement 3S-1, Subsection 4.2.3 of NQA-1-1986.</p> <p>Refer to Criterion 11 for additional information.</p>

BOARD  
CRITERION 3: DESIGN CONTROL - FOR SITE CHARACTERIZATION  
REVISION 3 (sheet 11 of 12)

bx

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 9: 10 CFR 50 APPENDIX B</b></p> <p>Design control measures shall be applied to items such as the following: reactor physics, stress, thermal, hydraulic, and accident analyses; compatibility of materials; accessibility for in-service inspection, maintenance, and repair; and delineation of acceptance criteria for inspections and tests.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented to the level of detail apparent in the requirement. Additional non mandatory guidance is provided in NQA-1-1986, Appendix 3A-1.</p> <p>In addition, the word "reactor" is deleted and the words "high level waste disposal" added in its stead (DOE-RL).</p> <p>In addition, the delineation of appropriate acceptance limits for verification and tests (site characterization testing) shall be directly relatable to the design input that must be confirmed via performance of the test (DOE-RL).</p>

bx  
bx  
bx

BQARD  
CRITERION 3: DESIGN CONTROL - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 12 of 12)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 10: 10 CFR 50 APPENDIX B</b></p> <p>Design changes, including field changes, shall be subject to design control measures commensurate with those applied to the original design and be approved by the organization that performed the original design unless the applicant designates another responsible organization.</p> <p><b>NRC REVIEW PLAN SECTION 3.10</b></p> <p>Design changes, including field changes, are subject to the same design controls that were applicable to the original design. Such a configuration control system should be in place at the earliest practicable time. These changes should be analyzed to assure that change is required. Associated changes to procedures and training should be considered, and changes should be communicated to all affected groups or individuals.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, the NRC has provided additional guidance for this requirement in Section 3.10 of the NRC Review Plan.</p> <p>This requirement shall be implemented as stated. In addition, Supplement 3S-1, Section 5 of NQA-1-1986 shall be implemented.</p> <p><b>NOTE: "Configuration Management and Change Control" shall comply with DOE Order 4700.1, Part C, "Configuration Management and Change Control."</b></p>

BQARD  
**CRITERION 4: PROCUREMENT DOCUMENT CONTROL**  
 REVISION 1 (sheet 1 of 4)

Requirement	BWIP Project Implementation
	<p style="text-align: center;"><b>Site Characterization</b></p> <p>The intent of this criterion during site characterization is to establish the requirements for the control of Procurement Documents including content, in order to ensure that only correct and complete Procurement Documents are utilized by BWIP. This Criterion and Criterion 7 shall establish the requirements for the control of procurement activities, from procurement planning through supplier QA program approval, in order to assure that qualified suppliers furnish BWIP materials, equipment, and services. (Refer to BQARD interpretation of NRC Review Plan Section 4.2 for additional information.)</p> <p>Note the NQA-1 definitions of "Procurement Documents," "Final Design (Documents)," and "Design Output (Documents)." As used herein, Procurement Documents means all documents included within the "bid package" (or equivalent) transmitted to suppliers, and other directly related documents (e.g., RFP's, contract modifications). Procurement Documents include "Final Design" documents which, during site characterization are often approved "Statements of Work." Final Design Documents shall include those technical QA requirements applicable to the procurement, and the organization preparing the Final Design Documents shall recommend to the purchaser those programmatic QA requirements applicable to the procurement. It is preferable that the supplier documentation to be submitted for both the QA technical and QA programmatic requirements be identified in a consolidated "Deliverable List" (or "submittal list") that is an integral part of the Final Design Documents. In any case, agreement between the design organization and the purchaser with respect to both QA technical and</p>

BOARD  
CRITERION 4: PROCUREMENT DOCUMENT - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 2 of 4)

Requirement	BWIP Project Implementation
	<p>recommended programmatic requirements shall be reached prior to design review of the Design Output Documents. The purchaser shall assure that any QA requirements not included in the Final Design Documents are included within the Procurement Documents.</p> <p>Note that Criterion 6, "Document Control," NRC Review Plan 6.5, identifies Procurement Documents for inclusion within a document control system.</p> <p>Note that Procurement Document changes (i.e., contract modifications) that result from unsatisfactory supplier performance may be considered "significant conditions adverse to quality" and shall be documented as required by Criterion 16, NRC Review Plan Section 16.4.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is identical to its intent during site characterization.</p>

BOARD  
CRITERION 4: PROCUREMENT DOCUMENT - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 3 of 4)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p>Measures shall be established to assure that applicable regulatory requirements, design bases, and other requirements which are necessary to assure adequate quality are suitably included or referenced in the documents for procurement of material, equipment, and services, whether purchased by the applicant or by its contractors or subcontractors.</p> <p><b>NRC REVIEW PLAN SECTION 4.2</b></p> <p>Organizational responsibilities are described for: (1) procurement planning; (2) the preparation, review, approval, and control of procurement documents; (3) supplier selection; (4) bid evaluations; and (5) review and concurrence of supplier QA programs prior to initiation of activities affected by the program. The involvement of the QA organization is described.</p>	<p>This requirement shall be met by implementing NQA-1-1986, Basic Requirement 4 and Supplement 4S-1.</p> <p>For site characterization, additional guidance has been provided in Section 4.2 of the NRC Review Plan.</p> <p>This requirement shall be implemented as stated.</p> <p>In addition, Sections 2, 3, and 4 of Supplement 4S-1 and Supplement 7S-1, Sections 1, 3, 4, and 5 of NQA-1-1986, shall be implemented for activity (2).</p>

BQARD  
CRITERION 4: PROCUREMENT DOCUMENT - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 4 of 4)

Requirement	BWIP Project Implementation
<p data-bbox="102 310 691 346"><b>REQUIREMENT 2: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="102 376 995 508">To the extent necessary, procurement documents shall require contractors or subcontractors to provide a quality assurance program consistent with the pertinent provisions of this appendix.</p> <p data-bbox="102 535 549 571"><b>NRC REVIEW PLAN SECTION 4.1</b></p> <p data-bbox="102 601 1010 954">Procedures are established for the review of procurement documents by QA personnel to determine the applicable regulatory requirements, design bases, and other requirements are referenced or stated in procurement documents; there are adequate acceptance and rejection criteria, where appropriate; and procurement documents have been prepared, reviewed, and approved in accordance with QA program requirements. Procurement documents should require contractors, subcontractors, and consultants to provide an acceptable Quality Assurance program.</p>	<p data-bbox="1076 383 1847 419">This requirement shall be implemented as stated.</p> <p data-bbox="1076 446 1968 512">For site characterization, additional guidance has been provided in Section 4.1 of the NRC Review Plan.</p> <p data-bbox="1076 604 2000 703">This requirement shall be implemented as stated. In addition, Supplement 4S-1, Sections 2 and 3 of NQA-1-1986 shall be implemented.</p> <p data-bbox="1076 730 1968 862">Note that Federal Acquisition Regulations (FAR's) may require acceptance inspections if the procurement includes turnover of tangible, capital equipment to the purchaser.</p> <p data-bbox="1076 888 1947 1053">It is anticipated that BWIP site characterization activities will require a limited number of acceptance inspections. These will be planned and conducted on a case-by-case basis in response to project procurement regulations and procedures.</p>

BQARD  
CRITERION 5: INSTRUCTIONS, PROCEDURES, AND DRAWINGS  
REVISION 2 (sheet 1 of 3)

Requirement	BWIP Project Implementation
	<p style="text-align: center;"><b>Site Characterization</b></p> <p>The intent of this criterion during site characterization is to establish the requirements for the control of project quality-related activities through the use of written procedures, instructions, and drawings (that have been subjected to a documented review/verification and approval process), in order to ensure that activities are performed correctly, and if required, can be reproduced at a later date.</p> <p>NOTE: NQA-1 Supplement S-1 makes a distinction between "Procedure" and "Qualified Procedure," which is "an approved procedure <u>that has been demonstrated</u> to meet the specified requirements for its intended purpose." Qualified procedures are normally required in advance of performance of a special process (Criterion 9). Those technical procedures required by Criterion 5 may be converted to "Qualified Procedures," if desired, upon determination by the design organization (Criteria 3) that the procedure produced valid results. Also refer to Criterion 2 for additional procedural information.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is identical to its intent during site characterization.</p>

BQARD  
CRITERION 5: INSTRUCTIONS, PROCEDURES, AND DRAWINGS - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 2 of 3)

Requirement	BWIP Project Implementation
<p data-bbox="102 310 697 346"><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="102 373 981 538">Activities affecting quality shall be prescribed by documented instructions, procedures, or drawings, of a type appropriate to the circumstances and shall be accomplished in accordance with these instructions, procedures, or drawings.</p> <p data-bbox="102 564 549 601"><b>NRC REVIEW PLAN SECTION 5.1</b></p> <p data-bbox="102 627 995 852">Organizational responsibilities are described for assuring that quality-related activities are: (1) specified in instruction, procedures, and drawings; and (2) accomplished through implementation of these documents. These documents should be verified and approved as described in Section 3 (of the NRC Review Plan).</p>	<p data-bbox="1074 376 1889 446">This requirement is addressed in NQA-1-1986, Basic Requirement 5.</p> <p data-bbox="1074 472 1968 541">For site characterization, additional guidance has been provided in Section 5.1 of the NRC Review Plan.</p> <p data-bbox="1074 634 1868 733">This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>



BQARD  
CRITERION 6: DOCUMENT CONTROL  
REVISION 2 (sheet 1 of 4)

Requirement	BWIP Project Implementation
	<p style="text-align: center;"><b>Site Characterization</b></p> <p>The intent of this criterion during site characterization is to establish the requirements for the control of project quality-affecting documents, in order to ensure that correct and applicable documents are available at the location where the activity will be performed prior to commencing the work.</p> <p>NOTE: NQA-1 Supplement S-1 provides an acceptable definition of "Document" and "QA Record," as well as the distinction between the two. Further, NQA-1 permits a "Deviation" from the specified requirements of a controlled document provided an approved "waiver" is obtained on a case-by-case basis. Project participants shall establish a deviation/waiver procedure that ensures adequate control over case-by-case changes to controlled documents, if deviations/waivers are to be used.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is identical to its intent during site characterization.</p>

BQARD  
**CRITERION 6: DOCUMENT CONTROL - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 2 of 4)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p>Measures shall be established to control the issuance of documents, such as instructions, procedures, and drawings, including changes thereto, which prescribe all activities affecting quality.</p> <p><b>NRC REVIEW PLAN SECTION 6.1</b></p> <p>The scope of the document control program is described, and the types of controlled documents are identified.</p> <p><b>NRC REVIEW PLAN SECTION 6.2</b></p> <p>Procedures for the review, approval, issuance, and revision of documents are established. These procedures assure technical adequacy and inclusion of appropriate quality requirements. The QA organization reviews and concurs with these documents with respect to quality-related aspects.</p> <p><b>NRC REVIEW PLAN SECTION 6.5</b></p> <p>A master list or equivalent document control system is established to identify the current revision of instructions, procedures, specifications, drawings, and procurement documents.</p> <p><b>NRC REVIEW PLAN SECTION 6.6</b></p> <p>When documents which require verification are released prior to verification, they are so identified and controlled.</p>	<p>This requirement shall be implemented as stated in NQA-1-1986, Basic Requirement 6 and Supplement 6S-1.</p> <p>Additional guidance has been provided in Sections 6.1, 6.2, 6.5, and 6.6 of the NRC Review Plan.</p> <p>This requirement shall be met by implementing all requirements in NQA-1-1986, Supplement 6S-1, Sections 1 and 2, provided the requirement to describe the scope of the document control program is addressed.</p> <p>This requirement shall be implemented as stated. In addition, NQA-1-1986, Supplement 6S-1 shall be implemented.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated, and in addition, any project data resulting from application of the unverified document shall be clearly identified (DOE-RL).</p>

BQARD  
CRITERION 6: DOCUMENT CONTROL - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 3 of 4)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 2: 10 CFR 50 APPENDIX B</b></p> <p>These measures shall assure that documents, including changes, are reviewed for adequacy and approved for release by authorized personnel and are distributed to and used at the location where the prescribed activity is performed.</p>	<p>This requirement shall be implemented as stated in NQA-1-1986, Supplement 6S-1, Section 1.</p> <p>Additional guidance has been provided in Sections 6.3 and 6.4 of the NRC Review Plan.</p>
<p><b>NRC REVIEW PLAN SECTION 6.3</b></p> <p>Procedures are established to assure that correct and applicable documents are available at the location where the activity will be performed <u>prior</u> to commencing the work.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>
<p><b>NRC REVIEW PLAN SECTION 6.4</b></p> <p>Procedures are established and described to assure that obsolete or superseded documents are removed and replaced by applicable revisions at work areas in a timely manner.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>

BQARD  
CRITERION 6: DOCUMENT CONTROL - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 4 of 4)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 3: 10 CFR 50 APPENDIX B</b></p> <p>Changes to documents shall be reviewed and approved by the same organizations that performed the original review and approval unless the applicant designates another responsible organization.</p>	<p>This requirement shall be met by implementing Supplement 6S-1, Section 3 of NQA-1-1986.</p> <p>In addition, change controls shall comply with DOE Order 4700.1, Part C, "Configuration Management and Change Control."</p>

BOARD  
CRITERION 7: CONTROL OF PURCHASED MATERIAL, EQUIPMENT, AND SERVICES  
REVISION 2 (sheet 1 of 7)

Requirement	BWIP Project Implementation
	<p style="text-align: center;"><b>Site Characterization</b></p> <p>The intent of this criterion during site characterization is to establish the minimum requirements for control of purchased material, equipment and services, to ensure they conform to the procurement documents. Documentary evidence that items (not limited to materials and equipment) conform to procurement requirements shall be provided by the supplier and reviewed and accepted by the purchaser prior to installation or use of the items.</p> <p>Procedures shall be written to provide for: (a) source evaluation and selection, (b) inspection of items at the source or upon delivery, and (c) periodic assessment of the suppliers quality program. Documentary evidence that items conform to procurement requirements shall be provided by the supplier and retained at the nuclear facility.</p> <p>Note that this criterion provides greater definition of "QA Records" as it applies to external suppliers. Refer also to NQA-1 Supplement S-1 for definition of the terms used herein.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is identical to its intent during site characterization.</p>

**BOARD**  
**CRITERION 7: CONTROL OF PURCHASED MATERIAL, EQUIPMENT, AND SERVICES - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 2 of 7)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p>Measures shall be established to assure that purchased material, equipment, and services, whether purchased directly or through contractors and subcontractors, conform to the procurement documents.</p> <p><b>NRC REVIEW PLAN SECTION 7.1</b></p> <p>Organization responsibilities are described for the control of purchased material, equipment, and services.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Section 7.1 of the NRC Review Plan.</p> <p>This requirement shall be met by implementing Supplement 7S-1, Section 2 of HQA-1-1986.</p> <p>In addition, receiving inspection requirements may be minimized for items packaged for preservation at the supplier's activity, provided inspection is performed at the supplier's activity and Criterion 13, "Handling, Storage, and Shipping," is appropriately implemented for the procurement (DOE-RL).</p>

**BOARD**  
**CRITERION 7: CONTROL OF PURCHASED MATERIAL, EQUIPMENT, AND SERVICES - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 3 of 7)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 2: 10 CFR 50 APPENDIX B</b></p> <p>These measures shall include provisions, as appropriate, for source evaluation and selection, objective evidence of quality furnished by the contractor or subcontractor, inspection at the contractor or subcontractor source, and examination of products upon delivery.</p> <p><b>NRC REVIEW PLAN SECTION 7.2</b></p> <p>Procedures governing procurement of items or services, including appropriate QA organization participation, provide for: (a) evaluation and selection of suppliers; (b) verification of supplier's activities; and (c) receiving inspections.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Section 7.2 of the NRC Review Plan.</p>  <p>This requirement shall be implemented as stated. In addition Supplement 7S-1 Section(s) 3, 4, 5, 8, and 10 of NQA-1-1986 shall be implemented.</p>

BOARD  
**CRITERION 7: CONTROL OF PURCHASED MATERIAL, EQUIPMENT, AND SERVICES - FOR SITE CHARACTERIZATION**  
**REVISION 3 (sheet 4 of 7)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 3: 10 CFR 50 APPENDIX B</b></p> <p>Documentary evidence that material and equipment conform to the procurement requirements shall be available at the nuclear powerplant or fuel reprocessing plant site prior to installation or use of such material and equipment.</p> <p><b>NRC REVIEW PLAN SECTION 7.3</b></p> <p>The organization providing materials, equipment, or services furnishes the following records to the purchaser:</p> <ul style="list-style-type: none"> <li>a. Documentation that identifies the service and the specific procurement requirements (e.g., codes, standards, and specifications) met.</li> <li>b. Documentation identifying any procurement requirements that have not been met.</li> <li>c. A description of those nonconformances from the procurement requirements dispositioned "accept as is" or "repair."</li> </ul> <p>The procedure for review and acceptance of these documents should be described in the purchaser's QA program.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Section 7.3 of the NRC Review Plan.</p> <p>The words "repository site" shall be substituted where appropriate.</p> <p>This requirement shall be met by implementing Supplement 7S-1, Section 8 of NQA-1-1986.</p> <p>This requirement shall be met by implementing Supplement 7S-1, Sections 8 and 9 of NQA-1-1986.</p> <p>This requirement shall be met by implementing Supplement 7S-1, Section 9, Subsection (b) of NQA-1-1986.</p> <p>This requirement shall be met by implementing Supplement 7S-1, Sections 5, 6, 7, and 9 of NQA-1-1986.</p>

BQARD  
CRITERION 7: CONTROL OF PURCHASED MATERIAL, EQUIPMENT, AND SERVICES - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 5 of 7)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 4: 10 CFR 50 APPENDIX B</b></p> <p>This documentary evidence shall be retained at the nuclear powerplant or fuel reprocessing plant site and shall be sufficient to identify the specific requirements, such as codes, standards, or specifications, met by the purchased material and equipment.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated, with the words "repository site" substituted where appropriate.</p> <p>Refer to Criteria 17 for additional records retention requirements.</p>

**BOARD**  
**CRITERION 7: CONTROL OF PURCHASED MATERIAL, EQUIPMENT, AND SERVICES - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 6 of 7)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 5: 10 CFR 50 APPENDIX B</b></p> <p>The effectiveness of the control of quality by contractors and subcontractors shall be assessed by the applicant or designee at intervals consistent with the importance, complexity, and quantity of the product or services.</p> <p><b>NRC REVIEW PLAN SECTION 7.4</b></p> <p>Suppliers' certificates of conformance are periodically evaluated by audits, independent inspections, or tests to assure they are valid and the results documented.</p> <p><b>NRC REVIEW PLAN SECTION 7.5</b></p> <p>In developing quality assurance requirements for data collection test equipment and other equipment, consideration should be given to whether proper performance of a test can be determined during or after testing (i.e., whether failure or malfunction of test equipment can be detected). When no specific QA controls are found to be necessary, special quality/performance verification requirements shall be established and described in procedures governing the use of the equipment.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Sections 7.4 and 7.5 of the NRC Review Plan.</p> <p>This requirement shall be implemented as stated. In addition, Supplement 7S-1, Section 8.2.1 of NQA-1-1986 shall be implemented.</p> <p>This requirement shall be met during the selection and use of equipment for data collection activities under Criterion 11, for use with Criterion 3.</p> <p>While preparation, review, and approval of data acquisition planning and procedure generation are controlled under the design control provisions of the QA program, actual performance of the experiments, measurement, collection, etc., for acquiring data is controlled under applicable provisions of Section 11.0, Test Control.</p>

BOARD  
CRITERION 7: CONTROL OF PURCHASED MATERIAL, EQUIPMENT, AND SERVICES - FOR SITE CHARACTERIZATION  
REVISION 1 (sheet 7 of 7)

Requirement	BWIP Project Implementation
:	<p>For instrumentation and/or equipment used in data collection, project participants are expected to consider whether failure or malfunction of the instrumentation during test will be detectable, either during data collection or by examination of the data. Where ability to detect such failure or malfunction is questionable, (a) technical and quality procurement requirements shall be selected specifically to minimize the likelihood of undetectable anomalies, and (b) test planning and procedures shall include any special provisions for equipment/instrumentation configuration, installation, and use that can further reduce risk of undetectable failure or malfunction.</p>

**BOARD**  
**CRITERION 8: IDENTIFICATION AND CONTROL OF MATERIALS, PARTS, AND COMPONENTS**  
**REVISION 2 (sheet 1 of 4)**

Requirement	BWIP Project Implementation
	<p style="text-align: center;"><b>Site Characterization</b></p> <p>The intent of this criterion during site characterization is to establish the requirements for identification and control of samples in order to ensure that the identity of a discrete sample is known with certainty at all times during its useful life on the BWIP. This criterion may also have applicability to other critical site characterization items. Note Test Procedure Requirements.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is to establish the requirements for identification and control (including traceability) of materials, parts, and components used in Level I repository construction, in order to ensure that only correct materials, parts, and components are utilized.</p>

BOARD

CRITERION 8: IDENTIFICATION AND CONTROL OF MATERIALS, PARTS, AND COMPONENTS - FOR SITE CHARACTERIZATION  
 REVISION 3 (sheet 2 of 4)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p>Measures shall be established for the identification and control of materials, parts, and components, including partially fabricated assemblies.</p> <p><b>NRC REVIEW PLAN SECTION 8.1</b></p> <p>Controls are established and described to identify and control samples. The description should include organization responsibilities.</p> <p><b>NRC REVIEW PLAN SECTION 8.3</b></p> <p>Identification of samples can be traced to the appropriate documentation such as drawings, specifications, purchase orders, drilling logs, test records, inspection documents, and nonconformance reports.</p>	<p>This requirement shall be implemented as stated. In addition, Supplement 8S-1 of NQA-1-1986 shall be implemented.</p> <p>For site characterization, additional guidance has been provided in section 8.1 and 8.3 of the NRC Review Plan.</p> <p>This requirement is addressed in NQA-1-1986, Supplement 8S-1, under the term "items."</p> <p>In addition, the method used to determine identification markings for each sample shall preclude the assignment of a discreet identifier to more than one discrete sample (DOE-RL).</p> <p>This requirement shall be met by implementing NQA-1-1986, Supplement 8S-1.</p>



BOARD  
CRITERION 8: IDENTIFICATION AND CONTROL OF MATERIALS, PARTS, AND COMPONENTS - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 4 of 4)

Requirement	BWIP Project Implementation
<p data-bbox="114 310 702 346"><b>REQUIREMENT 3: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="114 376 974 475">These identification and control measures shall be designed to prevent the use of incorrect or defective material, parts, and components.</p> <p data-bbox="114 535 557 571"><b>NRC REVIEW PLAN SECTION 8.4</b></p> <p data-bbox="114 601 910 670">Correct identification of samples is verified and documented prior to release for use or analysis.</p>	<p data-bbox="1085 383 1859 419">This requirement shall be implemented as stated.</p> <p data-bbox="1085 449 1979 518">For site characterization, additional guidance has been provided in Section 8.4 of the NRC Review Plan.</p> <p data-bbox="1085 607 1881 707">This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p data-bbox="1085 736 2008 925">In addition, for a sample discretely identified only by its container, verification and documentation shall be extended to include sample return to the discrete container, if permitted by lab practice. Any transfer of material shall contain the sample identification number (DOE-RL).</p>

BOARD  
CRITERION 9: CONTROL OF SPECIAL PROCESSES  
REVISION 2 (sheet 1 of 3)

Requirement	BWIP Project Implementation
	<p style="text-align: center;"><b>Site Characterization</b></p> <p>The intent of the criterion during site characterization is to establish the minimum requirements for the control of special processes, in order to ensure that site characterization processes where direct inspection is impossible or disadvantageous produce results that are demonstrably valid through the use of other accepted assurance techniques.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is identical to its intent during site characterization.</p>

BQARD  
**CRITERION 9: CONTROL OF SPECIAL PROCESSES - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 2 of 3)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p>Measures shall be established to assure that special processes, including welding, heat treating, and nondestructive testing, are controlled and accomplished by qualified personnel using qualified procedures in accordance with applicable codes, standards, specifications, criteria, and other special requirements.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, the NRC has provided additional guidance for this requirement in Sections 9.1 through 9.5 of the NRC Review Plan.</p>
<p><b>NRC REVIEW PLAN SECTION 9.1</b></p> <p>The criteria for determining those processes that are controlled as special processes are described. As complete a listing as possible of special processes, which are generally those processes where direct inspection is impossible or disadvantageous, is provided.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>
<p><b>NRC REVIEW PLAN SECTION 9.2</b></p> <p>Organizational responsibilities including those for the QA organization are described for qualification of special processes, equipment, and personnel.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>
<p><b>NRC REVIEW PLAN SECTION 9.3</b></p> <p>Procedures, equipment, and personnel associated with special processes are qualified and are in conformance with applicable codes, standards, QA procedures, and specifications. The QA organization is involved in the qualification activities to help assure they are satisfactorily performed.</p>	<p>This requirement shall be implemented as stated. In addition, Supplement 9S-1 of NQA-1-1986 shall be implemented.</p>

BOARD  
CRITERION 9: CONTROL OF SPECIAL PROCESSES - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 3 of 3)

Requirement	BWIP Project Implementation
<p data-bbox="89 315 534 348"><b>NRC REVIEW PLAN SECTION 9.4</b></p> <p data-bbox="89 376 938 480">Procedures are established for recording evidence of acceptable accomplishment of special processes using qualified procedures, equipment, and personnel.</p> <p data-bbox="89 505 534 538"><b>NRC REVIEW PLAN SECTION 9.5</b></p> <p data-bbox="89 566 938 670">Qualifications records of procedures, equipment, and personnel associated with special processes are established and maintained.</p>	<p data-bbox="1066 384 1874 450">This requirement shall be met by implementation of NQA-1-1986, Supplement 9S-1, Section 3.</p> <p data-bbox="1066 574 1906 674">This requirement shall be implemented as stated. In addition, Supplement 9S-1, Section 3.3 of NQA-1-1986 shall be implemented.</p>

BOARD  
CRITERION 10: INSPECTION  
REVISION 2 (sheet 1 of 9)

Requirement	BWIP Project Implementation
	<p data-bbox="1372 305 1713 338" style="text-align: center;">Site Characterization</p> <p data-bbox="1081 363 2021 561">Inspection as used herein means the independent verification of a physical characteristic being determined during a site characterization activity. The wording utilized by participants to implement this activity is not critical, provided implementation meets the functional intent of this criterion.</p> <p data-bbox="1081 586 2021 908">The intent of this criterion during site characterization is to establish the requirements for an inspection program that directly complements the Site Characterization Test Program, and to establish controls on inspections being performed within the program, in order to ensure that any resultant physical data is demonstrably valid. In addition to independent verification of the physical data being obtained, inspection shall also verify conformance to the instructions, procedures, and drawings being utilized.</p> <p data-bbox="1081 933 2021 1420">For site characterization data gathering activities (e.g., laboratory testing and analysis), a combination of inspection and special process methods may be better suited to provide reliability of the data gathered. Since the quality of the end result cannot be directly measured or inspected (there is no acceptance criteria for testing results), the control of testing may be similar to the controls of special processes (i.e., procedures approved prior to use through technical and/or peer reviews; testing personnel qualified through experience, education and training; equipment "qualified" through calibration; and monitoring of performance of the test). Data subjected to an independent technical and/or peer review will constitute a final verification of the data's validity.</p>

BQARD  
CRITERION 10: INSPECTION  
REVISION 3 (sheet 2 of 9)

ix

Requirement	BWIP Project Implementation
	<p>Final inspections shall be performed by qualified personnel not reporting directly to the immediate supervisors who are responsible for performing the work being inspected. Final inspections should be performed just prior to "tear down" or "cover up" of a site characterization activity; they are normally indicated by "hold points" on the inspection plan.</p> <p>All project personnel, particularly project inspection personnel, shall be advised that the phrase "acceptance inspection" has a specific contractual meaning and must be used with discretion. In addition, inspection planners and those producing inspection procedures shall ensure they are aware of and responsive to Federal Acquisition Regulations pertaining to inspections.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is similar to its intent during site characterization, with the possible exception of inspection report distribution, and greater utilization of the guidance in DOE Order 4700.1.</p>

ix

BOARD  
CRITERION 10: INSPECTION - FOR SITE CHARACTERIZATION  
REVISION 3 (sheet 3 of 9)

Requirement	BWIP Project Implementation
<p data-bbox="129 299 719 337"><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="129 365 1051 530">A program for inspection of activities affecting quality shall be established and executed by or for the organization performing the activity to verify conformance with the documented instructions, procedures, and drawings for accomplishing the activity.</p> <p data-bbox="129 844 587 882"><b>NRC REVIEW PLAN SECTION 10.1</b></p> <p data-bbox="129 910 1034 1108">The scope of the inspection program is described that indicates an effective inspection program has been established. Program procedures provide criteria for determining when inspections are required or define how and when inspections are performed. The QA organization participates in these functions.</p>	<p data-bbox="1102 370 1874 408">This requirement shall be implemented as stated.</p> <p data-bbox="1102 436 1991 535">In addition, the program shall be operative and provide input to the design documents and procurement documents used during site characterization (DOE-RL).</p> <p data-bbox="1102 563 2040 728">In addition, the procedures shall require that adequate interfacing occurs between the performing organization and the inspecting organization to permit cost effective use of personnel on a daily basis from both organizations (DOE-RL).</p> <p data-bbox="1102 756 1991 822">For site characterization, additional guidance has been provided in Section 10.1 of the NRC Review Plan.</p> <p data-bbox="1102 915 2013 1014">This requirement shall be implemented as stated. In addition, Supplement 10S-1, Sections 4, 5.1, 6, and 7 of NQA-1-1986 shall be implemented.</p>



BQARD  
CRITERION 10: INSPECTION - FOR SITE CHARACTERIZATION  
REVISION 3 (sheet 5 of 9)

Requirement	BWIP Project Implementation
<p data-bbox="75 462 539 495"><b>NRC REVIEW PLAN SECTION 10.6</b></p> <p data-bbox="75 529 927 621">Inspection results are documented and evaluated, and their acceptability is determined by a responsible individual.</p>	<p data-bbox="1052 319 1908 420">Certification of inspection personnel shall be met by implementation of NQA-1-1986, Supplement 2S-1 and Appendix 2A-1.</p> <p data-bbox="1052 512 1843 579">This requirement shall be met by implementing Supplement 10S-1, Sections 6 and 8 of NQA-1-1986.</p> <p data-bbox="1052 604 1972 747">In addition, each inspection shall be documented, and all inspection results pertaining to an activity shall be furnished to the reviewer of the resultant data (Criterion 3) (DOE-RL).</p>

BOARD  
CRITERION 10: INSPECTION - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 6 of 9)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 3: 10 CF 50 APPENDIX B</b></p> <p>Examinations, measurements, or tests of material or products processed shall be performed for each work operation where necessary to assure quality.</p> <p><b>NRC REVIEW PLAN SECTION 10.4</b></p> <p>Inspection procedures, instructions, or checklists provide for the following:</p> <ul style="list-style-type: none"><li>a. Identification of characteristics and activities to be inspected.</li><li>b. A description of the method of inspection.</li><li>c. Identification of the individuals or groups responsible for performing the inspection operation.</li><li>d. Acceptance and rejection criteria.</li><li>e. Identification of required procedures, drawings, and specifications and revisions.</li><li>f. Recording inspector or data recorder and the results of the inspection operation.</li><li>g. Specifying necessary measuring and test equipment including accuracy requirements.</li></ul>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Section 10.4 of the NRC Review Plan.</p> <p>This requirement shall be implemented as stated. In addition, Supplement 10S-1, Section 8 of NQA-1-1986 shall be implemented.</p>

BOARD  
CRITERION 10: INSPECTION - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 7 of 9)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 4: 10 CFR 50 APPENDIX B</b></p> <p>If inspection of processed material or products is impossible or disadvantageous, indirect control by monitoring processing methods, equipment, and personnel shall be provided.</p>	<p>This requirement shall be met by implementation of NQA-1-1986, Supplement 10S-1, Section 5.</p> <p>Inspection of certain defined special processes shall be met by implementation of Criterion 9.</p>

BOARD  
CRITERION 10: INSPECTION - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 8 of 9)

Requirement	BWIP Project Implementation
<p data-bbox="122 360 707 394"><b>REQUIREMENT 5: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="122 423 1028 491">Both inspection and process monitoring shall be provided when control is inadequate without both.</p>	<p data-bbox="1094 416 1895 485">This requirement shall be met by implementation of Supplement 10S-1, Section 5 of NQA-1-1986.</p>

BQARD  
CRITERION 10: INSPECTION - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 9 of 9)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 6: 10 CFR 50 APPENDIX B</b></p> <p>If mandatory inspection hold points, which require witnessing or inspecting by the applicant's designated representative and beyond which work shall not proceed without the consent of its designated representative are required, the specific hold points shall be indicated in appropriate documents.</p> <p><b>NRC REVIEW PLAN SECTION 10.5</b></p> <p>Procedures include identification of mandatory inspection hold points beyond which work may not proceed until inspected by a designated inspector.</p>	<p>This requirement shall be met by implementing Supplement 10S-1, Section 3 of NQA-1-1986.</p> <p>For site characterization, the NRC has provided additional guidance for this requirement as shown in Section 10.5 of the NRC Review Plan.</p> <p>This requirement shall be met by implementing Supplement 10S-1, Section 3 of NQA-1-1986.</p>

BQARD  
CRITERION 11: TEST CONTROL  
REVISION 1 (sheet 1 of 8)

x

Requirement	BWIP Project Implementation
	<p data-bbox="1331 307 1671 337" style="text-align: center;"><b>Site Characterization</b></p> <p data-bbox="1037 370 1969 948">The intent of this criterion during site characterization is to establish the minimum requirements that shall be met by the implemented Site Characterization Test Program. These controls are necessary in order to ensure that information resulting from the test program is both complete and of demonstrably adequate quality. Note that test program as used by the NRC during site characterization refers to testing performed in advance of, or concurrent with, and in support of, the design of the repository system components (both engineered and natural). Therefore, this criterion requires significant interfacing with the repository design organization to ensure that an adequate basis exists to support repository design development and verification. The criterion extends the design organization interfacing down to a level of detail that includes review of specific test procedures, as well as evaluation and acceptance of test results.</p> <p data-bbox="1037 981 1969 1268">It is not intended that this criterion apply to testing performed incidental to the development of a test process that will later be used for site characterization testing, unless the purpose of the testing is to verify the adequacy of the test process design. Also excluded are preliminary borings and geophysical testing needed to decide whether site characterization should be undertaken, unless it is intended that the test results have an additional use within the site characterization phase.</p>

x

BOARD  
CRITERION 11: TEST CONTROL  
REVISION 2 (sheet 2 of 8)

Requirement	BWIP Project Implementation
	<p data-bbox="1257 318 1842 351">Potentially Licenseable Construction</p> <p data-bbox="1083 381 2023 546">The intent of this criterion during construction is similar to its intent during site characterization, except that interfacing with the design organization is not required unless testing is for design prototype qualification.</p>

BOARD  
**CRITERION 11: TEST CONTROL - FOR SITE CHARACTERIZATION**  
**REVISION 3 (sheet 3 of 8)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p>A test program shall be established to assure that all testing required to demonstrate that structures, systems, and components will perform satisfactorily in service is identified and performed in accordance with written test procedures which incorporate the requirements and acceptance limits contained in applicable design documents.</p> <p><b>NRC REVIEW PLAN SECTION 11.1</b></p> <p>The description of the scope of the test control program indicates an effective test program has been established. Program procedures provide criteria for: (a) determining when a test is required or how and when testing activities are performed; and (b) the test program is conducted by trained or appropriately qualified personnel. The QA organization, as a minimum, audits these functions.</p>	<p>This requirement shall be met by implementing the requirements of NQA-1-1986, Supplement 11S-1 as further defined in Section A below.</p> <p>Additional guidance has been provided in Sections 11.1, 11.2, and 11.3 of the NRC Review Plan.</p> <p>A. The first sentence of this requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be met by implementing the guidance provided in figure 3 of the NRC Review Plan, as summarized below.</p> <p>1. A Test Control Program Plan shall be developed which defines program requirements based on:</p> <ul style="list-style-type: none"> <li>a. Site issues</li> <li>b. Information needs</li> <li>c. Program objectives.</li> </ul> <p>This plan shall include:</p> <ul style="list-style-type: none"> <li>a. Purpose</li> <li>b. Scope</li> <li>c. Description of work</li> <li>d. Specific requirements</li> <li>e. Interfaces</li> <li>f. Equipment and facilities</li> <li>g. Milestones.</li> </ul>

BQARD  
**CRITERION 11: TEST CONTROL - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 4 of 8)**

Requirement	BWIP Project Implementation
	<p>Individual test plans shall be developed which define how needed information will be gathered. These plans shall include, as appropriate, the following:</p> <ul style="list-style-type: none"> <li>a. Test objectives</li> <li>b. Scope of tests</li> <li>c. Justification</li> <li>d. Test descriptions</li> <li>e. Expected results</li> <li>f. Listing of required technical implementing procedures</li> <li>g. Responsibilities/personnel</li> <li>h. Schedule</li> <li>i. Format of reports</li> <li>j. References</li> <li>k. List of applicable QA administrative procedures</li> <li>l. List of required QA technical procedures.</li> </ul> <p>B. The second sentence of this requirement is not specifically addressed in NQA-1-1986, Supplement 11S-1. Therefore, Requirement "(a)" of this sentence shall be implemented as stated, and Requirement "(b)" of this sentence shall be implemented in Criterion 2.</p> <p>C. The requirement of sentence three is that the quality assurance organization shall, as a minimum, audit these functions in accordance with the requirements of Criterion 18, "Audits."</p>

BQARD  
CRITERION 11: TEST CONTROL - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 5 of 8)

Requirement	BWIP Project Implementation
<p data-bbox="131 300 595 333"><b>NRC REVIEW PLAN SECTION 11.2</b></p> <p data-bbox="131 366 1059 465">Test plans and procedures are reviewed in accordance with the verification requirements in Sections 3.7, 3.8, and 3.9 (of the NRC Review Plan).</p>	<p data-bbox="1102 376 2017 498">This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated. See Criterion 3 for the detailed interpretation of NRC Review Plan, Sections 3.7, 3.8, and 3.9.</p>
<p data-bbox="131 558 595 591"><b>NRC REVIEW PLAN SECTION 11.3</b></p> <p data-bbox="131 624 1004 746">The potential sources of uncertainty and error in test plans and procedures, and parameters which must be controlled and measured to assure that tests are well controlled, are identified.</p>	<p data-bbox="1102 631 2047 723">This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p data-bbox="1102 756 2025 878">Note that NRC Review Plan, Section 11.3 provides identification of some of the inspectable characteristics that are to be verified in accordance with Criterion 10, NRC Review Plan, Section 10.4.</p>

BQARD  
CRITERION 11: TEST CONTROL - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 6 of 8)

Requirement	BWIP Project Implementation
<p data-bbox="97 318 683 348"><b>REQUIREMENT 2: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="97 381 970 541">The test program shall include, as appropriate, proof tests prior to installation, preoperational tests, and operational tests during nuclear power plant or fuel reprocessing plant operations, of structures, systems, and components.</p>	<p data-bbox="1070 368 1953 467">This requirement shall be met by implementing all the requirements of NQA-1-1986, Supplement 11S-1 Section 2, with the following modification made:</p> <p data-bbox="1070 497 2006 979">A. The words "prototype qualification tests, production tests, proof tests prior to installation, construction tests, preoperations tests, and operational tests" shall be deleted and the words "site characterization activities" substituted in their stead. Involved are performance of laboratory and field investigations (site characterization activities) involving various technical areas (e.g., geology, hydrology, seismology, geophysics, geochemistry, and rock mechanics), all of which are generally considered part of geotechnical studies and/or investigations. In addition, waste package testing and conceptual design activities are performed, including development of performance requirements for repository system components (DOE-RL).</p>

BQARD  
**CRITERION 11: TEST CONTROL - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 7 of 8)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 3: 10 CFR 50 APPENDIX B</b></p> <p>Test procedures shall include provisions for assuring that prerequisites for the given test have been met, that adequate test instrumentation is available and used, and that the test is performed under suitable environmental conditions.</p> <p><b>NRC REVIEW PLAN SECTION 11.4</b></p> <p>Test procedures or instructions provide for the following:</p> <ul style="list-style-type: none"> <li>A. The requirements and acceptance limits are contained in applicable documents, including precision and accuracy.</li> <li>B. Instructions for performing the test.</li> <li>C. Test prerequisites such as calibrated instrumentation, adequate test equipment and instrumentation, completeness of item to be tested, suitable and controlled environmental conditions, and provisions for data collection and storage.</li> <li>D. Mandatory inspection hold points (as required).</li> <li>E. Acceptance and rejection criteria, including required levels of precision and accuracy.</li> <li>F. Methods of data analysis.</li> <li>G. Methods of documenting or recording test data and results.</li> <li>H. Provisions for assuring test prerequisites have been met.</li> </ul>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, the NRC has provided additional guidance for this requirement in the NRC Review Plan Section 11.4.</p> <p>This requirement is not specifically addressed in NQA-1-1986, in the detail given in the NRC Review Plan. Therefore, this requirement shall be implemented as stated.</p> <p>In addition, the test procedures shall be complete to the extent that another qualified individual may at a later date reproduce the test results, if deemed necessary. Test results that are outside the identified acceptance limits, or other nonconformances with respect to a test procedure, shall be dispositioned utilizing Criterion 15, "Nonconformances" (DOE-RL).</p>

BQARD  
**CRITERION 11: TEST CONTROL - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 8 of 8)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 4: 10 CFR 50 APPENDIX B</b></p> <p>Test results shall be documented and evaluated to assure that test requirements have been satisfied.</p> <p><b>NRC REVIEW PLAN SECTION 11.5</b></p> <p>Test results are documented, evaluated, and their acceptability determined by a responsible individual or group as described in Section 3.0 (of the NRC Review Plan).</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, the NRC has provided additional guidance for this requirement in Section 11.5 of the NRC Review Plan.</p> <p>This requirement shall be met by implementing NQA-1-1986, Supplement 11S-1, paragraph 4, provided: the words "as described in Criterion 3" are added after the "responsible party."</p> <p>The requirement for test records shall be met by implementing the requirements of the NRC Review Plan Section 17.3, and the requirements of NQA-1-1986, Supplement 11S-1, paragraph 5.</p> <p>In addition, document requirements for experiment and research for geologic repository projects are specified in OGR/B-3, Supplement 5, Section 5.0.</p>

**BQARD**  
**CRITERION 12: CONTROL OF MEASURING AND TEST EQUIPMENT**  
**REVISION 2 (sheet 1 of 4)**

<b>Requirement</b>	<b>BWIP Project Implementation</b>
	<p style="text-align: center;"><b>Site Characterization</b></p> <p>The intent of this criterion during site characterization is to establish the controls necessary over measuring and test equipment, in order to ensure that tools, gages, instruments, and other measuring and testing devices used in activities affecting quality are demonstrably accurate. Measures shall be established to define the scope of the program, describe the types of equipment to be controlled, the organizations responsible for implementing the program, and the records to be maintained to show evidence that the program is functioning.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is identical to its intent during site characterization.</p>

BQARD  
**CRITERION 12: CONTROL OF MEASURING AND TEST EQUIPMENT - FOR SITE CHARACTERIZATION**  
**REVISION 3 (sheet 2 of 4)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p>Measures shall be established to assure that tools, gages, instruments, and other measuring and testing devices used in activities affecting quality are properly controlled, calibrated, and adjusted at specified periods to maintain accuracy within necessary limits.</p> <p><b>NRC REVIEW PLAN SECTION 12.1</b></p> <p>The scope of the program for the control of measuring and test equipment is described and the types of equipment to be controlled are established.</p> <p><b>NRC REVIEW PLAN SECTION 12.2</b></p> <p>QA and other organizations' responsibilities are described for establishing, implementing, and assuring effectiveness of the calibration program.</p>	<p>This requirement shall be implemented as stated. In addition, Supplement 12S-1, Section 4 of NQA-1-1986 shall be implemented.</p> <p>For site characterization, additional guidance has been provided in Sections 12.1 through 12.7 of the NRC Review Plan.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>

BQARD  
**CRITERION 12: CONTROL OF MEASURING AND TEST EQUIPMENT - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 3 of 4)**

Requirement	BWIP Project Implementation
<p><b>NRC REVIEW PLAN SECTION 12.3</b></p> <p>Procedures are established and described for calibration (technique and frequency), maintenance, and control of the measuring and test equipment (instruments, tools, gages, fixtures, reference and transfer standards, and nondestructive test equipment) used for measurement, inspection, and monitoring. The review and documented concurrence of these functions is identified.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>
<p><b>NRC REVIEW PLAN SECTION 12.4</b></p> <p>Measuring and test equipment is labeled, tagged or otherwise documented to indicate due date of the next calibration and to provide traceability to calibration test data.</p>	<p>This requirement shall be implemented as stated. In addition, Supplement 12S-1, Section 5 of NQA-1-1986 shall be implemented.</p>
<p><b>NRC REVIEW PLAN SECTION 12.5</b></p> <p>Measuring and test equipment is calibrated at specified intervals based on required accuracy, precision, purpose, degree of usage, stability, characteristics, and other conditions which could affect measurement.</p>	<p>This requirement shall be implemented as stated. In addition, Supplement 12S-1, Sections 2, 3, and 4 of NQA-1-1986 shall be implemented.</p>

BOARD  
**CRITERION 12: CONTROL OF MEASURING AND TEST EQUIPMENT - FOR SITE CHARACTERIZATION**  
 REVISION 2 (sheet 4 of 4)

Requirement	BWIP Project Implementation
<p><b>NRC REVIEW PLAN SECTION 12.6</b></p> <p>Calibration standards are traceable to nationally recognized standards. Where national standards do not exist, provisions are established to document acceptability of the calibration standard used.</p>	<p>This requirement shall be implemented as stated. In addition, Supplement 12S-1, Section 3.1 of NQA-1-1986 shall be implemented.</p> <p>In sentence 2 of the supplement section the words "the basis for calibration shall be documented" shall be deleted and the words "provisions are established to document acceptability of the calibration standard used" shall be added in their place, which only serves as a clarification.</p>
<p><b>NRC REVIEW PLAN SECTION 12.7</b></p> <p>When measuring and test equipment is found to be out of calibration, evaluations are made and documented to determine the validity and acceptability of measurements performed since the last calibration. Inspections or tests are repeated on items determined to be suspect.</p>	<p>This requirement shall be implemented as stated. In addition, Supplement 12S-1, Section 3.2 of NQA-1-1986 shall be implemented.</p> <p>In addition, refer to Criterion 15 for documentation requirements (DOE-RL).</p>

BQARD  
CRITERION 13: HANDLING, SHIPPING AND STORAGE  
REVISION 2 (sheet 1 of 3)

Requirement	BWIP Project Implementation
	<p style="text-align: center;"><b>Site Characterization</b></p> <p>The intent of this criterion during site characterization is to establish the minimum requirements for the control of samples during handling, shipping and storage to ensure that samples are appropriately and adequately handled, preserved, stored, packaged, and shipped. Significant interfacing is required with the site testing organizations to establish correct methods for the preservation and shipping of sensitive items (e.g., environmental and geological samples taken during site characterization). This criterion may also have applicability to other critical site characterization items. Note Test Procedure Requirements.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is identical to its intent during site characterization: that is, to establish requirements for controlling the handling, storage, shipping, cleaning, and preservation of materials and equipment used in level I repository construction, in order to prevent damage or deterioration.</p>



BOARD  
CRITERION 13: HANDLING, SHIPPING AND STORAGE - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 3 of 3)

Requirement	BWIP Project Implementation
<p data-bbox="102 303 685 340">REQUIREMENT 2: 10 CFR 50 APPENDIX B</p> <p data-bbox="102 370 1023 497">When necessary for particular products, special protective environments, such as inert gas atmosphere, specific moisture content levels, and temperature levels, shall be specified and provided.</p> <p data-bbox="102 525 557 561">NRC REVIEW PLAN SECTION 13.2</p> <p data-bbox="102 591 1006 756">Procedures are established and described to control sample handling, storage, packaging, and shipping in accordance with design and procurement requirements to preclude damage, loss, or deterioration by environmental conditions such as temperature or humidity.</p>	<p data-bbox="1074 376 1847 413">This requirement shall be implemented as stated.</p> <p data-bbox="1074 442 1964 505">For site characterization, additional guidance has been provided in Section 13.2 of the NRC Review Plan.</p> <p data-bbox="1074 596 1910 692">This requirement shall be implemented as stated. In addition, Supplement 13S-1, Sections 3.1 and 3.2 of HQA-1-1986 shall be implemented.</p>

**BQARD**  
**CRITERION 14: INSPECTION, TEST AND OPERATING STATUS**  
**REVISION 2 (sheet 1 of 4)**

<b>Requirement</b>	<b>BWIP Project Implementation</b>
	<p style="text-align: center;"><b>Site Characterization</b></p> <p>The intent of this criterion during site characterization is to establish the minimum requirements for controlling the status of site characterization inspection, test, and testing equipment to ensure the status of inspection and test activities for a specific sample or material are known with certainty, and the operating/operational status of test equipment is also known.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is similar to its intent during site characterization.</p>

BOARD  
CRITERION 14: INSPECTION, TEST AND OPERATING STATUS - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 2 of 4)

Requirement	BWIP Project Implementation
<p data-bbox="113 307 695 340"><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="113 373 1031 533">Measures shall be established to indicate, by the use of markings such as stamps, tags, labels, routing cards, or other suitable means, the status of inspections and tests performed upon individual items of the nuclear powerplant or fuel reprocessing plant.</p> <p data-bbox="113 599 569 632"><b>NRC REVIEW PLAN SECTION 14.1</b></p> <p data-bbox="113 665 953 759">Procedures are established to indicate by the use of markings the status of inspections and tests on individual items.</p>	<p data-bbox="1079 365 1850 398">This requirement shall be implemented as stated.</p> <p data-bbox="1079 422 2011 525">For site characterization, the NRC has provided additional guidance for this requirement in Section 14.1 of the NRC Review Plan.</p> <p data-bbox="1079 654 1997 723">This requirement shall be met by implementing NQA-1-1986, Basic Requirement 14.</p> <p data-bbox="1079 753 2018 943">In addition, procedures shall be established to ensure that inspection, test, and operating status is clearly indicated by means of markings, tagging, boundary markers, etc., as appropriate to the nature of the equipment or natural region affected and of the inspection, test or operation involved.</p> <p data-bbox="1079 976 1969 1136">In addition, procedures shall be established to control the issuance and use of unique marking devices (e.g., stamps, tags, labels) to ensure traceability to the individual or to the specific activity utilizing the marking device (DOE-RL).</p>

BQARD  
CRITERION 14: INSPECTION, TEST AND OPERATING STATUS - FOR SITE CHARACTERIZATION  
REVISION 3 (sheet 3 of 4)

Requirement	BWIP Project Implementation
<p data-bbox="103 332 689 369">REQUIREMENT 2: 10 CFR 50 APPENDIX B</p> <p data-bbox="103 394 980 537">These measures shall provide for the identification of items which have satisfactorily passed required inspections and tests, where necessary to preclude inadvertent bypassing of such inspections and tests.</p>	<p data-bbox="1078 403 1940 470">This requirement shall be implemented as specified in NQA-1-1986, Basic Requirement 14.</p>

x

x

BOARD  
CRITERION 14: INSPECTION, TEST AND OPERATING STATUS - FOR SITE CHARACTERIZATION  
REVISION 3 (sheet 4 of 4)

Requirement	BWIP Project Implementation
<p>REQUIREMENT 3: 10 CFR 50 APPENDIX B</p> <p>Measures shall also be established for indicating the operating status of structures, systems, and components of the nuclear power plant or fuel reprocessing plant, such as by tagging valves and switches, to prevent inadvertent operation.</p>	<p>This requirement shall be implemented as stated in NQA-1-1986, Basic Requirement 14.</p>

BOARD  
CRITERION 15: NONCONFORMING MATERIALS, PARTS, OR COMPONENTS  
REVISION 2 (sheet 1 of 4)

Requirement	BWIP Project Implementation
	<p>The intent of this criterion during site characterization is to establish the minimum requirements for controlling project nonconformances, to ensure that all nonconformances affecting site characterization activities are identified, documented, segregated, reviewed, tracked, dispositioned, affected organization notified, corrected, and trended, and the implementation of the corrective action is verified.</p> <p>Refer to HQA-1-1986 Supplement S-1 for Nonconformance definition. Note that procedural deficiencies are included.</p> <p>"Reject" shall not be used to disposition test data unless the root cause clearly establishes a basis for rejection of the data. "Accept" or "use-as-is" dispositions generally implies a design change will need to be made.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is identical to its intent during site characterization.</p>



BQARD  
**CRITERION 15: NONCONFORMING MATERIALS, PARTS, OR COMPONENTS - FOR SITE CHARACTERIZATION**  
 REVISION 3 (sheet 3 of 4)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 2: 10 CFR 50 APPENDIX B</b></p> <p>These measures shall include, as appropriate, procedures for identification, documentation, segregation, disposition, and notification to affected organizations.</p>	<p>This requirement shall be implemented as stated. In addition, Supplement 15S-1, Sections 2, 3, and 4 of NQA-1-1986 shall be implemented.</p> <p>For site characterization, additional guidance has been provided in Sections 15.1, 15.2, 15.3, and 15.4 of the NRC Review Plan.</p>
<p><b>NRC REVIEW PLAN SECTION 15.2</b></p> <p>QA responsibilities related to nonconformance control are described.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>
<p><b>NRC REVIEW PLAN SECTION 15.3</b></p> <p>Documentation identifies and describes the nonconformance, dispositions the nonconformance, and includes signature approval of the disposition.</p>	<p>This requirement shall be implemented as specified in NQA-1-1986, Basic Requirement 15.</p>
<p><b>NRC REVIEW PLAN SECTION 15.4</b></p> <p>Nonconformance reports are periodically analyzed by the QA organization to show quality trends and to help identify root causes of nonconformances, and the significant results are reported to upper management for review and assessment.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented consistent with Criterion 16.</p>

BQARD  
CRITERION 15: NONCONFORMING MATERIALS, PARTS, OR COMPONENTS - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 4 of 4)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 3: 10 CFR 50 APPENDIX B</b></p> <p>Nonconforming items shall be reviewed and accepted, rejected, repaired or reworked in accordance with documented procedures.</p>	<p>This requirement shall be implemented as stated. In addition, Supplement 15S-1, Sections 4.4 and 4.5 of NQA-1-1986 shall be implemented.</p>

BOARD  
CRITERION 16: CORRECTIVE ACTION  
REVISION 2 (sheet 1 of 4)

Requirement	BWIP Project Implementation
	<p style="text-align: center;"><b>Site Characterization</b></p> <p>The intent of this criterion during site characterization is to establish the minimum requirements for controlling project corrective actions, to ensure that conditions adverse to quality are identified and corrected in a timely manner. Each project participant shall identify the need for corrective action, ensure that corrective action is initiated (which may involve actions to preclude recurrence), and verify that corrective action is implemented in a timely manner. Participants shall define a method to classify significant conditions adverse to quality and shall provide for documenting and reporting these conditions, including actions taken to preclude repetition, as well as evaluation of the impact on completed work, and report these actions to higher management for review and assessment.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is identical to its intent during site characterization.</p>

BQARD  
**CRITERION 16: CORRECTIVE ACTION - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 2 of 4)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p>Measures shall be established to assure that conditions adverse to quality, such as failures, malfunctions, deficiencies, deviations, defective material and equipment, and nonconformances are promptly identified and corrected.</p> <p><b>NRC REVIEW PLAN SECTION 16.1</b></p> <p>Procedures are established indicating an effective corrective action program has been established. The QA organization reviews and documents concurrence with the procedures.</p> <p><b>NRC REVIEW PLAN SECTION 16.2</b></p> <p>Corrective action is documented and initiated following a nonconformance to preclude recurrence. The QA organization is involved in documented concurrence of the adequacy of corrective action to assure that QA requirements are satisfied.</p> <p><b>NRC REVIEW PLAN SECTION 16.3</b></p> <p>Follow-up action is taken by the QA organization to verify proper implementation of corrective action and to close out the corrective action in a timely manner.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Sections 16.1, 16.2, and 16.3 of the NRC Review Plan.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p>

**BOARD**  
**CRITERION 16: CORRECTIVE ACTION - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 3 of 4)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 2: 10 CFR 50 APPENDIX B</b></p> <p>In the case of significant conditions adverse to quality, the measures shall assure that the cause of the condition is determined and corrective action taken to preclude repetition.</p>	<p>This requirement shall be met by implementing NQA-1-1986, Basic Requirement 16.</p>

BQAR7  
**CRITERION 16: CORRECTIVE ACTION - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 4 of 4)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 3: 10 CFR 50 APPENDIX B</b></p> <p>The identification of the significant condition adverse to quality, the cause of the condition, and the corrective action taken shall be documented and reported to appropriate levels of management.</p> <p><b>NRC REVIEW PLAN SECTION 16.4</b></p> <p>Significant conditions adverse to quality, the cause of the conditions, and the corrective action taken to preclude repetition are documented and reported to immediate management and upper levels of management for review and assessment.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, the NRC has provided additional guidance for this requirement in Section 16.4 of the NRC Review Plan.</p> <p>This requirement is also addressed in NQA-1-1986, Basic Requirement 16.</p> <p>In addition, trend analysis of NCR's and audit findings shall be used to help identify significant conditions adverse to quality, and the cause of the conditions (DOE-RL).</p> <p>In addition, significant conditions adverse to quality shall require an Unusual Occurrence Report (HQ-OCRMM).</p> <p><u>Unusual Occurrence Reporting.</u> Contractors are required to report any significant event that results in any deviation from the planned or expected behavior of an activity or operation of course of events that has or could have significant programmatic (reliability, cost, or schedule), safety, health, or environmental impacts. Significant events are to be reported in accordance with DOE Order 5000.3 (HQ-OGR).</p> <p>In addition, significant conditions adverse to quality shall be reported to <u>both</u> the integrating contractor and DOE-RL QSD as soon as possible but not later than five calendar days from the date of occurrence (DOE-RL).</p>

BOARD  
CRITERION 17: QUALITY ASSURANCE RECORDS  
REVISION 2 (sheet 1 of 7)

Requirement	BWIP Project Implementation
	<p style="text-align: center;"><b>Site Characterization</b></p> <p>The intent of this criterion during site characterization is to establish the requirements for control of project records, to ensure that documents and samples that furnish evidence of activities affecting quality remain valid and retrievable.</p> <p>In general, a QA record is preceded by a controlled document. Upon completion of the controlled document, it is incorporated into the QA Records System. Subsequent changes to the controlled document also become QA records, identifiable to but distinct from the initial QA records. It is essential that QA records be correct and complete, and allow accurate determination of the "final" or "as-built" conditions.</p> <p>In addition, records submitted to the Commission must be of demonstrable validity. Therefore, access to the QA record copy of BWIP documents and samples will be limited and controlled. Corrections to a QA record may be accomplished under limited and controlled conditions, provided the original, incorrect area of the QA record remains legible. Samples, if removed from the controlled storage facility, shall be handled in such a manner as to preclude adulteration (DOE-RL).</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is identical to its intent during site characterization.</p>



BQARD  
**CRITERION 17: QUALITY ASSURANCE RECORDS - FOR SITE CHARACTERIZATION**  
 REVISION 2 (sheet 3 of 7)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 2: 10 CFR 50 APPENDIX B</b></p> <p>The records shall include at least the following: Operating logs and the results of reviews, inspections, tests, audits, monitoring of work performance, and materials analyses.</p> <p><b>NRC REVIEW PLAN SECTION 17.1</b></p> <p>The scope of the records program is described. QA records include geotechnical samples and data; results of reviews; inspections; test, audits, and material analyses; monitoring of work performance; qualification of personnel, procedures, and equipment; and other documentation such as drawings, specifications, procurement documents, calibration procedures and reports; design review reports; peer review reports; nonconformance reports; and corrective action reports.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Section 17.1 of the NRC Review Plan.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p>In addition, each participant shall establish a definitive list of documents that are to become quality assurance records (DOE-RL).</p> <p>In addition, each participant's records program shall be consistent with the project Records Management Plan (HQ-OGR).</p> <p>Records of personnel qualification evaluations, indoctrination, training, and proficiency evaluations shall be retained as lifetime QA records. (OGR/B-3, Supplement 1, Section 5.7)</p> <p>Additional requirements for the control of QA records are specified in OGR/B-3, Supplement 4.</p>

BQARD  
CRITERION 17: QUALITY ASSURANCE RECORDS - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 4 of 7)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 3: 10 CFR 50 APPENDIX B</b></p> <p>The records shall also include closely related data such as qualifications of personnel, procedures, and equipment.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated, and as required by OGR/B-3, Supplement 5.</p>

BQARD  
CRITERION 17: QUALITY ASSURANCE RECORDS - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 5 of 7)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 4: 10 CFR 50 APPENDIX B</b></p> <p>Inspection and test records shall, as a minimum, identify the inspector or data recorder, the type of observation, the results, the acceptability, and the action taken in connection with any deficiencies noted.</p> <p><b>NRC REVIEW PLAN SECTION 17.3</b></p> <p>Inspection and test records contain the following where applicable:</p> <ul style="list-style-type: none"><li>a. A description of the type of observation.</li><li>b. The date and results of the inspection or test.</li><li>c. Information related to conditions adverse to quality.</li><li>d. Inspector or data recorder identification.</li><li>e. Evidence as to the acceptability of the results.</li><li>f. Action taken to resolve any discrepancies noted.</li></ul>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Section 17.3 of the NRC Review Plan.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p>In addition, the inspection record shall be identifiable with the test activity inspected, and the person evaluating test or inspection results shall be identified (DOE-RL).</p>

**BQARD**  
**CRITERION 17: QUALITY ASSURANCE RECORDS - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 6 of 7)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 5: 10 CFR 50 APPENDIX B</b></p> <p>Records shall be identifiable and retrievable.</p>	<p>This requirement shall be met by implementing Supplement 17S-1, Sections 2 and 5 of NQA-1-1986, provided participants record storage facility is consistent with Requirement 17.4.</p>

**BQARD**  
**CRITERION 17: QUALITY ASSURANCE RECORDS - FOR SITE CHARACTERIZATION**  
**REVISION 3 (sheet 7 of 7)**

Requirement	BWIP Project Implementation
<p data-bbox="123 307 715 343"><b>REQUIREMENT 6: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="123 370 1034 498">Consistent with applicable regulatory requirements, the applicant shall establish requirements concerning record retention, such as duration, location, and assigned responsibility.</p> <p data-bbox="123 563 583 599"><b>NRC REVIEW PLAN SECTION 17.4</b></p> <p data-bbox="123 629 938 692">Suitable facilities for the storage of records are described and utilized.</p>	<p data-bbox="1102 376 2002 439">This requirement shall be met by implementing Supplement 17S-1, Sections 2, 3, 4, and 6 of NQA-1-1986.</p> <p data-bbox="1102 472 1991 535">For site characterization, additional guidance has been provided in Section 17.4 of the NRC Review Plan.</p> <p data-bbox="1102 634 1825 697">This requirement shall be met by implementing Supplement 17S-1, Section 4 of NQA-1-1986.</p>

**BQARD**  
**CRITERION 18: AUDITS**  
**REVISION 2 (sheet 1 of 7)**

<b>Requirement</b>	<b>BWIP Project Implementation</b>
	<p>The intent of this criterion during site characterization is to establish requirements for a comprehensive system of planned and periodic audits, as well as establish controls over the audit process, in order to ensure that the management feedback information contained in BWIP audit reports is timely, impartial, and correct.</p> <p>Project participants are advised that audit planning must include consideration of surveillance results, inspection results, previous audit results, NCR's, and project deliverables, as well as the need to provide coverage over a defined period of time.</p> <p>After confirmation of QA program implementation, audits performed within BWIP shall place emphasis upon verification of the achievement of quality in project end products.</p> <p style="text-align: center;"><b>Potentially Licenseable Construction</b></p> <p>The intent of this criterion during construction is identical to its intent during site characterization.</p>

BQARD  
**CRITERION 18: AUDITS - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 2 of 7)**

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 1: 10 CFR 50 APPENDIX B</b></p> <p>A comprehensive system of planned and periodic audits shall be carried out to verify compliance with all aspects of the quality assurance program and to determine the effectiveness of the program.</p> <p><b>NRC REVIEW PLAN SECTION 18.1</b></p> <p>Internal and external audits to assure that procedures and activities comply with the overall QA program are performed by DOE and its contractors. DOE should perform audits of the prime contractor and representative subcontractors, consultants, vendors, and laboratories to assess the effectiveness of the prime contractor's audit program.</p> <p><b>NRC REVIEW PLAN SECTION 18.2</b></p> <p>An audit plan is prepared identifying audits to be performed, their frequencies, and schedules. Audits are regularly scheduled based upon the status and safety importance of the activities being performed and are initiated early enough to assure effective QA.</p>	<p>This requirement shall be implemented as stated.</p> <p>For site characterization, additional guidance has been provided in Sections 18.1, 18.2, 18.3, 18.6, 18.7, and 18.8 of the NRC Review Plan.</p> <p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p>This requirement shall be met by implementing Supplement 18S-1, Section 2, and each audit of the audit plan shall receive the detailed planning required by Section 3.1 of NQA-1-1986.</p> <p>In addition, frequency of regularly scheduled internal and external audits shall be based on evaluation of all applicable and active elements of the quality assurance programs. These evaluations shall include an assessment of the effectiveness of the applicable and active elements of the program based on such information as the following (DOE-RL):</p> <ul style="list-style-type: none"> <li>(a) Previous audits and corrective actions</li> <li>(b) Nonconformance reports</li> <li>(c) Independent information (e.g., from other sources such as generic experience of the nuclear industry, ASME, peer organizations, regulating bodies).</li> </ul>

BQARD  
**CRITERION 18: AUDITS - FOR SITE CHARACTERIZATION**  
**REVISION 2 (sheet 3 of 7)**

Requirement	BWIP Project Implementation
<p><b>NRC REVIEW PLAN SECTION 18.3</b></p> <p>Audits include an objective evaluation of the quality-related practices, procedures, instructions, activities, and items and the review of documents and records to ensure that the QA program is effective and properly implemented.</p>	<p>Regularly scheduled audits shall be supplemented by additional audits for one of the reasons given below:</p> <ul style="list-style-type: none"> <li>(a) To determine the capability of a Supplier's quality assurance program prior to awarding a contract or purchase order</li> <li>(b) When after award of a contract sufficient time has elapsed for implementing the quality assurance program and it is appropriate to determine that the organization is adequately performing the functions as defined in the quality assurance program description, codes, standards, and other contract documents</li> <li>(c) When significant changes are made in functional areas of the quality assurance program (e.g., significant reorganization or procedure revisions)</li> <li>(d) When it is suspected that the quality of an item is in jeopardy due to deficiencies in the quality assurance program</li> <li>(d) When a systematic, independent assessment of program effectiveness is considered desirable</li> <li>(f) When it is necessary to verify implementation of required corrective action.</li> </ul> <p>This requirement shall be met by implementing Supplement 18S-1, Section 4 of NQA-1-1986.</p> <p>In addition, all audits shall include an evaluation of the extent to which top management is aware of and acts on critical project information related to quality (DOE-RL).</p> <p>In addition, participants shall submit audit schedules, audit schedule revisions, and audit reports to the integrating contractor (HQ-OGR).</p>

BQARD  
CRITERION 18: AUDITS - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 4 of 7)

Requirement	BWIP Project Implementation
<p><b>NRC REVIEW PLAN SECTION 18.6</b></p> <p>A tracking system for audit findings is established to help assure that all findings are appropriately addressed and to trend audit findings.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p>In addition, each audit report shall include an "Executive Summary" of the audit findings (HQ-OCRWM).</p>
<p><b>NRC REVIEW PLAN SECTION 18.7</b></p> <p>The audited organization describes in a formal report the corrective action to be taken to address findings. This report is submitted to the auditing organization and/or responsible management.</p>	<p>This requirement shall be met by implementing Supplement 18S-1, Section 6 of NQA-1-1986.</p>
<p><b>NRC REVIEW PLAN SECTION 18.8</b></p> <p>In the resolution of findings, the root cause of each finding is also identified and corrective action for it described.</p>	<p>This requirement is not specifically addressed in NQA-1-1986. Therefore, this requirement shall be implemented as stated.</p> <p>In addition, the impact of the findings on completed work shall be evaluated (DOE-RL).</p>

BQARD  
CRITERION 18: AUDITS - FOR SITE CHARACTERIZATION  
REVISION 2 (sheet 5 of 7)

Requirement	BWIP Project Implementation
<p data-bbox="123 310 706 348"><b>REQUIREMENT 2: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="123 376 1012 502">The audits shall be performed in accordance with the written procedures or checklists by appropriately trained personnel not having direct responsibilities in the areas being audited.</p> <p data-bbox="123 563 576 601"><b>NRC REVIEW PLAN SECTION 18.5</b></p> <p data-bbox="123 629 1012 754">Audits are performed in accordance with pre-established written procedures or checklists and conducted by trained personnel having no direct responsibilities in the areas being audited.</p>	<p data-bbox="1091 381 1864 419">This requirement shall be implemented as stated.</p> <p data-bbox="1091 447 1996 541">For site characterization, the NRC has provided additional guidance for this requirement in Section 18.5 of the NRC Review Plan.</p> <p data-bbox="1091 634 2013 728">This requirement shall be implemented as stated. In addition, Supplement 18S-1, Sections 3.1, 3.2, and 3.3 of NQA-1-1986 shall be implemented.</p> <p data-bbox="1091 761 2013 948">In addition, auditor orientation shall be specific to the audit to be performed, so that the auditors are prepared for their specific roles during the audit, and are familiar with the audited organization, key individuals, and policies and procedures, as well as how to select systems for reviews (DOE-RL).</p>

BOARD  
CRITERION 18: AUDITS - FOR SITE CHARACTERIZATION  
REVISION 3 (sheet 6 of 7)

Requirement	BWIP Project Implementation
<p data-bbox="110 323 697 360"><b>REQUIREMENT 3: 10 CFR 50 APPENDIX B</b></p> <p data-bbox="110 386 966 459">Audit results shall be documented and reviewed by management having responsibility in the area audited.</p> <p data-bbox="110 581 566 617"><b>NRC REVIEW PLAN SECTION 18.4</b></p> <p data-bbox="110 644 983 746">Audit data are analyzed by the QA organization and the results are reported to responsible management for review, assessment, and appropriate action.</p>	<p data-bbox="1081 393 1855 429">This requirement shall be implemented as stated.</p> <p data-bbox="1081 455 1987 558">For site characterization, the NRC has provided additional guidance for this requirement in Section 18.4 of the NRC Review Plan.</p> <p data-bbox="1081 650 1970 809">This requirement shall be implemented as stated. The auditee's and auditor's organizations shall respond to this requirement and to Requirement 18.6. In addition, Supplement 18S-1, Section 5 of NQA-1-1986 shall be implemented.</p>

BQARD  
CRITERION 18: AUDITS - FOR SITE CHARACTERIZATION  
REVISION 3 (sheet 7 of 7)

Requirement	BWIP Project Implementation
<p><b>REQUIREMENT 4: 10 CFR 50 APPENDIX B</b></p> <p>Follow-up action, including reaudit of deficient areas, shall be taken where indicated.</p>	<p>This requirement shall be met by implementing Supplement 18S-1, Sections 6 and 7 of NQA-1-1986 and the requirements of Criterion 18, sheet 3 of this document.</p> <p>Audit records shall comply with Supplement 18S-1, Section 8 of NQA-1-1986.</p>