

3.7 PLANT SYSTEMS

3.7.5 Auxiliary Feedwater (AFW) System

LCO 3.7.5 Three AFW trains shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One steam supply to turbine driven AFW pump inoperable.	A.1 Restore steam supply to OPERABLE status.	7 days <u>AND</u> 10 days from discovery of failure to meet the LCO
B. One ESW supply to turbine driven AFW pump inoperable	B.1 Restore ESW supply to OPERABLE status.	72 hours <u>AND</u> 10 days from discovery of failure to meet the LCO
C. One AFW train inoperable for reasons other than Condition A or B.	C.1 Restore AFW train to OPERABLE status.	72 hours* <u>AND</u> 10 days from discovery of failure to meet the LCO

(continued)

*With the exception that the Completion Time associated with the Condition C entry on 2/3/04 for the turbine driven auxiliary feedwater pump has been extended on a one-time only basis to 144 hours. At the time a formal cause of the inoperability is determined, Condition D will be entered immediately.