

To : ~~NRC~~ NRC
 Facility : CR3 Department :
 Address : CR3-01242 / MAIL CODE: N/A
~~DC DESK~~


From : CR3DOCSVCS Attention: DOCUMENT SERVICES - SA2A
 Address : FLORIDA POWER CORPORATION
 CRYSTAL RIVER COMPLEX
 15760 WEST POWERLINE STREET
 City : CRYSTAL RIVER State:FL Postal Code: 34428-6708
 Country : UNITED STATES
 Email :
 Contact :

Date/Time : 03/11/04 08:06 Transmittal Group Id:0000015578
 Trans No. : 000145404 Title:
 Total Items: 00001

PASSPORT DOCUMENT

TRANSMITTAL

Page: 1



Item	Facility	Type	Sub	Document Number	Sheet	Doc Status	Revision	Doc Date	Copy #	Media	Copies
0001	CR3	POM	EMG	EM0225C		ACTIVE	003			H	01

If a document was not received or is no longer required check the response below and return to sender.

Documents noted above not received (identify those not received).

I no longer require distribution of these documents (identify those no longer required).

Date: _____ Signature: _____

AP45

PROGRESS ENERGY
CRYSTAL RIVER UNIT 3
PLANT OPERATING MANUAL

EM-225C
POST ACCIDENT MONITORING OF
REACTOR BUILDING TEMPERATURE

TABLE OF CONTENTS

SECTION	PAGE
1.0 PURPOSE.....	3
2.0 REFERENCES.....	3
2.1 Developmental References.....	3
3.0 PERSONNEL INDOCTRINATION	3
3.1 Definitions	3
3.2 Responsibilities.....	3
3.3 Limits And Precautions	3
4.0 INSTRUCTIONS.....	4
5.0 FOLLOW-UP ACTIONS.....	5
ENCLOSURE	
1 Limiting RB Temperature.....	6

1.0 PURPOSE

The purpose of this procedure is to provide guidance to the TSC Accident Assessment Team to monitor and take action to ensure Reactor Building (RB) temperatures remain below the qualified threshold limits for environmentally qualified components. If temperatures approach a predetermined limit, then actions will be taken to reduce RB temperatures to acceptable values.

2.0 REFERENCES

2.1 Developmental References

2.1.1 ITS 3.6.5 Containment Air Temperature

2.1.2 Environmental and Seismic Qualification Program Manual

2.1.3 IOC NOE 97-2534, Assessment to support EM-225C for SBLOCA EQ Concerns, dated 12/4/97

2.1.4 Calculation M-97-0072, CR-3 Containment Analysis for SBLOCA, Rev. 2

2.1.5 PC 97-7607

2.1.6 IOC NSM 98-0592, Close out of the DR/JCO related to PC 97-7607 - RB EQ Temperatures from a SBLOCA event, dated 4/2/98

2.1.7 Calculation M-97-0132, CR3 Containment Analysis, Rev. 6

2.1.8 PC 00-0830, Enclosure 1 curve in EM-225C appears to be incorrect, dated 3/16/00

2.1.9 Calculation M-90-0021, Building Spray and Decay Heat NPSH, Rev. 12

3.0 PERSONNEL INDOCTRINATION

3.1 Definitions

None

3.2 Responsibilities

The TSC Accident Assessment Team is responsible for monitoring RB temperatures post accident, and to provide recommendations to the Emergency Coordinator to initiate building spray if temperatures reach the limits established in this procedure.

3.3 Limits And Precautions

3.3.1 Large break LOCAs and larger small break LOCAs will result in RB Pressures that actuate building spray automatically. Actions to manually start building spray to reduce RB temperatures will not be required in these situations.

3.3.2 Prior to starting any ES powered component, adequate load margin must be available if the ES 4160 volt busses are energized from the emergency diesel generators.

3.3.3 Prior to starting a building spray pump, building spray flow control valves must be set for 1200 gpm if ECCS suction has been transferred to the RB Sump.

3.3.4 If a SGTR is in progress then ensure adequate RB sump level is available prior to transferring or starting a BS pump from the RB Sump. With a SGTR, sufficient RB sump level might not be available due to loss from the SGTR. Reference calculation M-90-0021 for BSP NPSH requirements.

4.0 INSTRUCTIONS

4.1 IF at least one building spray pump is running, THEN exit this procedure. No further action is required.

4.2 IF an RCS leak is occurring in the reactor building, THEN begin plotting average RB temperature on Enclosure 1 for at least 1 hour intervals in the beginning of the event. The plotting interval can be changed based on plant conditions.

4.3 RB Temperature is the average of the following four temperature elements:

TEMPERATURE ELEMENT	CONTROL ROOM RECORDER	RECALL POINT	COMPUTER POINT	RB ELEV.
AH-536-TE	AH-536-TIR	RECL-77	S358	102
AH-537-TE		RECL-78	S359	125
AH-538-TE		RECL-80	S382	180
AH-539-TE	∇	RECL-81	S383	235
AVERAGE			S837	

4.4 IF average RB Temperature is in the "Acceptable" Region of Enclosure 1 and decreasing, THEN exit this procedure.

4.5 IF at any time average RB temperature reaches "Action Required boundary" region of Enclosure 1, THEN obtain Emergency Coordinator concurrence to start at least one building spray pump.

4.6 IF a building spray pump is required and EC concurrence has been obtained, THEN perform the following:

4.6.1 Ensure load is available on the emergency diesel generators per EOP-13, Rule 5.

4.6.2 Ensure Building Spray flow controls are set at 1500 GPM and "Remote" if pumps are aligned to BWST, or 1200 GPM and "LOCAL" if aligned to the RB Sump.

4.6.3 Notify the control room to start one building spray pump.

4.7 Continue to monitor RB Temperature.

4.8 IF RB Temperature does not lower to the acceptable region of Enclosure 1,
THEN notify control room to start a second building spray pump if available.

NOTE


If building spray pumps are running, Emergency Operating Procedures provide guidance to secure them. If building spray pumps are secured, begin additional monitoring of RB Temperatures until a continuing decreasing trend is achieved.

4.9 WHEN building spray pumps are running,
THEN exit this procedure.

5.0 FOLLOW-UP ACTIONS

None

EM-225C Limiting RB Temperature



Summary of Changes
(PRR 120816)

SECTION	CHANGE
Cover sheet	Changed the coversheet to Progress Energy
Enclosure 1	Replaced curve with a revised format that will allow printing of the curve without causing the upper portion to turn gray. The curve parameters and values were not changed (Ref PRR 120816)
2.1.9	Updated revision level of Calc M-90-0021 to Rev. 12 – no impact on procedure