

PLANT SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

- 3) Verifying that the system maintains the control room envelope at a positive pressure of greater than or equal to 1/8 inch Water Gauge at less than or equal to a pressurization flow of 2000 cfm relative to adjacent areas during system operation ⁽¹⁾; and
 - 4) Verifying that the makeup filter unit heaters dissipate 4.5 ± 0.45 kW when tested in accordance with ANSI N510-1980.
- f. After each complete or partial replacement of a HEPA filter bank, by verifying that the HEPA filter bank satisfies the in-place penetration and bypass leakage testing acceptance criteria of less than 0.05% in accordance with ANSI N510-1980 for a DOP test aerosol while operating the system at a flow rate of 6000 cfm \pm 10% for the cleanup units and 1000 cfm \pm 10% for the makeup units; and
- g. After each complete or partial replacement of a charcoal adsorber bank, by verifying that the charcoal adsorber bank satisfies the in-place penetration and bypass leakage testing acceptance criteria of less than 0.10% in accordance with ANSI N510-1980 for a halogenated hydrocarbon refrigerant test gas while operating the system at a flow rate of 6000 cfm \pm 10% for the cleanup units and 1000 cfm \pm 10% for the makeup units.

(1) Measured points at a positive pressure but less than 1/8 inch Water Gauge are acceptable if an evaluation, considering appropriate compensatory action, demonstrates that the condition meets the requirements of GDC-19. The provisions of this note expire at 0800 on September 19, 2005.