



Bottom Mounted Nozzle Strategic Plan

July Update to NRC

Larry Mathews, Southern Nuclear
Chair, MRP Alloy 600 ITG

Mel Arey, Duke Energy
MRP Alloy 600 ITG

July 19, 2004

Conference Call



Meeting Agenda

- BM Nozzle NDE Demonstration Program
- BMN Safety Assessment Plan
- Integrated Inspection Plan
 - Planned Inspections
 - Callaway BM Nozzle Inspection Results
- BM Nozzle Strategic Plan
- Summary



Bottom Mounted Nozzle Strategic Plan Elements

- BM Nozzle NDE Demonstration Program
 - MRP Alloy 600 ITG
- BMN Safety Assessment Plan
 - Combined effort of MRP Alloy 600 ITG, BWOG, and WOG
- Integrated Industry Inspection Plan
 - MRP Alloy 600 ITG and PWR Owners
- BMN Repairs
 - Commercial techniques available





BMN NDE Performance Demonstration Program

Larry Mathews, Southern Nuclear
Chair, Alloy 600 ITG




BMN Practice Mockups

- 4 Practice Mockups
 - 2 Westinghouse 3/4-Loop
 - 2 B&W Designs
 - Tube Only
 - Tube w/repair weld
- Made available in 2003



BMN Blind Demonstration Mockups

- 7 Mockups for Volumetric and Surface Inspection
 - 6 Full-Scale Mockups
 - 2 Westinghouse 2-Loop Design
 - 2 B&W Design
 - 2 Westinghouse 3/4-Loop Design
 - 1 Plastic Mockup that holds coupons containing Laboratory-grown SCC



Status of Demonstrations

- Demonstrations to-date
 - WesDyne International
 - AREVA (formerly known as Framatome)
 - Other inspection vendors have been invited to participate
- Techniques Demonstrated
 - Used currently available technology (best effort)
 - Demonstrations have been UT of nozzle base material: TOFD
- Future Demonstrations
 - Improved UT of nozzle base material
 - ET of the wetted surface of the J-groove weld



Status of Demonstrations (cont'd)

- Demonstration Results
 - Both vendors experienced false calls on UT of nozzle base material
 - Seeing improvement in second round
 - Due to geometry of repair configurations, UT inspections did not cover 100% of targeted inspection area
 - Initial ET efforts on J-groove weld experienced delivery system limitations
- Future Activities
 - WesDyne UT & ET Demo - August 2004
 - AREVA ET Demo - January 2005





Bottom Mounted Nozzle Safety Assessment Plan

WOG, Dave Bajumpaa, Dominion

B&WOG, Bill Gray, AREVA






Industry BMN Safety Assessment Plan

- Primary Elements of Plan
 - Failure Modes and Effects Analysis
 - Review of Design and Manufacturing Data
 - LOCA Analysis
 - Stress Analysis & Fracture Mechanics Analysis
 - Collateral Damage Assessment
 - Wastage Assessment
 - Inspection History and Ongoing Results
 - Core Damage Frequency
 - Long Term Inspection Recommendations
 - Repair Recommendations



Bottom Mounted Nozzle Assessment Work Plan



Westinghouse Owners Group BMN Safety Assessment Program

- Program is funded
- Work initiated Summer 2003
- All deliverables are currently on schedule to support overall program



WOG BMN Safety Assessment Program

- Design Basis Investigation and Inspection Summary
 - Complete
- Design and Fabrication of BM Nozzles
 - Draft report completed
 - Comments received
 - Final report pending
- Failure Modes and Effects Analysis
 - Draft issued for WOG review
 - Comments received and being resolved
 - Final report expected Fall 2004



WOG BMN Safety Assessment Program

- Integrity Evaluation
 - Finite element analysis draft reports received
 - Fracture mechanics work is in progress
 - Two additional configurations need to be addressed based on fabrication history search
- Risk Evaluation
 - Small break LOCA analyses are in progress to support risk evaluation



B&W Owners Group BMN Safety Assessment Program

- Program is funded
- Work initiated March 2004
- All deliverables are currently on schedule to support overall program



B&W Owners Group

BMN Safety Assessment Program

- Design and Manufacturing Data
 - Draft issued for B&WOG review
 - Comments received
 - Final report pending
- LOCA Analysis
 - Draft issued for B&WOG review
 - Comments received
 - Final report pending



B&W Owners Group

BMN Safety Assessment Program (cont'd)

- FMEA Support (WOG lead)
 - Reviewed initial draft
 - Working with WOG to resolve comments
- Collateral Damage
- Stress Analysis





Integrated Industry Inspection Plan

Mel Arey, Duke Energy



Integrated Industry Inspection Plan

- Purpose
 - Perform selected volumetric inspections while the work progresses to determine long term inspection and monitoring strategy.
 - Gather additional data to determine extent of the problem.
 - Develop a proactive industry management program that assures safe and reliable operation.



Integrated Industry Inspection Plan

- Potential Inspections:
 - BMV of lower vessel head
 - UT of nozzle base material
 - Enhanced visual of j-groove weld or ET of j-groove weld
- Inspection results will be reviewed to determine if a susceptibility model could/should be developed
- Supports development of a long-term BMN inspection strategy



Industry Communications

- June 2003, MRP Letter
 - Perform bare metal examination of any Alloy 600 nozzles on bottom head
 - Non-visual NDE may ultimately be a prudent and necessary component in a comprehensive inspection plan
- August 2003, NRC Bulletin 2003-02
 - NRC recommendations consistent with MRP guidance
- May 2004, MRP Letter
 - Continue with bare metal visual inspections per previous recommendations
 - Utilities with an upcoming 10-year reactor vessel ISI should plan volumetric inspections



Planned BMN Volumetric Inspections_{note}


- Spring 2004
 - Callaway
- Fall 2004
 - Watts Bar 2
 - Turkey Point 3
 - Oconee 3
 - Catawba 2
- Spring 2005
 - Turkey Point 4
 - Prairie Island 2
 - STP 2
 - Catawba 1
 - McGuire 2

Note: Performance of inspection is predicated on the successful completion of the BMN NDE demonstrations



Callaway BM Nozzle Inspection

- Performed in conjunction with the 10-year vessel examination
- Inspected 58 nozzles
 - 2 Time of Flight Diffraction (TOFD) probes
 - One axially oriented for circ flaws
 - One circumferentially oriented for axial flaws
 - 30 degree dual element probe to interrogate the weld interface
 - Eddy current probe for surface breaking flaws
- No indications were noted



BMN Repairs

- Commercial techniques are currently available
- Industry identified the attributes of an ideal repair
 - Prioritized for use in evaluating available commercial techniques or new designs.
 - Listed the various strengths and weaknesses of each attribute.





Summary and Wrap-Up

Larry Mathews, Southern Nuclear
Chair, Alloy 600 ITG



Bottom Mounted Nozzle Strategic Plan Elements

- BM Nozzle NDE Demonstration Program
 - MRP Alloy 600 ITG
- BMN Safety Assessment Plan
 - Combined effort of MRP Alloy 600 ITG, BWOG, and WOG
- Integrated Industry Inspection Plan
 - MRP Alloy 600 ITG and PWR Owners
- BMN Repairs
 - Commercial techniques available



Project Activities

- Summer 2004
 - NDE Demonstration Program
 - On-going with periodic reports
- Fall 2004
 - Failure Modes and Effects Analysis
- Fall 2005
 - Wastage Assessment
 - LOCA Analysis
 - Fracture Mechanics and Deterministic Calculations
 - Core Damage Frequency
- Spring 2006
 - Final BMN Inspection Strategy
 - Final BMN Assessment



Summary and Conclusions

- NDE demonstrations are underway
- Safety assessment work is underway
- Bare metal visual inspections have not identified indications of leakage
- Multiple volumetric examinations are planned for upcoming outage seasons

- There continues to be no immediate safety concern



Wrap-up

- NRC Comments?
 - Discussion

