

Main Turbine Bypass System and Moisture Separator Reheater
3.7.6

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
SR 3.7.6.1 : Verify each main turbine bypass valve opens at least 5%.	120 days
SR 3.7.6.2 Verify one complete cycle of each main turbine bypass valve.	Once after each entry into MODE 4
SR 3.7.6.3 Perform a system functional test.	18 months
SR 3.7.6.4 Verify the TURBINE BYPASS SYSTEM RESPONSE TIME is within limits.	18 months :